MODIFIED ESTIMATE

BRUHAT BANGALORE MAHANAGARA PALIKE

Name Of Work:- PACKAGE NO.03 (CONSISTS OF 5 WORKS)

MODIFIED ESTIMATE

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.01		**Removing and resetting Stone Slab of drain and pointing in C.M (1:3) (Approved Rate)**										
		Ward No 07										
		2nd Cross Road Sunshine apartment										
		(From North to South)										
		RHS										
0	15		Sqm	1	15.00	1.35	1.35	1.35		20.25		
15	30		Sqm	1	15.00	1.35	1.35	1.35		20.25		
30	45		Sqm	1	15.00	1.35	1.35	1.35		20.25		
45	60		Sqm	1	15.00	1.35	1.35	1.35		20.25		
60	67.2		Sqm	1	7.20	1.35	1.35	1.35		9.72		
		Muniswamy Gowda Layout										
		1st A K.V.J Road										
		(From West to East)										
		LHS										
0	15		Sqm	1	15.00	1.35	1.35	1.35		20.25		
15	30		Sqm	1	15.00	1.35	1.35	1.35		20.25		
30	34.2		Sqm	1	4.20	1.35	1.35	1.35		5.67		
		RHS										
		(From West to East)										
0	20.8	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
20.8	29.1		Sqm	1	8.30	1.35	1.35	1.35		11.21		
29.1	34.2		Sqm	1	5.10	1.35	1.35	1.35		6.89		
		2nd A Cross Road										
		(From West to East)										
		LHS										
0	15		Sqm	1	15.00	1.35	1.35	1.35		20.25		
15	19.7		Sqm	1	4.70	1.35	1.35	1.35		6.35		
19.7	29.3		Sqm	1	9.60	1.35	1.35	1.35		12.96		
29.3	34.1		Sqm	1	4.80	1.35	1.35	1.35		6.48		
		RHS										
0	15		Sqm	1	15.00	1.35	1.35	1.35		20.25		
15	30		Sqm	1	15.00	1.35	1.35	1.35		20.25		
30	34		Sqm	1	4.00	1.35	1.35	1.35		5.40		
		Ward No 08										
		Tata Nagar										
		Kote Layout										
		Rohitha Gardens Apartment opposite Road										
		LHS										
		(From West to East)										
0	7.9		Sqm	1	7.90	0.60	0.60	0.60		4.74		
7.9	17.5		Sqm	1	9.60	0.60	0.60	0.60		5.76		
17.5	24.3	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
24.3	39.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
39.3	54.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
54.3	69.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
69.3	84.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
84.3	99.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
99.3	114.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
114.3	129.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
129.3	144.3		Sqm	1	15.00	0.60	0.60	0.60		9.00		
144.3	145.3		Sqm	1	1.00	0.60	0.60	0.60		0.60		
145.3	151.2	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
151.2	166.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
166.2	167.8		Sqm	1	1.60	0.60	0.60	0.60		0.96		
167.8	174.6	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
174.6	189.6		Sqm	1	15.00	0.60	0.60	0.60		9.00		
189.6	204.6		Sqm	1	15.00	0.60	0.60	0.60		9.00		
204.6	216.6		Sqm	1	12.00	0.60	0.60	0.60		7.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		LHS										
		(From East to West)										
0	15		Sqm	1	15.00	0.60	0.60	0.60		9.00		
15	30		Sqm	1	15.00	0.60	0.60	0.60		9.00		
30	44.8		Sqm	1	14.80	0.60	0.60	0.60		8.88		
44.8	49.4	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
49.4	64.4		Sqm	1	15.00	0.60	0.60	0.60		9.00		
64.4	68.5		Sqm	1	4.10	0.60	0.60	0.60		2.46		
68.5	73.4	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
73.4	88.4		Sqm	1	15.00	0.60	0.60	0.60		9.00		
88.4	92.6		Sqm	1	4.20	0.60	0.60	0.60		2.52		
92.6	98.2	Road Break	Sqm	1	0.00	0.60	0.60	0.60		0.00		
98.2	113.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
113.2	128.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
128.2	143.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
143.2	158.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
158.2	173.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
173.2	188.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
188.2	203.2		Sqm	1	15.00	0.60	0.60	0.60		9.00		
		Ward No 10										
		Ramanna Garden										
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
		RHS										
2.00	6.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
10.00	14.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
22.00	28.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
33.00	38.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
48.00	52.30		Sqm	1	4.30	1.35	1.35	1.35		5.81		
59.00	65.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
72.00	76.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
83.00	86.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
95.00	99.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
106.00	111.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
120.00	123.20		Sqm	1	3.20	1.35	1.35	1.35		4.32		
		BLUE MOON GARDEN										
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
		LHS										
3.00	7.80		Sqm	1	4.80	1.35	1.35	1.35		6.48		
		BLOOM FIELD GARDEN										
		Main Road										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
		LHS										
0.00	7.10	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
8.00	12.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
14.00	17.10		Sqm	1	3.10	1.35	1.35	1.35		4.19		
		2nd Cross Road, House no: #48 to House no:#42										
		(From South to North)										
		LHS										
3.00	4.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
12.00	17.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
19.00	23.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
27.00	32.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
34.00	39.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
42.00	47.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
55.00	59.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
74.00	76.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
80.00	84.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
2.00	104.60		Sqm	1	2.60	1.35	1.35	1.35		3.51		
112.00	115.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		2nd Cross Road, House no: #68 to House no:#59										
		(From North to South)										
		LHS										
3.00	8.40		Sqm	1	5.40	1.35	1.35	1.35		7.29		
12.00	16.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
23.00	28.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
34.00	37.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
55.00	58.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		RHS										
6.00	10.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
25.00	30.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
38.00	41.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
52.00	58.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
60.00	62.40		Sqm	1	2.40	1.35	1.35	1.35		3.24		
		1st Cross Road, House no: #127 to House no:#95										
		(From South to North)										
		LHS										
7.00	9.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
12.00	15.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
25.00	30.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
36.00	41.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
43.00	48.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
50.00	54.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
64.00	68.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
82.00	86.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
96.00	101.30		Sqm	1	5.30	1.35	1.35	1.35		7.16		
112.00	115.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		RHS										
6.00	10.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
13.00	18.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	34.50		Sqm	1	4.50	1.35	1.35	1.35		6.08		
45.00	48.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
53.00	56.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
63.00	68.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
73.00	78.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
87.00	91.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
104.00	108.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
110.00	112.90		Sqm	1	2.90	1.35	1.35	1.35		3.92		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
		LHS										
8.00	10.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
19.00	21.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
25.00	28.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
32.00	35.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
37.00	40.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
42.60	51.80	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
51.80	55.40	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
60.00	64.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
69.00	72.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
85.40	89.00		Sqm	1	3.60	1.35	1.35	1.35		4.86		
96.00	100.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
105.00	109.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
116.20	124.90	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
127.00	128.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
133.40	135.70	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
137.00	139.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
[illegible].00	149.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
156.80	164.50	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
164.50	184.00	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
186.00	190.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
195.00	198.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
203.00	210.90	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
220.00	223.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
227.00	230.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
237.00	240.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
245.00	248.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
255.00	259.10		Sqm	1	4.10	1.35	1.35	1.35		5.54		
264.00	270.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
273.00	275.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
281.00	288.20		Sqm	1	7.20	1.35	1.35	1.35		9.72		
		RHS										
6.00	8.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
13.00	15.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
18.00	20.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
23.10	24.70	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
27.00	29.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
35.00	38.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
42.70	50.90	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
50.90	55.00	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
59.00	63.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
70.00	76.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
82.10	97.00	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
104.00	106.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
113.00	116.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
123.00	126.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
130.00	132.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
138.00	140.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
143.40	151.50	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
155.00	159.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
164.50	167.70	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
174.00	177.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
183.00	186.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
191.00	194.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
200.00	202.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
210.00	213.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
220.00	222.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
229.00	233.50	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
236.00	238.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
241.00	244.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
246.00	248.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
253.00	260.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
265.80	274.50	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
280.00	283.30		Sqm	1	3.30	1.35	1.35	1.35		4.46		
289.00	297.00		Sqm	1	8.00	1.35	1.35	1.35		10.80		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		NORTH TO SOUTH										
		LHS										
7.00	11.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
15.00	20.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
36.00	43.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
50.00	55.50		Sqm	1	5.50	1.35	1.35	1.35		7.43		
70.00	75.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
86.00	90.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
101.00	105.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
110.00	113.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		RHS										
2.00	5.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
8.00	10.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	17.40		Sqm	1	2.40	1.35	1.35	1.35		3.24		
[illegible].00	25.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
28.00	30.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
32.30	36.20	No work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
36.20	45.70	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
48.00	50.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
55.00	57.50		Sqm	1	2.50	1.35	1.35	1.35		3.38		
60.00	62.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
64.00	66.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
69.00	71.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
74.00	75.50		Sqm	1	1.50	1.35	1.35	1.35		2.03		
77.60	85.30	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
90.00	91.00		Sqm	1	1.00	1.35	1.35	1.35		1.35		
96.00	98.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
108.00	111.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
		3rd Cross Road										
		(From South to North)										
		LHS										
4.00	8.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
15.00	20.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	34.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
45.00	48.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
60.00	63.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
74.20	77.00		Sqm	1	2.80	1.35	1.35	1.35		3.78		
80.00	83.20		Sqm	1	3.20	1.35	1.35	1.35		4.32		
90.00	93.80		Sqm	1	3.80	1.35	1.35	1.35		5.13		
100.00	104.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
110.00	114.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
118.00	123.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
130.00	133.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
145.00	148.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
153.00	156.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
161.00	165.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
168.00	171.20		Sqm	1	3.20	1.35	1.35	1.35		4.32		
		RHS										
6.00	8.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
14.00	16.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
25.50	29.10		Sqm	1	3.60	1.35	1.35	1.35		4.86		
35.00	39.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
45.00	47.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
54.00	57.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
76.00	77.80		Sqm	1	1.80	1.35	1.35	1.35		2.43		
88.00	92.50		Sqm	1	4.50	1.35	1.35	1.35		6.08		
97.00	100.40		Sqm	1	3.40	1.35	1.35	1.35		4.59		
104.00	107.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
115.40	120.00		Sqm	1	4.60	1.35	1.35	1.35		6.21		
124.00	127.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
132.80	135.30		Sqm	1	2.50	1.35	1.35	1.35		3.38		
140.00	143.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
147.00	150.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
155.00	157.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
162.50	165.00		Sqm	1	2.50	1.35	1.35	1.35		3.38		
169.00	172.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
175.00	178.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
179.00	181.10		Sqm	1	2.10	1.35	1.35	1.35		2.83		
		5th Cross Road										
		(From North to South)										
		LHS										
7.00	10.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
17.00	21.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
25.00	27.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
30.00	33.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
34.20	42.00	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
50.00	57.00		Sqm	1	7.00	1.35	1.35	1.35		9.45		
64.00	68.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
70.00	72.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
73.40	82.50	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
.00	88.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
94.00	96.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
104.00	108.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
112.00	114.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
140.00	143.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
145.00	154.80		Sqm	1	9.80	1.35	1.35	1.35		13.23		
		RHS										
8.00	13.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
19.00	24.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
35.00	38.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
48.00	53.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
66.00	70.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
86.00	90.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
96.00	99.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
107.00	111.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
124.00	127.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
141.00	144.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
149.00	153.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
157.00	162.80		Sqm	1	5.80	1.35	1.35	1.35		7.83		
		(From North to South)										
		LHS										
4.00	8.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
20.00	25.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
30.00	34.10		Sqm	1	4.10	1.35	1.35	1.35		5.54		
38.60	46.10	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
51.00	53.00		Sqm	1	2.00	1.35	1.35	1.35		2.70		
58.00	63.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
66.00	71.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
77.80	86.20	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
90.00	93.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
97.00	101.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
116.20	117.60		Sqm	1	1.40	1.35	1.35	1.35		1.89		
117.60	126.40	Road Break	Sqm	1	0.00	1.35	1.35	1.35		0.00		
126.40	131.70	No Work	Sqm	1	0.00	1.35	1.35	1.35		0.00		
143.00	147.90		Sqm	1	4.90	1.35	1.35	1.35		6.62		
		RHS										
6.00	9.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
16.00	21.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
28.00	31.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
55.00	60.00		Sqm	1	5.00	1.35	1.35	1.35		6.75		
69.00	75.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
87.00	90.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
101.00	105.00		Sqm	1	4.00	1.35	1.35	1.35		5.40		
117.00	120.00		Sqm	1	3.00	1.35	1.35	1.35		4.05		
125.00	131.00		Sqm	1	6.00	1.35	1.35	1.35		8.10		
140.00	149.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
151.00	154.30		Sqm	1	3.30	1.35	1.35	1.35		4.46		
										Total Executed Quantity	**1487.70**	**139.73**	**207877.00**
										Tender Quantity	**4199.07**		
Item no.02		**Removing and Resetting of Footpath Slab and pointing in C.M (1:3) (Approved Rate)**										
		Ward No 07										
		Muniswamy Gowda Layout										
		1st A K.V.J Road										
		RHS										
		(From West to East)										
0.00	20.80	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
20.80	29.10		Sqm	1	8.30	0.90	0.90	0.90		7.47		
29.10	34.20		Sqm	1	5.10	0.90	0.90	0.90		4.59		
		3rd Cross Near Vidya Niketan School Road										
		(From South to North)										
		LHS										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
30.00	39.50		Sqm	1	9.50	0.90	0.90	0.90		8.55		
39.50	46.30	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
46.30	61.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
61.30	75.70		Sqm	1	14.40	0.90	0.90	0.90		12.96		
75.70	81.90	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
81.90	96.90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
96.90	111.50		Sqm	1	14.60	0.90	0.90	0.90		13.14		
111.50	118.50	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
118.50	133.50		Sqm	1	15.00	0.90	0.90	0.90		13.50		
133.50	135.30		Sqm	1	1.80	0.90	0.90	0.90		1.62		
		RHS										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	90.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90.00	105.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105.00	120.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120.00	135.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
		Culvert Slab										
		Muniswamy Gowda Layout										
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
			Sqm	1	6.00	1.80	1.80	1.80		10.80		
		Chiranjeevi Layout										
		3rd Cross Road										
			Sqm	1	4.80	1.20	1.20	1.20		5.76		
		3rd Cross Near Vidya Niketan School Road										
			Sqm	1	5.60	1.20	1.20	1.20		6.72		
		Veerannapalya										
		6th A Cross Road										
			Sqm	1	6.20	1.80	1.80	1.80		11.16		
		6th B Cross Road										
			Sqm	1	5.00	1.80	1.80	1.80		9.00		
		6th Cross Road										
			Sqm	1	7.70	1.80	1.80	1.80		13.86		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
		LHS										
0	9.2	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
12	24		Sqm	1	12.00	0.75	0.75	0.75		9.00		
26	34		Sqm	1	8.00	0.75	0.75	0.75		6.00		
35.8	42.5	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
44	54		Sqm	1	10.00	0.75	0.75	0.75		7.50		
56	66		Sqm	1	10.00	0.75	0.75	0.75		7.50		
68	80		Sqm	1	12.00	0.75	0.75	0.75		9.00		
82	92		Sqm	1	10.00	0.75	0.75	0.75		7.50		
93.4	97.9	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
99	110		Sqm	1	11.00	0.75	0.75	0.75		8.25		
112	124		Sqm	1	12.00	0.75	0.75	0.75		9.00		
126	141		Sqm	1	15.00	0.75	0.75	0.75		11.25		
145	153		Sqm	1	8.00	0.75	0.75	0.75		6.00		
155	158.7		Sqm	1	3.70	0.75	0.75	0.75		2.77		
		RHS										
		(From East to West)										
2	9.3		Sqm	1	7.30	0.75	0.75	0.75		5.48		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
11	18.3		Sqm	1	7.30	0.75	0.75	0.75		5.48		
18.3	26.2	Road Break	Sqm	1	0.00	0.75	0.75	0.75		0.00		
28	38		Sqm	1	10.00	0.75	0.75	0.75		7.50		
40	51		Sqm	1	11.00	0.75	0.75	0.75		8.25		
53	67		Sqm	1	14.00	0.75	0.75	0.75		10.50		
68.4	72.4	Road Break	Sqm	1	0.00	0.75	0.75	0.75		0.00		
74	81		Sqm	1	7.00	0.75	0.75	0.75		5.25		
83	97		Sqm	1	14.00	0.75	0.75	0.75		10.50		
98.2	106.1	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
108	116		Sqm	1	8.00	0.75	0.75	0.75		6.00		
117.5	121	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
121	125.2	Road Break	Sqm	1	0.00	0.75	0.75	0.75		0.00		
127	136		Sqm	1	9.00	0.75	0.75	0.75		6.75		
138	140		Sqm	1	2.00	0.75	0.75	0.75		1.50		
141.2	144.7	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
146	157		Sqm	1	11.00	0.75	0.75	0.75		8.25		
158	163.2		Sqm	1	5.20	0.75	0.75	0.75		3.90		
		6th A Cross Road										
		(From North to South)										
		LHS										
5	13		Sqm	1	8.00	0.75	0.75	0.75		6.00		
15	23		Sqm	1	8.00	0.75	0.75	0.75		6.00		
24.9	32.7	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
34	45		Sqm	1	11.00	0.75	0.75	0.75		8.25		
47	57		Sqm	1	10.00	0.75	0.75	0.75		7.50		
59	68		Sqm	1	9.00	0.75	0.75	0.75		6.75		
70	84		Sqm	1	14.00	0.75	0.75	0.75		10.50		
85	98.3	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
100	111.7		Sqm	1	11.70	0.75	0.75	0.75		8.78		
115	128		Sqm	1	13.00	0.75	0.75	0.75		9.75		
130	142.2		Sqm	1	12.20	0.75	0.75	0.75		9.15		
		RHS										
		(From North to South)										
6	12.8		Sqm	1	6.80	0.75	0.75	0.75		5.10		
12.8	26.2	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
26.2	44	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
44	45.3	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
45.3	49.6		Sqm	1	4.30	0.75	0.75	0.75		3.23		
49.6	64.6		Sqm	1	15.00	0.75	0.75	0.75		11.25		
64.6	74.4	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
76	86		Sqm	1	10.00	0.75	0.75	0.75		7.50		
88	96		Sqm	1	8.00	0.75	0.75	0.75		6.00		
98	99.4		Sqm	1	1.40	0.90	0.90	0.90		1.26		
99.4	101.4	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
102	104.5		Sqm	1	2.50	0.75	0.75	0.75		1.88		
		Devi Nagar Main Road										
		(From West to East)										
		LHS										
3	14		Sqm	1	11.00	0.90	0.90	0.90		9.90		
15.1	26.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
28	35		Sqm	1	7.00	0.90	0.90	0.90		6.30		
36.8	48.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
50	61		Sqm	1	11.00	0.90	0.90	0.90		9.90		
63	76		Sqm	1	13.00	0.90	0.90	0.90		11.70		
77	90		Sqm	1	13.00	0.90	0.90	0.90		11.70		
92.7	97.7	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
99	109		Sqm	1	10.00	0.90	0.90	0.90		9.00		
111	120		Sqm	1	9.00	0.90	0.90	0.90		8.10		
122	129		Sqm	1	7.00	0.90	0.90	0.90		6.30		
130.2	137.1	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
139	150		Sqm	1	11.00	0.90	0.90	0.90		9.90		
152	161.3		Sqm	1	9.30	0.90	0.90	0.90		8.37		
		RHS										
		(From West to East)										
0	5	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
7	16		Sqm	1	9.00	0.90	0.90	0.90		8.10		
18	25.4		Sqm	1	7.40	0.90	0.90	0.90		6.66		
25.4	32.7	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
32.7	42.4	New CC Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
42.4	48.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
50	58		Sqm	1	8.00	0.90	0.90	0.90		7.20		
60	71		Sqm	1	11.00	0.90	0.90	0.90		9.90		
73	85		Sqm	1	12.00	0.90	0.90	0.90		10.80		
87.5	94.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
96	106.5		Sqm	1	10.50	0.90	0.90	0.90		9.45		
109.3	121.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
121.4	128.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
128.3	137		Sqm	1	8.70	0.90	0.90	0.90		7.83		
		Muneshwara Layout										
		1st Main Road										
		LHS										
		(From South to North)										
4	15		Sqm	1	11.00	0.90	0.90	0.90		9.90		
18	30.1		Sqm	1	12.10	0.90	0.90	0.90		10.89		
30.1	39.7	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
41	52		Sqm	1	11.00	0.75	0.75	0.75		8.25		
55	67		Sqm	1	12.00	0.75	0.75	0.75		9.00		
67	82	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
82	84.8	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
86	92.1		Sqm	1	6.10	0.90	0.90	0.90		5.49		
92.1	97.3	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
99	108		Sqm	1	9.00	0.90	0.90	0.90		8.10		
110	117.1		Sqm	1	7.10	0.90	0.90	0.90		6.39		
117.1	125.7	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
125.7	128.3		Sqm	1	2.60	0.90	0.90	0.90		2.34		
128.3	143.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
143.3	145.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
145.4	150	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
150	164.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
166	175.5		Sqm	1	9.50	0.90	0.90	0.90		8.55		
175.5	181.6	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
181.6	185.1	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
188	198.7		Sqm	1	10.70	0.90	0.90	0.90		9.63		
198.7	207.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
209	220		Sqm	1	11.00	0.90	0.90	0.90		9.90		
222	234		Sqm	1	12.00	0.90	0.90	0.90		10.80		
236	246		Sqm	1	10.00	0.90	0.90	0.90		9.00		
248	253		Sqm	1	5.00	0.90	0.90	0.90		4.50		
253	258.2	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
260	270		Sqm	1	10.00	0.90	0.90	0.90		9.00		
274	282.2		Sqm	1	8.20	0.90	0.90	0.90		7.38		
282.2	289.5	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
289.5	295.5	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
298	307		Sqm	1	9.00	0.90	0.90	0.90		8.10		
311	319.3		Sqm	1	8.30	0.90	0.90	0.90		7.47		
321.3	325.6	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
325.6	328.7		Sqm	1	3.10	0.90	0.90	0.90		2.79		
328.7	345.2	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
345.2	355	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
355	363		Sqm	1	8.00	0.90	0.90	0.90		7.20		
364	373.1	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		RHS										
		(From South to North)										
0	3	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
5	14		Sqm	1	9.00	0.90	0.90	0.90		8.10		
15	25		Sqm	1	10.00	0.90	0.90	0.90		9.00		
25	36.4	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
36.4	40.7	Road Break	Sqm	1	0.00	0.75	0.75	0.75		0.00		
43	53		Sqm	1	10.00	0.90	0.90	0.90		9.00		
55	64		Sqm	1	9.00	0.90	0.90	0.90		8.10		
67	72	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
72	79.5		Sqm	1	7.50	0.90	0.90	0.90		6.75		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
79.5	85.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
88	99		Sqm	1	11.00	0.90	0.90	0.90		9.90		
101	110		Sqm	1	9.00	0.90	0.90	0.90		8.10		
111	117.1		Sqm	1	6.10	0.90	0.90	0.90		5.49		
117.1	122.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
125	133		Sqm	1	8.00	0.90	0.90	0.90		7.20		
138	145.3		Sqm	1	7.30	0.90	0.90	0.90		6.57		
145.3	149.9	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
154	164.9		Sqm	1	10.90	0.90	0.90	0.90		9.81		
168	176		Sqm	1	8.00	0.90	0.90	0.90		7.20		
178	181.6		Sqm	1	3.60	0.90	0.90	0.90		3.24		
181.6	185.2	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
185.2	198.9	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
200	210.7		Sqm	1	10.70	0.90	0.90	0.90		9.63		
210.7	215.4	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
218	228		Sqm	1	10.00	0.90	0.90	0.90		9.00		
230	243.1		Sqm	1	13.10	0.90	0.90	0.90		11.79		
243.1	248.4	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
250	260		Sqm	1	10.00	0.90	0.90	0.90		9.00		
262	274		Sqm	1	12.00	0.90	0.90	0.90		10.80		
274	278	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
278	285	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
287	295.2		Sqm	1	8.20	0.90	0.90	0.90		7.38		
295.2	310.2	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
310.2	314.2	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
318	327.8		Sqm	1	9.80	0.75	0.75	0.75		7.35		
330	343.3		Sqm	1	13.30	0.75	0.75	0.75		9.98		
343.3	350	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
350	355.1		Sqm	1	5.10	0.90	0.90	0.90		4.59		
355.1	364.1	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
366	372.9		Sqm	1	6.90	0.90	0.90	0.90		6.21		
372.9	381.9	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Tata Nagar										
		5th Main Road										
		LHS										
		(From South to North)										
0	15		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15	29.6		Sqm	1	14.60	1.20	1.20	1.20		17.52		
		RHS										
		(From South to North)										
0	6.8		Sqm	1	6.80	1.20	1.20	1.20		8.16		
6.8	10.6	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
10.6	18.2		Sqm	1	7.60	1.20	1.20	1.20		9.12		
18.2	21.4	No Work	Sqm	1	0.00	1.20	1.20	1.20		0.00		
21.4	30.6	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
30.6	38.8	Road Break	Sqm	1	0.00	1.20	1.20	1.20		0.00		
38.8	44.7		Sqm	1	5.90	1.20	1.20	1.20		7.08		
50	59.7		Sqm	1	9.70	0.90	0.90	0.90		8.73		
59.7	65.9	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
65.9	78	No Work	Sqm	1	0.00	1.20	1.20	1.20		0.00		
78	90.4	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
90.4	100		Sqm	1	9.60	1.20	1.20	1.20		11.52		
103	114.8		Sqm	1	11.80	1.20	1.20	1.20		14.16		
114.8	127.1	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
131	139.5		Sqm	1	8.50	1.20	1.20	1.20		10.20		
139.5	143.2	No Work	Sqm	1	0.00	1.20	1.20	1.20		0.00		
143.2	158.2	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
158.2	164	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
164	172.6		Sqm	1	8.60	1.20	1.20	1.20		10.32		
172.6	188.2	No Work	Sqm	1	0.00	1.20	1.20	1.20		0.00		
196	206.4		Sqm	1	10.40	1.20	1.20	1.20		12.48		
206.4	214.7	No Work	Sqm	1	0.00	1.20	1.20	1.20		0.00		
214.7	226.2	Road Break	Sqm	1	0.00	1.20	1.20	1.20		0.00		
230	238.3		Sqm	1	8.30	1.20	1.20	1.20		9.96		
238.3	250.4	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
253	259.3		Sqm	1	6.30	0.75	0.75	0.75		4.73		
259.3	262.6	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
265	275		Sqm	1	10.00	1.20	1.20	1.20		12.00		
277	287		Sqm	1	10.00	1.20	1.20	1.20		12.00		
289	299.2		Sqm	1	10.20	1.20	1.20	1.20		12.24		
299.2	300.3	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
300.3	308.1		Sqm	1	7.80	1.20	1.20	1.20		9.36		
314	323.1		Sqm	1	9.10	1.20	1.20	1.20		10.92		
323.1	336.4	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
338	345.8		Sqm	1	7.80	0.75	0.75	0.75		5.85		
345.8	348.7		Sqm	1	2.90	0.90	0.90	0.90		2.61		
348.7	360.3	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
360.3	363.2		Sqm	1	2.90	0.75	0.75	0.75		2.17		
363.2	366.8	Bs Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
366.8	368.1		Sqm	1	1.30	0.75	0.75	0.75		0.98		
368.1	372.1		Sqm	1	4.00	1.20	1.20	1.20		4.80		
		1st Main Road										
		LHS										
		(From South to North)										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30.4		Sqm	1	15.40	0.90	0.90	0.90		13.86		
		Tata Nagar										
		1st Cross Road										
		(West to East)										
		(From 4th Main to Rohitha Garden Apartment)										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30.8		Sqm	1	15.80	0.90	0.90	0.90		14.22		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
		LHS										
0	7.9	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
7.9	17.5		Sqm	1	9.60	0.90	0.90	0.90		8.64		
17.5	24.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
26	35		Sqm	1	9.00	0.90	0.90	0.90		8.10		
35	42	New CC	Sqm	1	0.00	0.90	0.90	0.90		0.00		
48	57		Sqm	1	9.00	0.90	0.90	0.90		8.10		
60	72		Sqm	1	12.00	0.90	0.90	0.90		10.80		
74	84		Sqm	1	10.00	0.90	0.90	0.90		9.00		
86	91.2		Sqm	1	5.20	0.90	0.90	0.90		4.68		
91.2	98		Sqm	1	6.80	0.90	0.90	0.90		6.12		
100	108		Sqm	1	8.00	0.75	0.75	0.75		6.00		
110	121		Sqm	1	11.00	0.75	0.75	0.75		8.25		
124	133		Sqm	1	9.00	0.90	0.90	0.90		8.10		
135	145.3		Sqm	1	10.30	0.75	0.75	0.75		7.73		
145.3	151.2	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
154	164.2		Sqm	1	10.20	0.90	0.90	0.90		9.18		
166.2	167.8		Sqm	1	1.60	0.90	0.90	0.90		1.44		
167.8	174.6	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
180	189.6		Sqm	1	9.60	0.90	0.90	0.90		8.64		
189.6	195.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
195.3	201		Sqm	1	5.70	0.90	0.90	0.90		5.13		
201	204.6		Sqm	1	3.60	0.90	0.90	0.90		3.24		
207	216.6		Sqm	1	9.60	0.90	0.90	0.90		8.64		
		(From West to East)										
		LHS										
3	8.8		Sqm	1	5.80	0.90	0.90	0.90		5.22		
8.8	15.1	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
17	25.8		Sqm	1	8.80	0.90	0.90	0.90		7.92		
25.8	40.8	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
40.8	44.8	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
44.8	49.4	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
51	62		Sqm	1	11.00	0.90	0.90	0.90		9.90		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
63	68.5		Sqm	1	5.50	0.90	0.90	0.90		4.95		
8.5	73.4	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
75	87		Sqm	1	12.00	0.90	0.90	0.90		10.80		
88.4	92.6		Sqm	1	4.20	0.90	0.90	0.90		3.78		
92.6	98.2	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
102	112.6		Sqm	1	10.60	0.90	0.90	0.90		9.54		
116	128.3		Sqm	1	12.30	0.90	0.90	0.90		11.07		
130	143.2		Sqm	1	13.20	0.90	0.90	0.90		11.88		
146	158.2		Sqm	1	12.20	0.90	0.90	0.90		10.98		
164	173.2		Sqm	1	9.20	0.90	0.90	0.90		8.28		
176	188.2		Sqm	1	12.20	0.90	0.90	0.90		10.98		
190	203.2		Sqm	1	13.20	0.90	0.90	0.90		11.88		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
		LHS										
3	14.5		Sqm	1	11.50	0.90	0.90	0.90		10.35		
16	28		Sqm	1	12.00	0.90	0.90	0.90		10.80		
30	32.4		Sqm	1	2.40	0.90	0.90	0.90		2.16		
		Balaji Layout										
		Hoysala Commanders Retreat										
		6th Cross Road										
		(From West to East)										
		LHS										
5	13.1		Sqm	1	8.10	0.90	0.90	0.90		7.29		
15	18.8		Sqm	1	3.80	0.90	0.90	0.90		3.42		
18.8	33.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
33.4	39	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
42	47.7		Sqm	1	5.70	0.90	0.90	0.90		5.13		
47.7	56.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
58	65.4		Sqm	1	7.40	0.90	0.90	0.90		6.66		
65.4	73.4	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
73.4	88.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
88.4	91.7	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
92	105		Sqm	1	13.00	0.90	0.90	0.90		11.70		
105	120	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
120	122	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
122	131.1		Sqm	1	9.10	0.90	0.90	0.90		8.19		
131.1	146.6	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		(From West to East)										
		RHS										
8	15		Sqm	1	7.00	0.90	0.90	0.90		6.30		
15	20.2		Sqm	1	5.20	0.90	0.90	0.90		4.68		
20.2	33.7	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
35	42.5		Sqm	1	7.50	0.90	0.90	0.90		6.75		
42.5	55.1	No Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
55.1	64	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
68	79		Sqm	1	11.00	0.90	0.90	0.90		9.90		
82	92.6		Sqm	1	10.60	0.90	0.90	0.90		9.54		
92.6	102.1	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
104	113		Sqm	1	9.00	0.90	0.90	0.90		8.10		
114	120.1		Sqm	1	6.10	0.90	0.90	0.90		5.49		
120.1	129.3	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
132	142.1		Sqm	1	10.10	0.90	0.90	0.90		9.09		
144	157		Sqm	1	13.00	0.90	0.90	0.90		11.70		
159	168		Sqm	1	9.00	0.90	0.90	0.90		8.10		
170	182		Sqm	1	12.00	0.90	0.90	0.90		10.80		
182	192.6		Sqm	1	10.60	0.90	0.90	0.90		9.54		
192.6	201.7	No Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
		LHS										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0	6.6	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
6.6	68.9	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
70	76.2		Sqm	1	6.20	0.90	0.90	0.90		5.58		
76.2	118	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
118	127.2	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
130	143		Sqm	1	13.00	0.90	0.90	0.90		11.70		
145	156.4		Sqm	1	11.40	0.90	0.90	0.90		10.26		
156.4	163.7	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
166	178.7		Sqm	1	12.70	0.90	0.90	0.90		11.43		
183	193.7		Sqm	1	10.70	0.90	0.90	0.90		9.63		
195	203.5		Sqm	1	8.50	0.90	0.90	0.90		7.65		
203.5	212.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
215	227.2		Sqm	1	12.20	0.90	0.90	0.90		10.98		
231	242.3		Sqm	1	11.30	0.90	0.90	0.90		10.17		
242.3	248.3	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
253	263.3		Sqm	1	10.30	0.90	0.90	0.90		9.27		
266	273.5		Sqm	1	7.50	0.90	0.90	0.90		6.75		
273.5	278.3	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
280	291		Sqm	1	11.00	0.90	0.90	0.90		9.90		
292	298.6		Sqm	1	6.60	0.90	0.90	0.90		5.94		
		1st Cross Road										
		(From East to West)										
		LHS										
0	5.4	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
10	18.9		Sqm	1	8.90	0.75	0.75	0.75		6.68		
20.4	28.2		Sqm	1	7.80	0.75	0.75	0.75		5.85		
28.2	41.1	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
42	52.1		Sqm	1	10.10	0.90	0.90	0.90		9.09		
		(From East to West)										
		RHS										
0	7.1		Sqm	1	7.10	0.75	0.75	0.75		5.33		
7.1	22.1	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
22.1	37.1	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
37.1	42.8	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
42.8	49.3		Sqm	1	6.50	0.75	0.75	0.75		4.88		
		2nd Cross Road										
		(From East to West)										
		LHS										
3	13		Sqm	1	10.00	0.90	0.90	0.90		9.00		
15	16.4		Sqm	1	1.40	0.90	0.90	0.90		1.26		
16.4	28.8	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
30	42		Sqm	1	12.00	0.90	0.90	0.90		10.80		
43.8	52.2		Sqm	1	8.40	0.90	0.90	0.90		7.56		
		RHS										
2	9.3		Sqm	1	7.30	0.90	0.90	0.90		6.57		
12	16.6		Sqm	1	4.60	0.90	0.90	0.90		4.14		
16.6	21.7	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
22	30.1		Sqm	1	8.10	0.90	0.90	0.90		7.29		
30.1	52.2	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Culvert Slab										
		Devi Nagar										
		6th A Cross Road										
			Sqm	1	5.50	1.50	1.50	1.50		8.25		
		5th Cross Road										
			Sqm	1	6.70	1.50	1.20	1.35		9.05		
		4th Cross Road										
			Sqm	1	5.50	1.50	1.50	1.50		8.25		
		Nayana Vegetable Road										
			Sqm	1	4.20	1.50	1.50	1.50		6.30		
		Muneshwara Layout										
		3rd Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
			Sqm	1	4.90	1.50	1.50	1.50		7.35		
		4th Cross Road										
			Sqm	1	3.70	1.50	1.50	1.50		5.55		
			Sqm	1	4.90	1.50	1.50	1.50		7.35		
		5th Cross Road										
			Sqm	1	3.60	1.50	1.50	1.50		5.40		
			Sqm	1	5.50	1.50	1.50	1.50		8.25		
			Sqm	1	3.60	1.50	1.50	1.50		5.40		
		6th Cross Road										
			Sqm	1	4.90	1.50	1.50	1.50		7.35		
		8th Cross Road										
			Sqm	1	3.70	1.50	1.50	1.50		5.55		
		Ward No 10										
		BLOOM FIELD GARDEN										
		Main Road										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
		LHS										
0	100	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
105	113		Sqm	1	8.00	0.75	0.75	0.75		6.00		
117	124		Sqm	1	7.00	0.75	0.75	0.75		5.25		
130	136		Sqm	1	6.00	0.75	0.75	0.75		4.50		
140	145		Sqm	1	5.00	0.75	0.75	0.75		3.75		
149	154.5		Sqm	1	5.50	0.75	0.75	0.75		4.13		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
		LHS										
0	55.4	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
60	68		Sqm	1	8.00	0.75	0.75	0.75		6.00		
74	80		Sqm	1	6.00	0.75	0.75	0.75		4.50		
86	91		Sqm	1	5.00	0.75	0.75	0.75		3.75		
101	106		Sqm	1	5.00	0.75	0.75	0.75		3.75		
111	115		Sqm	1	4.00	0.75	0.75	0.75		3.00		
116.2	228.1	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
233	238		Sqm	1	5.00	0.75	0.75	0.75		3.75		
240	244		Sqm	1	4.00	0.75	0.75	0.75		3.00		
245.1	255.7	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
260	265		Sqm	1	5.00	0.75	0.75	0.75		3.75		
270	274		Sqm	1	4.00	0.75	0.75	0.75		3.00		
283	287.9		Sqm	1	4.90	0.75	0.75	0.75		3.67		
		RHS										
0	119.9	No work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
119.9	120.5		Sqm	1	0.60	0.75	0.75	0.75		0.45		
120.5	204.8	No work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
206	210		Sqm	1	4.00	0.75	0.75	0.75		3.00		
213	233.5	No work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
235	236		Sqm	1	1.00	0.60	0.60	0.60		0.60		
237	241.8	No work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
243	245.9		Sqm	1	2.90	0.60	0.60	0.60		1.74		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
		RHS										
0	2.1		Sqm	1	2.10	0.75	0.75	0.75		1.58		
5	8		Sqm	1	3.00	0.90	0.90	0.90		2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
9.6	13.8	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
14	16		Sqm	1	2.00	0.90	0.90	0.90		1.80		
16.4	51.3	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
52	55		Sqm	1	3.00	0.75	0.75	0.75		2.25		
58.1	62	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
62	63.7		Sqm	1	1.70	0.90	0.90	0.90		1.53		
63.7	69.1	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
70	72		Sqm	1	2.00	0.75	0.75	0.75		1.50		
77.6	85.3	Road Break	Sqm	1	0.00	0.00	0.00	0.00		0.00		
88	91		Sqm	1	3.00	0.75	0.75	0.75		2.25		
96	97.7		Sqm	1	1.70	0.75	0.75	0.75		1.28		
		3rd Cross Road										
		(From South to North)										
		LHS										
0	74.2	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
75	80		Sqm	1	5.00	0.75	0.75	0.75		3.75		
83	87.2	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
88	90		Sqm	1	2.00	0.75	0.75	0.75		1.50		
93.8	152	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
153	156		Sqm	1	3.00	0.75	0.75	0.75		2.25		
159.4	160.7	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
163	166		Sqm	1	3.00	0.75	0.75	0.75		2.25		
174	179.2		Sqm	1	5.20	0.75	0.75	0.75		3.90		
		RHS										
0	5.7	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
7	11		Sqm	1	4.00	0.75	0.75	0.75		3.00		
14.1	77.8	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
79	83		Sqm	1	4.00	0.75	0.75	0.75		3.00		
90	92		Sqm	1	2.00	0.75	0.75	0.75		1.50		
100.4	124	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
126	130		Sqm	1	4.00	0.75	0.75	0.75		3.00		
132.8	135.3	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
137	140		Sqm	1	3.00	0.75	0.75	0.75		2.25		
144.1	147.2	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
149	152		Sqm	1	3.00	0.75	0.75	0.75		2.25		
157	160		Sqm	1	3.00	0.75	0.75	0.75		2.25		
163	164.2	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
166	170		Sqm	1	4.00	0.75	0.75	0.75		3.00		
173	180.2		Sqm	1	7.20	0.75	0.75	0.75		5.40		
		5th Cross Road										
		(From North to South)										
		LHS										
0	21.3	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
22	25		Sqm	1	3.00	0.75	0.75	0.75		2.25		
27.1	82.5	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
85	90		Sqm	1	5.00	0.75	0.75	0.75		3.75		
93	96		Sqm	1	3.00	0.75	0.75	0.75		2.25		
110	118		Sqm	1	8.00	0.75	0.75	0.75		6.00		
121	131		Sqm	1	10.00	0.75	0.75	0.75		7.50		
134	139		Sqm	1	5.00	0.75	0.75	0.75		3.75		
155	160		Sqm	1	5.00	0.75	0.75	0.75		3.75		
									Total Executed Quantity	**2154.02**	**271.37**	**584536.00**
									Tender Quantity	**3181.31**		
Item no.03		**Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3)**										
		Ward No 07										
		For Drain										
		VeerannaPalya										
		6th A Cross Road										
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	114.50		Cum	1	9.50	1.10	1.10	1.10	0.90	9.41		
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	114.70		Cum	1	9.70	1.10	1.10	1.10	0.90	9.60		
		6th B Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
45.00	60.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
120.00	121.80		Cum	1	1.80	0.95	0.95	0.95	0.90	1.54		
		6th Cross Road										
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30.00	33.60		Cum	1	3.60	0.95	0.95	0.95	0.90	3.08		
33.60	39.20	Road Break	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
39.20	54.20		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
54.20	69.20		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
69.20	78.00		Cum	1	8.80	0.95	0.95	0.95	0.90	7.52		
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	112.10		Cum	1	7.10	1.10	1.10	1.10	0.90	7.03		
		For Culvert										
		Muniswami Gowda Layout										
		2nd Cross Road										
			Cum	1	5.80	1.70	1.70	1.70	0.95	9.37		
		Drain Desilt										
		2nd Cross Road Sunshine apartment										
		(From North to South)										
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	67.20		Cum	1	7.20	0.45	0.45	0.45	0.45	1.46		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Muniswamy Gowda Layout										
		1st A K.V.J Road										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	34.20		Cum	1	4.20	0.45	0.45	0.45	0.45	0.85		
		RHS										
		(From West to East)										
0.00	20.80	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
20.80	29.10		Cum	1	8.30	0.45	0.45	0.45	0.45	1.68		
29.10	34.20		Cum	1	5.10	0.45	0.45	0.45	0.45	1.03		
		2nd A Cross Road										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	19.70		Cum	1	4.70	0.45	0.45	0.45	0.45	0.95		
19.70	29.30		Cum	1	9.60	0.45	0.45	0.45	0.45	1.94		
29.30	34.10		Cum	1	4.80	0.45	0.45	0.45	0.45	0.97		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	34.00		Cum	1	4.00	0.45	0.45	0.45	0.45	0.81		
		3rd Cross Near Vidya Niketan School Road										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	39.50		Cum	1	9.50	0.45	0.45	0.45	0.45	1.92		
39.50	46.30	Culvert	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
46.30	61.30		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
61.30	75.70		Cum	1	14.40	0.45	0.45	0.45	0.45	2.92		
75.70	81.90	Culvert	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
81.90	96.90		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
96.90	111.50		Cum	1	14.60	0.45	0.45	0.45	0.45	2.96		
111.50	118.50	Culvert	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
118.50	133.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
133.50	135.30		Cum	1	1.80	0.45	0.45	0.45	0.45	0.36		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
		Culvert Desilt										
		Muniswamy Gowda Layout										
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
			Cum	1	6.00	1.40	1.40	1.40	0.45	3.78		
		Chiranjeevi Layout										
		3rd Cross Road										
			Cum	1	4.80	0.80	0.80	0.80	0.45	1.73		
		3rd Cross Near Vidya Niketan School Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
			Cum	1	5.60	0.80	0.80	0.80	0.45	2.02		
		Veerannapalya										
		6th A Cross Road										
			Cum	1	6.20	1.40	1.40	1.40	0.45	3.91		
		6th B Cross Road										
			Cum	1	5.00	1.40	1.40	1.40	0.45	3.15		
		6th Cross Road										
			Cum	1	7.70	1.40	1.40	1.40	0.45	4.85		
		Ward No 08										
		For Drain										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		LHS										
		(From West To East)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.86	14.19		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.88	14.52		
120.00	135.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
135.00	139.00		Cum	1	4.00	1.10	1.10	1.10	0.90	3.96		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
120.00	130.70		Cum	1	10.70	1.10	1.10	1.10	0.90	10.59		
130.70	139.00	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
139.00	154.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
154.00	169.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
169.00	184.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
184.00	199.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
199.00	214.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
214.00	229.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
229.00	232.80		Cum	1	3.80	1.10	1.10	1.10	0.90	3.76		
232.80	240.20	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
240.20	255.20		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
255.20	270.20		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
270.20	279.00		Cum	1	8.80	1.10	1.10	1.10	0.80	7.74		
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	22.70		Cum	1	7.70	1.10	1.10	1.10	0.90	7.62		
22.70	30.10	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
30.10	45.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.10	60.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.10	75.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.10	90.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.10	105.10		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
105.10	120.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
120.10	132.20		Cum	1	12.10	1.10	1.10	1.10	0.90	11.98		
132.20	139.90	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
139.90	154.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
154.90	169.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
169.90	184.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
184.90	199.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
199.90	214.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
214.90	229.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
229.90	244.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
244.90	259.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
259.90	274.90		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
274.90	278.10		Cum	1	3.20	1.10	1.10	1.10	0.90	3.17		
		Balaji Layout										
		7th Cross Road										
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.75	12.38		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
60.00	67.80		Cum	1	7.80	1.10	1.10	1.10	0.90	7.72		
		(From West To East)										
		RHS										
0.00	12.50	No Work	Cum	1	0.00	0.95	0.95	0.95	0.00	0.00		
12.50	27.50		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
27.50	42.50		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
42.50	57.50		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
57.50	72.50		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
72.50	74.10		Cum	1	1.60	0.95	0.95	0.95	0.80	1.22		
74.10	89.10		Cum	1	15.00	1.10	1.10	1.10	0.85	14.03		
89.10	104.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
104.10	119.10		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
119.10	121.10		Cum	1	2.00	1.10	1.10	1.10	0.90	1.98		
		#560 Sri HariKrishna										
		LHS										
		(North To South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	101.00		Cum	1	11.00	1.10	1.10	1.10	0.90	10.89		
		RHS										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	103.00		Cum	1	13.00	1.10	1.10	1.10	0.90	12.87		
		Balaji Layout										
		Msc Provision Store Road										
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	79.00		Cum	1	4.00	1.10	1.10	1.10	0.90	3.96		
		1st Cross Road										
		(West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	59.10		Cum	1	14.10	1.10	1.10	1.10	0.90	13.96		
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	59.50		Cum	1	14.50	1.10	1.10	1.10	0.90	14.36		
		For Culvert										
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		RHS										
			Cum	1	8.30	1.40	1.40	1.40	0.80	9.30		
			Cum	1	7.40	1.70	1.70	1.70	0.75	9.44		
		LHS										
			Cum	1	7.40	1.70	1.70	1.70	0.75	9.44		
			Cum	1	7.70	1.70	1.70	1.70	0.75	9.82		
		2nd Main Road Dead End										
			Cum	1	6.50	1.70	1.70	1.70	0.75	8.29		
			Cum	1	5.60	1.70	1.70	1.70	0.75	7.14		
		Ward No 08										
		For Drain										
		AMCO Layout										
		LHS										
		(N-S)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
120.00	135.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
135.00	150.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
150.00	165.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
165.00	180.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
180.00	195.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
195.00	210.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
210.00	225.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
225.00	240.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
240.00	255.00		Cum	1	15.00	1.10	1.10	1.10	1.20	19.80		
255.00	270.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
270.00	285.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
285.00	290.10		Cum	1	5.10	1.10	1.10	1.10	0.90	5.05		
		For Culvert										
		Sarovara Layout										
		1st Main Road										
			Cum	1	6.70	1.40	1.40	1.40	0.95	8.91		
		Cross Road	Cum	1	5.10	1.40	1.40	1.40	0.95	6.78		
		Drain Desilt										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0	6.6	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
6.6	21.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
21.6	36.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
36.6	51.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
51.6	66.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
66.6	81.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
76.2	91.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
91.2	106.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
106.2	118		Cum	1	11.80	0.60	0.60	0.60	0.50	3.54		
118	127.2	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
127.2	142.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
142.2	156.4		Cum	1	14.20	0.60	0.60	0.60	0.50	4.26		
156.4	163.7	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
163.7	178.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
178.7	193.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
193.7	203.5		Cum	1	9.80	0.60	0.60	0.60	0.50	2.94		
203.5	212.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
212.3	227.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
227.3	240.7		Cum	1	13.40	0.60	0.60	0.60	0.50	4.02		
240.7	248.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
248.3	263.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
263.3	273.5		Cum	1	10.20	0.60	0.60	0.60	0.50	3.06		
		1st Cross Road										
		(From East to West)										
		LHS										
0	15		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15	30		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30	45		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45	52.1		Cum	1	7.10	0.45	0.45	0.45	0.45	1.44		
		(From East to West)										
		RHS										
0	15		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15	30		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30	45		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45	49.3		Cum	1	4.30	0.45	0.45	0.45	0.45	0.87		
		2nd Cross Road										
		(From East to West)										
		LHS										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	16.4		Cum	1	1.40	0.60	0.60	0.60	0.50	0.42		
16.4	28.8	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
28.8	43.8		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
43.8	52.2		Cum	1	8.40	0.60	0.60	0.60	0.50	2.52		
		RHS										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30.1		Cum	1	15.10	0.60	0.60	0.60	0.50	4.53		
30.1	52.2	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
		Tata Nagar										
		Kote Layout										
		opposite Road										
		LHS										
		(From West to East)										
0	7.9		Cum	1	7.90	0.60	0.60	0.60	0.50	2.37		
7.9	17.5		Cum	1	9.60	0.60	0.60	0.60	0.50	2.88		
17.5	24.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
24.3	39.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
39.3	54.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
54.3	69.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
69.3	84.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
84.3	99.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
99.3	114.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
114.3	129.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
129.3	144.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
144.3	145.3		Cum	1	1.00	0.60	0.60	0.60	0.50	0.30		
145.3	151.2	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
151.2	166.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
166.2	167.8		Cum	1	1.60	0.60	0.60	0.60	0.50	0.48		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
167.8	174.6	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
174.6	189.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
189.6	204.6		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
204.6	216.6		Cum	1	12.00	0.60	0.60	0.60	0.50	3.60		
		LHS										
		(From East to West)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	44.8		Cum	1	14.80	0.60	0.60	0.60	0.50	4.44		
44.8	49.4	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
49.4	64.4		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
64.4	68.5		Cum	1	4.10	0.60	0.60	0.60	0.50	1.23		
68.5	73.4	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
73.4	88.4		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
88.4	92.6		Cum	1	4.20	0.60	0.60	0.60	0.50	1.26		
92.6	98.2	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
98.2	113.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
113.2	128.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
128.2	143.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
143.2	158.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
158.2	173.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
173.2	188.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
188.2	203.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
		Tata Nagar										
		1st Cross Road										
		Ketering)										
		RHS										
		(From West to East)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	30.8		Cum	1	0.80	0.60	0.60	0.60	0.50	0.24		
		Balaji Layout										
		6th Cross Road										
		Hoysala Commanders Retreat										
		(From West to East)										
		LHS										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	33.4		Cum	1	3.40	0.60	0.60	0.60	0.50	1.02		
33.4	39	Culvert	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
39	54		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
54	69		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
69	73.7	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
73.7	88.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
88.7	103.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
103.7	118.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
118.7	133.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
133.7	146.6		Cum	1	12.90	0.60	0.60	0.60	0.50	3.87		
		RHS										
		(From West to East)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	45		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45	55.1		Cum	1	10.10	0.60	0.60	0.60	0.50	3.03		
55.1	64	Culvert	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
64	79		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
79	94		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
94	109		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
109	124		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
124	139		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
139	154		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
154	169		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
169	184		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
184	199		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
199	201.7		Cum	1	2.70	0.60	0.60	0.60	0.50	0.81		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
		LHS										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	32.4		Cum	1	2.40	0.60	0.60	0.60	0.50	0.72		
		Tata Nagar										
		5th Main Road										
		LHS										
		(From South to North)										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
15	29.6		Cum	1	14.60	0.90	0.90	0.90	0.50	6.57		
		RHS										
		(From South to North)										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
15	18.2		Cum	1	3.20	0.90	0.90	0.90	0.50	1.44		
18.2	21.4	No Work	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
21.4	30.6		Cum	1	9.20	0.90	0.90	0.90	0.50	4.14		
30.6	38.8	Road Break	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
38.8	44.7		Cum	1	5.90	0.90	0.90	0.90	0.50	2.66		
44.7	59.7		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
59.7	65.9		Cum	1	6.20	0.90	0.90	0.90	0.50	2.79		
65.9	78	No Work	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
78	90.4		Cum	1	12.40	0.90	0.90	0.90	0.50	5.58		
90.4	105.4		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
105.4	114.8		Cum	1	9.40	0.90	0.90	0.90	0.50	4.23		
114.8	127.1		Cum	1	12.30	0.90	0.90	0.90	0.50	5.54		
127.1	139.5		Cum	1	12.40	0.90	0.90	0.90	0.50	5.58		
139.5	143.2	No Work	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
143.2	158.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
158.2	164		Cum	1	5.80	0.90	0.90	0.90	0.50	2.61		
164	172.6		Cum	1	8.60	0.90	0.90	0.90	0.50	3.87		
172.6	188.2	No Work	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
188.2	206.4		Cum	1	18.20	0.90	0.90	0.90	0.50	8.19		
206.4	214.7	No Work	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
214.7	226.2	Road Break	Cum	1	0.00	0.90	0.90	0.90	0.50	0.00		
226.2	241.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
241.2	256.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
256.2	271.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
271.2	286.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
286.2	301.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
301.2	316.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
316.2	331.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
331.2	346.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
346.2	361.2		Cum	1	15.00	0.90	0.90	0.90	0.50	6.75		
361.2	372.1		Cum	1	10.90	0.90	0.90	0.90	0.50	4.91		
		1st Main Road										
		LHS										
		(From South to North)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30.4		Cum	1	15.40	0.60	0.60	0.60	0.50	4.62		
		RHS										
		(From South to North)										
0	14.5		Cum	1	14.50	0.60	0.60	0.60	0.50	4.35		
		Tata Nagar										
		1st Cross Road										
		(West to East)										
		Garden Apartment)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30.8		Cum	1	15.80	0.60	0.60	0.60	0.50	4.74		
		Layout)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		6th Cross Road										
		(From East to West)										
		LHS										
0	9.2	No Work	Cum	1	0.00	0.45	0.45	0.45	0.50	0.00		
9.2	24.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
24.2	39.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
39.2	54.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
54.2	69.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
69.2	84.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
84.2	99.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
99.2	114.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
114.2	129.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
129.2	144.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
144.2	159.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
159.2	160		Cum	1	0.80	0.45	0.45	0.45	0.50	0.18		
		RHS										
		(From East to West)										
0	15		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
15	18.3		Cum	1	3.30	0.45	0.45	0.45	0.50	0.74		
18.3	26.2	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.50	0.00		
26.2	41.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
41.2	56.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
56.2	68.4		Cum	1	12.20	0.45	0.45	0.45	0.50	2.75		
68.4	72.4	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.50	0.00		
72.4	87.4		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
87.4	102.4		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
102.4	117.4		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
117.4	121		Cum	1	3.60	0.45	0.45	0.45	0.50	0.81		
121	125.2	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.50	0.00		
125.2	140.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
140.2	155.2		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
155.2	163.2		Cum	1	8.00	0.45	0.45	0.45	0.50	1.80		
		6th A Cross Road										
		(From North to South)										
		LHS										
0	15		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
15	30		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
30	45		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
45	60		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
60	75		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
75	90		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
90	105		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
105	120		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
120	135		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
135	142.2		Cum	1	7.20	0.45	0.45	0.45	0.50	1.62		
		RHS										
		(From North to South)										
0	15		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
15	26.2		Cum	1	11.20	0.45	0.45	0.45	0.50	2.52		
26.2	44	No Work	Cum	1	0.00	0.45	0.45	0.45	0.50	0.00		
44	59		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
59	74		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
74	89		Cum	1	15.00	0.45	0.45	0.45	0.50	3.38		
89	104.5		Cum	1	15.50	0.45	0.45	0.45	0.50	3.49		
		Devi Nagar Main Road										
		(From West to East)										
		LHS										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	36.8		Cum	1	6.80	0.60	0.60	0.60	0.50	2.04		
36.8	48.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
48.3	63.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
63.3	78.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
78.3	92.7		Cum	1	14.40	0.60	0.60	0.60	0.50	4.32		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
92.7	97.7	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
97.7	112.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
112.7	127.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
127.7	130.2		Cum	1	2.50	0.60	0.60	0.60	0.50	0.75		
130.2	137.1	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
137.1	152.1		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
152.1	161.3		Cum	1	9.20	0.60	0.60	0.60	0.50	2.76		
		RHS										
		(From West to East)										
0	5	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
5	20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
20	25.4		Cum	1	5.40	0.60	0.60	0.60	0.50	1.62		
25.4	32.7	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
32.7	42.4		Cum	1	9.70	0.60	0.60	0.60	0.50	2.91		
42.4	48.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
48.3	63.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
63.3	78.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
78.3	87.5		Cum	1	9.20	0.60	0.60	0.60	0.50	2.76		
87.5	94.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
94.3	109.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
109.3	121.4		Cum	1	12.10	0.60	0.60	0.60	0.50	3.63		
121.4	128.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
128.3	137		Cum	1	8.70	0.60	0.60	0.60	0.50	2.61		
		Muneshwara Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0	15		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15	30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30	45		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45	60		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60	75		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75	90		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90	92.1		Cum	1	2.10	0.60	0.60	0.60	0.50	0.63		
92.1	97.3	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
97.3	112.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
112.3	117.1		Cum	1	4.80	0.60	0.60	0.60	0.50	1.44		
117.1	125.7	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
125.7	140.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
140.7	145.4		Cum	1	4.70	0.60	0.60	0.60	0.50	1.41		
145.4	150	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
150	165		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
165	180		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
180	181.6		Cum	1	1.60	0.60	0.60	0.60	0.50	0.48		
181.6	185.1	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
185.1	200.1		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
200.1	215.1		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
215.1	230.1		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
230.1	245.1		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
245.1	253		Cum	1	7.90	0.60	0.60	0.60	0.50	2.37		
253	258.2	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
258.2	273.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
273.2	288.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
288.2	289.5		Cum	1	1.30	0.60	0.60	0.60	0.50	0.39		
289.5	295.5	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
295.5	310.5		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
310.5	321.3		Cum	1	10.80	0.60	0.60	0.60	0.50	3.24		
321.3	325.6	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
325.6	328.7		Cum	1	3.10	0.60	0.60	0.60	0.50	0.93		
328.7	345.2	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
345.2	360.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
360.2	373.1		Cum	1	12.90	0.60	0.60	0.60	0.50	3.87		
		RHS										
		(From South to North)										
0	3	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
3	18		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
18	33		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
33	36.4		Cum	1	3.40	0.60	0.60	0.60	0.50	1.02		
36.4	40.7	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
40.7	55.7		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
55.7	67		Cum	1	11.30	0.60	0.60	0.60	0.50	3.39		
67	72	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
72	87		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
87	102		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
102	117.1		Cum	1	15.10	0.60	0.60	0.60	0.50	4.53		
117.1	122.3	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
122.3	137.3		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
137.3	145.3		Cum	1	8.00	0.60	0.60	0.60	0.50	2.40		
145.3	149.9	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
149.9	164.9		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
164.9	179.9		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
179.9	181.6		Cum	1	1.70	0.60	0.60	0.60	0.50	0.51		
181.6	185.2	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
185.2	200.2		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
200.2	210.7		Cum	1	10.50	0.60	0.60	0.60	0.50	3.15		
210.7	215.4	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
215.4	230.4		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
230.4	243.1		Cum	1	12.70	0.60	0.60	0.60	0.50	3.81		
243.1	248.4	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
248.4	263.4		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
263.4	278		Cum	1	14.60	0.60	0.60	0.60	0.50	4.38		
278	285	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
285	300		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
300	315		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
315	330		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
330	343.3		Cum	1	13.30	0.60	0.60	0.60	0.50	3.99		
343.3	350	No Work	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
350	365		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
365	380		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
380	381.9		Cum	1	1.90	0.60	0.60	0.60	0.50	0.57		
		Culvert Desilt										
		Devi Nagar										
		6th A Cross Road										
			Cum	1	5.50	1.10	1.10	1.10	0.45	2.72		
		5th Cross Road										
			Cum	1	6.70	1.10	1.10	1.10	0.45	3.32		
		4th Cross Road										
			Cum	1	5.50	1.10	1.10	1.10	0.45	2.72		
		Nayana Vegetable Road										
			Cum	1	4.20	1.10	1.10	1.10	0.45	2.08		
		Muneshwara Layout										
		3rd Cross Road										
			Cum	1	4.90	1.10	1.10	1.10	0.45	2.43		
		4th Cross Road										
			Cum	1	3.70	1.10	1.10	1.10	0.45	1.83		
			Cum	1	4.90	1.10	1.10	1.10	0.45	2.43		
		5th Cross Road										
			Cum	1	3.60	1.10	1.10	1.10	0.45	1.78		
			Cum	1	5.50	1.10	1.10	1.10	0.45	2.72		
			Cum	1	3.60	1.10	1.10	1.10	0.45	1.78		
		6th Cross Road										
			Cum	1	4.90	1.10	1.10	1.10	0.45	2.43		
		8th Cross Road										
			Cum	1	3.70	1.10	1.10	1.10	0.45	1.83		
		Ward No 10										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		For Drain										
		2nd Cross Road (From house										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
45.00	58.10		Cum	1	13.10	0.95	0.95	0.95	0.90	11.20		
58.10	60.00	NO WORK	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
120.00	135.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
135.00	150.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
150.00	165.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
165.00	169.90		Cum	1	4.90	0.95	0.95	0.95	0.90	4.19		
169.90	172.00	NO WORK	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
172.00	187.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
187.00	202.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
202.00	217.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
217.00	232.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
232.00	247.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
247.00	254.00		Cum	1	7.00	0.95	0.95	0.95	0.90	5.99		
202.00	262.10	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
262.10	277.10		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
277.10	292.10		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
292.10	302.20		Cum	1	10.10	0.95	0.95	0.95	0.90	8.64		
		RHS										
		(From Vidyaranyapura Main Road)										
		From South to North										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15.00	45.00		Cum	1	30.00	0.95	0.95	0.95	0.90	25.65		
45.00	75.00		Cum	1	30.00	0.95	0.95	0.95	0.90	25.65		
75.00	76.30		Cum	1	1.30	0.95	0.95	0.95	0.90	1.11		
76.30	91.30		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
91.30	106.30		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
106.30	121.30		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
121.30	122.10		Cum	1	0.80	0.95	0.95	0.95	0.90	0.68		
122.10	124.70	No Work	Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
124.70	139.70		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
139.70	154.70		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
154.70	169.70		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
169.70	184.00		Cum	1	14.30	0.95	0.95	0.95	0.90	12.23		
184.70	193.00		Cum	1	0.00	0.95	0.95	0.95	0.90	0.00		
		Chamundeswari Layout										
		3rd Cross Road (Shree Nagamma Devasthana)										
		(From East to West)										
		RHS										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
45.00	60.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
120.00	135.00		Cum	1	15.00	0.95	0.95	0.95	0.90	12.83		
135.00	136.40		Cum	1	1.40	0.95	0.95	0.95	0.90	1.20		
		Doddabomsandra										
		Gas Godown Road										
0.00	6.80		Cum	1	6.80	0.95	0.95	0.95	0.90	5.81		
		For Culvert										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		BEL 2nd Block										
		5th Cross Road										
			Cum	1	7.40	1.70	1.70	1.70	0.95	11.95		
		Chamundeshwari Layout										
		6th Cross Road										
			Cum	1	5.50	1.40	1.40	1.40	0.80	6.16		
		7th Cross Road										
			Cum	1	6.10	1.40	1.40	1.40	0.80	6.83		
		8th Cross Road										
			Cum	1	5.60	1.40	1.40	1.40	0.80	6.27		
		9th Cross Road										
			Cum	1	6.10	1.40	1.40	1.40	0.80	6.83		
		10th Cross Road										
			Cum	1	5.60	1.40	1.40	1.40	0.80	6.27		
		Gas godown Road										
			Cum	1	7.30	1.40	1.40	1.40	0.95	9.71		
			Cum	1	5.50	1.40	1.40	1.40	0.95	7.32		
		Patel Gopalappa Layout										
		7th Cross road	Cum	1	7.20	1.40	1.40	1.40	0.95	9.58		
		Near 7th Cross Road	Cum	1	6.50	2.00	2.00	2.00	1.85	24.05		
		Muneshwara layout										
		1st Main road	Cum	1	5.50	1.40	1.40	1.40	0.95	7.32		
		Drain Desilt										
		RAMMANA GARDEN										
		1st Main road C Ramya layout										
		Ranachandra pura main road to house no.41A										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	165.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
165.00	180.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
180.00	195.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
195.00	200.20		Cum	1	5.20	0.60	0.60	0.60	0.50	1.56		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	165.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
165.00	180.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
180.00	195.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
195.00	200.20		Cum	1	5.20	0.60	0.60	0.60	0.50	1.56		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Chamundeshwari Layout										
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	26.20		Cum	1	11.20	0.60	0.60	0.60	0.50	3.36		
26.20	31.50	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
31.50	46.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
46.50	57.40		Cum	1	10.90	0.60	0.60	0.60	0.50	3.27		
57.40	64.80	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
64.80	79.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
79.80	90.10		Cum	1	10.30	0.60	0.60	0.60	0.50	3.09		
90.10	96.00	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
96.00	111.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
111.00	122.20		Cum	1	11.20	0.60	0.60	0.60	0.50	3.36		
122.20	128.50	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
128.50	143.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
143.50	158.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
158.50	159.80		Cum	1	1.30	0.60	0.60	0.60	0.50	0.39		
159.80	166.70	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
166.70	181.70		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
181.70	196.70		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
196.70	203.10		Cum	1	6.40	0.60	0.60	0.60	0.50	1.92		
203.10	210.40	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
210.40	223.10		Cum	1	12.70	0.60	0.60	0.60	0.50	3.81		
223.10	235.90		Cum	1	12.80	0.60	0.60	0.60	0.50	3.84		
235.90	242.20	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
242.20	257.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
257.20	267.90		Cum	1	10.70	0.60	0.60	0.60	0.50	3.21		
267.90	275.00	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
275.00	290.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
290.00	300.00		Cum	1	10.00	0.60	0.60	0.60	0.50	3.00		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	165.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
165.00	180.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
180.00	195.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
195.00	203.00		Cum	1	8.00	0.60	0.60	0.60	0.50	2.40		
203.00	210.40	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
210.40	225.40		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
225.40	235.90		Cum	1	10.50	0.60	0.60	0.60	0.50	3.15		
235.90	242.20	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
242.20	257.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
257.20	268.50		Cum	1	11.30	0.60	0.60	0.60	0.50	3.39		
268.50	275.00	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
275.00	290.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
290.00	300.10		Cum	1	10.10	0.60	0.60	0.60	0.50	3.03		
		Rammana garden Main road										
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	65.50		Cum	1	5.50	0.60	0.60	0.60	0.50	1.65		
65.50	72.50	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
72.50	87.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
87.50	102.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
102.50	117.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
117.50	132.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
132.50	147.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
147.50	162.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
162.50	177.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
177.50	192.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
192.50	207.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
207.50	223.20		Cum	1	15.70	0.60	0.60	0.60	0.50	4.71		
		RHS										
		From house no :43 to 93										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	26.80		Cum	1	11.80	0.60	0.60	0.60	0.50	3.54		
26.80	36.90	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
36.90	51.90		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
51.90	65.50		Cum	1	13.60	0.60	0.60	0.60	0.50	4.08		
65.50	72.50	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
72.50	87.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
87.50	102.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
102.50	117.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
117.50	132.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
132.50	147.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
147.50	162.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
162.50	177.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
177.50	192.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
192.50	207.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
207.50	223.20		Cum	1	15.70	0.60	0.60	0.60	0.50	4.71		
		Samashana Road										
		2nd main Road										
		(From East to West)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	139.20		Cum	1	4.20	0.60	0.60	0.60	0.50	1.26		
		RHS										
0.00	14.70		Cum	1	14.70	0.60	0.60	0.60	0.50	4.41		
14.70	22.40	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
22.40	37.40		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
37.40	51.50		Cum	1	14.10	0.60	0.60	0.60	0.50	4.23		
51.50	58.80	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
58.80	73.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
73.80	84.80		Cum	1	11.00	0.60	0.60	0.60	0.50	3.30		
84.80	92.70	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
92.70	107.70		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
107.70	122.70		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
122.70	138.50		Cum	1	15.80	0.60	0.60	0.60	0.50	4.74		
		3rd Cross Road										
		(From South to North)										
		LHS										
0.00	15.50		Cum	1	15.50	0.60	0.60	0.60	0.50	4.65		
15.50	30.00		Cum	1	14.50	0.60	0.60	0.60	0.50	4.35		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	72.00		Cum	1	12.00	0.60	0.60	0.60	0.50	3.60		
72.00	79.30	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
79.30	94.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
94.30	109.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
109.30	124.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
124.30	139.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
139.30	154.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
		RHS										
0.00	15.50		Cum	1	15.50	0.60	0.60	0.60	0.50	4.65		
15.50	30.00		Cum	1	14.50	0.60	0.60	0.60	0.50	4.35		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	155.40		Cum	1	5.40	0.60	0.60	0.60	0.50	1.62		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
		LHS										
0.00	15.40		Cum	1	15.40	0.60	0.60	0.60	0.50	4.62		
		RHS										
0.00	15.60		Cum	1	15.60	0.60	0.60	0.60	0.50	4.68		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	79.10		Cum	1	4.10	0.60	0.60	0.60	0.50	1.23		
		RHS										
0.00	10.10		Cum	1	10.10	0.60	0.60	0.60	0.50	3.03		
10.10	17.80	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
17.80	32.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
32.80	44.30		Cum	1	11.50	0.60	0.60	0.60	0.50	3.45		
44.30	51.20	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
51.20	66.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
66.20	79.10		Cum	1	12.90	0.60	0.60	0.60	0.50	3.87		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	21.80		Cum	1	6.80	0.60	0.60	0.60	0.50	2.04		
		RHS								0.00		
0.00	15.10		Cum	1	15.10	0.60	0.60	0.60	0.50	4.53		
		From house no #15 to house no -7										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	83.50		Cum	1	8.50	0.60	0.60	0.60	0.50	2.55		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	70.00		Cum	1	10.00	0.60	0.60	0.60	0.50	3.00		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	152.00		Cum	1	2.00	0.60	0.60	0.60	0.50	0.60		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	151.50		Cum	1	1.50	0.45	0.45	0.45	0.45	0.30		
		BLUE MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
0.00	14.60		Cum	1	14.60	0.60	0.60	0.60	0.50	4.38		
14.60	23.10	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
23.10	38.10		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
38.10	53.10		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
53.10	55.10		Cum	1	2.00	0.60	0.60	0.60	0.50	0.60		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	46.30		Cum	1	1.30	0.60	0.60	0.60	0.50	0.39		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	114.50		Cum	1	9.50	0.60	0.60	0.60	0.50	2.85		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		LHS										
0.00	14.80		Cum	1	14.80	0.45	0.45	0.45	0.45	3.00		
14.80	23.30	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
23.30	38.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
38.30	53.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
53.30	68.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
68.30	75.00		Cum	1	6.70	0.60	0.60	0.60	0.50	2.01		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	32.10		Cum	1	2.10	0.60	0.60	0.60	0.50	0.63		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	50.10		Cum	1	5.10	0.60	0.60	0.60	0.50	1.53		
		1st Cross Road										
		From House no: 33 to Empty site										
		(From East to West)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	73.40		Cum	1	13.40	0.60	0.60	0.60	0.50	4.02		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	73.40		Cum	1	13.40	0.60	0.60	0.60	0.50	4.02		
		BLOOM FIELD GARDEN										
		Main Road										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
		LHS										
0.00	7.10	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
7.10	22.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
22.10	29.10		Cum	1	7.00	0.45	0.45	0.45	0.45	1.42		
29.10	34.30	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
34.30	49.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
49.30	64.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
64.30	79.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
79.30	94.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
94.30	100.00		Cum	1	5.70	0.60	0.60	0.60	0.50	1.71		
100.00	115.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
115.00	120.00		Cum	1	5.00	0.60	0.60	0.60	0.50	1.50		
120.00	135.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
135.00	150.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
150.00	165.50		Cum	1	15.50	0.60	0.60	0.60	0.50	4.65		
165.50	180.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
180.50	195.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
195.50	210.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
210.50	212.50		Cum	1	2.00	0.60	0.60	0.60	0.50	0.60		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
5.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	50.90		Cum	1	5.90	0.60	0.60	0.60	0.50	1.77		
50.90	58.40	Road Break	Sqm	1	0.00	0.60	0.60	0.60	0.50	0.00		
58.40	73.40		Sqm	1	15.00	0.60	0.60	0.60	0.50	4.50		
73.40	84.20		Sqm	1	10.80	0.60	0.60	0.60	0.50	3.24		
84.20	92.00		Sqm	1	7.80	0.60	0.60	0.60	0.50	2.34		
92.00	107.00		Sqm	1	15.00	0.60	0.60	0.60	0.50	4.50		
107.00	122.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
122.00	125.80		Cum	1	3.80	0.60	0.60	0.60	0.50	1.14		
125.80	133.40	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
133.40	148.40		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
148.40	163.40		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
163.40	165.50		Cum	1	2.10	0.60	0.60	0.60	0.50	0.63		
165.50	173.30	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
173.30	188.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
188.30	203.30		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
203.30	212.20		Cum	1	8.90	0.60	0.60	0.60	0.50	2.67		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
		LHS										
0.00	5.80		Cum	1	5.80	0.60	0.60	0.60	0.50	1.74		
5.80	20.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
20.80	35.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
35.80	50.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
50.80	65.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
65.80	75.80		Cum	1	10.00	0.60	0.60	0.60	0.50	3.00		
75.80	85.20		Cum	1	9.40	0.60	0.60	0.60	0.50	2.82		
85.20	100.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
100.20	115.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
115.20	128.20		Cum	1	13.00	0.60	0.60	0.60	0.50	3.90		
128.20	135.80	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
135.80	145.90		Cum	1	10.10	0.60	0.60	0.60	0.50	3.03		
145.90	160.90		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
160.90	175.90		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
175.90	190.90		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
190.90	200.20		Cum	1	9.30	0.60	0.60	0.60	0.50	2.79		
		RHS										
0.00	5.80		Cum	1	5.80	0.45	0.45	0.45	0.45	1.17		
5.80	20.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
20.80	35.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
35.80	50.80		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
50.80	63.40		Cum	1	12.60	0.60	0.60	0.60	0.50	3.78		
63.40	72.50		Cum	1	9.10	0.60	0.60	0.60	0.50	2.73		
72.50	87.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
87.50	102.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
102.50	117.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
117.50	132.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
132.50	147.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
147.50	162.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
162.50	177.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
177.50	192.50		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
192.50	200.20		Cum	1	7.70	0.60	0.60	0.60	0.50	2.31		
		2nd Cross Road, House no: #48 to House no:#42										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	25.90		Cum	1	10.90	0.45	0.45	0.45	0.45	2.21		
25.90	40.90		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
40.90	51.80		Cum	1	10.90	0.45	0.45	0.45	0.45	2.21		
51.80	66.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
66.80	81.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
81.80	84.50		Cum	1	2.70	0.45	0.45	0.45	0.45	0.55		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
1.50	99.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
99.50	101.00		Cum	1	1.50	0.45	0.45	0.45	0.45	0.30		
101.00	109.20		Cum	1	8.20	0.45	0.45	0.45	0.45	1.66		
109.20	124.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
124.20	127.10		Cum	1	2.90	0.45	0.45	0.45	0.45	0.59		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	90.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
90.00	105.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
105.00	120.50		Cum	1	15.50	0.60	0.60	0.60	0.50	4.65		
		2nd Cross Road, House no: #68 to House no:#59										
		(From North to South)										
		LHS										
0.00	8.50		Cum	1	8.50	0.45	0.45	0.45	0.45	1.72		
8.50	23.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
23.50	35.20		Cum	1	11.70	0.45	0.45	0.45	0.45	2.37		
35.20	50.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
50.20	63.80		Cum	1	13.60	0.45	0.45	0.45	0.45	2.75		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	63.80		Cum	1	3.80	0.45	0.45	0.45	0.45	0.77		
		1st Cross Road, House no: #127 to House no:#95										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	35.40		Cum	1	5.40	0.45	0.45	0.45	0.45	1.09		
35.40	47.50		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
47.50	62.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
62.50	77.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
77.50	92.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
92.50	105.00		Cum	1	12.50	0.45	0.45	0.45	0.45	2.53		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	126.10		Cum	1	6.10	0.45	0.45	0.45	0.45	1.24		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	35.40		Cum	1	5.40	0.45	0.45	0.45	0.45	1.09		
35.40	47.50		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
47.50	62.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
62.50	77.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
77.50	92.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
92.50	105.00		Cum	1	12.50	0.45	0.45	0.45	0.45	2.53		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	126.20		Cum	1	6.20	0.45	0.45	0.45	0.45	1.26		
		1st Cross Road, House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	80.60		Cum	1	5.60	0.60	0.60	0.60	0.50	1.68		
		RHS										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
60.00	75.00		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
75.00	80.10		Cum	1	5.10	0.60	0.60	0.60	0.50	1.53		
		4th Cross Road										
		(From South to North)										
		LHS										
0.00	10.80		Cum	1	10.80	0.45	0.45	0.45	0.45	2.19		
10.80	25.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
25.80	40.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
40.80	44.00		Cum	1	3.20	0.45	0.45	0.45	0.45	0.65		
		RHS										
0.00	13.40		Cum	1	13.40	0.60	0.60	0.60	0.50	4.02		
13.40	21.20	Road Break	Cum	1	0.00	0.60	0.60	0.60	0.50	0.00		
21.20	36.20		Cum	1	15.00	0.60	0.60	0.60	0.50	4.50		
36.20	44.10		Cum	1	7.90	0.60	0.60	0.60	0.50	2.37		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	17.70		Cum	1	2.70	0.45	0.45	0.45	0.45	0.55		
17.70	21.70		Cum	1	4.00	0.45	0.45	0.45	0.45	0.81		
21.70	36.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
36.70	42.60		Cum	1	5.90	0.45	0.45	0.45	0.45	1.19		
42.60	51.80	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
51.80	55.40	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
55.40	70.40		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
70.40	85.40		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
85.40	100.40		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
100.40	115.40		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
115.40	116.20		Cum	1	0.80	0.45	0.45	0.45	0.45	0.16		
116.20	124.90	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
124.90	133.40		Cum	1	8.50	0.45	0.45	0.45	0.45	1.72		
133.40	135.70	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
135.70	150.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.70	156.80		Cum	1	6.10	0.45	0.45	0.45	0.45	1.24		
156.80	164.50	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
164.50	184.00	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
184.00	199.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
199.00	203.00		Cum	1	4.00	0.45	0.45	0.45	0.45	0.81		
203.00	210.90	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
210.90	225.90		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
225.90	228.10		Cum	1	2.20	0.45	0.45	0.45	0.45	0.45		
228.10	243.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
243.10	245.10		Cum	1	2.00	0.45	0.45	0.45	0.45	0.41		
245.10	255.70		Cum	1	10.60	0.45	0.45	0.45	0.45	2.15		
255.70	270.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
270.70	285.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
285.70	299.10		Cum	1	13.40	0.45	0.45	0.45	0.45	2.71		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	20.10		Cum	1	5.10	0.45	0.45	0.45	0.45	1.03		
20.10	23.10		Cum	1	3.00	0.45	0.45	0.45	0.45	0.61		
23.10	24.70	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
24.70	39.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.70	42.70		Cum	1	3.00	0.45	0.45	0.45	0.45	0.61		
42.70	50.90	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
50.90	55.00	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
55.00	70.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
70.00	82.10		Cum	1	12.10	0.45	0.45	0.45	0.45	2.45		
82.10	97.00	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
97.00	112.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
112.00	119.90		Cum	1	7.90	0.45	0.45	0.45	0.45	1.60		
119.90	120.50		Cum	1	0.60	0.45	0.45	0.45	0.45	0.12		
120.50	135.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.50	143.40		Cum	1	7.90	0.45	0.45	0.45	0.45	1.60		
143.40	151.50	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
151.50	164.50		Cum	1	13.00	0.45	0.45	0.45	0.45	2.63		
164.50	167.70	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
167.70	182.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
182.70	197.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
197.70	204.80		Cum	1	7.10	0.45	0.45	0.45	0.45	1.44		
204.80	213.00		Cum	1	8.20	0.45	0.45	0.45	0.45	1.66		
213.00	228.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
228.00	229.00		Cum	1	1.00	0.45	0.45	0.45	0.45	0.20		
229.00	233.50	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
233.50	237.00		Cum	1	3.50	0.45	0.45	0.45	0.45	0.71		
237.00	241.80		Cum	1	4.80	0.45	0.45	0.45	0.45	0.97		
241.80	250.20		Cum	1	8.40	0.45	0.45	0.45	0.45	1.70		
250.20	265.80		Cum	1	15.60	0.45	0.45	0.45	0.45	3.16		
265.80	274.50	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
274.50	289.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
289.50	298.10		Cum	1	8.60	0.45	0.45	0.45	0.45	1.74		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		NORTH TO SOUTH										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	117.20		Cum	1	12.20	0.45	0.45	0.45	0.45	2.47		
		RHS										
0.00	3.30		Cum	1	3.30	0.45	0.45	0.45	0.45	0.67		
3.30	9.60		Cum	1	6.30	0.45	0.45	0.45	0.45	1.28		
9.60	13.80		Cum	1	4.20	0.45	0.45	0.45	0.45	0.85		
13.80	16.40		Cum	1	2.60	0.45	0.45	0.45	0.45	0.53		
16.40	32.30		Cum	1	15.90	0.45	0.45	0.45	0.45	3.22		
32.30	36.20	No work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
36.20	45.70	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
45.70	51.30		Cum	1	5.60	0.45	0.45	0.45	0.45	1.13		
51.30	58.10		Cum	1	6.80	0.45	0.45	0.45	0.45	1.38		
58.10	62.00		Cum	1	3.90	0.45	0.45	0.45	0.45	0.79		
62.00	63.70		Cum	1	1.70	0.45	0.45	0.45	0.45	0.34		
63.70	69.10		Cum	1	5.40	0.45	0.45	0.45	0.45	1.09		
69.10	77.60		Cum	1	8.50	0.45	0.45	0.45	0.45	1.72		
77.60	85.30	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
85.30	100.30		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
100.30	101.20		Cum	1	0.90	0.45	0.45	0.45	0.45	0.18		
101.20	116.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
		3rd Cross Road										
		(From South to North)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	74.20		Cum	1	14.20	0.45	0.45	0.45	0.45	2.88		
74.20	83.00		Cum	1	8.80	0.45	0.45	0.45	0.45	1.78		
83.00	87.20		Cum	1	4.20	0.45	0.45	0.45	0.45	0.85		
87.20	93.80		Cum	1	6.60	0.45	0.45	0.45	0.45	1.34		
93.80	108.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
108.80	123.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
123.80	138.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
138.80	152.00		Cum	1	13.20	0.45	0.45	0.45	0.45	2.67		
152.00	159.40		Cum	1	7.40	0.45	0.45	0.45	0.45	1.50		
159.40	160.70		Cum	1	1.30	0.45	0.45	0.45	0.45	0.26		
160.70	175.70		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
175.70	181.20		Cum	1	5.50	0.45	0.45	0.45	0.45	1.11		
		RHS										
0.00	5.70		Cum	1	5.70	0.45	0.45	0.45	0.45	1.15		
5.70	14.10		Cum	1	8.40	0.45	0.45	0.45	0.45	1.70		
14.10	29.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
29.10	44.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
44.10	59.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
59.10	74.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
74.10	77.80		Cum	1	3.70	0.45	0.45	0.45	0.45	0.75		
77.80	92.80		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
92.80	100.40		Cum	1	7.60	0.45	0.45	0.45	0.45	1.54		
100.40	115.40		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
115.40	124.00		Cum	1	8.60	0.45	0.45	0.45	0.45	1.74		
124.00	132.80		Cum	1	8.80	0.45	0.45	0.45	0.45	1.78		
132.80	135.30		Cum	1	2.50	0.45	0.45	0.45	0.45	0.51		
135.30	144.10		Cum	1	8.80	0.45	0.45	0.45	0.45	1.78		
144.10	147.20		Cum	1	3.10	0.45	0.45	0.45	0.45	0.63		
147.20	162.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
162.20	163.00		Cum	1	0.80	0.45	0.45	0.45	0.45	0.16		
163.00	164.20		Cum	1	1.20	0.45	0.45	0.45	0.45	0.24		
164.20	179.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
179.20	181.20		Cum	1	2.00	0.45	0.45	0.45	0.45	0.41		
		5th Cross Road										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	21.30		Cum	1	6.30	0.45	0.45	0.45	0.45	1.28		
21.30	27.10		Cum	1	5.80	0.45	0.45	0.45	0.45	1.17		
27.10	34.20		Cum	1	7.10	0.45	0.45	0.45	0.45	1.44		
34.20	42.00	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
42.00	57.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
57.00	72.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
72.00	73.40		Cum	1	1.40	0.45	0.45	0.45	0.45	0.28		
73.40	82.50	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
82.50	97.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
97.50	112.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
112.50	127.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
127.50	142.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
142.50	157.50		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
157.50	169.50		Cum	1	12.00	0.45	0.45	0.45	0.45	2.43		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	165.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
165.00	168.60		Cum	1	3.60	0.45	0.45	0 45	0.45	0.73		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	38.60		Cum	1	8.60	0.45	0.45	0.45	0.45	1.74		
38.60	46.10	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
46.10	61.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
61.10	76.10		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
76.10	77.80		Cum	1	1.70	0.45	0.45	0.45	0.45	0.34		
77.80	86.20	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
86.20	101.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
101.20	116.20		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
116.20	117.60		Cum	1	1.40	0.45	0.45	0.45	0.45	0.28		
117.60	126.40	Road Break	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
126.40	131.70	No Work	Cum	1	0.00	0.45	0.45	0.45	0.45	0.00		
131.70	150.00		Cum	1	18.30	0.45	0.45	0.45	0.45	3.71		
		RHS										
0.00	15.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
15.00	30.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
30.00	45.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
45.00	60.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
60.00	75.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
75.00	90.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
90.00	105.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
105.00	120.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
120.00	135.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
135.00	150.00		Cum	1	15.00	0.45	0.45	0.45	0.45	3.04		
150.00	157.20		Cum	1	7.20	0.45	0.45	0.45	0.45	1.46		
									Total Executed Quantity	**5519.80**		
									Tender Quantity	**5214.55**		
									Quantity Upto 125%	**5519.80**	**351.05**	**1937726.00**

Item no.04	**Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite /trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates**

		Ward No 07										
		Drain PCC										
		VeerannaPalya										
		6th A Cross Road										
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	114.50		Cum	1	9.50	1.10	1.10	1.10	0.15	1.57		
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	114.70		Cum	1	9.70	1.10	1.10	1.10	0.15	1.60		
		6th B Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
5.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
45.00	60.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
120.00	121.80		Cum	1	1.80	0.95	0.95	0.95	0.15	0.26		
		6th Cross Road										
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30.00	33.60		Cum	1	3.60	0.95	0.95	0.95	0.15	0.51		
33.60	39.20	Road Break	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
39.20	54.20		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
54.20	69.20		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
69.20	78.00		Cum	1	8.80	0.95	0.95	0.95	0.15	1.25		
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	112.10		Cum	1	7.10	1.10	1.10	1.10	0.15	1.17		
		Culvert PCC										
		Muniswami Gowda Layout										
		2nd Cross Road										
			Cum	1	5.80	1.70	1.70	1.70	0.15	1.48		
		Ward No 08										
		Drain PCC										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		LHS										
		(From West To East)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120.00	135.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
135.00	139.00		Cum	1	4.00	1.10	1.10	1.10	0.15	0.66		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120.00	130.70		Cum	1	10.70	1.10	1.10	1.10	0.15	1.77		
130.70	139.00	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
9.00	154.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
154.00	169.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
169.00	184.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
184.00	199.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
199.00	214.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
214.00	229.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
229.00	232.80		Cum	1	3.80	1.10	1.10	1.10	0.15	0.63		
232.80	240.20	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
240.20	255.20		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
255.20	270.20		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
270.20	279.00		Cum	1	8.80	1.10	1.10	1.10	0.15	1.45		
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	22.70		Cum	1	7.70	1.10	1.10	1.10	0.15	1.27		
22.70	30.10	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
30.10	45.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.10	60.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.10	75.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.10	90.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.10	105.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.10	120.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120.10	132.20		Cum	1	12.10	1.10	1.10	1.10	0.15	2.00		
132.20	139.90	Culvert	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
139.90	154.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
154.90	169.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
169.90	184.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
184.90	199.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
199.90	214.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
214.90	229.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
229.90	244.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
244.90	259.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
259.90	274.90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
274.90	278.10		Cum	1	3.20	1.10	1.10	1.10	0.15	0.53		
		Balaji Layout										
		7th Cross Road										
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	67.80		Cum	1	7.80	1.10	1.10	1.10	0.15	1.29		
		(From West To East)										
		RHS										
0.00	12.50	No Work	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
12.50	27.50		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
27.50	42.50		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
42.50	57.50		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
57.50	72.50		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
72.50	74.10		Cum	1	1.60	0.95	0.95	0.95	0.15	0.23		
74.10	89.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
89.10	104.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
104.10	119.10		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
119.10	121.10		Cum	1	2.00	1.10	1.10	1.10	0.15	0.33		
		#560 Sri HariKrishna										
		LHS										
		(North To South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	101.00		Cum	1	11.00	1.10	1.10	1.10	0.15	1.82		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		RHS										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	103.00		Cum	1	13.00	1.10	1.10	1.10	0.15	2.15		
		Balaji Layout										
		Msc Provision Store Road										
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	79.00		Cum	1	4.00	1.10	1.10	1.10	0.15	0.66		
		1st Cross Road										
		(West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	59.10		Cum	1	14.10	1.10	1.10	1.10	0.15	2.33		
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	59.50		Cum	1	14.50	1.10	1.10	1.10	0.15	2.39		
		For Culvert										
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		RHS										
			Cum	1	8.30	1.40	1.40	1.40	0.15	1.74		
			Cum	1	7.40	1.70	1.70	1.70	0.15	1.89		
		LHS										
			Cum	1	7.40	1.70	1.70	1.70	0.15	1.89		
			Cum	1	7.70	1.70	1.70	1.70	0.15	1.96		
		2nd Main Road Dead End										
			Cum	1	6.50	1.70	1.70	1.70	0.15	1.66		
			Cum	1	5.60	1.70	1.70	1.70	0.15	1.43		
		Ward No 08										
		Drain PCC										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(N-S)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120.00	135.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
5.00	150.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
150.00	165.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
165.00	180.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
180.00	195.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
195.00	210.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
210.00	225.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
225.00	240.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
240.00	255.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
255.00	270.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
270.00	285.00		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
285.00	290.10		Cum	1	5.10	1.10	1.10	1.10	0.15	0.84		
		Culvert PCC										
		Sarovara Layout										
		1st Main Road										
			Cum	1	6.70	1.40	1.40	1.40	0.15	1.41		
		Cross Road	Cum	1	5.10	1.40	1.40	1.40	0.15	1.07		
		Ward No 10										
		Drain PCC										
		2nd Cross Road (From house #1032 to Vidyaranyapura Main Road)										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
45.00	58.10		Cum	1	13.10	0.95	0.95	0.95	0.15	1.87		
58.10	60.00	NO WORK	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
120.00	135.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
135.00	150.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
150.00	165.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
165.00	169.90		Cum	1	4.90	0.95	0.95	0.95	0.15	0.70		
169.90	172.00	NO WORK	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
172.00	187.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
187.00	202.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
202.00	217.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
217.00	232.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
232.00	247.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
247.00	254.00		Cum	1	7.00	0.95	0.95	0.95	0.15	1.00		
202.00	262.10	Culvert	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
262.10	277.10		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
277.10	292.10		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
292.10	302.20		Cum	1	10.10	0.95	0.95	0.95	0.15	1.44		
		RHS										
		(From Vidyaranyapura Main Road)										
		From South to North										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15.00	45.00		Cum	1	30.00	0.95	0.95	0.95	0.15	4.28		
45.00	75.00		Cum	1	30.00	0.95	0.95	0.95	0.15	4.28		
75.00	76.30		Cum	1	1.30	0.95	0.95	0.95	0.15	0.19		
76.30	91.30		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
91.30	106.30		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
106.30	121.30		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
121.30	122.10		Cum	1	0.80	0.95	0.95	0.95	0.15	0.11		
122.10	124.70	No Work	Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		
124.70	139.70		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
139.70	154.70		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
154.70	169.70		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
169.70	184.00		Cum	1	14.30	0.95	0.95	0.95	0.15	2.04		
184.70	193.00		Cum	1	0.00	0.95	0.95	0.95	0.15	0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Chamundeswari Layout										
		3rd Cross Road (Shree Nagamma Devasthana)										
		(From East to West)										
		RHS										
0.00	15.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
15.00	30.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
30.00	45.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
45.00	60.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
60.00	75.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
75.00	90.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
90.00	105.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
105.00	120.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
120.00	135.00		Cum	1	15.00	0.95	0.95	0.95	0.15	2.14		
135.00	136.40		Cum	1	1.40	0.95	0.95	0.95	0.15	0.20		
		Doddabomsandra										
		Gas Godown Road										
0.00	6.80		Cum	1	6.80	0.95	0.95	0.95	0.15	0.97		
		For Culvert										
		BEL 2nd Block										
		5th Cross Road										
			Cum	1	7.40	1.70	1.70	1.70	0.15	1.89		
		Chamundeshwari Layout										
		6th Cross Road										
			Cum	1	5.50	1.40	1.40	1.40	0.15	1.16		
		7th Cross Road										
			Cum	1	6.10	1.40	1.40	1.40	0.15	1.28		
		8th Cross Road										
			Cum	1	5.60	1.40	1.40	1.40	0.15	1.18		
		9th Cross Road										
			Cum	1	6.10	1.40	1.40	1.40	0.15	1.28		
		10th Cross Road										
			Cum	1	5.60	1.40	1.40	1.40	0.15	1.18		
		Gas godown Road										
			Cum	1	7.30	1.40	1.40	1.40	0.15	1.53		
			Cum	1	5.50	1.40	1.40	1.40	0.15	1.16		
		Patel Gopalappa Layout										
		7th Cross road	Cum	1	7.20	1.40	1.40	1.40	0.15	1.51		
		Near 7th Cross Road	Cum	1	6.50	2.00	2.00	2.00	0.15	1.95		
		Muneshwara layout										
		1st Main road	Cum	1	5.50	1.40	1.40	1.40	0.15	1.16		
									Total Executed Quantity	**452.99**	**6413.65**	**2905331.00**
									Tender Quantity	**723.79**		
Item no.05		**Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications**										
		For Drain	Tonne		844.94			0.06		**46.61**		
		For Culvert	Tonne		65.36			0.12		**7.80**		
									Total Executed Quantity	**54.41**	**106436.07**	**5791280.00**
									Tender Quantity	**68.14**		
Item no.06		**Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates**											

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Bottom Raft										
		Ward No 07										
		VeerannaPalya										
		6th A Cross Road										
		RHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	114.50		Cum	1	9.50	0.90	0.90	0.90	0.15	1.28		
		LHS										
		(From North to South)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	114.70		Cum	1	9.70	0.90	0.90	0.90	0.15	1.31		
		6th B Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
45.00	60.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
120.00	121.80		Cum	1	1.80	0.75	0.75	0.75	0.15	0.20		
		6th Cross Road										
		RHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	33.60		Cum	1	3.60	0.75	0.75	0.75	0.15	0.41		
33.60	39.20	Road Break	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
39.20	54.20		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
54.20	69.20		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
69.20	78.00		Cum	1	8.80	0.75	0.75	0.75	0.15	0.99		
		LHS										
		(From East to West)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	112.10		Cum	1	7.10	0.90	0.90	0.90	0.15	0.96		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		LHS										
		(From West To East)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	120.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120.00	135.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135.00	139.00		Cum	1	4.00	0.90	0.90	0.90	0.15	0.54		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	120.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120.00	130.70		Cum	1	10.70	0.90	0.90	0.90	0.15	1.44		
130.70	139.00	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
139.00	154.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
154.00	169.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
169.00	184.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
184.00	199.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
199.00	214.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
214.00	229.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
229.00	232.80		Cum	1	3.80	0.90	0.90	0.90	0.15	0.51		
232.80	240.20	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
240.20	255.20		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255.20	270.20		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270.20	279.00		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	22.70		Cum	1	7.70	0.90	0.90	0.90	0.15	1.04		
22.70	30.10	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
30.10	45.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.10	60.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.10	75.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.10	90.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.10	105.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.10	120.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120.10	132.20		Cum	1	12.10	0.90	0.90	0.90	0.15	1.63		
132.20	139.90	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
139.90	154.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
154.90	169.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
169.90	184.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
184.90	199.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
199.90	214.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
214.90	229.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
229.90	244.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
244.90	259.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
259.90	274.90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
274.90	278.10		Cum	1	3.20	0.90	0.90	0.90	0.15	0.43		
		Balaji Layout										
		7th Cross Road										
		(From West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	67.80		Cum	1	7.80	0.90	0.90	0.90	0.15	1.05		
		(From West To East)										
		RHS										
0.00	12.50	No Work	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
12.50	27.50		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
27.50	42.50		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
42.50	57.50		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
57.50	72.50		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
72.50	74.10		Cum	1	1.60	0.75	0.75	0.75	0.15	0.18		
74.10	89.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
89.10	104.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
104.10	119.10		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
119.10	121.10		Cum	1	2.00	0.90	0.90	0.90	0.15	0.27		
		#560 Sri HariKrishna										
		LHS										
		(North To South)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	101.00		Cum	1	11.00	0.90	0.90	0.90	0.15	1.49		
		RHS										
		(South To North)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	103.00		Cum	1	13.00	0.90	0.90	0.90	0.15	1.76		
		Balaji Layout										
		Msc Provision Store Road										
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	79.00		Cum	1	4.00	0.90	0.90	0.90	0.15	0.54		
		1st Cross Road										
		(West To East)										
		LHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	59.10		Cum	1	14.10	0.90	0.90	0.90	0.15	1.90		
		RHS										
		(East To West)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	59.50		Cum	1	14.50	0.90	0.90	0.90	0.15	1.96		
		Ward No 08										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(N-S)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105.00	120.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120.00	135.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
135.00	150.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
150.00	165.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
165.00	180.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
180.00	195.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
195.00	210.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
210.00	225.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
225.00	240.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
240.00	255.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
255.00	270.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
270.00	285.00		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
285.00	290.10		Cum	1	5.10	0.90	0.90	0.90	0.15	0.69		
		Ward No 10										
		Bottom Raft										
		BEL 2nd Block										
		2nd Cross Road (From house #1032 to Vidyaranyapura Main Road)										
		(From North to South)										
		LHS										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
45.00	58.10		Cum	1	13.10	0.75	0.75	0.75	0.15	1.47		
58.10	60.00	NO WORK	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
120.00	135.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
135.00	150.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
150.00	165.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
165.00	169.90		Cum	1	4.90	0.75	0.75	0.75	0.15	0.55		
169.90	172.00	NO WORK	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
172.00	187.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
187.00	202.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
202.00	217.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
217.00	232.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
232.00	247.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
247.00	254.00		Cum	1	7.00	0.75	0.75	0.75	0.15	0.79		
202.00	262.10	Culvert	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
262.10	277.10		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
277.10	292.10		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
292.10	302.20		Cum	1	10.10	0.75	0.75	0.75	0.15	1.14		
		RHS										
		(From Vidyaranyapura Main Road)										
		From South to North										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	45.00		Cum	1	30.00	0.75	0.75	0.75	0.15	3.38		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
45.00	75.00		Cum	1	30.00	0.75	0.75	0.75	0.15	3.38		
75.00	76.30		Cum	1	1.30	0.75	0.75	0.75	0.15	0.15		
76.30	91.30		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
91.30	106.30		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
106.30	121.30		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
121.30	122.10		Cum	1	0.80	0.75	0.75	0.75	0.15	0.09		
122.10	124.70	No Work	Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
124.70	139.70		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
139.70	154.70		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
154.70	169.70		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
169.70	184.00		Cum	1	14.30	0.75	0.75	0.75	0.15	1.61		
184.70	193.00		Cum	1	0.00	0.75	0.75	0.75	0.15	0.00		
		Chamundeswari Layout										
		3rd Cross Road (Shree Nagamma Devasthana)										
		(From East to West)										
		RHS										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
30.00	45.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
45.00	60.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
60.00	75.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
75.00	90.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
90.00	105.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
105.00	120.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
120.00	135.00		Cum	1	15.00	0.75	0.75	0.75	0.15	1.69		
135.00	136.40		Cum	1	1.40	0.75	0.75	0.75	0.15	0.16		
		Doddabomsandra										
		Gas Godown Road										
0.00	6.80		Cum	1	6.80	0.75	0.75	0.75	0.15	0.77		
		Side Wall										
		Ward No 07										
		VeerannaPalya										
		6th A Cross Road										
		RHS										
		(From North to South)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	114.50		Cum	2	9.50	0.15	0.15	0.15	0.60	1.71		
		LHS										
		(From North to South)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	114.70		Cum	2	9.70	0.15	0.15	0.15	0.60	1.75		
		6th B Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120.00	121.80		Cum	2	1.80	0.15	0.15	0.15	0.60	0.32		
		6th Cross Road										
		RHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	33.60		Cum	2	3.60	0.15	0.15	0.15	0.60	0.65		
33.60	39.20	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
39.20	54.20		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
54.20	69.20		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
69.20	78.00		Cum	2	8.80	0.15	0.15	0.15	0.60	1.58		
		LHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	112.10		Cum	2	7.10	0.15	0.15	0.15	0.60	1.28		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		LHS										
		(From West To East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.56	2.52		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.58	2.61		
120.00	135.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
135.00	139.00		Cum	2	4.00	0.15	0.15	0.15	0.60	0.72		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120.00	130.70		Cum	2	10.70	0.15	0.15	0.15	0.60	1.93		
130.70	139.00	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
139.00	154.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
154.00	169.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
169.00	184.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
184.00	199.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
199.00	214.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
214.00	229.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
229.00	232.80		Cum	2	3.80	0.15	0.15	0.15	0.60	0.68		
232.80	240.20	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
240.20	255.20		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
255.20	270.20		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
270.20	279.00		Cum	2	8.80	0.15	0.15	0.15	0.50	1.32		
		(From West To East)										
		LHS										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	22.70		Cum	2	7.70	0.15	0.15	0.15	0.60	1.39		
22.70	30.10	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
30.10	45.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.10	60.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.10	75.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.10	90.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.10	105.10		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
105.10	120.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120.10	132.20		Cum	2	12.10	0.15	0.15	0.15	0.60	2.18		
132.20	139.90	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
139.90	154.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
154.90	169.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
169.90	184.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
184.90	199.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
199.90	214.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
214.90	229.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
229.90	244.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
244.90	259.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
259.90	274.90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
274.90	278.10		Cum	2	3.20	0.15	0.15	0.15	0.60	0.58		
		Balaji Layout										
		7th Cross Road										
		(From West To East)										
		LHS										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.45	2.03		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
60.00	67.80		Cum	2	7.80	0.15	0.15	0.15	0.60	1.40		
		(From West To East)										
		RHS										
0.00	12.50	No Work	Cum	2	0.00	0.15	0.15	0.15	0.00	0.00		
12.50	27.50		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
27.50	42.50		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
42.50	57.50		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
57.50	72.50		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
72.50	74.10		Cum	2	1.60	0.15	0.15	0.15	0.50	0.24		
74.10	89.10		Cum	2	15.00	0.15	0.15	0.15	0.55	2.48		
89.10	104.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
104.10	119.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
119.10	121.10		Cum	2	2.00	0.15	0.15	0.15	0.60	0.36		
		#560 Sri HariKrishna										
		LHS										
		(North To South)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	101.00		Cum	2	11.00	0.15	0.15	0.15	0.60	1.98		
		RHS										
		(South To North)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	103.00		Cum	2	13.00	0.15	0.15	0.15	0.60	2.34		
		Balaji Layout										
		Msc Provision Store Road										
		RHS										
		(East To West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	79.00		Cum	2	4.00	0.15	0.15	0.15	0.60	0.72		
		1st Cross Road										
		(West To East)										
		LHS										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	59.10		Cum	2	14.10	0.15	0.15	0.15	0.60	2.54		
		RHS										
		(East To West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	59.50		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
		Ward No 08										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(N-S)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
120.00	135.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
135.00	150.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
150.00	165.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
165.00	180.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
180.00	195.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
195.00	210.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
210.00	225.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
225.00	240.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
240.00	255.00		Cum	2	15.00	0.15	0.15	0.15	0.90	4.05		
255.00	270.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
270.00	285.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
285.00	290.10		Cum	2	5.10	0.15	0.15	0.15	0.60	0.92		
		Ward No 10										
		BEL 2nd Block										
		(From North to South)										
		LHS										
0.00	12.00		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
12.00	14.00		Cum	2	2.00	0.15	0.15	0.15	0.55	0.33		
14.00	17.10		Cum	2	3.10	0.15	0.15	0.15	0.40	0.37		
17.10	21.40		Cum	2	4.30	0.15	0.15	0.15	0.25	0.32		
21.40	32.80		Cum	2	11.40	0.15	0.15	0.15	0.60	2.05		
32.80	34.40		Cum	2	1.60	0.15	0.15	0.15	0.35	0.17		
34.40	49.40		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
49.40	56.60		Cum	2	7.20	0.15	0.15	0.15	0.60	1.30		
56.60	58.10		Cum	2	1.50	0.15	0.15	0.15	0.55	0.25		
58.10	60.00	No WORK	Cum	2	0.00	0.15	0.15	0.15	0.00	0.00		
60.00	62.60		Cum	2	2.60	0.15	0.15	0.15	0.45	0.35		
62.60	77.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
77.60	92.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
92.60	107.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
107.60	122.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
122.60	137.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
137.60	152.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
152.60	167.60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
167.60	169.90		Cum	2	2.30	0.15	0.15	0.15	0.60	0.41		
169.90	172.00	No WORK	Cum	2	0.00	0.15	0.15	0.15	0.00	0.00		
172.00	187.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
187.00	202.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
202.00	217.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
217.00	232.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
232.00	247.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
247.00	254.00		Cum	2	7.00	0.15	0.15	0.15	0.60	1.26		
254.00	262.10	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
262.10	277.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
277.10	292.10		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
292.10	302.20		Cum	2	10.10	0.15	0.15	0.15	0.60	1.82		
		RHS										
		(From Vidyaranyapura Main Road)										
		From South to North										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	45.00		Cum	2	30.00	0.15	0.15	0.15	0.60	5.40		
45.00	75.00		Cum	2	30.00	0.15	0.15	0.15	0.60	5.40		
75.00	76.30		Cum	2	1.30	0.15	0.15	0.15	0.60	0.23		
76.30	91.30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
91.30	106.30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
106.30	121.30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
121.30	122.10		Cum	2	0.80	0.15	0.15	0.15	0.60	0.14		
122.10	124.70	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
124.70	139.70		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
139.70	154.70		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
154.70	169.70		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
169.70	184.00		Cum	2	14.30	0.15	0.15	0.15	0.60	2.57		
184.70	193.00		Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
		Chamundeswari Layout										
		3rd Cross Road (Shree Nagamma Devasthana)										
		(From East to West)										
		RHS										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120.00	135.00		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
135.00	136.40		Cum	2	1.40	0.15	0.15	0.15	0.60	0.25		
		Doddabomsandra										
		Gas Godown Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	6.80		Cum	2	6.80	0.15	0.15	0.15	0.60	1.22		
									Sub Total	844.94		
		Culvert										
		Bottom raft										
		Ward no 7										
		Muniswami Gowda Layout										
		2nd Cross Road										
			Cum	1	5.80	1.50	1.50	1.50	0.20	1.74		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		RHS										
			Cum	1	8.30	1.20	1.20	1.20	0.20	1.99		
			Cum	1	7.40	1.50	1.50	1.50	0.20	2.22		
		LHS										
			Cum	1	7.40	1.50	1.50	1.50	0.20	2.22		
			Cum	1	7.70	1.50	1.50	1.50	0.20	2.31		
		2nd Main Road Dead End										
			Cum	1	6.50	1.50	1.50	1.50	0.20	1.95		
			Cum	1	5.60	1.50	1.50	1.50	0.20	1.68		
		Ward No 08										
		Sarovara Layout										
		1st Main Road										
			Cum	1	6.70	1.20	1.20	1.20	0.20	1.61		
		Cross Road	Cum	1	5.10	1.20	1.20	1.20	0.20	1.22		
		Ward No 10										
		BEL 2nd Block										
		5th Cross Road										
			Cum	1	7.40	1.50	1.50	1.50	0.20	2.22		
		Chamundeshwari Layout										
		6th Cross Road										
			Cum	1	5.50	1.20	1.20	1.20	0.20	1.32		
		7th Cross Road										
			Cum	1	6.10	1.20	1.20	1.20	0.20	1.46		
		8th Cross Road										
			Cum	1	5.60	1.20	1.20	1.20	0.20	1.34		
		9th Cross Road										
			Cum	1	6.10	1.20	1.20	1.20	0.20	1.46		
		10th Cross Road										
			Cum	1	5.60	1.20	1.20	1.20	0.20	1.34		
		Gas godown Road										
			Cum	1	7.30	1.20	1.20	1.20	0.20	1.75		
			Cum	1	5.50	1.20	1.20	1.20	0.20	1.32		
		Patel Gopalappa Layout										
		7th Cross road	Cum	1	7.20	1.20	1.20	1.20	0.20	1.73		
		Near 7th Cross Road	Cum	1	6.50	1.80	1.80	1.80	0.20	2.34		
		Muneshwara layout										
		1st Main road	Cum	1	5.50	1.20	1.20	1.20	0.20	1.32		
		Side Wall										
		Ward no 7										
		Muniswami Gowda Layout										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross Road										
			Cum	2	5.80	0.20	0.20	0.20	0.60	1.39		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		RHS										
			Cum	2	8.30	0.20	0.20	0.20	0.45	1.49		
			Cum	2	7.40	0.20	0.20	0.20	0.40	1.18		
		LHS										
			Cum	2	7.40	0.20	0.20	0.20	0.40	1.18		
			Cum	2	7.70	0.20	0.20	0.20	0.40	1.23		
		2nd Main Road Dead End										
			Cum	2	6.50	0.20	0.20	0.20	0.40	1.04		
			Cum	2	5.60	0.20	0.20	0.20	0.40	0.90		
		Ward No 08										
		Sarovara Layout										
		1st Main Road										
			Cum	2	6.70	0.20	0.20	0.20	0.60	1.61		
		Cross Road	Cum	2	5.10	0.20	0.20	0.20	0.60	1.22		
		Ward No 10										
		BEL 2nd Block										
		5th Cross Road										
			Cum	2	7.40	0.23	0.23	0.23	0.60	2.04		
		Chamundeshwari Layout										
		6th Cross Road										
			Cum	2	5.50	0.23	0.23	0.23	0.45	1.14		
		7th Cross Road										
			Cum	2	6.10	0.23	0.23	0.23	0.45	1.26		
		8th Cross Road										
			Cum	2	5.60	0.23	0.23	0.23	0.45	1.16		
		9th Cross Road										
			Cum	2	6.10	0.23	0.23	0.23	0.45	1.26		
		10th Cross Road										
			Cum	2	5.60	0.23	0.23	0.23	0.45	1.16		
		Gas godown Road										
			Cum	2	7.30	0.23	0.23	0.23	0.60	2.01		
			Cum	2	5.50	0.23	0.23	0.23	0.60	1.52		
		Patel Gopalappa Layout										
		7th Cross road	Cum	2	7.20	0.23	0.23	0.23	0.60	1.99		
		Near 7th Cross Road	Cum	2	6.50	0.23	0.23	0.23	1.50	4.49		
		Muneshwara layout										
		1st Main road	Cum	2	5.50	0.23	0.23	0.23	0.60	1.52		
									Sub Total	**65.36**		
		Bed Correction										
		Ward No 08										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0.00	15.00		Cum	1	15.00	0.60	0.60	0.60	0.15	1.35		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	30.00		Cum	1	15.00	0.60	0.60	0.60	0.15	1.35		
30.00	45.00		Cum	1	15.00	0.60	0.60	0.60	0.15	1.35		
45.00	60.00		Cum	1	15.00	0.60	0.60	0.60	0.15	1.35		
60.00	62.30		Cum	1	2.30	0.60	0.60	0.60	0.15	0.21		
									Sub Total	**5.61**		
									Total Executed Quantity	**915.91**	**7236.31**	**6627791.00**
									Tender Quantity	**1027.69**		
Item no.07		**Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates**										
		Ward No 07										
		Flagging Course PCC										
		Muniswamy Gowda Layout										
		1st A Cross K.V.J Road										
		LHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	34.20		Cum	2	4.20	0.20	0.20	0.20	0.10	0.17		
		RHS										
		(From West to East)										
0.00	20.80	No Work	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
20.80	34.20		Cum	2	13.40	0.20	0.20	0.20	0.10	0.54		
		2nd A Cross K.V.J Road										
		LHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	34.10		Cum	2	4.10	0.20	0.20	0.20	0.10	0.16		
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	34.00		Cum	2	4.00	0.20	0.20	0.20	0.10	0.16		
		Vayunandana Layout										
		Compound										
		LHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	45.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
45.00	60.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
60.00	75.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
75.00	90.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
90.00	105.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
105.00	120.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
120.00	122.10		Cum	2	2.10	0.20	0.20	0.20	0.10	0.08		
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	45.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
45.00	60.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
60.00	75.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
75.00	90.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
90.00	105.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
105.00	109.30		Cum	2	4.30	0.20	0.20	0.20	0.10	0.17		
		Flagging Course Coping										
		Muniswamy Gowda Layout										
		1st A Cross K.V.J Road										
		LHS										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	34.20		Cum	2	4.20	0.15	0.15	0.15	0.10	0.13		
		RHS										
		(From West to East)										
0.00	20.80	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
20.80	34.20		Cum	2	13.40	0.15	0.15	0.15	0.10	0.40		
		2nd A Cross K.V.J Road										
		LHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	34.10		Cum	2	4.10	0.15	0.15	0.15	0.10	0.12		
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	34.00		Cum	2	4.00	0.15	0.15	0.15	0.10	0.12		
		Vayunandana Layout										
		Nerubhavi Munirathnamma Compound										
		LHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
105.00	120.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
120.00	122.10		Cum	2	2.10	0.15	0.15	0.15	0.10	0.06		
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	45.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
45.00	60.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
60.00	75.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
75.00	90.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
90.00	105.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
105.00	109.30		Cum	2	4.30	0.15	0.15	0.15	0.10	0.13		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		RHS										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	11.30	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
11.30	19.30		Cum	1	8.00	0.20	0.20	0.20	0.10	0.16		
19.30	28.90	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
28.90	37.60		Cum	1	8.70	0.20	0.20	0.20	0.10	0.17		
37.60	47.20	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
47.20	62.20		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
62.20	65.20		Cum	1	3.00	0.20	0.20	0.20	0.10	0.06		
65.20	78.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
78.50	93.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
93.50	101.70		Cum	1	8.20	0.20	0.20	0.20	0.10	0.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
101.70	114.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
114.50	129.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
129.50	137.50		Cum	1	8.00	0.20	0.20	0.20	0.10	0.16		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	3.50		Cum	1	3.50	0.20	0.20	0.20	0.10	0.07		
3.50	7.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
7.50	12.90		Cum	1	5.40	0.20	0.20	0.20	0.10	0.11		
12.90	51.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
51.50	66.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
66.50	81.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
81.50	96.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
96.50	106.60		Cum	1	10.10	0.20	0.20	0.20	0.10	0.20		
106.60	119.20	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
119.20	130.70		Cum	1	11.50	0.20	0.20	0.20	0.10	0.23		
130.70	139.00	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
139.00	140.90	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
140.90	155.90		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
155.90	170.90		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
170.90	177.10		Cum	1	6.20	0.20	0.20	0.20	0.10	0.12		
177.10	186.10	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
186.10	201.10		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
201.10	204.80		Cum	1	3.70	0.20	0.20	0.20	0.10	0.07		
204.80	214.20	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
214.20	223.30		Cum	1	9.10	0.20	0.20	0.20	0.10	0.18		
223.30	232.80	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
232.80	240.20	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
240.20	255.20		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
255.20	270.20		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
270.20	276.30		Cum	1	6.10	0.20	0.20	0.20	0.10	0.12		
276.30	279.10	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		(From West To East)										
		LHS										
0.00	14.60		Cum	1	14.60	0.20	0.20	0.20	0.10	0.29		
14.60	17.90	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
17.90	21.40		Cum	1	3.50	0.20	0.20	0.20	0.10	0.07		
21.40	22.70	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
22.70	30.10	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
30.10	31.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
31.50	46.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
46.50	61.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
61.50	76.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
76.50	91.50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
91.50	106.10		Cum	1	14.60	0.20	0.20	0.20	0.10	0.29		
106.10	119.50	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
119.50	130.80		Cum	1	11.30	0.20	0.20	0.20	0.10	0.23		
130.80	132.20	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
132.20	139.90	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
139.90	140.60	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
140.60	155.60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
155.60	165.80		Cum	1	10.20	0.20	0.20	0.20	0.10	0.20		
165.80	173.00	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
173.00	184.20		Cum	1	11.20	0.20	0.20	0.20	0.10	0.22		
184.20	185.30	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
185.30	200.30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
200.30	215.30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
215.30	230.30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
230.30	242.60		Cum	1	12.30	0.20	0.20	0.20	0.10	0.25		
242.60	252.10	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
252.10	267.10		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
267.10	277.30		Cum	1	10.20	0.20	0.20	0.20	0.10	0.20		
277.30	278.90	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		1st Cross Road										
		LHS										
		(West To East)										
0.00	4.50		Cum	1	4.50	0.20	0.20	0.20	0.10	0.09		
4.50	5.10	No Kerb	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
5.10	12.70		Cum	1	7.60	0.20	0.20	0.20	0.10	0.15		
12.70	27.70		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
27.70	38.00		Cum	1	10.30	0.20	0.20	0.20	0.10	0.21		
38.00	39.10		Cum	1	1.10	0.20	0.20	0.20	0.10	0.02		
39.10	42.60		Cum	1	3.50	0.20	0.20	0.20	0.10	0.07		
42.60	48.40	No Kerb	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
48.40	52.80		Cum	1	4.40	0.20	0.20	0.20	0.10	0.09		
52.80	53.90		Cum	1	1.10	0.20	0.20	0.20	0.10	0.02		
53.90	59.10		Cum	1	5.20	0.20	0.20	0.20	0.10	0.10		
		(East To West)										
		RHS										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	42.20		Cum	1	12.20	0.20	0.20	0.20	0.10	0.24		
42.20	46.70		Cum	1	4.50	0.20	0.20	0.20	0.10	0.09		
46.70	48.70	No Kerb	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
48.70	54.10		Cum	1	5.40	0.20	0.20	0.20	0.10	0.11		
54.10	57.40		Cum	1	3.30	0.20	0.20	0.20	0.10	0.07		
57.40	59.50	No Kerb	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		Ward No 08										
		Flagging Course PCC										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	45.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
45.00	60.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
60.00	62.30		Cum	2	2.30	0.20	0.20	0.20	0.10	0.09		
		Kote Layout(Sapthagiri Hall)										
		opposite Road										
		LHS										
		(From West to East)										
0.00	7.90		Cum	2	7.90	0.20	0.20	0.20	0.10	0.32		
7.90	17.50		Cum	2	9.60	0.20	0.20	0.20	0.10	0.38		
17.50	24.30	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
24.30	39.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
39.30	54.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
54.30	69.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
69.30	84.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
84.30	99.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
99.30	114.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
114.30	129.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
129.30	144.30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
144.30	145.30		Cum	2	1.00	0.20	0.20	0.20	0.10	0.04		
145.30	151.20	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
151.20	166.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
166.20	167.80		Cum	2	1.60	0.20	0.20	0.20	0.10	0.06		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
167.80	174.60	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
174.60	189.60		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
189.60	204.60		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
204.60	216.60		Cum	2	12.00	0.20	0.20	0.20	0.10	0.48		
		LHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	44.80		Cum	2	14.80	0.20	0.20	0.20	0.10	0.59		
44.80	49.40	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
49.40	64.40		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
64.40	68.50		Cum	2	4.10	0.20	0.20	0.20	0.10	0.16		
68.50	73.40	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
73.40	88.40		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
88.40	92.60		Cum	2	4.20	0.20	0.20	0.20	0.10	0.17		
92.60	98.20	Road Break	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
98.20	113.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
113.20	128.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
128.20	143.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
143.20	158.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
158.20	173.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
173.20	188.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
188.20	203.20		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
		Tata Nagar										
		1st Cross Road										
		Ketering)										
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15.00	30.00		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30.00	30.80		Cum	2	0.80	0.20	0.20	0.20	0.10	0.03		
		Balaji Layout										
		6th Cross Road										
		Hoysala Commanders Retreat										
		(From West to East)										
		LHS										
0.00	56.40	No Work	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
56.40	65.40		Cum	2	9.00	0.20	0.20	0.20	0.10	0.36		
65.40	122.00	No Work	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
122.00	131.10		Cum	2	9.10	0.20	0.20	0.20	0.10	0.36		
		Flagging Course Coping										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0.00	6.60	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
6.60	21.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
21.60	36.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
36.60	51.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
51.60	66.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
66.60	76.20		Cum	2	9.60	0.15	0.15	0.15	0.10	0.29		
76.20	91.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
91.20	106.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
106.20	118.00		Cum	2	11.80	0.15	0.15	0.15	0.10	0.35		
118.00	127.20	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
127.20	142.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
142.20	156.40		Cum	2	14.20	0.15	0.15	0.15	0.10	0.43		
156.40	163.70	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
163.70	178.70		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
178.70	193.70		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
193.70	203.50		Cum	2	9.80	0.15	0.15	0.15	0.10	0.29		
203.50	212.30	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
212.30	227.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
227.30	240.70		Cum	2	13.40	0.15	0.15	0.15	0.10	0.40		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
240.70	248.30	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
248.30	263.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
263.30	273.50		Cum	2	10.20	0.15	0.15	0.15	0.10	0.31		
		Kote Layout(Sapthagiri Hall)										
		Rohitha Gardens Apartment opposite Road										
		LHS										
		(From West to East)										
0.00	7.90		Cum	2	7.90	0.15	0.15	0.15	0.10	0.24		
7.90	17.50		Cum	2	9.60	0.15	0.15	0.15	0.10	0.29		
17.50	24.30	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
24.30	39.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
39.30	54.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
54.30	69.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
69.30	84.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
84.30	99.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
99.30	114.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
114.30	129.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
129.30	144.30		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
144.30	145.30		Cum	2	1.00	0.15	0.15	0.15	0.10	0.03		
145.30	151.20	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
151.20	166.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
166.20	167.80		Cum	2	1.60	0.15	0.15	0.15	0.10	0.05		
167.80	174.60	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
174.60	189.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
189.60	204.60		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
204.60	216.60		Cum	2	12.00	0.15	0.15	0.15	0.10	0.36		
		LHS										
		(From East to West)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	44.80		Cum	2	14.80	0.15	0.15	0.15	0.10	0.44		
44.80	49.40	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
49.40	64.40		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
64.40	68.50		Cum	2	4.10	0.15	0.15	0.15	0.10	0.12		
68.50	73.40	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
73.40	88.40		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
88.40	92.60		Cum	2	4.20	0.15	0.15	0.15	0.10	0.13		
92.60	98.20	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
98.20	113.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
113.20	128.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
128.20	143.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
143.20	158.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
158.20	173.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
173.20	188.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
188.20	203.20		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
		Tata Nagar										
		1st Cross Road										
		(From H.No #485 to R.P Ketering)										
		RHS										
		(From West to East)										
0.00	15.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
15.00	30.00		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
30.00	30.80		Cum	2	0.80	0.15	0.15	0.15	0.10	0.02		
		Balaji Layout										
		6th Cross Road										
		Hoysala Commanders Retreat										
		(From West to East)										
		LHS										
0.00	39.00	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
39.00	47.70		Cum	2	8.70	0.15	0.15	0.15	0.10	0.26		
47.70	56.40	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
56.40	65.40		Cum	2	9.00	0.15	0.15	0.15	0.10	0.27		
65.40	73.70	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
73.70	88.70		Cum	2	15.00	0.15	0.15	0.15	0.10	0.45		
88.70	104.00		Cum	2	15.30	0.15	0.15	0.15	0.10	0.46		
104.00	122.00	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
122.00	131.10		Cum	2	9.10	0.15	0.15	0.15	0.10	0.27		
		RHS										
0.00	42.50	No Work	Cum	2	0.00	0.15	0.15	0.15	0.10	0.00		
42.50	55.10		Cum	2	12.60	0.15	0.15	0.15	0.10	0.38		
55.10	64.00		Cum	2	8.90	0.15	0.15	0.15	0.10	0.27		
		For Kerb PCC										
		AMCO Layout										
		A Block 1st Main Road,										
		(North To South)										
		L.H.S										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	45.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45.00	60.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60.00	75.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
75.00	90.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
90.00	105.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
105.00	120.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
120.00	135.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
135.00	150.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
150.00	165.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
165.00	180.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
180.00	195.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
195.00	210.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
210.00	225.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
225.00	229.60		Cum	1	4.60	0.20	0.20	0.20	0.10	0.09		
		R.H.S										
		(North To South)										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	19.80		Cum	1	4.80	0.20	0.20	0.20	0.10	0.10		
19.80	27.10	No Kerb	Cum	0	7.30	0.20	0.20	0.20	0.10	0.00		
27.10	30.00		Cum	1	2.90	0.20	0.20	0.20	0.10	0.06		
30.00	42.90		Cum	1	12.90	0.20	0.20	0.20	0.10	0.26		
42.90	45.00	No Kerb	Cum	0	2.10	0.20	0.20	0.20	0.10	0.00		
45.00	46.00	No Kerb	Cum	0	1.00	0.20	0.20	0.20	0.10	0.00		
46.00	50.60		Cum	1	4.60	0.20	0.20	0.20	0.10	0.09		
50.60	59.10	No Kerb	Cum	0	8.50	0.20	0.20	0.20	0.10	0.00		
59.10	60.00		Cum	1	0.90	0.20	0.20	0.20	0.10	0.02		
60.00	75.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
75.00	85.30		Cum	1	10.30	0.20	0.20	0.20	0.10	0.21		
85.30	90.00	No Kerb	Cum	0	4.70	0.20	0.20	0.20	0.10	0.00		
90.00	96.10	No Kerb	Cum	0	6.10	0.20	0.20	0.20	0.10	0.00		
96.10	105.00		Cum	1	8.90	0.20	0.20	0.20	0.10	0.18		
105.00	120.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
120.00	135.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
135.00	135.20		Cum	1	0.20	0.20	0.20	0.20	0.10	0.00		
135.20	142.70	No Kerb	Cum	0	7.50	0.20	0.20	0.20	0.10	0.00		
142.70	150.00		Cum	1	7.30	0.20	0.20	0.20	0.10	0.15		
150.00	165.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
165.00	170.80		Cum	1	5.80	0.20	0.20	0.20	0.10	0.12		
		Sapthagiri Hall Road										
		R.H.S										
		(East To West)										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	21.90		Cum	1	6.90	0.20	0.20	0.20	0.10	0.14		
21.90	30.00	No Kerb	Cum	0	8.10	0.20	0.20	0.20	0.10	0.00		
30.00	38.40	No Kerb	Cum	0	8.40	0.20	0.20	0.20	0.10	0.00		
38.40	43.30		Cum	1	4.90	0.20	0.20	0.20	0.10	0.10		
43.30	45.00	No Kerb	Cum	0	1.70	0.20	0.20	0.20	0.10	0.00		
45.00	49.70	No Kerb	Cum	0	4.70	0.20	0.20	0.20	0.10	0.00		
49.70	56.80		Cum	1	7.10	0.20	0.20	0.20	0.10	0.14		
56.80	60.00	No Kerb	Cum	0	3.20	0.20	0.20	0.20	0.10	0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	72.20	No Kerb	Cum	0	12.20	0.20	0.20	0.20	0.10	0.00		
72.20	75.00		Cum	1	2.80	0.20	0.20	0.20	0.10	0.06		
75.00	85.40		Cum	1	10.40	0.20	0.20	0.20	0.10	0.21		
85.40	90.00	No Kerb	Cum	0	4.60	0.20	0.20	0.20	0.10	0.00		
90.00	90.50	No Kerb	Cum	0	0.50	0.20	0.20	0.20	0.10	0.00		
90.50	105.00		Cum	1	14.50	0.20	0.20	0.20	0.10	0.29		
105.00	114.30		Cum	1	9.30	0.20	0.20	0.20	0.10	0.19		
114.30	118.20	No Kerb	Cum	0	3.90	0.20	0.20	0.20	0.10	0.00		
118.20	120.00		Cum	1	1.80	0.20	0.20	0.20	0.10	0.04		
120.00	128.20		Cum	1	8.20	0.20	0.20	0.20	0.10	0.16		
128.20	132.70	No Kerb	Cum	0	4.50	0.20	0.20	0.20	0.10	0.00		
132.70	135.00		Cum	1	2.30	0.20	0.20	0.20	0.10	0.05		
135.00	138.60		Cum	1	3.60	0.20	0.20	0.20	0.10	0.07		
138.60	146.90	No Kerb	Cum	0	8.30	0.20	0.20	0.20	0.10	0.00		
146.90	150.00		Cum	1	3.10	0.20	0.20	0.20	0.10	0.06		
150.00	165.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
165.00	174.50		Cum	1	9.50	0.20	0.20	0.20	0.10	0.19		
174.50	180.00	No Kerb	Cum	0	5.50	0.20	0.20	0.20	0.10	0.00		
180.00	185.60	No Kerb	Cum	0	5.60	0.20	0.20	0.20	0.10	0.00		
185.60	194.80		Cum	1	9.20	0.20	0.20	0.20	0.10	0.18		
		L.H.S										
		(East To west)										
0.00	15.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15.00	30.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30.00	44.20		Cum	1	14.20	0.20	0.20	0.20	0.10	0.28		
44.20	45.00	No Kerb	Cum	0	0.80	0.20	0.20	0.20	0.10	0.00		
45.00	50.30	No Kerb	Cum	0	5.30	0.20	0.20	0.20	0.10	0.00		
50.30	60.00		Cum	1	9.70	0.20	0.20	0.20	0.10	0.19		
60.00	67.80		Cum	1	7.80	0.20	0.20	0.20	0.10	0.16		
67.80	75.00	No Kerb	Cum	0	7.20	0.20	0.20	0.20	0.10	0.00		
75.00	83.90	No Kerb	Cum	0	8.90	0.20	0.20	0.20	0.10	0.00		
83.90	90.00		Cum	1	6.10	0.20	0.20	0.20	0.10	0.12		
90.00	91.80		Cum	1	1.80	0.20	0.20	0.20	0.10	0.04		
91.80	99.30	No Kerb	Cum	0	7.50	0.20	0.20	0.20	0.10	0.00		
99.30	105.00		Cum	1	5.70	0.20	0.20	0.20	0.10	0.11		
105.00	120.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
120.00	131.50		Cum	1	11.50	0.20	0.20	0.20	0.10	0.23		
131.50	135.00	No Kerb	Cum	0	0.00	0.20	0.20	0.20	0.10	0.00		
135.00	135.40	No Kerb	Cum	0	0.00	0.20	0.20	0.20	0.10	0.00		
135.40	143.00		Cum	1	7.60	0.20	0.20	0.20	0.10	0.15		
143.00	149.70	No Kerb	Cum	0	6.70	0.20	0.20	0.20	0.10	0.00		
149.70	150.00		Cum	1	0.30	0.20	0.20	0.20	0.10	0.01		
150.00	165.00		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
165.00	174.80		Cum	1	9.80	0.20	0.20	0.20	0.10	0.20		
174.80	180.00	No Kerb	Cum	0	5.20	0.20	0.20	0.20	0.10	0.00		
180.00	195.00	No Kerb	Cum	0	15.00	0.20	0.20	0.20	0.10	0.00		
195.00	197.50	No Kerb	Cum	0	2.50	0.20	0.20	0.20	0.10	0.00		
197.50	210.00		Cum	1	12.50	0.20	0.20	0.20	0.10	0.25		
210.00	216.50		Cum	1	6.50	0.20	0.20	0.20	0.10	0.13		
216.50	225.00	No Kerb	Cum	0	8.50	0.20	0.20	0.20	0.10	0.00		
225.00	240.00	No Kerb	Cum	0	15.00	0.20	0.20	0.20	0.10	0.00		
240.00	245.80	No Kerb	Cum	0	5.80	0.20	0.20	0.20	0.10	0.00		
245.80	255.00		Cum	1	9.20	0.20	0.20	0.20	0.10	0.18		
255.00	255.50		Cum	1	0.50	0.20	0.20	0.20	0.10	0.01		
									Total Executed Qty	**90.76**	**6614.58**	**600346.00**
									Tender Quantity	**100.03**		
Item no.08		**Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.**										
		Ward No 07										
		Muniswamy Gowda Layout										
		1st A Cross K.V.J Road										
		LHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	34.20		Sqm	2	4.20				0.20	1.68		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		RHS										
		(From West to East)										
0.00	20.80	No Work	Sqm	2	0.00				0.20	0.00		
20.80	34.20		Sqm	2	13.40				0.20	5.36		
		2nd A Cross K.V.J Road										
		LHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	34.10		Sqm	2	4.10				0.20	1.64		
		RHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	34.00		Sqm	2	4.00				0.20	1.60		
		Vayunandana Layout										
		Nerubhavi Munirathnamma Compound										
		LHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	45.00		Sqm	2	15.00				0.20	6.00		
45.00	60.00		Sqm	2	15.00				0.20	6.00		
60.00	75.00		Sqm	2	15.00				0.20	6.00		
75.00	90.00		Sqm	2	15.00				0.20	6.00		
90.00	105.00		Sqm	2	15.00				0.20	6.00		
105.00	120.00		Sqm	2	15.00				0.20	6.00		
120.00	122.10		Sqm	2	2.10				0.20	0.84		
		RHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	45.00		Sqm	2	15.00				0.20	6.00		
45.00	60.00		Sqm	2	15.00				0.20	6.00		
60.00	75.00		Sqm	2	15.00				0.20	6.00		
75.00	90.00		Sqm	2	15.00				0.20	6.00		
90.00	105.00		Sqm	2	15.00				0.20	6.00		
105.00	109.30		Sqm	2	4.30				0.20	1.72		
		Ward No 08										
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	45.00		Sqm	2	15.00				0.20	6.00		
45.00	60.00		Sqm	2	15.00				0.20	6.00		
60.00	62.30		Sqm	2	2.30				0.20	0.92		
		Kote Layout(Sapthagiri Hall)										
		Rohitha Gardens Apartment opposite Road										
		LHS										
		(From West to East)										
0.00	7.90		Sqm	2	7.90				0.20	3.16		
7.90	17.50		Sqm	2	9.60				0.20	3.84		
17.50	24.30	Road Break	Sqm	2	0.00				0.20	0.00		
24.30	39.30		Sqm	2	15.00				0.20	6.00		
39.30	54.30		Sqm	2	15.00				0.20	6.00		
54.30	69.30		Sqm	2	15.00				0.20	6.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
69.30	84.30		Sqm	2	15.00				0.20	6.00		
84.30	99.30		Sqm	2	15.00				0.20	6.00		
99.30	114.30		Sqm	2	15.00				0.20	6.00		
114.30	129.30		Sqm	2	15.00				0.20	6.00		
129.30	144.30		Sqm	2	15.00				0.20	6.00		
144.30	145.30		Sqm	2	1.00				0.20	0.40		
145.30	151.20	Road Break	Sqm	2	0.00				0.20	0.00		
151.20	166.20		Sqm	2	15.00				0.20	6.00		
166.20	167.80		Sqm	2	1.60				0.20	0.64		
167.80	174.60	Road Break	Sqm	2	0.00				0.20	0.00		
174.60	189.60		Sqm	2	15.00				0.20	6.00		
189.60	204.60		Sqm	2	15.00				0.20	6.00		
204.60	216.60		Sqm	2	12.00				0.20	4.80		
		LHS										
		(From East to West)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	44.80		Sqm	2	14.80				0.20	5.92		
44.80	49.40	Road Break	Sqm	2	0.00				0.20	0.00		
49.40	64.40		Sqm	2	15.00				0.20	6.00		
64.40	68.50		Sqm	2	4.10				0.20	1.64		
68.50	73.40	Road Break	Sqm	2	0.00				0.20	0.00		
73.40	88.40		Sqm	2	15.00				0.20	6.00		
88.40	92.60		Sqm	2	4.20				0.20	1.68		
92.60	98.20	Road Break	Sqm	2	0.00				0.20	0.00		
98.20	113.20		Sqm	2	15.00				0.20	6.00		
113.20	128.20		Sqm	2	15.00				0.20	6.00		
128.20	143.20		Sqm	2	15.00				0.20	6.00		
143.20	158.20		Sqm	2	15.00				0.20	6.00		
158.20	173.20		Sqm	2	15.00				0.20	6.00		
173.20	188.20		Sqm	2	15.00				0.20	6.00		
188.20	203.20		Sqm	2	15.00				0.20	6.00		
		Tata Nagar										
		1st Cross Road										
		(From H.No #485 to R.P Ketering)										
		RHS										
		(From West to East)										
0.00	15.00		Sqm	2	15.00				0.20	6.00		
15.00	30.00		Sqm	2	15.00				0.20	6.00		
30.00	30.80		Sqm	2	0.80				0.20	0.32		
		Balaji Layout										
		6th Cross Road										
		Hoysala Commanders Retreat										
		(From West to East)										
		LHS										
0.00	56.40	No Work	Sqm	2	0.00				0.20	0.00		
56.40	65.40		Sqm	2	9.00				0.20	3.60		
65.40	122.00	No Work	Sqm	2	0.00				0.20	0.00		
122.00	131.10		Sqm	2	9.10				0.20	3.64		
									Total Executed Qty	**337.40**	**1225.22**	**413390.00**
									Tender Quantity	**370.00**		
Item no.09		**Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work**										
		Ward No 07										
		VeerannaPalya										
		6th A Cross Road										
		RHS										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	28.50		Sqm	1	13.50	0.90	0.90	0.90		12.15		
28.50	35.30	No Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
35.30	50.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
50.30	65.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
65.30	80.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
80.30	87.10		Sqm	1	6.80	0.90	0.90	0.90		6.12		
87.10	98.30	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
98.30	113.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
113.30	114.90		Sqm	1	1.60	0.90	0.90	0.90		1.44		
		LHS										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	32.80		Sqm	1	2.80	0.90	0.90	0.90		2.52		
32.80	38.70	No Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
38.70	44.50		Sqm	1	5.80	0.90	0.90	0.90		5.22		
44.50	53.30	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
53.30	68.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
68.30	83.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
83.30	98.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
98.30	113.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
113.30	114.70		Sqm	1	1.40	0.90	0.90	0.90		1.26		
		6th B Cross Road										
		RHS										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	20.40	No Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
20.40	35.40		Sqm	1	15.00	0.75	0.75	0.75		11.25		
35.40	50.40		Sqm	1	15.00	0.75	0.75	0.75		11.25		
50.40	65.40		Sqm	1	15.00	0.75	0.75	0.75		11.25		
65.40	80.40		Sqm	1	15.00	0.75	0.75	0.75		11.25		
80.40	87.60		Sqm	1	7.20	0.75	0.75	0.75		5.40		
87.60	92.80	No Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
92.80	107.80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
107.80	121.90		Sqm	1	14.10	0.75	0.75	0.75		10.58		
		6th Cross Road										
		RHS										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	30.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30.00	33.60		Sqm	1	3.60	0.75	0.75	0.75		2.70		
33.60	39.20	Road Break	Sqm	1	0.00	0.75	0.75	0.75		0.00		
39.20	54.20		Sqm	1	15.00	0.75	0.75	0.75		11.25		
54.20	63.30		Sqm	1	9.10	0.75	0.75	0.75		6.83		
63.30	78.00	No Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
		LHS										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	59.00		Sqm	1	14.00	0.90	0.90	0.90		12.60		
59.00	71.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
71.80	86.80		Sqm	1	15.00	0.90	0.90	0.90		13.50		
86.80	90.60		Sqm	1	3.80	0.90	0.90	0.90		3.42		
		Vayunandana Layout										
		Nerubhavi Munirathnamma Compound										
		LHS										
		(From West to East)										
0.00	2.30		Sqm	1	2.30	0.90	0.90	0.90		2.07		
2.30	4.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
4.00	19.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
19.00	34.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
34.00	40.20		Sqm	1	6.20	0.90	0.90	0.90		5.58		
40.20	55.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
55.20	59.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
69.20	71.50		Sqm	1	12.30	0.90	0.90	0.90		11.07		
71.50	75.40	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
75.40	81.80		Sqm	1	6.40	0.90	0.90	0.90		5.76		
81.80	84.10	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
84.10	99.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
99.10	114.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
114.10	122.10		Sqm	1	8.00	0.90	0.90	0.90		7.20		
		RHS										
		(From West to East)										
0.00	5.60		Sqm	1	5.60	0.90	0.90	0.90		5.04		
5.60	14.60	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
14.60	29.60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
29.60	32.70		Sqm	1	3.10	0.90	0.90	0.90		2.79		
32.70	46.30	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
46.30	51.30		Sqm	1	5.00	0.90	0.90	0.90		4.50		
51.30	66.30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
66.30	78.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
78.70	91.60		Sqm	1	12.90	0.90	0.90	0.90		11.61		
91.60	98.40	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
98.40	109.30		Sqm	1	10.90	0.90	0.90	0.90		9.81		
109.30	115.80		Sqm	1	6.50	0.90	0.90	0.90		5.85		
		Cross Road										
		L.H.S										
		(North To South)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	90.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90.00	105.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105.00	120.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120.00	135.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		LHS										
		(From West To East)										
0.00	12.80		Sqm	1	12.80	0.90	0.90	0.90		11.52		
12.80	27.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
27.80	42.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
42.80	57.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
57.80	72.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
72.80	73.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
73.00	88.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
88.00	91.20		Sqm	1	3.20	0.90	0.90	0.90		2.88		
91.20	101.00		Sqm	1	9.80	0.90	0.90	0.90		8.82		
101.00	109.60		Sqm	1	8.60	0.90	0.90	0.90		7.74		
109.60	118.90	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
118.90	127.50		Sqm	1	8.60	0.90	0.90	0.90		7.74		
127.50	139.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0.00	3.50		Sqm	1	3.50	0.90	0.90	0.90		3.15		
3.50	8.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
8.50	13.50		Sqm	1	5.00	0.90	0.90	0.90		4.50		
13.50	19.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
19.00	19.80		Sqm	1	0.80	0.90	0.90	0.90		0.72		
19.80	28.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
8.70	39.50		Sqm	1	10.80	0.90	0.90	0.90		9.72		
39.50	54.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
54.50	69.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
69.50	70.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
70.50	82.40		Sqm	1	11.90	0.90	0.90	0.90		10.71		
82.40	94.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
94.70	106.60		Sqm	1	11.90	0.90	0.90	0.90		10.71		
106.60	119.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
119.20	130.70		Sqm	1	11.50	0.90	0.90	0.90		10.35		
130.70	139.00	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
139.00	140.90	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
140.90	155.90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
155.90	170.90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
170.90	177.10		Sqm	1	6.20	0.90	0.90	0.90		5.58		
177.10	192.10	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
192.10	196.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
196.00	198.20		Sqm	1	2.20	0.90	0.90	0.90		1.98		
198.20	201.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
201.80	204.80		Sqm	1	3.00	0.90	0.90	0.90		2.70		
204.80	214.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
214.20	223.30		Sqm	1	9.10	0.90	0.90	0.90		8.19		
223.30	232.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
232.80	240.20	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
240.20	248.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
248.50	257.40		Sqm	1	8.90	0.90	0.90	0.90		8.01		
257.40	262.30	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
262.30	278.10		Sqm	1	15.80	0.90	0.90	0.90		14.22		
278.10	279.10	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		(From West To East)										
		LHS										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	22.70		Sqm	1	7.70	0.90	0.90	0.90		6.93		
22.70	30.10	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
30.10	45.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.10	48.20		Sqm	1	3.10	0.90	0.90	0.90		2.79		
48.20	63.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
63.20	64.90	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
64.90	79.90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
79.90	94.90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
94.90	106.10		Sqm	1	11.20	0.90	0.90	0.90		10.08		
106.10	118.60	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
118.60	130.80		Sqm	1	12.20	0.90	0.90	0.90		10.98		
130.80	132.20	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
132.20	139.90	Culvert	Sqm	1	0.00	0.90	0.90	0.90		0.00		
139.90	140.60	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
140.60	155.60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
155.60	161.00		Sqm	1	5.40	0.90	0.90	0.90		4.86		
161.00	173.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
173.00	185.30		Sqm	1	12.30	0.90	0.90	0.90		11.07		
185.30	200.30	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
200.30	204.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
204.50	213.00		Sqm	1	8.50	0.90	0.90	0.90		7.65		
213.00	228.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
228.00	231.00	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
231.00	242.60		Sqm	1	11.60	0.90	0.90	0.90		10.44		
242.60	252.10	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
252.10	267.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
267.10	278.90		Sqm	1	11.80	0.90	0.90	0.90		10.62		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Balaji Layout										
		7th Cross Road										
		(From West To East)										
		LHS										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	31.50		Sqm	1	1.50	0.90	0.90	0.90		1.35		
31.50	40.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
40.50	51.80		Sqm	1	11.30	0.90	0.90	0.90		10.17		
51.80	58.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
58.50	64.20		Sqm	1	5.70	0.90	0.90	0.90		5.13		
64.20	67.80	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		(From West To East)										
		RHS										
0.00	12.50	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
12.50	13.40	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
13.40	16.90		Sqm	1	3.50	0.75	0.75	0.75		2.63		
16.90	30.70	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
30.70	38.70		Sqm	1	8.00	0.75	0.75	0.75		6.00		
38.70	53.70	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
53.70	65.70	Bs Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
65.70	74.70		Sqm	1	9.00	0.75	0.75	0.75		6.75		
74.70	87.70		Sqm	1	13.00	0.90	0.90	0.90		11.70		
87.70	102.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
102.70	106.40	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
106.40	113.30		Sqm	1	6.90	0.90	0.90	0.90		6.21		
113.30	121.10	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Sri HariKrishna #560 Rajeev										
		(North To South)										
0.00	5.80		Sqm	1	5.80	0.90	0.90	0.90		5.22		
5.80	18.30	B.S Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
18.30	31.00		Sqm	1	12.70	0.90	0.90	0.90		11.43		
31.00	43.80	B.S Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
43.80	58.80		Sqm	1	15.00	0.90	0.90	0.90		13.50		
58.80	73.80		Sqm	1	15.00	0.90	0.90	0.90		13.50		
73.80	88.80		Sqm	1	15.00	0.90	0.90	0.90		13.50		
88.80	101.00		Sqm	1	12.20	0.90	0.90	0.90		10.98		
		(south To North)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	92.60		Sqm	1	17.60	0.90	0.90	0.90		15.84		
92.60	103.00	B.S Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Balaji Layout										
		Msc Provision Store Road										
		(East To West)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	27.20		Sqm	1	12.20	0.90	0.90	0.90		10.98		
27.20	41.10	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
41.10	56.10		Sqm	1	15.00	0.90	0.90	0.90		13.50		
56.10	66.10		Sqm	1	10.00	0.90	0.90	0.90		9.00		
66.10	69.10	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
69.10	79.00		Sqm	1	9.90	0.90	0.90	0.90		8.91		
		1st Cross Road										
		LHS										
		(West To East)										
0.00	4.50	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
1.50	5.10		Sqm	1	0.60	0.90	0.90	0.90		0.54		
5.10	12.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
12.70	27.70		Sqm	1	15.00	0.90	0.90	0.90		13.50		
27.70	38.00		Sqm	1	10.30	0.90	0.90	0.90		9.27		
38.00	39.10	no work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
39.10	42.60		Sqm	1	3.50	0.90	0.90	0.90		3.15		
42.60	48.40	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
48.40	52.80		Sqm	1	4.40	0.90	0.90	0.90		3.96		
52.80	53.90	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
53.90	59.10		Sqm	1	5.20	0.90	0.90	0.90		4.68		
		RHS										
		(East To West)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	42.20		Sqm	1	12.20	0.90	0.90	0.90		10.98		
42.20	46.70	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
46.70	48.70		Sqm	1	2.00	0.90	0.90	0.90		1.80		
48.70	54.10		Sqm	1	5.40	0.90	0.90	0.90		4.86		
54.10	57.40	Bs Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
57.40	59.50		Sqm	1	2.10	0.90	0.90	0.90		1.89		
		Missing Slab	Sqm	20	0.90	0.60	0.60	0.60		10.80		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
		LHS										
9.20	12.00		Sqm	1	2.80	0.75	0.75	0.75		2.10		
24.00	26.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
34.00	35.80		Sqm	1	1.80	0.75	0.75	0.75		1.35		
42.50	44.00		Sqm	1	1.50	0.75	0.75	0.75		1.13		
54.00	56.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
66.00	68.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
80.00	82.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
92.00	93.40		Sqm	1	1.40	0.75	0.75	0.75		1.05		
97.90	99.00		Sqm	1	1.10	0.75	0.75	0.75		0.82		
110.00	112.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
124.00	126.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
141.00	145.00		Sqm	1	4.00	0.75	0.75	0.75		3.00		
153.00	155.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
158.70	160.00		Sqm	1	1.30	0.75	0.75	0.75		0.98		
		RHS										
		(From East to West)										
0.00	2.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
9.30	11.00		Sqm	1	1.70	0.75	0.75	0.75		1.28		
26.20	28.00		Sqm	1	1.80	0.75	0.75	0.75		1.35		
38.00	40.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
51.00	53.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
67.00	68.40		Sqm	1	1.40	0.75	0.75	0.75		1.05		
72.40	74.00		Sqm	1	1.60	0.75	0.75	0.75		1.20		
81.00	83.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
97.00	98.20		Sqm	1	1.20	0.75	0.75	0.75		0.90		
106.10	108.00		Sqm	1	1.90	0.75	0.75	0.75		1.43		
116.00	117.50		Sqm	1	1.50	0.75	0.75	0.75		1.13		
125.20	127.00		Sqm	1	1.80	0.75	0.75	0.75		1.35		
136.00	138.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
140.00	141.20		Sqm	1	1.20	0.75	0.75	0.75		0.90		
144.70	146.00		Sqm	1	1.30	0.75	0.75	0.75		0.98		
157.00	158.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
		6th A Cross Road										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		LHS										
0.00	5.00		Sqm	1	5.00	0.75	0.75	0.75		3.75		
13.00	15.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
23.00	24.90		Sqm	1	1.90	0.75	0.75	0.75		1.43		
32.70	34.00		Sqm	1	1.30	0.75	0.75	0.75		0.97		
45.00	47.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
57.00	59.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
68.00	70.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
84.00	85.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
98.30	100.00		Sqm	1	1.70	0.75	0.75	0.75		1.28		
111.70	115.00		Sqm	1	3.30	0.75	0.75	0.75		2.48		
128.00	130.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
		RHS										
		(From North to South)										
0.00	6.00		Sqm	1	6.00	0.75	0.75	0.75		4.50		
74.40	76.00		Sqm	1	1.60	0.75	0.75	0.75		1.20		
86.00	88.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
96.00	98.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
101.40	102.00		Sqm	1	0.60	0.75	0.75	0.75		0.45		
		Devi Nagar Main Road										
		(From West to East)										
		LHS										
0.00	3.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
14.00	15.10		Sqm	1	1.10	0.90	0.90	0.90		0.99		
26.30	28.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
35.00	36.80		Sqm	1	1.80	0.90	0.90	0.90		1.62		
48.30	50.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
61.00	63.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
76.00	77.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
90.00	92.70		Sqm	1	2.70	0.90	0.90	0.90		2.43		
97.70	99.00		Sqm	1	1.30	0.90	0.90	0.90		1.17		
109.00	111.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
120.00	122.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
129.00	130.20		Sqm	1	1.20	0.90	0.90	0.90		1.08		
137.10	139.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
150.00	152.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
		RHS										
		(From West to East)										
5.00	7.00	Road Break	Sqm	1	2.00	0.90	0.90	0.90		1.80		
16.00	18.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
48.30	50.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
58.00	60.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
71.00	73.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
85.00	87.50		Sqm	1	2.50	0.90	0.90	0.90		2.25		
94.30	96.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
106.50	109.30		Sqm	1	2.80	0.90	0.90	0.90		2.52		
		Muneshwara Layout										
		1st Main Road										
		LHS										
		(From South to North)										
0.00	4.00		Sqm	1	4.00	0.90	0.90	0.90		3.60		
15.00	18.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
39.70	41.00		Sqm	1	1.30	0.75	0.75	0.75		0.97		
52.00	55.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
84.80	86.00		Sqm	1	1.20	0.90	0.90	0.90		1.08		
97.30	99.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
108.00	110.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
164.30	166.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
185.10	188.00		Sqm	1	2.90	0.90	0.90	0.90		2.61		
207.40	209.00		Sqm	1	1.60	0.90	0.90	0.90		1.44		
220.00	222.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
234.00	236.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
246.00	248.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
258.20	260.00		Sqm	1	1.80	0.90	0.90	0.90		1.62		
270.00	274.00		Sqm	1	4.00	0.90	0.90	0.90		3.60		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
295.50	298.00		Sqm	1	2.50	0.90	0.90	0.90		2.25		
307.00	311.00		Sqm	1	4.00	0.90	0.90	0.90		3.60		
319.30	321.30		Sqm	1	2.00	0.90	0.90	0.90		1.80		
363.00	364.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
		RHS										
		(From South to North)										
3.00	5.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
14.00	15.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
40.70	43.00		Sqm	1	2.30	0.75	0.75	0.75		1.73		
53.00	55.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
64.00	67.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
85.30	88.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
99.00	101.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
110.00	111.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
122.30	125.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
133.00	138.00		Sqm	1	5.00	0.90	0.90	0.90		4.50		
149.90	154.00		Sqm	1	4.10	0.90	0.90	0.90		3.69		
164.90	168.00		Sqm	1	3.10	0.90	0.90	0.90		2.79		
176.00	178.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
198.90	200.00		Sqm	1	1.10	0.90	0.90	0.90		0.99		
215.40	218.00		Sqm	1	2.60	0.90	0.90	0.90		2.34		
228.00	230.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
248.40	250.00		Sqm	1	1.60	0.90	0.90	0.90		1.44		
260.00	262.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
285.00	287.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
314.20	318.00		Sqm	1	3.80	0.90	0.90	0.90		3.42		
327.80	330.00		Sqm	1	2.20	0.75	0.75	0.75		1.65		
364.10	366.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
		Tata Nagar										
		5th Main Road										
		RHS										
		(From South to North)										
44.70	50.00		Sqm	1	5.30	1.20	1.20	1.20		6.36		
100.00	103.00		Sqm	1	3.00	1.20	1.20	1.20		3.60		
127.10	131.00		Sqm	1	3.90	0.90	0.90	0.90		3.51		
188.20	196.00		Sqm	1	7.80	1.20	1.20	1.20		9.36		
226.20	230.00		Sqm	1	3.80	1.20	1.20	1.20		4.56		
250.40	253.00		Sqm	1	2.60	1.20	1.20	1.20		3.12		
262.60	265.00		Sqm	1	2.40	1.20	1.20	1.20		2.88		
275.00	277.00		Sqm	1	2.00	1.20	1.20	1.20		2.40		
287.00	289.00		Sqm	1	2.00	1.20	1.20	1.20		2.40		
308.10	314.00		Sqm	1	5.90	0.75	0.75	0.75		4.42		
336.40	338.00		Sqm	1	1.60	1.20	1.20	1.20		1.92		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
		LHS										
24.30	26.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
42.00	48.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
57.00	60.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
72.00	74.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
84.00	86.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
98.00	100.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
108.00	110.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
121.00	124.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
133.00	135.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
151.20	154.00		Sqm	1	2.80	0.90	0.90	0.90		2.52		
164.20	166.20		Sqm	1	2.00	0.75	0.75	0.75		1.50		
174.60	180.00		Sqm	1	5.40	0.90	0.90	0.90		4.86		
204.60	207.00		Sqm	1	2.40	0.90	0.90	0.90		2.16		
		(From West to East)										
		LHS										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	3.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
15.10	17.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
49.40	51.00		Sqm	1	1.60	0.90	0.90	0.90		1.44		
62.00	63.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
73.40	75.00		Sqm	1	1.60	0.90	0.90	0.90		1.44		
87.00	88.40		Sqm	1	1.40	0.90	0.90	0.90		1.26		
98.20	102.00		Sqm	1	3.80	0.90	0.90	0.90		3.42		
112.60	116.00		Sqm	1	3.40	0.90	0.90	0.90		3.06		
128.30	130.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
143.20	146.00		Sqm	1	2.80	0.90	0.90	0.90		2.52		
158.20	164.00		Sqm	1	5.80	0.90	0.90	0.90		5.22		
173.20	176.00		Sqm	1	2.80	0.90	0.90	0.90		2.52		
188.20	190.00		Sqm	1	1.80	0.90	0.90	0.90		1.62		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
		LHS										
0.00	3.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
14.50	16.00		Sqm	1	1.50	0.90	0.90	0.90		1.35		
28.00	30.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
		Balaji Layout										
		Hoysala Commanders Retreat										
		6th Cross Road										
		(From West to East)										
		LHS										
0.00	5.00		Sqm	1	5.00	0.90	0.90	0.90		4.50		
13.10	15.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
39.00	42.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
56.40	58.00		Sqm	1	1.60	0.90	0.90	0.90		1.44		
91.70	92.00		Sqm	1	0.30	0.90	0.90	0.90		0.27		
		(From West to East)										
		RHS										
0.00	8.00		Sqm	1	8.00	0.90	0.90	0.90		7.20		
33.70	35.00		Sqm	1	1.30	0.90	0.90	0.90		1.17		
64.00	68.00		Sqm	1	4.00	0.90	0.90	0.90		3.60		
79.00	82.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
102.10	104.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
113.00	114.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
129.30	132.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
142.10	144.00		Sqm	1	1.90	0.90	0.90	0.90		1.71		
157.00	159.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
168.00	170.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
		LHS										
127.20	130.00		Sqm	1	2.80	0.90	0.90	0.90		2.52		
143.00	145.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
163.70	166.00		Sqm	1	2.30	0.90	0.90	0.90		2.07		
178.70	183.00		Sqm	1	4.30	0.90	0.90	0.90		3.87		
193.70	195.00		Sqm	1	1.30	0.90	0.90	0.90		1.17		
212.30	215.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
227.20	231.00		Sqm	1	3.80	0.90	0.90	0.90		3.42		
248.30	253.00		Sqm	1	4.70	0.90	0.90	0.90		4.23		
263.30	266.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
278.30	280.00		Sqm	1	1.70	0.90	0.90	0.90		1.53		
291.00	292.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
		1st Cross Road										
		(From East to West)										
		LHS										
5.40	10.00		Sqm	1	4.60	0.75	0.75	0.75		3.45		
18.90	20.40		Sqm	1	1.50	0.75	0.75	0.75		1.13		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
1.10	42.00		Sqm	1	0.90	0.90	0.90	0.90		0.81		
		2nd Cross Road										
		(From East to West)										
		LHS										
0.00	3.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
13.00	15.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
28.80	30.00		Sqm	1	1.20	0.90	0.90	0.90		1.08		
42.00	43.80		Sqm	1	1.80	0.90	0.90	0.90		1.62		
		RHS										
0.00	2.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
9.30	12.00		Sqm	1	2.70	0.90	0.90	0.90		2.43		
21.70	22.00		Sqm	1	0.30	0.90	0.90	0.90		0.27		
		Saravora Layout										
		AMCO Layout										
		LHS										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	62.30		Sqm	1	2.30	0.90	0.90	0.90		2.07		
		Sarovara Layout										
		AMCO Layout										
		1st Main Road										
		LHS										
		(N-S)										
0.00	15.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15.00	30.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30.00	45.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45.00	60.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60.00	75.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75.00	90.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90.00	105.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105.00	120.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120.00	135.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
135.00	150.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
150.00	165.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
165.00	180.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
180.00	195.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
195.00	210.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
210.00	225.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
225.00	240.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
240.00	255.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
255.00	270.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
270.00	285.00		Sqm	1	15.00	0.90	0.90	0.90		13.50		
285.00	290.10		Sqm	1	5.10	0.90	0.90	0.90		4.59		
		Ward No 10										
		Vidyaranyapura Sub division`										
		2nd Cross Road (From house										
		(From North to South)										
		LHS										
0.00	0.80		Sqm	1	0.80	0.75	0.75	0.75		0.60		
0.80	12.00	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
12.00	14.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
14.00	17.10	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
17.10	23.20	old CC	Sqm	1	6.10	0.75	0.75	0.75		4.58		
23.20	26.60		Sqm	1	3.40	0.75	0.75	0.75		2.55		
26.60	29.70	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
29.70	34.40	old CC	Sqm	1	4.70	0.75	0.75	0.75		3.53		
34.40	36.90		Sqm	1	2.50	0.75	0.75	0.75		1.88		
36.90	38.60	old CC	Sqm	1	1.70	0.75	0.75	0.75		1.28		
38.60	40.40		Sqm	1	1.80	0.75	0.75	0.75		1.35		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.40	52.90	old CC	Sqm	1	12.50	0.75	0.75	0.75		9.38		
52.90	56.60	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
56.60	58.10		Sqm	1	1.50	0.75	0.75	0.75		1.13		
58.10	60.00	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
60.00	70.00	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
70.00	75.10		Sqm	1	5.10	0.75	0.75	0.75		3.83		
75.10	78.60	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
78.60	82.90		Sqm	1	4.30	0.75	0.75	0.75		3.23		
82.90	97.90	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
97.90	105.40	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
105.40	106.60		Sqm	1	1.20	0.75	0.75	0.75		0.90		
106.60	115.90	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
115.90	130.90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
130.90	138.10		Sqm	1	7.20	0.75	0.75	0.75		5.40		
138.10	143.70	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
143.70	156.10		Sqm	1	12.40	0.75	0.75	0.75		9.30		
156.10	164.00	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
164.00	166.80		Sqm	1	2.80	0.75	0.75	0.75		2.10		
166.80	169.90	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
169.90	172.00	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
172.00	186.80	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
186.80	201.80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
201.80	216.80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
216.80	231.80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
231.80	246.80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
246.80	254.00		Sqm	1	7.20	0.75	0.75	0.75		5.40		
254.00	262.10	Culvert	Sqm	1	0.00	0.75	0.75	0.75		0.00		
262.10	277.10		Sqm	1	15.00	0.75	0.75	0.75		11.25		
277.10	292.10		Sqm	1	15.00	0.75	0.75	0.75		11.25		
292.10	302.20		Sqm	1	10.10	0.75	0.75	0.75		7.57		
		RHS										
		(From Vidyaranyapura Main Road)										
		From South to North										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	45.00		Sqm	1	30.00	0.75	0.75	0.75		22.50		
45.00	75.00		Sqm	1	30.00	0.75	0.75	0.75		22.50		
75.00	76.30		Sqm	1	1.30	0.75	0.75	0.75		0.97		
		Chamundeswari Layout										
		3rd Cross Road (Shree Nagamma Devasthana)										
		(From East to West)										
		RHS										
0.00	15.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15.00	30.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30.00	45.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45.00	60.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60.00	75.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75.00	90.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90.00	105.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105.00	120.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120.00	135.00		Sqm	1	15.00	0.75	0.75	0.75		11.25		
135.00	136.40		Sqm	1	1.40	0.75	0.75	0.75		1.05		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Doddabomsandra										
		Gas Godown Road										
0.00	6.80		Sqm	1	6.80	0.75	0.75	0.75		5.10		
		BLOOM FIELD GARDEN										
		Main Road										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
		LHS										
100.00	103.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
113.00	115.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
124.00	126.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
136.50	139.00		Sqm	1	2.50	0.75	0.75	0.75		1.88		
145.00	149.00		Sqm	1	4.00	0.75	0.75	0.75		3.00		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
		LHS										
58.00	60.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
71.00	74.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
83.00	86.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
98.00	100.50		Sqm	1	2.50	0.75	0.75	0.75		1.88		
109.00	111.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
231.00	233.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
239.00	240.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
244.00	245.10		Sqm	1	1.10	0.75	0.75	0.75		0.82		
258.00	260.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
269.00	270.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
280.00	282.20		Sqm	1	2.20	0.75	0.75	0.75		1.65		
		RHS										
205.00	206.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
212.00	213.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
233.50	235.00		Sqm	1	1.50	0.60	0.60	0.60		0.90		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura										
		(From North to South)										
		RHS										
4.00	5.00		Sqm	1	1.00	0.90	0.90	0.90		0.90		
8.00	9.60		Sqm	1	1.60	0.90	0.90	0.90		1.44		
56.00	58.10		Sqm	1	2.10	0.75	0.75	0.75		1.58		
91.00	94.80		Sqm	1	3.80	0.75	0.75	0.75		2.85		
		3rd Cross Road										
		(From South to North)										
		LHS										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	92.80		Sqm	1	2.80	0.75	0.75	0.75		2.10		
152.00	153.00		Sqm	1	1.00	0.75	0.75	0.75		0.75		
156.00	158.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
161.00	163.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
		RHS										
12.00	14.10		Sqm	1	2.10	0.75	0.75	0.75		1.58		
86.00	88.70		Sqm	1	2.70	0.75	0.75	0.75		2.03		
97.00	100.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
124.00	126.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
130.00	132.80		Sqm	1	2.80	0.75	0.75	0.75		2.10		
142.00	144.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
		5th Cross Road										
25.00	27.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
82.00	85.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
90.00	93.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
108.00	110.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
118.00	121.00		Sqm	1	3.00	0.75	0.75	0.75		2.25		
131.00	132.70		Sqm	1	1.70	0.75	0.75	0.75		1.27		
153.00	155.00		Sqm	1	2.00	0.75	0.75	0.75		1.50		
									Total Executed Quantity	**2423.33**	**2175.19**	**5271193.00**
									Tender Quantity	**3479.69**		
Item no.10		**Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)**										
		Ward No 07										
		Muniswami Gowda Layout										
		2nd Cross Road										
			Sqm	1	5.80	1.50	1.50	1.50		8.70		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		RHS										
			Sqm	1	8.30	1.20	1.20	1.20		9.96		
			Sqm	1	7.40	1.50	1.50	1.50		11.10		
		LHS										
			Sqm	1	7.40	1.50	1.50	1.50		11.10		
			Sqm	1	7.70	1.50	1.50	1.50		11.55		
		2nd Main Road Dead End										
			Sqm	1	6.50	1.50	1.50	1.50		9.75		
			Sqm	1	5.60	1.50	1.50	1.50		8.40		
		Ward No 08										
		Sarovara Layout										
		1st Main Road										
			Sqm	1	6.70	1.20	1.20	1.20		8.04		
		Cross Road	Sqm	1	5.10	1.20	1.20	1.20		6.12		
		Ward No 10										
		Vidyaranyapura Sub division`										
		BEL 2nd Block										
		5th Cross Road										
			Sqm	1	7.40	1.50	1.50	1.50		11.10		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Chamundeshwari Layout										
		6th Cross Road										
			Sqm	1	5.50	1.20	1.20	1.20		6.60		
		7th Cross Road										
			Sqm	1	6.00	1.20	1.20	1.20		7.20		
		8th Cross Road										
			Sqm	1	5.40	1.20	1.20	1.20		6.48		
		9th Cross Road										
			Sqm	1	6.00	1.20	1.20	1.20		7.20		
		10th Cross Road										
			Sqm	1	5.40	1.20	1.20	1.20		6.48		
		Gas godown Road										
			Sqm	1	7.30	1.20	1.20	1.20		8.76		
			Sqm	1	5.50	1.20	1.20	1.20		6.60		
		Patel Gopalappa Layout										
		7th Cross road	Sqm	1	7.20	1.20	1.20	1.20		8.64		
		Near 7th Cross Road	Sqm	1	6.50	1.80	1.80	1.80		11.70		
		Muneshwara layout										
		1st Main road	Sqm	1	5.50	1.20	1.20	1.20		6.60		
									Total Executed Qty	**172.08**	**5287.84**	**909932.00**
									Tender Quantity	**510.24**		
Item no.11		**Providing B S slabs of selected quality roughly dressed having a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete. as directed by the Engineer in Charge of the work (excluding GST and Area Leading Charges)**										
		Item is Not Operated										
Item no.12		**Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work (Approved Rate)**										
		Ward No 08										
		Shanubhoga Narayanappa Layout	Nos									
		1st D Cross Road										
		RHS										
		(From East To West)										
		(From H.No #532 To										
0	11.3	No Work	m	1	0.00					0.00		
11.3	19.3		m	1	8.00					8.00		
19.3	28.9	No Work	m	1	0.00					0.00		
28.9	37.6		m	1	8.70					8.70		
37.6	47.2	No Work	m	1	0.00					0.00		
47.2	62.2		m	1	15.00					15.00		
62.2	65.2		m	1	3.00					3.00		
65.2	78.5	No Work	m	1	0.00					0.00		
78.5	93.5		m	1	15.00					15.00		
93.5	101.7		m	1	8.20					8.20		
101.7	114.5	No Work	m	1	0.00					0.00		
114.5	129.5		m	1	15.00					15.00		
129.5	137.5		m	1	8.00					8.00		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0	3.5		m	1	3.50					3.50		
3.5	7.5	No Work	m	1	0.00					0.00		
7.5	12.9		m	1	5.40					5.40		
12.9	51.5	No Work	m	1	0.00					0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
1.5	66.5		m	1	15.00					15.00		
66.5	81.5		m	1	15.00					15.00		
81.5	96.5		m	1	15.00					15.00		
96.5	106.6		m	1	10.10					10.10		
106.6	119.2	No Work	m	1	0.00					0.00		
119.2	130.7		m	1	11.50					11.50		
130.7	139	Culvert	m	1	0.00					0.00		
139	140.9	No Work	m	1	0.00					0.00		
140.9	155.9		m	1	15.00					15.00		
155.9	170.9		m	1	15.00					15.00		
170.9	177.1		m	1	6.20					6.20		
177.1	186.1	No Work	m	1	0.00					0.00		
186.1	201.1		m	1	15.00					15.00		
201.1	204.8		m	1	3.70					3.70		
204.8	214.2	No Work	m	1	0.00					0.00		
214.2	223.3		m	1	9.10					9.10		
223.3	232.8	No Work	m	1	0.00					0.00		
232.8	240.2	Culvert	m	1	0.00					0.00		
240.2	255.2		m	1	15.00					15.00		
255.2	270.2		m	1	15.00					15.00		
270.2	276.3		m	1	6.10					6.10		
276.3	279.1	No Work	m	1	0.00					0.00		
		(From West To East)										
		LHS										
0	14.6		m	1	14.60					14.60		
14.6	17.9	No Work	m	1	0.00					0.00		
17.9	21.4		m	1	3.50					3.50		
21.4	22.7	No Work	m	1	0.00					0.00		
22.7	30.1	Culvert	m	1	0.00					0.00		
30.1	31.5	No Work	m	1	0.00					0.00		
31.5	46.5		m	1	15.00					15.00		
46.5	61.5		m	1	15.00					15.00		
61.5	76.5		m	1	15.00					15.00		
76.5	91.5		m	1	15.00					15.00		
91.5	106.1		m	1	14.60					14.60		
106.1	119.5	No Work	m	1	0.00					0.00		
119.5	130.8		m	1	11.30					11.30		
130.8	132.2	No Work	m	1	0.00					0.00		
132.2	139.9	Culvert	m	1	0.00					0.00		
139.9	140.6	No Work	m	1	0.00					0.00		
140.6	155.6		m	1	15.00					15.00		
155.6	165.8		m	1	10.20					10.20		
165.8	173	No Work	m	1	0.00					0.00		
173	184.2		m	1	11.20					11.20		
184.2	185.3	No Work	m	1	0.00					0.00		
185.3	200.3		m	1	15.00					15.00		
200.3	215.3		m	1	15.00					15.00		
215.3	230.3		m	1	15.00					15.00		
230.3	242.6		m	1	12.30					12.30		
242.6	252.1	No Work	m	1	0.00					0.00		
252.1	267.1		m	1	15.00					15.00		
267.1	277.3		m	1	10.20					10.20		
277.3	278.9	No Work	m	1	0.00					0.00		
		1st Cross Road										
		LHS										
		(West To East)										
0	4.5		m	1	4.50					4.50		
4.5	5.1	No Kerb	m	1	0.00					0.00		
5.1	12.7		m	1	7.60					7.60		
12.7	27.7		m	1	15.00					15.00		
27.7	38		m	1	10.30					10.30		
38	39.1		m	1	1.10					1.10		
39.1	42.6		m	1	3.50					3.50		
42.6	48.4	No Kerb	m	1	0.00					0.00		
48.4	52.8		m	1	4.40					4.40		
52.8	53.9		m	1	1.10					1.10		
53.9	59.1		m	1	5.20					5.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(East To West)										
		RHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	42.2		m	1	12.20					12.20		
42.2	46.7		m	1	4.50					4.50		
46.7	48.7	No Kerb	m	1	0.00					0.00		
48.7	54.1		m	1	5.40					5.40		
54.1	57.4		m	1	3.30					3.30		
57.4	59.5	No Kerb	m	1	0.00					0.00		
		Ward No 08										
		AMCO Layout										
		A Block 1st Main Road,										
		(North To South)										
		L.H.S										
0.00	15.00		m	1	15.00					15.00		
15.00	30.00		m	1	15.00					15.00		
30.00	45.00		m	1	15.00					15.00		
45.00	60.00		m	1	15.00					15.00		
60.00	75.00		m	1	15.00					15.00		
75.00	90.00		m	1	15.00					15.00		
90.00	105.00		m	1	15.00					15.00		
105.00	120.00		m	1	15.00					15.00		
120.00	135.00		m	1	15.00					15.00		
135.00	150.00		m	1	15.00					15.00		
150.00	165.00		m	1	15.00					15.00		
165.00	180.00		m	1	15.00					15.00		
180.00	195.00		m	1	15.00					15.00		
195.00	210.00		m	1	15.00					15.00		
210.00	225.00		m	1	15.00					15.00		
225.00	229.60		m	1	4.60					4.60		
		R.H.S										
		(North To South)										
0.00	15.00		m	1	15.00					15.00		
15.00	19.80		m	1	4.80					4.80		
19.80	27.10	No Kerb	m	0	7.30					0.00		
27.10	30.00		m	1	2.90					2.90		
30.00	42.90		m	1	12.90					12.90		
42.90	45.00	No Kerb	m	0	2.10					0.00		
45.00	46.00	No Kerb	m	0	1.00					0.00		
46.00	50.60		m	1	4.60					4.60		
50.60	59.10	No Kerb	m	0	8.50					0.00		
59.10	60.00		m	1	0.90					0.90		
60.00	75.00		m	1	15.00					15.00		
75.00	85.30		m	1	10.30					10.30		
85.30	90.00	No Kerb	m	0	4.70					0.00		
90.00	96.10	No Kerb	m	0	6.10					0.00		
96.10	105.00		m	1	8.90					8.90		
105.00	120.00		m	1	15.00					15.00		
120.00	135.00		m	1	15.00					15.00		
135.00	135.20		m	1	0.20					0.20		
135.20	142.70	No Kerb	m	0	7.50					0.00		
142.70	150.00		m	1	7.30					7.30		
150.00	165.00		m	1	15.00					15.00		
165.00	170.80		m	1	5.80					5.80		
		Sapthagiri Hall Road										
		R.H.S										
		(East To West)										
0.00	15.00		m	1	15.00					15.00		
15.00	21.90		m	1	6.90					6.90		
21.90	30.00	No Kerb	m	0	8.10					0.00		
30.00	38.40	No Kerb	m	0	8.40					0.00		
38.40	43.30		m	1	4.90					4.90		
43.30	45.00	No Kerb	m	0	1.70					0.00		
45.00	49.70	No Kerb	m	0	4.70					0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.70	56.80		m	1	7.10					7.10		
56.80	60.00	No Kerb	m	0	3.20					0.00		
60.00	72.20	No Kerb	m	0	12.20					0.00		
72.20	75.00		m	1	2.80					2.80		
75.00	85.40		m	1	10.40					10.40		
85.40	90.00	No Kerb	m	0	4.60					0.00		
90.00	90.50	No Kerb	m	0	0.50					0.00		
90.50	105.00		m	1	14.50					14.50		
105.00	114.30		m	1	9.30					9.30		
114.30	118.20	No Kerb	m	0	3.90					0.00		
118.20	120.00		m	1	1.80					1.80		
120.00	128.20		m	1	8.20					8.20		
128.20	132.70	No Kerb	m	0	4.50					0.00		
132.70	135.00		m	1	2.30					2.30		
135.00	138.60		m	1	3.60					3.60		
138.60	146.90	No Kerb	m	0	8.30					0.00		
146.90	150.00		m	1	3.10					3.10		
150.00	165.00		m	1	15.00					15.00		
165.00	174.50		m	1	9.50					9.50		
174.50	180.00	No Kerb	m	0	5.50					0.00		
180.00	185.60	No Kerb	m	0	5.60					0.00		
185.60	194.80		m	1	9.20					9.20		
		L.H.S										
		(East To west)										
0.00	15.00		m	1	15.00					15.00		
15.00	30.00		m	1	15.00					15.00		
30.00	44.20		m	1	14.20					14.20		
44.20	45.00	No Kerb	m	0	0.80					0.00		
45.00	50.30	No Kerb	m	0	5.30					0.00		
50.30	60.00		m	1	9.70					9.70		
60.00	67.80		m	1	7.80					7.80		
67.80	75.00	No Kerb	m	0	7.20					0.00		
75.00	83.90	No Kerb	m	0	8.90					0.00		
83.90	90.00		m	1	6.10					6.10		
90.00	91.80		m	1	1.80					1.80		
91.80	99.30	No Kerb	m	0	7.50					0.00		
99.30	105.00		m	1	5.70					5.70		
105.00	120.00		m	1	15.00					15.00		
120.00	131.50		m	1	11.50					11.50		
131.50	135.00	No Kerb	m	0	0.00					0.00		
135.00	135.40	No Kerb	m	0	0.00					0.00		
135.40	143.00		m	1	7.60					7.60		
143.00	149.70	No Kerb	m	0	6.70					0.00		
149.70	150.00		m	1	0.30					0.30		
150.00	165.00		m	1	15.00					15.00		
165.00	174.80		m	1	9.80					9.80		
174.80	180.00	No Kerb	m	0	5.20					0.00		
180.00	195.00	No Kerb	m	0	15.00					0.00		
195.00	197.50	No Kerb	m	0	2.50					0.00		
197.50	210.00		m	1	12.50					12.50		
210.00	216.50		m	1	6.50					6.50		
216.50	225.00	No Kerb	m	0	8.50					0.00		
225.00	240.00	No Kerb	m	0	15.00					0.00		
240.00	245.80	No Kerb	m	0	5.80					0.00		
245.80	255.00		m	1	9.20					9.20		
255.00	255.50		m	1	0.50					0.50		
									Sub Total	1237.50		
			Nos						Total Length/0.45	2750.00		
									Total Executed Quantity	**2750.00**	**532.25**	**1463688.00**
									Tender Quantity	**3295.00**		
Item no.13		**Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces**										
		Ward No 08										
		Shanubhoga Narayanappa Layout	Sqm									
		1st D Cross Road										
		RHS										
		(From East To West)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From H.No #532 To Empty Site)										
0	11.3	No Work	Sqm	1	0.00				0.35	0.00		
11.3	19.3		Sqm	1	8.00				0.35	2.80		
19.3	28.9	No Work	Sqm	1	0.00				0.35	0.00		
28.9	37.6		Sqm	1	8.70				0.35	3.05		
37.6	47.2	No Work	Sqm	1	0.00				0.35	0.00		
47.2	62.2		Sqm	1	15.00				0.35	5.25		
62.2	65.2		Sqm	1	3.00				0.35	1.05		
65.2	78.5	No Work	Sqm	1	0.00				0.35	0.00		
78.5	93.5		Sqm	1	15.00				0.35	5.25		
93.5	101.7		Sqm	1	8.20				0.35	2.87		
101.7	114.5	No Work	Sqm	1	0.00				0.35	0.00		
114.5	129.5		Sqm	1	15.00				0.35	5.25		
129.5	137.5		Sqm	1	8.00				0.35	2.80		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
		RHS										
0	3.5		Sqm	1	3.50				0.35	1.23		
3.5	7.5	No Work	Sqm	1	0.00				0.35	0.00		
7.5	12.9		Sqm	1	5.40				0.35	1.89		
12.9	51.5	No Work	Sqm	1	0.00				0.35	0.00		
51.5	66.5		Sqm	1	15.00				0.35	5.25		
66.5	81.5		Sqm	1	15.00				0.35	5.25		
81.5	96.5		Sqm	1	15.00				0.35	5.25		
96.5	106.6		Sqm	1	10.10				0.35	3.54		
106.6	119.2	No Work	Sqm	1	0.00				0.35	0.00		
119.2	130.7		Sqm	1	11.50				0.35	4.03		
130.7	139	Culvert	Sqm	1	0.00				0.35	0.00		
139	140.9	No Work	Sqm	1	0.00				0.35	0.00		
140.9	155.9		Sqm	1	15.00				0.35	5.25		
155.9	170.9		Sqm	1	15.00				0.35	5.25		
170.9	177.1		Sqm	1	6.20				0.35	2.17		
177.1	186.1	No Work	Sqm	1	0.00				0.35	0.00		
186.1	201.1		Sqm	1	15.00				0.35	5.25		
201.1	204.8		Sqm	1	3.70				0.35	1.30		
204.8	214.2	No Work	Sqm	1	0.00				0.35	0.00		
214.2	223.3		Sqm	1	9.10				0.35	3.19		
223.3	232.8	No Work	Sqm	1	0.00				0.35	0.00		
232.8	240.2	Culvert	Sqm	1	0.00				0.35	0.00		
240.2	255.2		Sqm	1	15.00				0.35	5.25		
255.2	270.2		Sqm	1	15.00				0.35	5.25		
270.2	276.3		Sqm	1	6.10				0.35	2.14		
276.3	279.1	No Work	Sqm	1	0.00				0.35	0.00		
		(From West To East)										
		LHS										
0	14.6		Sqm	1	14.60				0.35	5.11		
14.6	17.9	No Work	Sqm	1	0.00				0.35	0.00		
17.9	21.4		Sqm	1	3.50				0.35	1.23		
21.4	22.7	No Work	Sqm	1	0.00				0.35	0.00		
22.7	30.1	Culvert	Sqm	1	0.00				0.35	0.00		
30.1	31.5	No Work	Sqm	1	0.00				0.35	0.00		
31.5	46.5		Sqm	1	15.00				0.35	5.25		
46.5	61.5		Sqm	1	15.00				0.35	5.25		
61.5	76.5		Sqm	1	15.00				0.35	5.25		
76.5	91.5		Sqm	1	15.00				0.35	5.25		
91.5	106.1		Sqm	1	14.60				0.35	5.11		
106.1	119.5	No Work	Sqm	1	0.00				0.35	0.00		
119.5	130.8		Sqm	1	11.30				0.35	3.96		
130.8	132.2	No Work	Sqm	1	0.00				0.35	0.00		
132.2	139.9	Culvert	Sqm	1	0.00				0.35	0.00		
139.9	140.6	No Work	Sqm	1	0.00				0.35	0.00		
140.6	155.6		Sqm	1	15.00				0.35	5.25		
155.6	165.8		Sqm	1	10.20				0.35	3.57		
165.8	173	No Work	Sqm	1	0.00				0.35	0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
73	184.2		Sqm	1	11.20				0.35	3.92		
184.2	185.3	No Work	Sqm	1	0.00				0.35	0.00		
185.3	200.3		Sqm	1	15.00				0.35	5.25		
200.3	215.3		Sqm	1	15.00				0.35	5.25		
215.3	230.3		Sqm	1	15.00				0.35	5.25		
230.3	242.6		Sqm	1	12.30				0.35	4.30		
242.6	252.1	No Work	Sqm	1	0.00				0.35	0.00		
252.1	267.1		Sqm	1	15.00				0.35	5.25		
267.1	277.3		Sqm	1	10.20				0.35	3.57		
277.3	278.9	No Work	Sqm	1	0.00				0.35	0.00		
		1st Cross Road										
		LHS										
		(West To East)										
0	4.5		Sqm	1	4.50				0.35	1.58		
4.5	5.1	No Kerb	Sqm	1	0.00				0.35	0.00		
5.1	12.7		Sqm	1	7.60				0.35	2.66		
12.7	27.7		Sqm	1	15.00				0.35	5.25		
27.7	38		Sqm	1	10.30				0.35	3.61		
38	39.1		Sqm	1	1.10				0.35	0.39		
39.1	42.6		Sqm	1	3.50				0.35	1.23		
42.6	48.4	No Kerb	Sqm	1	0.00				0.35	0.00		
48.4	52.8		Sqm	1	4.40				0.35	1.54		
52.8	53.9		Sqm	1	1.10				0.35	0.39		
53.9	59.1		Sqm	1	5.20				0.35	1.82		
		(East To West)										
		RHS										
0	15		Sqm	1	15.00				0.35	5.25		
15	30		Sqm	1	15.00				0.35	5.25		
30	42.2		Sqm	1	12.20				0.35	4.27		
42.2	46.7		Sqm	1	4.50				0.35	1.58		
46.7	48.7	No Kerb	Sqm	1	0.00				0.35	0.00		
48.7	54.1		Sqm	1	5.40				0.35	1.89		
54.1	57.4		Sqm	1	3.30				0.35	1.16		
57.4	59.5	No Kerb	Sqm	1	0.00				0.35	0.00		
		Ward No 08										
		AMCO Layout										
		A Block 1st Main Road,										
		(North To South)										
		L.H.S										
0.00	15.00		Sqm	1	15.00				0.35	5.25		
15.00	30.00		Sqm	1	15.00				0.35	5.25		
30.00	45.00		Sqm	1	15.00				0.35	5.25		
45.00	60.00		Sqm	1	15.00				0.35	5.25		
60.00	75.00		Sqm	1	15.00				0.35	5.25		
75.00	90.00		Sqm	1	15.00				0.35	5.25		
90.00	105.00		Sqm	1	15.00				0.35	5.25		
105.00	120.00		Sqm	1	15.00				0.35	5.25		
120.00	135.00		Sqm	1	15.00				0.35	5.25		
135.00	150.00		Sqm	1	15.00				0.35	5.25		
150.00	165.00		Sqm	1	15.00				0.35	5.25		
165.00	180.00		Sqm	1	15.00				0.35	5.25		
180.00	195.00		Sqm	1	15.00				0.35	5.25		
195.00	210.00		Sqm	1	15.00				0.35	5.25		
210.00	225.00		Sqm	1	15.00				0.35	5.25		
225.00	229.60		Sqm	1	4.60				0.35	1.61		
		R.H.S										
		(North To South)										
0.00	15.00		Sqm	1	15.00				0.35	5.25		
15.00	19.80		Sqm	1	4.80				0.35	1.68		
19.80	27.10	No Kerb	Sqm	0	7.30				0.35	0.00		
27.10	30.00		Sqm	1	2.90				0.35	1.02		
30.00	42.90		Sqm	1	12.90				0.35	4.52		
42.90	45.00	No Kerb	Sqm	0	2.10				0.35	0.00		
45.00	46.00	No Kerb	Sqm	0	1.00				0.35	0.00		
46.00	50.60		Sqm	1	4.60				0.35	1.61		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.60	59.10	No Kerb	Sqm	0	8.50				0.35	0.00		
59.10	60.00		Sqm	1	0.90				0.35	0.32		
60.00	75.00		Sqm	1	15.00				0.35	5.25		
75.00	85.30		Sqm	1	10.30				0.35	3.61		
85.30	90.00	No Kerb	Sqm	0	4.70				0.35	0.00		
90.00	96.10	No Kerb	Sqm	0	6.10				0.35	0.00		
96.10	105.00		Sqm	1	8.90				0.35	3.12		
105.00	120.00		Sqm	1	15.00				0.35	5.25		
120.00	135.00		Sqm	1	15.00				0.35	5.25		
135.00	135.20		Sqm	1	0.20				0.35	0.07		
135.20	142.70	No Kerb	Sqm	0	7.50				0.35	0.00		
142.70	150.00		Sqm	1	7.30				0.35	2.56		
150.00	165.00		Sqm	1	15.00				0.35	5.25		
165.00	170.80		Sqm	1	5.80				0.35	2.03		
		Sapthagiri Hall Road										
		R.H.S										
		(East To West)										
0.00	15.00		Sqm	1	15.00				0.35	5.25		
15.00	21.90		Sqm	1	6.90				0.35	2.42		
21.90	30.00	No Kerb	Sqm	0	8.10				0.35	0.00		
30.00	38.40	No Kerb	Sqm	0	8.40				0.35	0.00		
38.40	43.30		Sqm	1	4.90				0.35	1.72		
43.30	45.00	No Kerb	Sqm	0	1.70				0.35	0.00		
45.00	49.70	No Kerb	Sqm	0	4.70				0.35	0.00		
49.70	56.80		Sqm	1	7.10				0.35	2.49		
56.80	60.00	No Kerb	Sqm	0	3.20				0.35	0.00		
60.00	72.20	No Kerb	Sqm	0	12.20				0.35	0.00		
72.20	75.00		Sqm	1	2.80				0.35	0.98		
75.00	85.40		Sqm	1	10.40				0.35	3.64		
85.40	90.00	No Kerb	Sqm	0	4.60				0.35	0.00		
90.00	90.50	No Kerb	Sqm	0	0.50				0.35	0.00		
90.50	105.00		Sqm	1	14.50				0.35	5.08		
105.00	114.30		Sqm	1	9.30				0.35	3.26		
114.30	118.20	No Kerb	Sqm	0	3.90				0.35	0.00		
118.20	120.00		Sqm	1	1.80				0.35	0.63		
120.00	128.20		Sqm	1	8.20				0.35	2.87		
128.20	132.70	No Kerb	Sqm	0	4.50				0.35	0.00		
132.70	135.00		Sqm	1	2.30				0.35	0.81		
135.00	138.60		Sqm	1	3.60				0.35	1.26		
138.60	146.90	No Kerb	Sqm	0	8.30				0.35	0.00		
146.90	150.00		Sqm	1	3.10				0.35	1.09		
150.00	165.00		Sqm	1	15.00				0.35	5.25		
165.00	174.50		Sqm	1	9.50				0.35	3.33		
174.50	180.00	No Kerb	Sqm	0	5.50				0.35	0.00		
180.00	185.60	No Kerb	Sqm	0	5.60				0.35	0.00		
185.60	194.80		Sqm	1	9.20				0.35	3.22		
		L.H.S										
		(East To west)										
0.00	15.00		Sqm	1	15.00				0.35	5.25		
15.00	30.00		Sqm	1	15.00				0.35	5.25		
30.00	44.20		Sqm	1	14.20				0.35	4.97		
44.20	45.00	No Kerb	Sqm	0	0.80				0.35	0.00		
45.00	50.30	No Kerb	Sqm	0	5.30				0.35	0.00		
50.30	60.00		Sqm	1	9.70				0.35	3.40		
60.00	67.80		Sqm	1	7.80				0.35	2.73		
67.80	75.00	No Kerb	Sqm	0	7.20				0.35	0.00		
75.00	83.90	No Kerb	Sqm	0	8.90				0.35	0.00		
83.90	90.00		Sqm	1	6.10				0.35	2.14		
90.00	91.80		Sqm	1	1.80				0.35	0.63		
91.80	99.30	No Kerb	Sqm	0	7.50				0.35	0.00		
99.30	105.00		Sqm	1	5.70				0.35	2.00		
105.00	120.00		Sqm	1	15.00				0.35	5.25		
120.00	131.50		Sqm	1	11.50				0.35	4.03		
131.50	135.00	No Kerb	Sqm	0	0.00				0.35	0.00		
135.00	135.40	No Kerb	Sqm	0	0.00				0.35	0.00		
135.40	143.00		Sqm	1	7.60				0.35	2.66		
143.00	149.70	No Kerb	Sqm	0	6.70				0.35	0.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.70	150.00		Sqm	1	0.30				0.35	0.11		
150.00	165.00		Sqm	1	15.00				0.35	5.25		
165.00	174.80		Sqm	1	9.80				0.35	3.43		
174.80	180.00	No Kerb	Sqm	0	5.20				0.35	0.00		
180.00	195.00	No Kerb	Sqm	0	15.00				0.35	0.00		
195.00	197.50	No Kerb	Sqm	0	2.50				0.35	0.00		
197.50	210.00		Sqm	1	12.50				0.35	4.38		
210.00	216.50		Sqm	1	6.50				0.35	2.28		
216.50	225.00	No Kerb	Sqm	0	8.50				0.35	0.00		
225.00	240.00	No Kerb	Sqm	0	15.00				0.35	0.00		
240.00	245.80	No Kerb	Sqm	0	5.80				0.35	0.00		
245.80	255.00		Sqm	1	9.20				0.35	3.22		
255.00	255.50		Sqm	1	0.50				0.35	0.18		
								Total Executed Quantity		**433.13**	**98.16**	**42516.00**
								Tender Quantity		**736.40**		

Item no.14	**Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth. and as per the directions of the Engineer-in-charge of the work .**

		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
2.00	6.00		Cum	1	4.00	0.60	0.60	0.60	0.25	0.60		
8.00	13.00		Cum	1	5.00	0.75	0.75	0.75	0.25	0.94		
17.00	29.00		Cum	1	12.00	1.20	1.20	1.20	0.25	3.60		
32.00	43.00		Cum	1	11.00	1.00	1.00	1.00	0.25	2.75		
48.00	57.00		Cum	1	9.00	1.60	1.60	1.60	0.25	3.60		
63.00	71.00		Cum	1	8.00	1.20	1.20	1.20	0.25	2.40		
77.00	88.00		Cum	1	11.00	1.80	1.80	1.80	0.25	4.95		
94.00	103.00		Cum	1	9.00	1.10	1.10	1.10	0.25	2.48		
107.00	110.00		Cum	1	3.00	0.60	0.60	0.60	0.25	0.45		
112.00	118.00		Cum	1	6.00	1.70	1.70	1.70	0.25	2.55		
123.00	133.00		Cum	1	10.00	1.70	1.70	1.70	0.25	4.25		
137.00	144.00		Cum	1	7.00	1.80	1.80	1.80	0.25	3.15		
145.00	152.00		Cum	1	7.00	1.50	1.50	1.50	0.25	2.63		
154.00	163.00		Cum	1	9.00	1.35	1.35	1.35	0.25	3.04		
165.00	172.40		Cum	1	7.40	1.60	1.60	1.60	0.25	2.96		
173.10	180.00		Cum	1	6.90	1.50	1.50	1.50	0.25	2.59		
184.00	192.80		Cum	1	8.80	1.90	1.90	1.90	0.25	4.18		
195.00	200.80		Cum	1	5.80	2.00	2.00	2.00	0.25	2.90		
		Ravi Gowda Layout										
		(From North to South)										
3.50	12.00		Cum	1	8.50	1.30	1.30	1.30	0.25	2.76		
18.00	28.00		Cum	1	10.00	1.80	1.80	1.80	0.25	4.50		
32.80	41.00		Cum	1	8.20	2.30	2.30	2.30	0.25	4.72		
48.00	57.00		Cum	1	9.00	2.60	2.60	2.60	0.25	5.85		
62.40	70.00		Cum	1	7.60	1.80	1.80	1.80	0.25	3.42		
79.00	88.30		Cum	1	9.30	1.90	1.90	1.90	0.25	4.42		
96.00	101.20		Cum	1	5.20	2.30	2.30	2.30	0.25	2.99		
107.60	117.00		Cum	1	9.40	2.25	2.25	2.25	0.25	5.29		
120.00	126.00		Cum	1	6.00	1.40	1.40	1.40	0.25	2.10		
128.00	133.00		Cum	1	5.00	1.70	1.70	1.70	0.25	2.13		
137.00	140.00		Cum	1	3.00	1.60	1.60	1.60	0.25	1.20		
143.00	148.00		Cum	1	5.00	1.00	1.00	1.00	0.25	1.25		
155.00	162.60		Cum	1	7.60	1.70	1.70	1.70	0.25	3.23		
167.90	178.20		Cum	1	10.30	1.50	1.50	1.50	0.25	3.86		
183.00	191.00		Cum	1	8.00	1.60	1.60	1.60	0.25	3.20		
198.00	207.00		Cum	1	9.00	1.35	1.35	1.35	0.25	3.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	213.50		Cum	1	1.50	1.00	1.00	1.00	0.25	0.38		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
6.00	11.00		Cum	1	5.00	1.40	1.40	1.40	0.25	1.75		
17.00	28.00		Cum	1	11.00	1.60	1.60	1.60	0.25	4.40		
32.00	41.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
47.00	55.00		Cum	1	8.00	1.80	1.80	1.80	0.25	3.60		
58.70	64.70		Cum	1	6.00	2.00	2.00	2.00	0.25	3.00		
66.00	69.20		Cum	1	3.20	1.30	1.30	1.30	0.25	1.04		
		Jai Rama Layout Main Road										
		(From East to West)										
4.00	11.00		Cum	1	7.00	1.60	1.60	1.60	0.25	2.80		
17.00	27.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
33.70	41.60		Cum	1	7.90	1.00	1.00	1.00	0.25	1.98		
45.80	57.30		Cum	1	11.50	2.30	2.30	2.30	0.25	6.61		
63.40	73.40		Cum	1	10.00	1.70	1.70	1.70	0.25	4.25		
80.00	88.90		Cum	1	8.90	1.60	1.60	1.60	0.25	3.56		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.25	3.99		
108.00	111.00		Cum	1	3.00	2.00	2.00	2.00	0.25	1.50		
114.70	118.30		Cum	1	3.60	3.00	3.00	3.00	0.25	2.70		
		1st Cross Road (Or)										
		Five Star Security Service										
		(From South to North)										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
18.00	27.80		Cum	1	9.80	1.70	1.70	1.70	0.25	4.17		
33.00	41.50		Cum	1	8.50	1.65	1.65	1.65	0.25	3.51		
48.90	57.60		Cum	1	8.70	1.90	1.90	1.90	0.25	4.13		
61.80	67.90		Cum	1	6.10	2.60	2.60	2.60	0.25	3.97		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Cum	1	3.50	3.00	3.00	3.00	0.25	2.63		
6.00	13.00		Cum	1	7.00	3.00	3.00	3.00	0.25	5.25		
18.00	28.90		Cum	1	10.90	1.60	1.60	1.60	0.25	4.36		
32.60	42.70		Cum	1	10.10	1.90	1.90	1.90	0.25	4.80		
44.60	57.80		Cum	1	13.20	2.00	2.00	2.00	0.25	6.60		
63.50	74.50		Cum	1	11.00	2.30	2.30	2.30	0.25	6.33		
79.00	88.00		Cum	1	9.00	1.60	1.60	1.60	0.25	3.60		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.25	3.99		
108.00	118.00		Cum	1	10.00	2.60	2.60	2.60	0.25	6.50		
122.00	133.00		Cum	1	11.00	2.20	2.20	2.20	0.25	6.05		
137.00	147.00		Cum	1	10.00	1.70	1.70	1.70	0.25	4.25		
152.00	164.00		Cum	1	12.00	1.80	1.80	1.80	0.25	5.40		
167.00	178.00		Cum	1	11.00	2.00	2.00	2.00	0.25	5.50		
182.70	192.30		Cum	1	9.60	1.90	1.90	1.90	0.25	4.56		
197.60	208.60		Cum	1	11.00	2.20	2.20	2.20	0.25	6.05		
211.00	215.60		Cum	1	4.60	1.80	1.80	1.80	0.25	2.07		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Cum	1	3.40	1.80	1.80	1.80	0.25	1.53		
5.00	9.40		Cum	1	4.40	2.50	2.50	2.50	0.25	2.75		
12.00	18.50		Cum	1	6.50	1.70	1.70	1.70	0.25	2.76		
22.00	28.00		Cum	1	6.00	1.60	1.60	1.60	0.25	2.40		
34.00	37.80		Cum	1	3.80	1.10	1.10	1.10	0.25	1.05		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd A Cross Road										
		(From North to South)										
3.00	4.30		Cum	1	1.30	1.60	1.60	1.60	0.25	0.52		
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.25	2.28		
18.00	27.90		Cum	1	9.90	1.45	1.45	1.45	0.25	3.59		
34.60	42.10		Cum	1	7.50	1.75	1.75	1.75	0.25	3.28		
49.00	58.60		Cum	1	9.60	1.60	1.60	1.60	0.25	3.84		
63.60	72.90		Cum	1	9.30	1.45	1.45	1.45	0.25	3.37		
77.80	88.90		Cum	1	11.10	1.35	1.35	1.35	0.25	3.75		
93.10	103.60		Cum	1	10.50	1.20	1.20	1.20	0.25	3.15		
108.00	111.10		Cum	1	3.10	2.80	2.80	2.80	0.25	2.17		
		Dr. Rajkumar Road (or)1st A										
		(From East to West)										
3.00	11.00		Cum	1	8.00	1.60	1.60	1.60	0.25	3.20		
18.00	27.60		Cum	1	9.60	1.30	1.30	1.30	0.25	3.12		
34.00	42.60		Cum	1	8.60	1.60	1.60	1.60	0.25	3.44		
47.00	59.70		Cum	1	12.70	1.80	1.80	1.80	0.25	5.72		
62.30	74.20		Cum	1	11.90	2.00	2.00	2.00	0.25	5.95		
77.00	87.60		Cum	1	10.60	1.30	1.30	1.30	0.25	3.45		
92.60	94.40		Cum	1	1.80	1.10	1.10	1.10	0.25	0.50		
97.60	101.00		Cum	1	3.40	1.80	1.80	1.80	0.25	1.53		
105.00	109.20		Cum	1	4.20	1.10	1.10	1.10	0.25	1.16		
		2nd Cross Road										
		(From South to North)										
4.60	13.50		Cum	1	8.90	1.60	1.60	1.60	0.25	3.56		
17.80	27.90		Cum	1	10.10	1.20	1.20	1.20	0.25	3.03		
34.60	44.20		Cum	1	9.60	1.40	1.40	1.40	0.25	3.36		
47.60	58.70		Cum	1	11.10	1.80	1.80	1.80	0.25	5.00		
64.50	72.50		Cum	1	8.00	2.30	2.30	2.30	0.25	4.60		
77.00	88.00		Cum	1	11.00	1.90	1.90	1.90	0.25	5.23		
93.00	101.00		Cum	1	8.00	1.40	1.40	1.40	0.25	2.80		
107.00	117.00		Cum	1	10.00	1.70	1.70	1.70	0.25	4.25		
120.00	122.10		Cum	1	2.10	3.00	3.00	3.00	0.25	1.58		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
4.60	11.00		Cum	1	6.40	1.60	1.60	1.60	0.25	2.56		
18.60	27.60		Cum	1	9.00	1.55	1.55	1.55	0.25	3.49		
35.60	44.00		Cum	1	8.40	1.85	1.85	1.85	0.25	3.89		
49.50	57.60		Cum	1	8.10	2.00	2.00	2.00	0.25	4.05		
64.60	73.40		Cum	1	8.80	1.95	1.95	1.95	0.25	4.29		
78.90	87.90		Cum	1	9.00	2.10	2.10	2.10	0.25	4.73		
94.20	102.00		Cum	1	7.80	1.70	1.70	1.70	0.25	3.32		
108.00	117.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
126.00	132.00		Cum	1	6.00	1.70	1.70	1.70	0.25	2.55		
135.00	136.00		Cum	1	1.00	2.10	2.10	2.10	0.25	0.53		
		1st A K.V.J Road										
		(From West to East)										
3.60	12.50		Cum	1	8.90	0.90	0.90	0.90	0.25	2.00		
21.20	27.60		Cum	1	6.40	1.80	1.80	1.80	0.25	2.88		
31.00	33.30		Cum	1	2.30	1.60	1.60	1.60	0.25	0.92		
		2nd Cross Road Sunshine										
		(From North to South)										
3.00	11.80		Cum	1	8.80	2.00	2.00	2.00	0.25	4.40		
17.60	27.80		Cum	1	10.20	1.40	1.40	1.40	0.25	3.57		
32.80	41.20		Cum	1	8.40	1.70	1.70	1.70	0.25	3.57		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
60	57.90		Cum	1	9.30	1.65	1.65	1.65	0.25	3.84		
61.00	67.20		Cum	1	6.20	1.00	1.00	1.00	0.25	1.55		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
2.30	8.70		Cum	1	6.40	1.75	1.75	1.75	0.25	2.80		
9.90	15.00		Cum	1	5.10	2.10	2.10	2.10	0.25	2.68		
19.00	27.60		Cum	1	8.60	1.80	1.80	1.80	0.25	3.87		
33.60	43.50		Cum	1	9.90	1.60	1.60	1.60	0.25	3.96		
50.00	57.80		Cum	1	7.80	1.50	1.50	1.50	0.25	2.93		
68.50	73.00		Cum	1	4.50	1.20	1.20	1.20	0.25	1.35		
78.00	79.50		Cum	1	1.50	1.00	1.00	1.00	0.25	0.38		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
4.60	13.20		Cum	1	8.60	1.80	1.80	1.80	0.25	3.87		
18.50	27.40		Cum	1	8.90	1.60	1.60	1.60	0.25	3.56		
36.00	43.60		Cum	1	7.60	1.30	1.30	1.30	0.25	2.47		
47.00	52.30		Cum	1	5.30	1.40	1.40	1.40	0.25	1.86		
54.00	55.00		Cum	1	1.00	1.25	1.25	1.25	0.25	0.31		
		3rd Cross Near Vidya										
		(From North to South)										
3.70	11.40		Cum	1	7.70	1.80	1.80	1.80	0.25	3.47		
16.90	25.80		Cum	1	8.90	1.60	1.60	1.60	0.25	3.56		
34.60	41.20		Cum	1	6.60	1.40	1.40	1.40	0.25	2.31		
47.90	57.60		Cum	1	9.70	2.00	2.00	2.00	0.25	4.85		
64.50	74.50		Cum	1	10.00	2.60	2.60	2.60	0.25	6.50		
79.00	88.00		Cum	1	9.00	1.70	1.70	1.70	0.25	3.83		
92.60	98.80		Cum	1	6.20	2.40	2.40	2.40	0.25	3.72		
101.00	105.00		Cum	1	4.00	2.20	2.20	2.20	0.25	2.20		
108.60	117.00		Cum	1	8.40	1.90	1.90	1.90	0.25	3.99		
121.00	129.30		Cum	1	8.30	2.10	2.10	2.10	0.25	4.36		
129.30	131.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
132.00	138.00		Cum	1	6.00	1.70	1.70	1.70	0.25	2.55		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
3.00	13.40		Cum	1	10.40	1.40	1.40	1.40	0.25	3.64		
17.60	26.80		Cum	1	9.20	1.70	1.70	1.70	0.25	3.91		
33.00	43.20		Cum	1	10.20	1.60	1.60	1.60	0.25	4.08		
48.60	57.60		Cum	1	9.00	1.85	1.85	1.85	0.25	4.16		
62.80	74.00		Cum	1	11.20	1.90	1.90	1.90	0.25	5.32		
78.00	88.90		Cum	1	10.90	1.10	1.10	1.10	0.25	3.00		
92.80	104.00		Cum	1	11.20	1.85	1.85	1.85	0.25	5.18		
		6th B Cross Road										
		(From South to North)										
2.60	11.50		Cum	1	8.90	2.10	2.10	2.10	0.25	4.67		
18.00	27.60		Cum	1	9.60	1.90	1.90	1.90	0.25	4.56		
36.00	43.20		Cum	1	7.20	2.30	2.30	2.30	0.25	4.14		
51.00	57.90		Cum	1	6.90	2.00	2.00	2.00	0.25	3.45		
65.00	72.60		Cum	1	7.60	1.85	1.85	1.85	0.25	3.52		
80.00	87.50		Cum	1	7.50	2.10	2.10	2.10	0.25	3.94		
92.70	101.00		Cum	1	8.30	1.95	1.95	1.95	0.25	4.05		
114.00	118.50		Cum	1	4.50	2.00	2.00	2.00	0.25	2.25		
		6th Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From East to West)										
7.00	13.00		Cum	1	6.00	1.90	1.90	1.90	0.25	2.85		
17.00	27.60		Cum	1	10.60	1.45	1.45	1.45	0.25	3.84		
33.00	43.10		Cum	1	10.10	1.75	1.75	1.75	0.25	4.42		
47.60	58.00		Cum	1	10.40	1.85	1.85	1.85	0.25	4.81		
62.00	74.00		Cum	1	12.00	2.00	2.00	2.00	0.25	6.00		
78.00	86.90		Cum	1	8.90	1.60	1.60	1.60	0.25	3.56		
89.10	90.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
94.60	103.00		Cum	1	8.40	1.40	1.40	1.40	0.25	2.94		
108.00	117.10		Cum	1	9.10	1.60	1.60	1.60	0.25	3.64		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
2.00	5.00		Cum	1	3.00	0.80	0.80	0.80	0.25	0.60		
8.00	12.00		Cum	1	4.00	1.80	1.80	1.80	0.25	1.80		
15.00	23.00		Cum	1	8.00	1.80	1.80	1.80	0.25	3.60		
25.00	38.00		Cum	1	13.00	2.00	2.00	2.00	0.25	6.50		
40.00	50.00		Cum	1	10.00	2.00	2.00	2.00	0.25	5.00		
52.00	60.00		Cum	1	8.00	1.80	1.80	1.80	0.25	3.60		
		10th Cross Road,13th main										
		(North To South)										
3.00	9.00		Cum	1	6.00	2.00	2.00	2.00	0.25	3.00		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.25	2.50		
18.00	25.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
27.00	33.00		Cum	1	6.00	1.80	1.80	1.80	0.25	2.70		
35.00	38.00		Cum	1	3.00	0.90	0.90	0.90	0.25	0.68		
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	6.00		Cum	1	4.00	2.00	2.00	2.00	0.25	2.00		
8.00	15.00		Cum	1	7.00	1.50	1.50	1.50	0.25	2.63		
18.00	26.00		Cum	1	8.00	1.80	1.80	1.80	0.25	3.60		
28.00	36.00		Cum	1	8.00	2.00	2.00	2.00	0.25	4.00		
38.00	45.00		Cum	1	7.00	1.40	1.40	1.40	0.25	2.45		
47.00	60.00		Cum	1	13.00	2.00	2.00	2.00	0.25	6.50		
63.00	75.00		Cum	1	12.00	2.00	2.00	2.00	0.25	6.00		
79.00	90.00		Cum	1	11.00	1.50	1.50	1.50	0.25	4.13		
95.00	105.00		Cum	1	10.00	1.60	1.60	1.60	0.25	4.00		
112.00	120.00		Cum	1	8.00	1.40	1.40	1.40	0.25	2.80		
123.00	130.00		Cum	1	7.00	1.60	1.60	1.60	0.25	2.80		
133.00	137.00		Cum	1	4.00	1.40	1.40	1.40	0.25	1.40		
		9th A Cross, 13th main										
		(North To South)										
3.00	8.00		Cum	1	5.00	1.30	1.30	1.30	0.25	1.63		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.25	2.50		
19.00	30.00		Cum	1	11.00	1.50	1.50	1.50	0.25	4.13		
34.00	45.00		Cum	1	11.00	1.50	1.50	1.50	0.25	4.13		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.25	5.00		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.25	5.00		
83.00	90.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
92.00	100.00		Cum	1	8.00	2.00	2.00	2.00	0.25	4.00		
102.00	108.00		Cum	1	6.00	2.00	2.00	2.00	0.25	3.00		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Cum	1	15.00	5.10	5.95	5.53	0.25	20.72		
15.00	27.10		Cum	1	12.10	5.95	4.70	5.33	0.25	16.11		
27.10	30.00		Cum	1	2.90	6.30	5.95	6.13	0.25	4.44		
30.00	45.00		Cum	1	15.00	5.95	4.95	5.45	0.25	20.44		
45.00	60.00		Cum	1	15.00	4.95	5.75	5.35	0.25	20.06		
60.00	75.00		Cum	1	15.00	5.75	5.80	5.78	0.25	21.66		
75.00	90.00		Cum	1	15.00	5.80	5.40	5.60	0.25	21.00		
90.00	105.00		Cum	1	15.00	5.40	5.30	5.35	0.25	20.06		
105.00	120.00		Cum	1	15.00	5.30	5.85	5.58	0.25	20.91		
120.00	135.00		Cum	1	15.00	5.85	6.55	6.20	0.25	23.25		
135.00	139.20		Cum	1	4.20	6.55	6.00	6.28	0.25	6.59		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Cum	1	15.00	7.85	7.00	7.43	0.25	27.84		
15.00	30.00		Cum	1	15.00	7.00	5.95	6.48	0.25	24.28		
30.00	38.40		Cum	1	8.40	5.95	5.60	5.78	0.25	12.13		
38.40	45.00		Cum	1	6.60	7.25	6.85	7.05	0.25	11.63		
45.00	60.00		Cum	1	15.00	6.85	6.10	6.48	0.25	24.28		
60.00	75.00		Cum	1	15.00	6.10	6.55	6.33	0.25	23.72		
75.00	90.00		Cum	1	15.00	6.55	6.70	6.63	0.25	24.84		
90.00	105.00		Cum	1	15.00	6.70	7.10	6.90	0.25	25.88		
105.00	113.00		Cum	1	8.00	7.10	7.00	7.05	0.25	14.10		
113.00	120.00		Cum	1	7.00	5.05	5.00	5.03	0.25	8.79		
120.00	126.20		Cum	1	6.20	5.00	5.10	5.05	0.25	7.83		
126.20	130.50		Cum	1	4.30	5.95	6.00	5.98	0.25	6.42		
130.50	135.00		Cum	1	4.50	6.00	6.15	6.08	0.25	6.83		
135.00	150.00		Cum	1	15.00	6.15	6.80	6.48	0.25	24.28		
150.00	165.00		Cum	1	15.00	6.80	6.75	6.78	0.25	25.41		
165.00	165.40		Cum	1	0.40	6.75	6.80	6.78	0.25	0.68		
165.40	180.00		Cum	1	14.60	6.30	6.35	6.33	0.25	23.09		
180.00	195.00		Cum	1	15.00	6.35	6.00	6.18	0.25	23.16		
195.00	210.00		Cum	1	15.00	6.00	5.90	5.95	0.25	22.31		
210.00	225.00		Cum	1	15.00	5.90	6.20	6.05	0.25	22.69		
225.00	240.00		Cum	1	15.00	6.20	5.75	5.98	0.25	22.41		
240.00	249.30		Cum	1	9.30	5.75	6.00	5.88	0.25	13.66		
249.30	258.30		Cum	1	9.00	5.10	4.65	4.88	0.25	10.97		
258.30	273.30		Cum	1	15.00	5.45	5.25	5.35	0.25	20.06		
273.30	275.00		Cum	1	1.70	5.25	5.25	5.25	0.25	2.23		
273.30	284.00		Cum	1	10.70	5.25	5.75	5.50	0.25	14.71		
		1st Cross Road										
		(From North To South)										
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.25	2.28		
18.00	23.00		Cum	1	5.00	1.60	1.60	1.60	0.25	2.00		
27.00	35.00		Cum	1	8.00	1.20	1.20	1.20	0.25	2.40		
43.00	50.00		Cum	1	7.00	1.30	1.30	1.30	0.25	2.28		
52.00	58.00		Cum	1	6.00	1.60	1.60	1.60	0.25	2.40		
63.00	72.00		Cum	1	9.00	1.80	1.80	1.80	0.25	4.05		
77.00	88.00		Cum	1	11.00	1.70	1.70	1.70	0.25	4.68		
94.00	103.00		Cum	1	9.00	1.25	1.25	1.25	0.25	2.81		
108.00	116.00		Cum	1	8.00	1.15	1.15	1.15	0.25	2.30		
124.00	131.00		Cum	1	7.00	1.50	1.50	1.50	0.25	2.63		
138.00	147.00		Cum	1	9.00	1.40	1.40	1.40	0.25	3.15		
		Balaji Layout										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To										
2.50	10.00		Cum	1	7.50	0.90	0.90	0.90	0.25	1.69		
18.00	27.00		Cum	1	9.00	1.30	1.30	1.30	0.25	2.93		
34.00	41.00		Cum	1	7.00	0.75	0.75	0.75	0.25	1.31		
48.00	52.00		Cum	1	4.00	1.00	1.00	1.00	0.25	1.00		
54.20	55.80	**Culvert**	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
58.00	60.00		Cum	1	2.00	1.00	1.00	1.00	0.25	0.50		
63.00	72.00		Cum	1	9.00	1.30	1.30	1.30	0.25	2.93		
76.00	88.00		Cum	1	12.00	1.40	1.40	1.40	0.25	4.20		
93.00	103.00		Cum	1	10.00	1.80	1.80	1.80	0.25	4.50		
108.00	118.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
123.00	132.00		Cum	1	9.00	1.10	1.10	1.10	0.25	2.48		
137.00	149.00		Cum	1	12.00	1.60	1.60	1.60	0.25	4.80		
152.00	163.00		Cum	1	11.00	1.30	1.30	1.30	0.25	3.58		
169.00	178.00		Cum	1	9.00	1.40	1.40	1.40	0.25	3.15		
182.00	193.00		Cum	1	11.00	1.20	1.20	1.20	0.25	3.30		
197.00	209.00		Cum	1	12.00	1.80	1.80	1.80	0.25	5.40		
212.00	223.00		Cum	1	11.00	1.30	1.30	1.30	0.25	3.58		
225.00	228.20		Cum	1	3.20	0.60	0.60	0.60	0.25	0.48		
228.20	232.00		Cum	1	3.80	0.75	0.75	0.75	0.25	0.71		
234.00	245.20		Cum	1	11.20	1.25	1.25	1.25	0.25	3.50		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
3.00	13.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
18.00	28.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
34.00	43.60		Cum	1	9.60	1.70	1.70	1.70	0.25	4.08		
		(From West To East)										
0.00	3.90		Cum	1	3.90	1.30	1.30	1.30	0.25	1.27		
3.90	11.10		Cum	1	7.20	1.20	1.20	1.20	0.25	2.16		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
4.20	12.00		Cum	1	7.80	1.20	1.20	1.20	0.25	2.34		
15.00	18.80		Cum	1	3.80	3.80	3.80	3.80	0.25	3.61		
21.00	27.80		Cum	1	6.80	1.00	1.00	1.00	0.25	1.70		
32.60	42.60		Cum	1	10.00	1.25	1.25	1.25	0.25	3.13		
47.60	57.40		Cum	1	9.80	1.10	1.10	1.10	0.25	2.70		
64.30	71.00		Cum	1	6.70	1.60	1.60	1.60	0.25	2.68		
77.60	80.00		Cum	1	2.40	1.35	1.35	1.35	0.25	0.81		
83.40	90.20		Cum	1	6.80	1.00	1.00	1.00	0.25	1.70		
93.60	103.20		Cum	1	9.60	0.90	0.90	0.90	0.25	2.16		
107.80	116.90		Cum	1	9.10	1.40	1.40	1.40	0.25	3.19		
124.30	131.70		Cum	1	7.40	1.25	1.25	1.25	0.25	2.31		
138.40	147.00		Cum	1	8.60	1.35	1.35	1.35	0.25	2.90		
152.80	163.10		Cum	1	10.30	1.10	1.10	1.10	0.25	2.83		
		6th A Cross Road										
		(From West to East)										
3.00	6.00		Cum	1	3.00	3.00	3.00	3.00	0.25	2.25		
		(From South to North)										
2.30	6.40		Cum	1	4.10	2.20	2.20	2.20	0.25	2.26		
9.00	13.40		Cum	1	4.40	2.60	2.60	2.60	0.25	2.86		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
90	27.60		Cum	1	9.70	2.00	2.00	2.00	0.25	4.85		
36.20	44.20		Cum	1	8.00	1.35	1.35	1.35	0.25	2.70		
45.00	50.70		Cum	1	5.70	2.00	2.00	2.00	0.25	2.85		
50.70	60.00		Cum	1	9.30	1.80	1.80	1.80	0.25	4.19		
62.30	71.20		Cum	1	8.90	1.30	1.30	1.30	0.25	2.89		
77.80	88.90		Cum	1	11.10	1.70	1.70	1.70	0.25	4.72		
93.40	103.80		Cum	1	10.40	1.40	1.40	1.40	0.25	3.64		
107.00	119.00		Cum	1	12.00	1.60	1.60	1.60	0.25	4.80		
121.00	133.20		Cum	1	12.20	1.40	1.40	1.40	0.25	4.27		
137.00	141.70		Cum	1	4.70	1.00	1.00	1.00	0.25	1.18		
		Devi Nagar Main Road										
		(From West to East)										
2.50	11.00		Cum	1	8.50	1.70	1.70	1.70	0.25	3.61		
16.80	26.40		Cum	1	9.60	2.00	2.00	2.00	0.25	4.80		
33.20	43.50		Cum	1	10.30	1.90	1.90	1.90	0.25	4.89		
47.00	58.00		Cum	1	11.00	2.30	2.30	2.30	0.25	6.33		
63.00	71.00		Cum	1	8.00	1.60	1.60	1.60	0.25	3.20		
77.00	87.00		Cum	1	10.00	1.45	1.45	1.45	0.25	3.63		
93.50	103.00		Cum	1	9.50	1.80	1.80	1.80	0.25	4.28		
107.00	118.00		Cum	1	11.00	2.20	2.20	2.20	0.25	6.05		
123.00	134.00		Cum	1	11.00	2.00	2.00	2.00	0.25	5.50		
137.60	149.50		Cum	1	11.90	1.90	1.90	1.90	0.25	5.65		
151.00	163.40		Cum	1	12.40	1.60	1.60	1.60	0.25	4.96		
165.00	180.00		Cum	1	15.00	1.55	1.55	1.55	0.25	5.81		
183.00	194.30		Cum	1	11.30	1.30	1.30	1.30	0.25	3.67		
196.50	210.00		Cum	1	13.50	1.40	1.40	1.40	0.25	4.73		
212.30	225.00		Cum	1	12.70	1.25	1.25	1.25	0.25	3.97		
227.00	237.20		Cum	1	10.20	1.80	1.80	1.80	0.25	4.59		
237.20	239.00		Cum	1	1.80	2.00	2.00	2.00	0.25	0.90		
239.00	241.50		Cum	1	2.50	1.20	1.20	1.20	0.25	0.75		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Cum	1	3.20	1.10	1.10	1.10	0.25	0.88		
7.00	15.00		Cum	1	8.00	1.30	1.30	1.30	0.25	2.60		
18.00	28.40		Cum	1	10.40	0.90	0.90	0.90	0.25	2.34		
36.00	45.00		Cum	1	9.00	0.75	0.75	0.75	0.25	1.69		
47.80	57.90		Cum	1	10.10	1.60	1.60	1.60	0.25	4.04		
63.70	72.30		Cum	1	8.60	1.20	1.20	1.20	0.25	2.58		
78.90	88.00		Cum	1	9.10	1.70	1.70	1.70	0.25	3.87		
93.60	103.70		Cum	1	10.10	1.20	1.20	1.20	0.25	3.03		
111.00	120.00		Cum	1	9.00	1.45	1.45	1.45	0.25	3.26		
127.00	135.00		Cum	1	8.00	1.65	1.65	1.65	0.25	3.30		
138.90	149.00		Cum	1	10.10	1.80	1.80	1.80	0.25	4.55		
154.70	162.60		Cum	1	7.90	1.70	1.70	1.70	0.25	3.36		
168.90	177.50		Cum	1	8.60	1.90	1.90	1.90	0.25	4.09		
180.00	184.70		Cum	1	4.70	1.60	1.60	1.60	0.25	1.88		
184.70	186.20		Cum	1	1.50	1.70	1.70	1.70	0.25	0.64		
186.20	195.00		Cum	1	8.80	1.60	1.60	1.60	0.25	3.52		
197.00	208.90		Cum	1	11.90	1.40	1.40	1.40	0.25	4.17		
213.00	223.60		Cum	1	10.60	1.25	1.25	1.25	0.25	3.31		
227.00	237.80		Cum	1	10.80	1.30	1.30	1.30	0.25	3.51		
242.60	251.00		Cum	1	8.40	1.40	1.40	1.40	0.25	2.94		
257.00	267.60		Cum	1	10.60	1.60	1.60	1.60	0.25	4.24		
273.00	281.60		Cum	1	8.60	1.20	1.20	1.20	0.25	2.58		
286.00	293.70		Cum	1	7.70	0.90	0.90	0.90	0.25	1.73		
293.70	298.70		Cum	1	5.00	1.90	1.90	1.90	0.25	2.38		
298.70	300.00		Cum	1	1.30	0.90	0.90	0.90	0.25	0.29		
303.60	313.80		Cum	1	10.20	1.40	1.40	1.40	0.25	3.57		
317.00	328.70		Cum	1	11.70	1.30	1.30	1.30	0.25	3.80		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.40	342.60		Cum	1	10.20	1.15	1.15	1.15	0.25	2.93		
348.90	358.00		Cum	1	9.10	1.35	1.35	1.35	0.25	3.07		
360.00	363.50		Cum	1	3.50	2.00	2.00	2.00	0.25	1.75		
363.50	372.30		Cum	1	8.80	1.70	1.70	1.70	0.25	3.74		
374.00	386.00		Cum	1	12.00	1.50	1.50	1.50	0.25	4.50		
387.30	390.00		Cum	1	2.70	2.00	2.00	2.00	0.25	1.35		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
3.00	13.40		Cum	1	10.40	1.20	1.20	1.20	0.25	3.12		
18.00	29.50		Cum	1	11.50	1.90	1.90	1.90	0.25	5.46		
29.50	47.20	No Work	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
51.00	58.70		Cum	1	7.70	1.50	1.50	1.50	0.25	2.89		
62.70	73.80		Cum	1	11.10	1.70	1.70	1.70	0.25	4.72		
77.00	88.90		Cum	1	11.90	1.90	1.90	1.90	0.25	5.65		
92.60	103.50		Cum	1	10.90	1.35	1.35	1.35	0.25	3.68		
108.90	120.00		Cum	1	11.10	1.60	1.60	1.60	0.25	4.44		
123.60	134.50		Cum	1	10.90	1.80	1.80	1.80	0.25	4.91		
137.80	148.90		Cum	1	11.10	1.55	1.55	1.55	0.25	4.30		
150.30	158.50		Cum	1	8.20	1.70	1.70	1.70	0.25	3.48		
158.50	165.30		Cum	1	6.80	2.00	2.00	2.00	0.25	3.40		
168.00	179.00		Cum	1	11.00	1.80	1.80	1.80	0.25	4.95		
180.30	189.60		Cum	1	9.30	1.90	1.90	1.90	0.25	4.42		
189.60	193.50		Cum	1	3.90	2.00	2.00	2.00	0.25	1.95		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha										
0.00	4.00		Cum	1	4.00	2.00	2.00	2.00	0.25	2.00		
6.00	12.50		Cum	1	6.50	1.80	1.80	1.80	0.25	2.93		
15.00	22.00		Cum	1	7.00	1.90	1.90	1.90	0.25	3.33		
24.10	30.00		Cum	1	5.90	1.65	1.65	1.65	0.25	2.43		
32.40	38.10		Cum	1	5.70	1.50	1.50	1.50	0.25	2.14		
38.10	46.00		Cum	1	7.90	1.20	1.20	1.20	0.25	2.37		
48.90	58.00		Cum	1	9.10	1.30	1.30	1.30	0.25	2.96		
60.00	67.00		Cum	1	7.00	1.65	1.65	1.65	0.25	2.89		
69.00	75.00		Cum	1	6.00	1.30	1.30	1.30	0.25	1.95		
77.00	83.50		Cum	1	6.50	2.00	2.00	2.00	0.25	3.25		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens										
		1st Cross Road										
		(From West to East)										
2.60	12.60		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
17.80	27.60		Cum	1	9.80	1.60	1.60	1.60	0.25	3.92		
33.70	43.50		Cum	1	9.80	1.40	1.40	1.40	0.25	3.43		
47.00	56.90		Cum	1	9.90	1.15	1.15	1.15	0.25	2.85		
62.00	74.00		Cum	1	12.00	1.85	1.85	1.85	0.25	5.55		
75.00	87.00		Cum	1	12.00	1.10	1.10	1.10	0.25	3.30		
87.00	90.00		Cum	1	3.00	2.00	2.00	2.00	0.25	1.50		
92.30	102.00		Cum	1	9.70	1.80	1.80	1.80	0.25	4.37		
107.00	118.00		Cum	1	11.00	1.35	1.35	1.35	0.25	3.71		
120.00	129.20		Cum	1	9.20	1.75	1.75	1.75	0.25	4.03		
129.20	135.00		Cum	1	5.80	2.00	2.00	2.00	0.25	2.90		
136.70	148.70		Cum	1	12.00	1.25	1.25	1.25	0.25	3.75		
152.60	163.00		Cum	1	10.40	1.15	1.15	1.15	0.25	2.99		
167.00	179.80		Cum	1	12.80	1.05	1.05	1.05	0.25	3.36		
180.00	195.00		Cum	1	15.00	1.40	1.40	1.40	0.25	5.25		
195.00	209.00		Cum	1	14.00	1.30	1.30	1.30	0.25	4.55		
211.00	221.50		Cum	1	10.50	0.90	0.90	0.90	0.25	2.36		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Cross Road										
		(From North to South)										
4.60	13.40		Cum	1	8.80	1.10	1.10	1.10	0.25	2.42		
15.00	17.10		Cum	1	2.10	1.05	1.05	1.05	0.25	0.55		
17.10	22.80		Cum	1	5.70	1.20	1.20	1.20	0.25	1.71		
22.80	30.00		Cum	1	7.20	0.90	0.90	0.90	0.25	1.62		
34.30	41.00		Cum	1	6.70	0.75	0.75	0.75	0.25	1.26		
47.60	53.20		Cum	1	5.60	0.90	0.90	0.90	0.25	1.26		
54.00	60.00		Cum	1	6.00	0.90	0.90	0.90	0.25	1.35		
63.00	71.60		Cum	1	8.60	0.75	0.75	0.75	0.25	1.61		
79.00	85.20		Cum	1	6.20	1.00	1.00	1.00	0.25	1.55		
		2nd Cross Road										
		(From North to South)										
3.00	12.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
18.90	27.60		Cum	1	8.70	1.30	1.30	1.30	0.25	2.83		
33.60	42.50		Cum	1	8.90	1.10	1.10	1.10	0.25	2.45		
48.90	56.30		Cum	1	7.40	1.40	1.40	1.40	0.25	2.59		
62.80	71.60		Cum	1	8.80	1.00	1.00	1.00	0.25	2.20		
75.00	82.10		Cum	1	7.10	0.65	0.65	0.65	0.25	1.15		
		2nd A Cross Road										
		(From South to North)										
3.80	13.40		Cum	1	9.60	1.60	1.60	1.60	0.25	3.84		
16.70	25.90		Cum	1	9.20	1.70	1.70	1.70	0.25	3.91		
37.00	44.90		Cum	1	7.90	1.10	1.10	1.10	0.25	2.17		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Cum	1	4.20	1.90	1.90	1.90	0.25	2.00		
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.25	2.20		
21.00	28.50		Cum	1	7.50	1.60	1.60	1.60	0.25	3.00		
34.50	41.00		Cum	1	6.50	1.50	1.50	1.50	0.25	2.44		
46.00	52.20		Cum	1	6.20	1.40	1.40	1.40	0.25	2.17		
53.00	60.00		Cum	1	7.00	0.65	0.65	0.65	0.25	1.14		
62.00	67.30		Cum	1	5.30	0.75	0.75	0.75	0.25	0.99		
69.00	70.60		Cum	1	1.60	0.90	0.90	0.90	0.25	0.36		
73.00	81.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
85.00	89.00		Cum	1	4.00	1.10	1.10	1.10	0.25	1.10		
90.00	92.10		Cum	1	2.10	0.90	0.90	0.90	0.25	0.47		
92.10	95.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
98.00	103.40		Cum	1	5.40	1.40	1.40	1.40	0.25	1.89		
107.80	108.90		Cum	1	1.10	1.70	1.70	1.70	0.25	0.47		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
30.00	45.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
45.00	47.80		Cum	1	2.80	1.50	1.50	1.50	0.25	1.05		
47.80	56.10		Cum	1	8.30	1.50	1.50	1.50	0.25	3.11		
56.10	63.90		Cum	1	7.80	1.50	1.50	1.50	0.25	2.93		
63.90	65.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
65.50	75.00		Cum	1	9.50	1.50	1.50	1.50	0.25	3.56		
75.00	90.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
90.00	94.50		Cum	1	4.50	1.50	1.50	1.50	0.25	1.69		
94.50	105.00		Cum	1	10.50	1.50	1.50	1.50	0.25	3.94		
105.00	120.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
120.00	122.00		Cum	1	2.00	1.50	1.50	1.50	0.25	0.75		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	135.00		Cum	1	13.00	1.50	1.50	1.50	0.25	4.88		
135.00	150.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
150.00	154.00		Cum	1	4.00	1.50	1.50	1.50	0.25	1.50		
154.00	163.70		Cum	1	9.70	1.50	1.50	1.50	0.25	3.64		
163.70	169.70		Cum	1	6.00	1.50	1.50	1.50	0.25	2.25		
169.70	171.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
171.20	180.00		Cum	1	8.80	1.50	1.50	1.50	0.25	3.30		
180.00	181.80		Cum	1	1.80	1.50	1.50	1.50	0.25	0.68		
181.80	190.00		Cum	1	8.20	1.50	1.50	1.50	0.25	3.08		
190.00	205.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
205.00	216.10		Cum	1	11.10	1.50	1.50	1.50	0.25	4.16		
216.10	231.10		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
231.10	235.00		Cum	1	3.90	1.50	1.50	1.50	0.25	1.46		
235.00	250.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
250.00	265.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
265.00	280.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
280.00	295.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
295.00	300.00		Cum	1	5.00	1.50	1.50	1.50	0.25	1.88		
300.00	315.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
315.00	330.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
330.00	345.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
345.00	360.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
360.00	369.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	8.40	6.80	7.60	0.25	28.50		
15.00	29.20		Cum	1	14.20	6.80	6.90	6.85	0.25	24.32		
29.20	30.30	Culvert	Cum	0	0.00	0.00	0.00	0.00	0.25	0.00		
30.30	45.00		Cum	1	14.70	6.85	6.70	6.78	0.25	24.90		
45.00	60.00		Cum	1	15.00	6.70	6.60	6.65	0.25	24.94		
60.00	75.00		Cum	1	15.00	6.60	6.40	6.50	0.25	24.38		
75.00	79.70		Cum	1	4.70	6.40	5.75	6.08	0.25	7.14		
79.70	90.00		Cum	1	10.30	2.50	2.50	2.50	0.25	6.44		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
105.00	108.50		Cum	1	3.50	2.50	2.50	2.50	0.25	2.19		
108.50	118.70		Cum	1	10.20	2.50	2.50	2.50	0.25	6.38		
118.70	124.80		Cum	1	6.10	2.50	2.50	2.50	0.25	3.81		
124.80	135.00		Cum	1	10.20	2.50	2.50	2.50	0.25	6.38		
135.00	150.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
150.00	165.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
195.00	210.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
210.00	225.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
240.00	255.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
255.00	270.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
270.00	285.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
285.00	291.50		Cum	1	6.50	2.50	2.50	2.50	0.25	4.06		
291.50	298.00		Cum	1	6.50	2.50	2.50	2.50	0.25	4.06		
		1st Cross Road										
		(From East to West)										
3.40	13.70		Cum	1	10.30	1.60	1.60	1.60	0.25	4.12		
15.00	17.20		Cum	1	2.20	2.00	2.00	2.00	0.25	1.10		
18.90	28.00		Cum	1	9.10	1.40	1.40	1.40	0.25	3.19		
34.60	41.00		Cum	1	6.40	1.50	1.50	1.50	0.25	2.40		
41.00	50.20		Cum	1	9.20	1.30	1.30	1.30	0.25	2.99		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross Road										
		(From East to West)										
3.60	12.80		Cum	1	9.20	1.30	1.30	1.30	0.25	2.99		
17.80	27.90		Cum	1	10.10	1.10	1.10	1.10	0.25	2.78		
32.00	41.20		Cum	1	9.20	1.50	1.50	1.50	0.25	3.45		
45.00	50.20		Cum	1	5.20	2.00	2.00	2.00	0.25	2.60		
50.20	52.80		Cum	1	2.60	1.00	1.00	1.00	0.25	0.65		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
15.00	30.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
30.00	45.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
45.00	60.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
60.00	63.30		Cum	1	3.30	2.50	2.50	2.50	0.25	2.06		
63.30	75.00		Cum	1	11.70	2.50	2.50	2.50	0.25	7.31		
75.00	90.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
105.00	120.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
120.00	132.90		Cum	1	12.90	2.50	2.50	2.50	0.25	8.06		
132.90	147.10		Cum	1	14.20	2.50	2.50	2.50	0.25	8.87		
147.10	160.00		Cum	1	12.90	2.50	2.50	2.50	0.25	8.06		
160.00	165.00		Cum	1	5.00	2.50	2.50	2.50	0.25	3.13		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
195.00	198.80		Cum	1	3.80	2.50	2.50	2.50	0.25	2.38		
198.80	210.00		Cum	1	11.20	2.50	2.50	2.50	0.25	7.00		
210.00	219.70		Cum	1	9.70	2.50	2.50	2.50	0.25	6.06		
219.70	222.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
222.20	225.00		Cum	1	2.80	2.50	2.50	2.50	0.25	1.75		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
240.00	249.60		Cum	1	9.60	2.50	2.50	2.50	0.25	6.00		
249.60	257.30		Cum	1	7.70	2.50	2.50	2.50	0.25	4.81		
257.30	260.00		Cum	1	2.70	2.50	2.50	2.50	0.25	1.69		
260.00	275.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
275.00	292.00		Cum	1	17.00	2.50	2.50	2.50	0.25	10.63		
292.00	297.10		Cum	1	5.10	2.50	2.50	2.50	0.25	3.19		
297.10	300.00		Cum	1	2.90	2.50	2.50	2.50	0.25	1.81		
300.00	315.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
315.00	330.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
330.00	345.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
345.00	360.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
360.00	375.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
375.00	390.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
390.00	405.00		Cum	1	15.00	2.50	2.50	2.50	0.25	9.38		
405.00	414.50		Cum	1	9.50	2.50	2.50	2.50	0.25	5.94		
		AMCO Layout										
		1st Cross , Ganesh Temple										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
30.00	45.00		Cum	1	15.00	1.65	1.65	1.65	0.25	6.19		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.25	5.25		
60.00	69.30		Cum	1	9.30	1.10	1.10	1.10	0.25	2.56		
69.30	75.00		Cum	1	5.70	2.00	2.00	2.00	0.25	2.85		
75.00	90.00		Cum	1	15.00	2.20	2.20	2.20	0.25	8.25		
90.00	105.00		Cum	1	15.00	1.60	1.60	1.60	0.25	6.00		
105.00	111.40		Cum	1	6.40	3.50	3.50	3.50	0.25	5.60		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross, Ganesh Temple										
		(North To South)										
0.00	4.60		Cum	1	4.60	4.00	4.00	4.00	0.25	4.60		
4.60	15.00		Cum	1	10.40	2.10	2.10	2.10	0.25	5.46		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
30.00	45.00		Cum	1	15.00	1.40	1.40	1.40	0.25	5.25		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
60.00	75.00		Cum	1	15.00	2.00	2.00	2.00	0.25	7.50		
75.00	90.00		Cum	1	15.00	1.40	1.40	1.40	0.25	5.25		
90.00	100.30		Cum	1	10.30	1.30	1.30	1.30	0.25	3.35		
		Thindlu										
		Sri Laxmi Digital Shop										
		(North To South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.25	4.13		
15.00	30.00		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
30.00	45.00		Cum	1	15.00	1.00	1.00	1.00	0.25	3.75		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.25	5.25		
60.00	73.50		Cum	1	13.50	1.20	1.20	1.20	0.25	4.05		
		Anganawadi School Opp										
		(South to North)										
0.00	15.00		Cum	1	15.00	1.30	1.30	1.30	0.25	4.88		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
30.00	45.00		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.25	4.13		
60.00	75.00		Cum	1	15.00	1.00	1.00	1.00	0.25	3.75		
75.00	81.00		Cum	1	6.00	1.40	1.40	1.40	0.25	2.10		
		3rd Cross Road,Impact										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.25	4.13		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.25	7.50		
45.00	60.00		Cum	1	15.00	1.70	1.70	1.70	0.25	6.38		
60.00	75.00		Cum	1	15.00	1.90	1.90	1.90	0.25	7.13		
75.00	90.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
90.00	95.80		Cum	1	5.80	5.80	5.80	5.80	0.25	8.41		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Cum	1	15.00	2.20	2.20	2.20	0.25	8.25		
15.00	26.20		Cum	1	11.20	1.80	1.80	1.80	0.25	5.04		
		(North To South)										
0.00	15.00		Cum	1	15.00	1.70	1.70	1.70	0.25	6.38		
15.00	30.00		Cum	1	15.00	1.60	1.60	1.60	0.25	6.00		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.25	7.50		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
60.00	75.00		Cum	1	15.00	2.30	2.30	2.30	0.25	8.63		
75.00	90.00		Cum	1	15.00	1.90	1.90	1.90	0.25	7.13		
90.00	105.00		Cum	1	15.00	1.80	1.80	1.80	0.25	6.75		
105.00	120.00		Cum	1	15.00	2.20	2.20	2.20	0.25	8.25		
120.00	135.00		Cum	1	15.00	1.60	1.60	1.60	0.25	6.00		
135.00	150.00		Cum	1	15.00	2.10	2.10	2.10	0.25	7.88		
150.00	165.00		Cum	1	15.00	1.60	1.60	1.60	0.25	6.00		
165.00	169.00		Cum	1	4.00	1.90	1.90	1.90	0.25	1.90		
		Ward No 10										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Vidyaranyapura Sub division										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
4.00	9.00		Cum	1	5.00	0.90	0.90	0.90	0.25	1.13		
20.00	28.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
35.00	42.00		Cum	1	7.00	1.20	1.20	1.20	0.23	1.89		
65.00	71.00		Cum	1	6.00	1.30	1.30	1.30	0.23	1.76		
80.00	87.00		Cum	1	7.00	1.10	1.10	1.10	0.23	1.73		
94.00	102.00		Cum	1	8.00	0.90	0.90	0.90	0.23	1.62		
111.00	118.00		Cum	1	7.00	1.10	1.10	1.10	0.23	1.73		
125.00	133.00		Cum	1	8.00	1.30	1.30	1.30	0.23	2.34		
140.00	148.00		Cum	1	8.00	1.50	1.50	1.50	0.23	2.70		
155.00	162.00		Cum	1	7.00	1.20	1.20	1.20	0.23	1.89		
170.00	178.00		Cum	1	8.00	1.50	1.50	1.50	0.23	2.70		
185.00	195.00		Cum	1	10.00	1.20	1.20	1.20	0.23	2.70		
195.00	203.10		Cum	1	8.10	1.50	1.50	1.50	0.23	2.73		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
3.10	12.00		Cum	1	8.90	1.10	1.10	1.10	0.25	2.45		
20.00	28.00		Cum	1	8.00	1.30	1.30	1.30	0.25	2.60		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
50.00	58.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
80.00	87.00		Cum	1	7.00	1.30	1.30	1.30	0.25	2.28		
96.00	100.00		Cum	1	4.00	1.45	1.45	1.45	0.25	1.45		
112.00	120.00		Cum	1	8.00	1.30	1.30	1.30	0.25	2.60		
128.00	135.00		Cum	1	7.00	0.90	0.90	0.90	0.25	1.58		
137.00	150.00		Cum	1	13.00	0.60	0.60	0.60	0.25	1.95		
158.00	165.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
173.00	180.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
188.00	195.00		Cum	1	7.00	0.90	0.90	0.90	0.25	1.58		
200.00	210.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
217.00	225.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
232.00	240.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
248.00	255.00		Cum	1	7.00	0.90	0.90	0.90	0.25	1.58		
264.00	270.00		Cum	1	6.00	1.10	1.10	1.10	0.25	1.65		
272.00	277.40		Cum	1	5.40	1.00	1.00	1.00	0.25	1.35		
278.50	285.00		Cum	1	6.50	1.00	1.00	1.00	0.25	1.63		
290.00	300.00		Cum	1	10.00	1.20	1.20	1.20	0.25	3.00		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
3.50	12.00		Cum	1	8.50	0.60	0.60	0.60	0.25	1.28		
20.00	25.20		Cum	1	5.20	1.10	1.10	1.10	0.25	1.43		
27.00	33.90		Cum	1	6.90	0.50	0.50	0.50	0.25	0.86		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
50.00	60.00		Cum	1	10.00	0.80	0.80	0.80	0.25	2.00		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
80.00	90.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
95.00	105.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
106.00	109.10		Cum	1	3.10	1.10	1.10	1.10	0.25	0.85		
112.00	120.00		Cum	1	8.00	1.10	1.10	1.10	0.25	2.20		
125.00	135.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
138.00	142.80		Cum	1	4.80	1.10	1.10	1.10	0.25	1.32		
145.00	150.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
151.00	154.80		Cum	1	3.80	1.10	1.10	1.10	0.25	1.05		
157.00	165.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
168.00	172.80		Cum	1	4.80	1.10	1.10	1.10	0.25	1.32		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
181.00	185.00		Cum	1	4.00	1.20	1.20	1.20	0.25	1.20		
190.00	195.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
198.00	209.40		Cum	1	11.40	0.60	0.60	0.60	0.25	1.71		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
205.00	221.00		Cum	1	6.00	1.10	1.10	1.10	0.25	1.65		
		Samashana Road										
		2nd main Road										
		(From East to West)										
5.00	11.80		Cum	1	6.80	0.60	0.60	0.60	0.25	1.02		
13.00	15.00		Cum	1	2.00	1.20	1.20	1.20	0.25	0.60		
20.00	30.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
66.00	75.00		Cum	1	9.00	1.10	1.10	1.10	0.25	2.48		
81.00	90.00		Cum	1	9.00	1.10	1.10	1.10	0.25	2.48		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
115.00	120.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
125.00	135.00		Cum	1	10.00	0.70	0.70	0.70	0.25	1.75		
138.00	140.50		Cum	1	2.50	0.70	0.70	0.70	0.25	0.44		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	15.50		Cum	1	9.50	1.20	1.20	1.20	0.25	2.85		
20.00	30.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
47.00	51.00		Cum	1	4.00	1.00	1.00	1.00	0.25	1.00		
53.00	60.00		Cum	1	7.00	1.10	1.10	1.10	0.25	1.93		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
95.00	105.10		Cum	1	10.10	1.00	1.00	1.00	0.25	2.53		
110.00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
122.00	126.50		Cum	1	4.50	0.60	0.60	0.60	0.25	0.68		
130.00	135.00		Cum	1	5.00	0.60	0.60	0.60	0.25	0.75		
138.00	141.90		Cum	1	3.90	0.70	0.70	0.70	0.25	0.68		
144.00	150.00		Cum	1	6.00	0.70	0.70	0.70	0.25	1.05		
152.00	154.10		Cum	1	2.10	0.90	0.90	0.90	0.25	0.47		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Cum	1	1.60	0.60	0.60	0.60	0.25	0.24		
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.25	1.95		
34.00	45.00		Cum	1	11.00	1.00	1.00	1.00	0.25	2.75		
48.00	60.00		Cum	1	12.00	0.60	0.60	0.60	0.25	1.80		
63.00	75.00		Cum	1	12.00	0.90	0.90	0.90	0.25	2.70		
75.00	79.10		Cum	1	4.10	0.60	0.60	0.60	0.25	0.61		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
6.00	15.00		Cum	1	9.00	1.20	1.20	1.20	0.25	2.70		
17.00	23.30		Cum	1	6.30	0.70	0.70	0.70	0.25	1.10		
		From house no #15 to house no -7										
		(From North to South)										
5.00	15.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
22.00	30.00		Cum	1	8.00	1.20	1.20	1.20	0.25	2.40		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
51.00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.25	2.25		
65.00	73.00		Cum	1	8.00	1.30	1.30	1.30	0.25	2.60		
74.00	79.00		Cum	1	5.00	1.50	1.50	1.50	0.25	1.88		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
4.00	15.00		Cum	1	11.00	1.00	1.00	1.00	0.25	2.75		
25.00	29.60		Cum	1	9.60	1.40	1.40	1.40	0.25	3.36		
32.00	38.70		Cum	1	6.70	1.00	1.00	1.00	0.25	1.68		
40.00	45.00		Cum	1	5.00	1.80	1.80	1.80	0.25	2.25		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
65.00	75.00		Cum	1	10.00	1.70	1.70	1.70	0.25	4.25		
78.00	84.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
86.00	90.00		Cum	1	4.00	2.00	2.00	2.00	0.25	2.00		
100.00	103.00		Cum	1	3.00	0.60	0.60	0.60	0.25	0.45		
106.00	115.00		Cum	1	9.00	1.00	1.00	1.00	0.25	2.25		
117.00	127.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
129.00	139.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
140.00	148.00		Cum	1	8.00	1.40	1.40	1.40	0.25	2.80		
150.00	153.30		Cum	1	3.30	1.00	1.00	1.00	0.25	0.83		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
8.00	15.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
20.00	30.00		Cum	1	10.00	1.60	1.60	1.60	0.25	4.00		
35.00	43.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
45.00	47.30		Cum	1	2.30	1.30	1.30	1.30	0.25	0.75		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
7.00	15.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
22.00	30.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
38.00	45.00		Cum	1	7.00	1.80	1.80	1.80	0.25	3.15		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
65.00	75.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
108.00	112.00		Cum	1	4.00	0.70	0.70	0.70	0.25	0.70		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
20.00	30.00		Cum	1	10.00	1.30	1.30	1.30	0.25	3.25		
34.00	45.00		Cum	1	11.00	1.20	1.20	1.20	0.25	3.30		
49.00	50.10		Cum	1	1.10	2.00	2.00	2.00	0.25	0.55		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
5.00	15.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.25	1.95		
35.00	45.00		Cum	1	10.00	0.80	0.80	0.80	0.25	2.00		
50.00	60.00		Cum	1	10.00	0.70	0.70	0.70	0.25	1.75		
68.00	75.10		Cum	1	7.10	1.10	1.10	1.10	0.25	1.95		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	15.00		Cum	1	11.00	1.20	1.20	1.20	0.25	3.30		
20.00	30.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
30.00	34.30		Cum	1	4.30	1.00	1.00	1.00	0.25	1.08		
36.00	45.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.25	3.25		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
82.00	90.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
125.00	135.00		Cum	1	10.00	1.25	1.25	1.25	0.25	3.13		
140.00	150.00		Cum	1	10.00	0.90	0.90	0.90	0.25	2.25		
157.00	165.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
170.00	180.00		Cum	1	10.00	0.80	0.80	0.80	0.25	2.00		
182.00	187.20		Cum	1	5.20	2.00	2.00	2.00	0.25	2.60		
190.00	195.00		Cum	1	5.00	1.00	1.00	1.00	0.25	1.25		
199.00	210.00		Cum	1	11.00	1.10	1.10	1.10	0.25	3.03		
212.00	215.10		Cum	1	3.10	1.50	1.50	1.50	0.25	1.16		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
18.00	28.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
30.00	34.00		Cum	1	4.00	0.70	0.70	0.70	0.25	0.70		
36.00	40.00		Cum	1	4.00	0.80	0.80	0.80	0.25	0.80		
42.00	44.00		Cum	1	2.00	1.10	1.10	1.10	0.25	0.55		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	6.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
8.00	15.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.25	1.80		
38.00	45.00		Cum	1	7.00	1.10	1.10	1.10	0.25	1.93		
51.00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.25	2.25		
63.00	75.00		Cum	1	12.00	0.70	0.70	0.70	0.25	2.10		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
96.00	105.00		Cum	1	9.00	1.00	1.00	1.00	0.25	2.25		
108.00	117.00		Cum	1	9.00	0.70	0.70	0.70	0.25	1.58		
119.00	120.80		Cum	1	1.80	0.70	0.70	0.70	0.25	0.32		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
4.00	13.00		Cum	1	9.00	0.80	0.80	0.80	0.25	1.80		
15.00	28.00		Cum	1	13.00	1.00	1.00	1.00	0.25	3.25		
31.00	37.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
39.00	45.00		Cum	1	6.00	0.60	0.60	0.60	0.25	0.90		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
83.00	90.00		Cum	1	7.00	0.80	0.80	0.80	0.25	1.40		
95.00	105.00		Cum	1	10.00	0.70	0.70	0.70	0.25	1.75		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.25	1.93		
142.00	150.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
153.00	161.00		Cum	1	8.00	0.50	0.50	0.50	0.25	1.00		
165.00	172.00		Cum	1	7.00	0.70	0.70	0.70	0.25	1.23		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
183.00	190.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
195.00	200.20		Cum	1	5.20	1.60	1.60	1.60	0.25	2.08		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.50	0.50	0.50	0.25	0.88		
13.00	23.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
25.00	30.00		Cum	1	5.00	1.10	1.10	1.10	0.25	1.38		
37.00	45.00		Cum	1	8.00	0.70	0.70	0.70	0.25	1.40		
51.00	60.00		Cum	1	9.00	0.80	0.80	0.80	0.25	1.80		
61.00	65.50		Cum	1	4.50	1.40	1.40	1.40	0.25	1.58		
		2nd Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.00	1.00	1.00	0.25	1.25		
12.00	19.00		Cum	1	7.00	0.60	0.60	0.60	0.25	1.05		
21.00	30.00		Cum	1	9.00	1.00	1.00	1.00	0.25	2.25		
34.00	45.00		Cum	1	11.00	0.70	0.70	0.70	0.25	1.93		
50.00	60.00		Cum	1	10.00	0.50	0.50	0.50	0.25	1.25		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
95.00	105.00		Cum	1	10.00	0.80	0.80	0.80	0.25	2.00		
110.00	120.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
123.00	127.60		Cum	1	4.60	1.30	1.30	1.30	0.25	1.50		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
4.00	11.00		Cum	1	7.00	0.60	0.60	0.60	0.25	1.05		
13.00	20.00		Cum	1	7.00	1.30	1.30	1.30	0.25	2.28		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
34.00	45.00		Cum	1	11.00	0.75	0.75	0.75	0.25	2.06		
51.00	60.00		Cum	1	9.00	0.90	0.90	0.90	0.25	2.03		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
78.00	90.00		Cum	1	12.00	0.70	0.70	0.70	0.25	2.10		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.25	1.35		
111.00	120.00		Cum	1	9.00	1.20	1.20	1.20	0.25	2.70		
123.00	128.30		Cum	1	5.30	1.00	1.00	1.00	0.25	1.33		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.60	0.60	0.60	0.25	1.05		
12.00	20.00		Cum	1	8.00	0.70	0.70	0.70	0.25	1.40		
23.00	30.00		Cum	1	7.00	0.60	0.60	0.60	0.25	1.05		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.25	3.25		
63.00	71.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
75.00	79.00		Cum	1	4.00	1.20	1.20	1.20	0.25	1.20		
81.00	83.40		Cum	1	2.40	1.60	1.60	1.60	0.25	0.96		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
5.00	13.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
15.00	20.00		Cum	1	5.00	0.80	0.80	0.80	0.25	1.00		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
50.00	60.00		Cum	1	10.00	1.40	1.40	1.40	0.25	3.50		
63.00	75.00		Cum	1	12.00	1.20	1.20	1.20	0.25	3.60		
79.00	90.00		Cum	1	11.00	1.30	1.30	1.30	0.25	3.58		
97.00	105.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
110.00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
123.00	135.00		Cum	1	12.00	1.20	1.20	1.20	0.25	3.60		
140.00	150.00		Cum	1	10.00	0.60	0.60	0.60	0.25	1.50		
155.00	165.00		Cum	1	10.00	0.80	0.80	0.80	0.25	2.00		
172.00	180.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
189.00	195.00		Cum	1	6.00	1.00	1.00	1.00	0.25	1.50		
200.00	210.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
218.00	225.00		Cum	1	7.00	0.80	0.80	0.80	0.25	1.40		
230.00	240.00		Cum	1	10.00	1.00	1.00	1.00	0.25	2.50		
250.00	255.00		Cum	1	5.00	1.40	1.40	1.40	0.25	1.75		
261.00	270.00		Cum	1	9.00	1.30	1.30	1.30	0.25	2.93		
275.00	283.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
287.00	300.40		Cum	1	13.40	1.30	1.30	1.30	0.25	4.35		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
6.00	14.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.25	1.80		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
53.00	60.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
62.00	66.00		Cum	1	4.00	1.10	1.10	1.10	0.25	1.10		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.25	2.63		
80.00	90.00		Cum	1	10.00	1.20	1.20	1.20	0.25	3.00		
97.00	105.00		Cum	1	8.00	0.60	0.60	0.60	0.25	1.20		
111.00	120.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
129.00	135.00		Cum	1	6.00	0.90	0.90	0.90	0.25	1.35		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Cum	1	3.70	1.20	1.20	1.20	0.25	1.11		
3.70	5.50	Culvert	Cum	1	1.80	0.00	0.00	0.00	0.25	0.00		
15.00	30.00		Cum	1	15.00	0.60	0.50	0.55	0.25	2.06		
30.00	40.80		Cum	1	10.80	0.90	0.85	0.88	0.25	2.36		
40.80	55.00		Cum	1	14.20	1.10	0.60	0.85	0.25	3.02		
		9th A Cross Road										
		(From South to North)										
3.70	15.00		Cum	1	11.30	0.50	0.65	0.58	0.25	1.62		
15.00	16.10		Cum	1	1.10	1.15	0.35	0.75	0.25	0.21		
		9th Cross Road										
		(From North to South)										
23.00	30.00		Cum	1	7.00	1.20	1.20	1.20	0.25	2.10		
45.00	52.00		Cum	1	7.00	0.95	0.65	0.80	0.25	1.40		
60.00	71.00		Cum	1	11.00	1.15	1.15	1.15	0.25	3.16		
75.00	90.10		Cum	1	15.10	1.20	1.20	1.20	0.25	4.53		
90.90	97.30		Cum	1	6.40	0.85	0.50	0.68	0.25	1.08		
		7th A Cross Road										
		(From South to North)										
9.10	15.00		Cum	1	5.90	1.50	1.50	1.50	0.25	2.21		
15.00	18.30		Cum	1	3.30	0.35	0.35	0.35	0.25	0.29		
		7th Cross Road										
		(From North to South)										
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.25	4.13		
33.00	42.00		Cum	1	9.00	1.20	1.20	1.20	0.25	2.70		
45.00	55.80		Cum	1	10.80	0.60	0.60	0.60	0.25	1.62		
60.00	75.00		Cum	1	15.00	1.50	1.50	1.50	0.25	5.63		
79.00	84.50		Cum	1	5.50	1.20	1.20	1.20	0.25	1.65		
84.50	90.00		Cum	1	5.50	0.60	0.35	0.48	0.25	0.65		
91.20	93.10		Cum	1	1.90	1.20	1.20	1.20	0.25	0.57		
		6th Cross Road										
		(From North to South)										
10.00	15.00		Cum	1	5.00	0.60	0.60	0.60	0.25	0.75		
15.00	28.00		Cum	1	13.00	0.50	0.50	0.50	0.25	1.63		
42.00	45.00		Cum	1	3.00	0.70	0.70	0.70	0.25	0.53		
52.00	60.00		Cum	1	8.00	1.10	1.10	1.10	0.25	2.20		
62.50	75.00		Cum	1	12.50	1.00	1.00	1.00	0.25	3.13		
83.00	90.00		Cum	1	7.00	1.60	1.60	1.60	0.25	2.80		
91.50	92.30		Cum	1	0.80	1.20	1.20	1.20	0.25	0.24		
		6th A Cross Road										
		(From South to North)										
5.00	9.60		Cum	1	4.60	1.20	1.20	1.20	0.25	1.38		
11.80	15.00		Cum	1	3.20	1.20	1.20	1.20	0.25	0.96		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		5th Cross Road										
		(From North to South)										
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.25	2.20		
33.00	40.70		Cum	1	7.70	1.40	1.40	1.40	0.25	2.70		
48.00	56.00		Cum	1	8.00	1.00	1.00	1.00	0.25	2.00		
65.00	70.00		Cum	1	5.00	1.30	1.30	1.30	0.25	1.63		
79.00	85.00		Cum	1	6.00	1.45	1.45	1.45	0.25	2.18		
		5th A Cross Road										
		(From South to North)										
2.00	4.00		Cum	1	2.00	0.50	0.40	0.45	0.25	0.23		
9.20	15.00		Cum	1	5.80	1.20	1.20	1.20	0.25	1.74		
17.60	19.60		Cum	1	2.00	1.30	0.60	0.95	0.25	0.48		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
16.00	28.30		Cum	1	12.30	0.90	0.80	0.85	0.25	2.61		
30.00	44.20		Cum	1	14.20	1.10	0.35	0.73	0.25	2.57		
45.00	58.00		Cum	1	13.00	1.30	0.45	0.88	0.25	2.84		
60.00	73.00		Cum	1	13.00	0.70	0.55	0.63	0.25	2.03		
107.00	120.00		Cum	1	13.00	1.50	1.20	1.35	0.25	4.39		
124.00	134.00		Cum	1	10.00	1.20	1.20	1.20	0.25	3.00		
135.00	149.00		Cum	1	14.00	0.60	0.60	0.60	0.25	2.10		
153.00	165.00		Cum	1	12.00	1.60	1.60	1.60	0.25	4.80		
173.00	180.00		Cum	1	7.00	0.70	0.70	0.70	0.25	1.23		
183.00	195.00		Cum	1	12.00	1.10	1.10	1.10	0.25	3.30		
201.00	225.00		Cum	1	24.00	1.00	1.00	1.00	0.25	6.00		
228.00	240.00		Cum	1	12.00	1.60	1.60	1.60	0.25	4.80		
245.00	255.00		Cum	1	10.00	1.40	0.75	1.08	0.25	2.69		
258.00	270.00		Cum	1	12.00	1.20	1.20	1.20	0.25	3.60		
274.00	285.00		Cum	1	11.00	1.00	0.70	0.85	0.25	2.34		
287.00	300.00		Cum	1	13.00	1.20	1.20	1.20	0.25	3.90		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.50	10.00		Cum	1	5.50	1.50	1.50	1.50	0.25	2.06		
15.20	24.70		Cum	1	9.50	1.15	1.15	1.15	0.25	2.73		
29.00	30.00		Cum	1	1.00	1.45	1.45	1.45	0.25	0.36		
32.00	45.00		Cum	1	13.00	1.20	1.20	1.20	0.25	3.90		
48.00	60.00		Cum	1	12.00	1.40	1.40	1.40	0.25	4.20		
80.20	90.00		Cum	1	9.80	1.80	1.80	1.80	0.25	4.41		
97.00	105.00		Cum	1	8.00	1.20	1.20	1.20	0.25	2.40		
110.00	120.00		Cum	1	10.00	1.15	1.15	1.15	0.25	2.88		
125.00	136.00		Cum	1	11.00	1.20	1.20	1.20	0.25	3.30		
145.00	150.00		Cum	1	5.00	1.70	1.70	1.70	0.25	2.13		
154.00	165.00		Cum	1	11.00	1.35	1.35	1.35	0.25	3.71		
168.00	178.00		Cum	1	10.00	1.20	1.20	1.20	0.25	3.00		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
2.50	15.00		Cum	1	12.50	1.20	0.95	1.08	0.25	3.36		
30.00	44.00		Cum	1	14.00	1.70	1.20	1.45	0.25	5.08		
45.00	55.60		Cum	1	10.60	1.20	1.15	1.18	0.25	3.11		
60.00	74.30		Cum	1	14.30	1.10	1.10	1.10	0.25	3.93		
90.00	103.00		Cum	1	13.00	1.00	1.00	1.00	0.25	3.25		
105.00	122.00		Cum	1	17.00	1.40	1.40	1.40	0.25	5.95		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.25	1.93		
150.00	162.00		Cum	1	12.00	1.20	1.15	1.18	0.25	3.53		
165.00	168.60		Cum	1	3.60	1.60	1.60	1.60	0.25	1.44		
168.60	169.50		Cum	1	0.90	1.20	1.20	1.20	0.25	0.27		
		5th Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
9.30	14.50		Cum	1	5.20	1.20	1.20	1.20	0.25	1.56		
15.00	25.00		Cum	1	10.00	1.60	1.20	1.40	0.25	3.50		
30.00	44.20		Cum	1	14.20	1.20	1.20	1.20	0.25	4.26		
49.00	52.70		Cum	1	3.70	2.00	1.20	1.60	0.25	1.48		
55.00	57.60		Cum	1	2.60	1.20	1.20	1.20	0.25	0.78		
60.00	70.00		Cum	1	10.00	1.50	1.50	1.50	0.25	3.75		
71.50	85.00		Cum	1	13.50	0.50	0.50	0.50	0.25	1.69		
86.10	90.00		Cum	1	3.90	0.70	0.70	0.70	0.25	0.68		
93.50	103.00		Cum	1	9.50	1.10	1.10	1.10	0.25	2.61		
110.00	119.00		Cum	1	9.00	1.40	1.40	1.40	0.25	3.15		
120.00	132.00		Cum	1	12.00	1.60	1.60	1.60	0.25	4.80		
135.00	148.00		Cum	1	13.00	1.30	1.20	1.25	0.25	4.06		
150.00	158.00		Cum	1	8.00	1.20	1.20	1.20	0.25	2.40		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
13.00	24.00		Cum	1	11.00	1.60	1.60	1.60	0.25	4.40		
26.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
39.00	50.00		Cum	1	11.00	2.10	2.10	2.10	0.25	5.78		
54.00	64.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
66.00	75.00		Cum	1	9.00	1.80	1.80	1.80	0.25	4.05		
82.00	90.00		Cum	1	8.00	1.80	1.80	1.80	0.25	3.60		
92.00	101.00		Cum	1	9.00	1.80	1.80	1.80	0.25	4.05		
103.00	110.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
112.00	118.00		Cum	1	6.00	1.50	1.50	1.50	0.25	2.25		
120.00	123.00		Cum	1	3.00	1.10	1.10	1.10	0.25	0.83		
		11th Cross Road										
		North to South										
2.00	11.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
13.00	20.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
23.00	33.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
35.00	45.00		Cum	1	10.00	1.20	1.20	1.20	0.25	3.00		
50.00	60.00		Cum	1	10.00	1.10	1.10	1.10	0.25	2.75		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
74.00	80.00		Cum	1	6.00	1.90	1.90	1.90	0.25	2.85		
82.00	90.00		Cum	1	8.00	2.00	2.00	2.00	0.25	4.00		
93.00	100.00		Cum	1	7.00	2.00	2.00	2.00	0.25	3.50		
102.00	111.00		Cum	1	9.00	1.80	1.80	1.80	0.25	4.05		
115.00	122.00		Cum	1	7.00	1.70	1.70	1.70	0.25	2.98		
		17th Cross Road										
		North to South										
4.00	10.00		Cum	1	6.00	1.50	1.50	1.50	0.25	2.25		
13.00	23.00		Cum	1	10.00	1.80	1.80	1.80	0.25	4.50		
25.00	36.00		Cum	1	11.00	2.00	2.00	2.00	0.25	5.50		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
49.00	59.00		Cum	1	10.00	1.80	1.80	1.80	0.25	4.50		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
75.00	84.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
86.00	98.00		Cum	1	12.00	1.80	1.80	1.80	0.25	5.40		
100.00	109.00		Cum	1	9.00	1.20	1.20	1.20	0.25	2.70		
		3rd Cross Road										
		North to South										
3.00	10.00		Cum	1	7.00	1.00	1.00	1.00	0.25	1.75		
13.00	24.00		Cum	1	11.00	2.00	2.00	2.00	0.25	5.50		
26.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
37.00	47.00		Cum	1	10.00	1.80	1.80	1.80	0.25	4.50		
50.00	59.00		Cum	1	9.00	2.00	2.00	2.00	0.25	4.50		
		2nd Cross Road										
		North To South										
4.00	13.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	26.00		Cum	1	11.00	2.00	2.00	2.00	0.25	5.50		
28.00	36.00		Cum	1	8.00	1.30	1.30	1.30	0.25	2.60		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.25	3.38		
50.00	60.00		Cum	1	10.00	1.50	1.50	1.50	0.25	3.75		
66.00	73.00		Cum	1	7.00	1.50	1.50	1.50	0.25	2.63		
									Total Executed Quantity	**3673.73**		
									Tender Quantity	**3137.70**		
									Quantity Upto 125%	**3673.73**	**75.06**	**275751.00**
Item no.15		**Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work**										
		Item is Not Operated										
Item no.16		**Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
2.00	6.00		Cum	1	4.00	0.60	0.60	0.60	0.225	0.54		
8.00	13.00		Cum	1	5.00	0.75	0.75	0.75	0.225	0.84		
17.00	29.00		Cum	1	12.00	1.20	1.20	1.20	0.225	3.24		
32.00	43.00		Cum	1	11.00	1.00	1.00	1.00	0.225	2.48		
48.00	57.00		Cum	1	9.00	1.60	1.60	1.60	0.225	3.24		
63.00	71.00		Cum	1	8.00	1.20	1.20	1.20	0.225	2.16		
77.00	88.00		Cum	1	11.00	1.80	1.80	1.80	0.225	4.46		
94.00	103.00		Cum	1	9.00	1.10	1.10	1.10	0.225	2.23		
107.00	110.00		Cum	1	3.00	0.60	0.60	0.60	0.225	0.41		
112.00	118.00		Cum	1	6.00	1.70	1.70	1.70	0.225	2.30		
123.00	133.00		Cum	1	10.00	1.70	1.70	1.70	0.225	3.83		
137.00	144.00		Cum	1	7.00	1.80	1.80	1.80	0.225	2.84		
145.00	152.00		Cum	1	7.00	1.50	1.50	1.50	0.225	2.36		
154.00	163.00		Cum	1	9.00	1.35	1.35	1.35	0.225	2.73		
165.00	172.40		Cum	1	7.40	1.60	1.60	1.60	0.225	2.66		
173.10	180.00		Cum	1	6.90	1.50	1.50	1.50	0.225	2.33		
184.00	192.80		Cum	1	8.80	1.90	1.90	1.90	0.225	3.76		
195.00	200.80		Cum	1	5.80	2.00	2.00	2.00	0.225	2.61		
		Ravi Gowda Layout										
		(From North to South)										
3.50	12.00		Cum	1	8.50	1.30	1.30	1.30	0.225	2.49		
18.00	28.00		Cum	1	10.00	1.80	1.80	1.80	0.225	4.05		
32.80	41.00		Cum	1	8.20	2.30	2.30	2.30	0.225	4.24		
48.00	57.00		Cum	1	9.00	2.60	2.60	2.60	0.225	5.27		
62.40	70.00		Cum	1	7.60	1.80	1.80	1.80	0.225	3.08		
79.00	88.30		Cum	1	9.30	1.90	1.90	1.90	0.225	3.98		
96.00	101.20		Cum	1	5.20	2.30	2.30	2.30	0.225	2.69		
107.60	117.00		Cum	1	9.40	2.25	2.25	2.25	0.225	4.76		
120.00	126.00		Cum	1	6.00	1.40	1.40	1.40	0.225	1.89		
128.00	133.00		Cum	1	5.00	1.70	1.70	1.70	0.225	1.91		
137.00	140.00		Cum	1	3.00	1.60	1.60	1.60	0.225	1.08		
143.00	148.00		Cum	1	5.00	1.00	1.00	1.00	0.225	1.13		
155.00	162.60		Cum	1	7.60	1.70	1.70	1.70	0.225	2.91		
167.90	178.20		Cum	1	10.30	1.50	1.50	1.50	0.225	3.48		
183.00	191.00		Cum	1	8.00	1.60	1.60	1.60	0.225	2.88		
198.00	207.00		Cum	1	9.00	1.35	1.35	1.35	0.225	2.73		
212.00	213.50		Cum	1	1.50	1.00	1.00	1.00	0.225	0.34		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
6.00	11.00		Cum	1	5.00	1.40	1.40	1.40	0.225	1.58		
17.00	28.00		Cum	1	11.00	1.60	1.60	1.60	0.225	3.96		
32.00	41.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
47.00	55.00		Cum	1	8.00	1.80	1.80	1.80	0.225	3.24		
58.70	64.70		Cum	1	6.00	2.00	2.00	2.00	0.225	2.70		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	69.20		Cum	1	3.20	1.30	1.30	1.30	0.225	0.94		
		Jai Rama Layout Main Road										
		(From East to West)										
4.00	11.00		Cum	1	7.00	1.60	1.60	1.60	0.225	2.52		
17.00	27.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
33.70	41.60		Cum	1	7.90	1.00	1.00	1.00	0.225	1.78		
45.80	57.30		Cum	1	11.50	2.30	2.30	2.30	0.225	5.95		
63.40	73.40		Cum	1	10.00	1.70	1.70	1.70	0.225	3.83		
80.00	88.90		Cum	1	8.90	1.60	1.60	1.60	0.225	3.20		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.225	3.59		
108.00	111.00		Cum	1	3.00	2.00	2.00	2.00	0.225	1.35		
114.70	118.30		Cum	1	3.60	3.00	3.00	3.00	0.225	2.43		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
18.00	27.80		Cum	1	9.80	1.70	1.70	1.70	0.225	3.75		
33.00	41.50		Cum	1	8.50	1.65	1.65	1.65	0.225	3.16		
48.90	57.60		Cum	1	8.70	1.90	1.90	1.90	0.225	3.72		
61.80	67.90		Cum	1	6.10	2.60	2.60	2.60	0.225	3.57		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Cum	1	3.50	3.00	3.00	3.00	0.225	2.36		
6.00	13.00		Cum	1	7.00	3.00	3.00	3.00	0.225	4.73		
18.00	28.90		Cum	1	10.90	1.60	1.60	1.60	0.225	3.92		
32.60	42.70		Cum	1	10.10	1.90	1.90	1.90	0.225	4.32		
44.60	57.80		Cum	1	13.20	2.00	2.00	2.00	0.225	5.94		
63.50	74.50		Cum	1	11.00	2.30	2.30	2.30	0.225	5.69		
79.00	88.00		Cum	1	9.00	1.60	1.60	1.60	0.225	3.24		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.225	3.59		
108.00	118.00		Cum	1	10.00	2.60	2.60	2.60	0.225	5.85		
122.00	133.00		Cum	1	11.00	2.20	2.20	2.20	0.225	5.45		
137.00	147.00		Cum	1	10.00	1.70	1.70	1.70	0.225	3.83		
152.00	164.00		Cum	1	12.00	1.80	1.80	1.80	0.225	4.86		
167.00	178.00		Cum	1	11.00	2.00	2.00	2.00	0.225	4.95		
182.70	192.30		Cum	1	9.60	1.90	1.90	1.90	0.225	4.10		
197.60	208.60		Cum	1	11.00	2.20	2.20	2.20	0.225	5.45		
211.00	215.60		Cum	1	4.60	1.80	1.80	1.80	0.225	1.86		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Cum	1	3.40	1.80	1.80	1.80	0.225	1.38		
5.00	9.40		Cum	1	4.40	2.50	2.50	2.50	0.225	2.48		
12.00	18.50		Cum	1	6.50	1.70	1.70	1.70	0.225	2.49		
22.00	28.00		Cum	1	6.00	1.60	1.60	1.60	0.225	2.16		
34.00	37.80		Cum	1	3.80	1.10	1.10	1.10	0.225	0.94		
		2nd A Cross Road										
		(From North to South)										
3.00	4.30		Cum	1	1.30	1.60	1.60	1.60	0.225	0.47		
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.225	2.05		
18.00	27.90		Cum	1	9.90	1.45	1.45	1.45	0.225	3.23		
34.60	42.10		Cum	1	7.50	1.75	1.75	1.75	0.225	2.95		
49.00	58.60		Cum	1	9.60	1.60	1.60	1.60	0.225	3.46		
63.60	72.90		Cum	1	9.30	1.45	1.45	1.45	0.225	3.03		
77.80	88.90		Cum	1	11.10	1.35	1.35	1.35	0.225	3.37		
93.10	103.60		Cum	1	10.50	1.20	1.20	1.20	0.225	2.84		
108.00	111.10		Cum	1	3.10	2.80	2.80	2.80	0.225	1.95		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
3.00	11.00		Cum	1	8.00	1.60	1.60	1.60	0.225	2.88		
18.00	27.60		Cum	1	9.60	1.30	1.30	1.30	0.225	2.81		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
39.00	42.60		Cum	1	8.60	1.60	1.60	1.60	0.225	3.10		
47.00	59.70		Cum	1	12.70	1.80	1.80	1.80	0.225	5.14		
62.30	74.20		Cum	1	11.90	2.00	2.00	2.00	0.225	5.36		
77.00	87.60		Cum	1	10.60	1.30	1.30	1.30	0.225	3.10		
92.60	94.40		Cum	1	1.80	1.10	1.10	1.10	0.225	0.45		
97.60	101.00		Cum	1	3.40	1.80	1.80	1.80	0.225	1.38		
105.00	109.20		Cum	1	4.20	1.10	1.10	1.10	0.225	1.04		
		2nd Cross Road										
		(From South to North)										
4.60	13.50		Cum	1	8.90	1.60	1.60	1.60	0.225	3.20		
17.80	27.90		Cum	1	10.10	1.20	1.20	1.20	0.225	2.73		
34.60	44.20		Cum	1	9.60	1.40	1.40	1.40	0.225	3.02		
47.60	58.70		Cum	1	11.10	1.80	1.80	1.80	0.225	4.50		
64.50	72.50		Cum	1	8.00	2.30	2.30	2.30	0.225	4.14		
77.00	88.00		Cum	1	11.00	1.90	1.90	1.90	0.225	4.70		
93.00	101.00		Cum	1	8.00	1.40	1.40	1.40	0.225	2.52		
107.00	117.00		Cum	1	10.00	1.70	1.70	1.70	0.225	3.83		
120.00	122.10		Cum	1	2.10	3.00	3.00	3.00	0.225	1.42		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
4.60	11.00		Cum	1	6.40	1.60	1.60	1.60	0.225	2.30		
18.60	27.60		Cum	1	9.00	1.55	1.55	1.55	0.225	3.14		
35.60	44.00		Cum	1	8.40	1.85	1.85	1.85	0.225	3.50		
49.50	57.60		Cum	1	8.10	2.00	2.00	2.00	0.225	3.65		
64.60	73.40		Cum	1	8.80	1.95	1.95	1.95	0.225	3.86		
78.90	87.90		Cum	1	9.00	2.10	2.10	2.10	0.225	4.25		
94.20	102.00		Cum	1	7.80	1.70	1.70	1.70	0.225	2.98		
108.00	117.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
126.00	132.00		Cum	1	6.00	1.70	1.70	1.70	0.225	2.30		
135.00	136.00		Cum	1	1.00	2.10	2.10	2.10	0.225	0.47		
		1st A K.V.J Road										
		(From West to East)										
3.60	12.50		Cum	1	8.90	0.90	0.90	0.90	0.225	1.80		
21.20	27.60		Cum	1	6.40	1.80	1.80	1.80	0.225	2.59		
31.00	33.30		Cum	1	2.30	1.60	1.60	1.60	0.225	0.83		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
3.00	11.80		Cum	1	8.80	2.00	2.00	2.00	0.225	3.96		
17.60	27.80		Cum	1	10.20	1.40	1.40	1.40	0.225	3.21		
32.80	41.20		Cum	1	8.40	1.70	1.70	1.70	0.225	3.21		
48.60	57.90		Cum	1	9.30	1.65	1.65	1.65	0.225	3.45		
61.00	67.20		Cum	1	6.20	1.00	1.00	1.00	0.225	1.40		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
2.30	8.70		Cum	1	6.40	1.75	1.75	1.75	0.225	2.52		
9.90	15.00		Cum	1	5.10	2.10	2.10	2.10	0.225	2.41		
19.00	27.60		Cum	1	8.60	1.80	1.80	1.80	0.225	3.48		
33.60	43.50		Cum	1	9.90	1.60	1.60	1.60	0.225	3.56		
50.00	57.80		Cum	1	7.80	1.50	1.50	1.50	0.225	2.63		
68.50	73.00		Cum	1	4.50	1.20	1.20	1.20	0.225	1.22		
78.00	79.50		Cum	1	1.50	1.00	1.00	1.00	0.225	0.34		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
4.60	13.20		Cum	1	8.60	1.80	1.80	1.80	0.225	3.48		
18.50	27.40		Cum	1	8.90	1.60	1.60	1.60	0.225	3.20		
36.00	43.60		Cum	1	7.60	1.30	1.30	1.30	0.225	2.22		
47.00	52.30		Cum	1	5.30	1.40	1.40	1.40	0.225	1.67		
54.00	55.00		Cum	1	1.00	1.25	1.25	1.25	0.225	0.28		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
3.70	11.40		Cum	1	7.70	1.80	1.80	1.80	0.225	3.12		
16.90	25.80		Cum	1	8.90	1.60	1.60	1.60	0.225	3.20		
34.60	41.20		Cum	1	6.60	1.40	1.40	1.40	0.225	2.08		
47.90	57.60		Cum	1	9.70	2.00	2.00	2.00	0.225	4.37		
64.50	74.50		Cum	1	10.00	2.60	2.60	2.60	0.225	5.85		
79.00	88.00		Cum	1	9.00	1.70	1.70	1.70	0.225	3.44		
92.60	98.80		Cum	1	6.20	2.40	2.40	2.40	0.225	3.35		
101.00	105.00		Cum	1	4.00	2.20	2.20	2.20	0.225	1.98		
108.60	117.00		Cum	1	8.40	1.90	1.90	1.90	0.225	3.59		
121.00	129.30		Cum	1	8.30	2.10	2.10	2.10	0.225	3.92		
129.30	131.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
132.00	138.00		Cum	1	6.00	1.70	1.70	1.70	0.225	2.30		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
3.00	13.40		Cum	1	10.40	1.40	1.40	1.40	0.225	3.28		
17.60	26.80		Cum	1	9.20	1.70	1.70	1.70	0.225	3.52		
33.00	43.20		Cum	1	10.20	1.60	1.60	1.60	0.225	3.67		
48.60	57.60		Cum	1	9.00	1.85	1.85	1.85	0.225	3.75		
62.80	74.00		Cum	1	11.20	1.90	1.90	1.90	0.225	4.79		
78.00	88.90		Cum	1	10.90	1.10	1.10	1.10	0.225	2.70		
92.80	104.00		Cum	1	11.20	1.85	1.85	1.85	0.225	4.66		
		6th B Cross Road										
		(From South to North)										
2.60	11.50		Cum	1	8.90	2.10	2.10	2.10	0.225	4.21		
18.00	27.60		Cum	1	9.60	1.90	1.90	1.90	0.225	4.10		
36.00	43.20		Cum	1	7.20	2.30	2.30	2.30	0.225	3.73		
51.00	57.90		Cum	1	6.90	2.00	2.00	2.00	0.225	3.11		
65.00	72.60		Cum	1	7.60	1.85	1.85	1.85	0.225	3.16		
80.00	87.50		Cum	1	7.50	2.10	2.10	2.10	0.225	3.54		
92.70	101.00		Cum	1	8.30	1.95	1.95	1.95	0.225	3.64		
114.00	118.50		Cum	1	4.50	2.00	2.00	2.00	0.225	2.03		
		6th Cross Road										
		(From East to West)										
7.00	13.00		Cum	1	6.00	1.90	1.90	1.90	0.225	2.57		
17.00	27.60		Cum	1	10.60	1.45	1.45	1.45	0.225	3.46		
33.00	43.10		Cum	1	10.10	1.75	1.75	1.75	0.225	3.98		
47.60	58.00		Cum	1	10.40	1.85	1.85	1.85	0.225	4.33		
62.00	74.00		Cum	1	12.00	2.00	2.00	2.00	0.225	5.40		
78.00	86.90		Cum	1	8.90	1.60	1.60	1.60	0.225	3.20		
89.10	90.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
94.60	103.00		Cum	1	8.40	1.40	1.40	1.40	0.225	2.65		
108.00	117.10		Cum	1	9.10	1.60	1.60	1.60	0.225	3.28		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
2.00	5.00		Cum	1	3.00	0.80	0.80	0.80	0.225	0.54		
8.00	12.00		Cum	1	4.00	1.80	1.80	1.80	0.225	1.62		
15.00	23.00		Cum	1	8.00	1.80	1.80	1.80	0.225	3.24		
25.00	38.00		Cum	1	13.00	2.00	2.00	2.00	0.225	5.85		
40.00	50.00		Cum	1	10.00	2.00	2.00	2.00	0.225	4.50		
52.00	60.00		Cum	1	8.00	1.80	1.80	1.80	0.225	3.24		
		10th Cross Road,13th main										
		(North To South)										
3.00	9.00		Cum	1	6.00	2.00	2.00	2.00	0.225	2.70		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.225	2.25		
18.00	25.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
27.00	33.00		Cum	1	6.00	1.80	1.80	1.80	0.225	2.43		
35.00	38.00		Cum	1	3.00	0.90	0.90	0.90	0.225	0.61		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	6.00		Cum	1	4.00	2.00	2.00	2.00	0.225	1.80		
8.00	15.00		Cum	1	7.00	1.50	1.50	1.50	0.225	2.36		
18.00	26.00		Cum	1	8.00	1.80	1.80	1.80	0.225	3.24		
28.00	36.00		Cum	1	8.00	2.00	2.00	2.00	0.225	3.60		
38.00	45.00		Cum	1	7.00	1.40	1.40	1.40	0.225	2.21		
47.00	60.00		Cum	1	13.00	2.00	2.00	2.00	0.225	5.85		
63.00	75.00		Cum	1	12.00	2.00	2.00	2.00	0.225	5.40		
79.00	90.00		Cum	1	11.00	1.50	1.50	1.50	0.225	3.71		
95.00	105.00		Cum	1	10.00	1.60	1.60	1.60	0.225	3.60		
112.00	120.00		Cum	1	8.00	1.40	1.40	1.40	0.225	2.52		
123.00	130.00		Cum	1	7.00	1.60	1.60	1.60	0.225	2.52		
133.00	137.00		Cum	1	4.00	1.40	1.40	1.40	0.225	1.26		
		9th A Cross, 13th main										
		(North To South)										
3.00	8.00		Cum	1	5.00	1.30	1.30	1.30	0.225	1.46		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.225	2.25		
19.00	30.00		Cum	1	11.00	1.50	1.50	1.50	0.225	3.71		
34.00	45.00		Cum	1	11.00	1.50	1.50	1.50	0.225	3.71		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.225	4.50		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.225	4.50		
83.00	90.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
92.00	100.00		Cum	1	8.00	2.00	2.00	2.00	0.225	3.60		
102.00	108.00		Cum	1	6.00	2.00	2.00	2.00	0.225	2.70		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Cum	1	15.00	5.10	5.95	5.53	0.225	18.65		
15.00	27.10		Cum	1	12.10	5.95	4.70	5.33	0.225	14.50		
27.10	30.00		Cum	1	2.90	6.30	5.95	6.13	0.225	4.00		
30.00	45.00		Cum	1	15.00	5.95	4.95	5.45	0.225	18.39		
45.00	60.00		Cum	1	15.00	4.95	5.75	5.35	0.225	18.06		
60.00	75.00		Cum	1	15.00	5.75	5.80	5.78	0.225	19.49		
75.00	90.00		Cum	1	15.00	5.80	5.40	5.60	0.225	18.90		
90.00	105.00		Cum	1	15.00	5.40	5.30	5.35	0.225	18.06		
105.00	120.00		Cum	1	15.00	5.30	5.85	5.58	0.225	18.82		
120.00	135.00		Cum	1	15.00	5.85	6.55	6.20	0.225	20.93		
135.00	139.20		Cum	1	4.20	6.55	6.00	6.28	0.225	5.93		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Cum	1	15.00	7.85	7.00	7.43	0.225	25.06		
15.00	30.00		Cum	1	15.00	7.00	5.95	6.48	0.225	21.85		
30.00	38.40		Cum	1	8.40	5.95	5.60	5.78	0.225	10.91		
38.40	45.00		Cum	1	6.60	7.25	6.85	7.05	0.225	10.47		
45.00	60.00		Cum	1	15.00	6.85	6.10	6.48	0.225	21.85		
60.00	75.00		Cum	1	15.00	6.10	6.55	6.33	0.225	21.35		
75.00	90.00		Cum	1	15.00	6.55	6.70	6.63	0.225	22.36		
90.00	105.00		Cum	1	15.00	6.70	7.10	6.90	0.225	23.29		
105.00	113.00		Cum	1	8.00	7.10	7.00	7.05	0.225	12.69		
113.00	120.00		Cum	1	7.00	5.05	5.00	5.03	0.225	7.91		
120.00	126.20		Cum	1	6.20	5.00	5.10	5.05	0.225	7.04		
126.20	130.50		Cum	1	4.30	5.95	6.00	5.98	0.225	5.78		
130.50	135.00		Cum	1	4.50	6.00	6.15	6.08	0.225	6.15		
135.00	150.00		Cum	1	15.00	6.15	6.80	6.48	0.225	21.85		
150.00	165.00		Cum	1	15.00	6.80	6.75	6.78	0.225	22.87		
165.00	165.40		Cum	1	0.40	6.75	6.80	6.78	0.225	0.61		
165.40	180.00		Cum	1	14.60	6.30	6.35	6.33	0.225	20.78		
180.00	195.00		Cum	1	15.00	6.35	6.00	6.18	0.225	20.84		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
[illegible].00	210.00		Cum	1	15.00	6.00	5.90	5.95	0.225	20.08		
210.00	225.00		Cum	1	15.00	5.90	6.20	6.05	0.225	20.42		
225.00	240.00		Cum	1	15.00	6.20	5.75	5.98	0.225	20.17		
240.00	249.30		Cum	1	9.30	5.75	6.00	5.88	0.225	12.29		
249.30	258.30		Cum	1	9.00	5.10	4.65	4.88	0.225	9.87		
258.30	273.30		Cum	1	15.00	5.45	5.25	5.35	0.225	18.06		
273.30	275.00		Cum	1	1.70	5.25	5.25	5.25	0.225	2.01		
273.30	284.00		Cum	1	10.70	5.25	5.75	5.50	0.225	13.24		
		1st Cross Road										
		(From North To South)										
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.225	2.05		
18.00	23.00		Cum	1	5.00	1.60	1.60	1.60	0.225	1.80		
27.00	35.00		Cum	1	8.00	1.20	1.20	1.20	0.225	2.16		
43.00	50.00		Cum	1	7.00	1.30	1.30	1.30	0.225	2.05		
52.00	58.00		Cum	1	6.00	1.60	1.60	1.60	0.225	2.16		
63.00	72.00		Cum	1	9.00	1.80	1.80	1.80	0.225	3.65		
77.00	88.00		Cum	1	11.00	1.70	1.70	1.70	0.225	4.21		
94.00	103.00		Cum	1	9.00	1.25	1.25	1.25	0.225	2.53		
108.00	116.00		Cum	1	8.00	1.15	1.15	1.15	0.225	2.07		
124.00	131.00		Cum	1	7.00	1.50	1.50	1.50	0.225	2.36		
138.00	147.00		Cum	1	9.00	1.40	1.40	1.40	0.225	2.84		
		Balaji Layout										
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
2.50	10.00		Cum	1	7.50	0.90	0.90	0.90	0.225	1.52		
18.00	27.00		Cum	1	9.00	1.30	1.30	1.30	0.225	2.63		
34.00	41.00		Cum	1	7.00	0.75	0.75	0.75	0.225	1.18		
48.00	52.00		Cum	1	4.00	1.00	1.00	1.00	0.225	0.90		
54.20	55.80	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
58.00	60.00		Cum	1	2.00	1.00	1.00	1.00	0.225	0.45		
63.00	72.00		Cum	1	9.00	1.30	1.30	1.30	0.225	2.63		
76.00	88.00		Cum	1	12.00	1.40	1.40	1.40	0.225	3.78		
93.00	103.00		Cum	1	10.00	1.80	1.80	1.80	0.225	4.05		
108.00	118.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
123.00	132.00		Cum	1	9.00	1.10	1.10	1.10	0.225	2.23		
137.00	149.00		Cum	1	12.00	1.60	1.60	1.60	0.225	4.32		
152.00	163.00		Cum	1	11.00	1.30	1.30	1.30	0.225	3.22		
169.00	178.00		Cum	1	9.00	1.40	1.40	1.40	0.225	2.84		
182.00	193.00		Cum	1	11.00	1.20	1.20	1.20	0.225	2.97		
197.00	209.00		Cum	1	12.00	1.80	1.80	1.80	0.225	4.86		
212.00	223.00		Cum	1	11.00	1.30	1.30	1.30	0.225	3.22		
225.00	228.20		Cum	1	3.20	0.60	0.60	0.60	0.225	0.43		
228.20	232.00		Cum	1	3.80	0.75	0.75	0.75	0.225	0.64		
234.00	245.20		Cum	1	11.20	1.25	1.25	1.25	0.225	3.15		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
3.00	13.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
18.00	28.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
34.00	43.60		Cum	1	9.60	1.70	1.70	1.70	0.225	3.67		
		(From West To East)										
0.00	3.90		Cum	1	3.90	1.30	1.30	1.30	0.225	1.14		
3.90	11.10		Cum	1	7.20	1.20	1.20	1.20	0.225	1.94		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
4.20	12.00		Cum	1	7.80	1.20	1.20	1.20	0.225	2.11		
15.00	18.80		Cum	1	3.80	3.80	3.80	3.80	0.225	3.25		
21.00	27.80		Cum	1	6.80	1.00	1.00	1.00	0.225	1.53		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
42.60	42.60		Cum	1	10.00	1.25	1.25	1.25	0.225	2.81		
47.60	57.40		Cum	1	9.80	1.10	1.10	1.10	0.225	2.43		
64.30	71.00		Cum	1	6.70	1.60	1.60	1.60	0.225	2.41		
77.60	80.00		Cum	1	2.40	1.35	1.35	1.35	0.225	0.73		
83.40	90.20		Cum	1	6.80	1.00	1.00	1.00	0.225	1.53		
93.60	103.20		Cum	1	9.60	0.90	0.90	0.90	0.225	1.94		
107.80	116.90		Cum	1	9.10	1.40	1.40	1.40	0.225	2.87		
124.30	131.70		Cum	1	7.40	1.25	1.25	1.25	0.225	2.08		
138.40	147.00		Cum	1	8.60	1.35	1.35	1.35	0.225	2.61		
152.80	163.10		Cum	1	10.30	1.10	1.10	1.10	0.225	2.55		
		6th A Cross Road										
		(From West to East)										
3.00	6.00		Cum	1	3.00	3.00	3.00	3.00	0.225	2.03		
		(From South to North)										
2.30	6.40		Cum	1	4.10	2.20	2.20	2.20	0.225	2.03		
9.00	13.40		Cum	1	4.40	2.60	2.60	2.60	0.225	2.57		
17.90	27.60		Cum	1	9.70	2.00	2.00	2.00	0.225	4.37		
36.20	44.20		Cum	1	8.00	1.35	1.35	1.35	0.225	2.43		
45.00	50.70		Cum	1	5.70	2.00	2.00	2.00	0.225	2.57		
50.70	60.00		Cum	1	9.30	1.80	1.80	1.80	0.225	3.77		
62.30	71.20		Cum	1	8.90	1.30	1.30	1.30	0.225	2.60		
77.80	88.90		Cum	1	11.10	1.70	1.70	1.70	0.225	4.25		
93.40	103.80		Cum	1	10.40	1.40	1.40	1.40	0.225	3.28		
107.00	119.00		Cum	1	12.00	1.60	1.60	1.60	0.225	4.32		
121.00	133.20		Cum	1	12.20	1.40	1.40	1.40	0.225	3.84		
137.00	141.70		Cum	1	4.70	1.00	1.00	1.00	0.225	1.06		
		Devi Nagar Main Road										
		(From West to East)										
2.50	11.00		Cum	1	8.50	1.70	1.70	1.70	0.225	3.25		
16.80	26.40		Cum	1	9.60	2.00	2.00	2.00	0.225	4.32		
33.20	43.50		Cum	1	10.30	1.90	1.90	1.90	0.225	4.40		
47.00	58.00		Cum	1	11.00	2.30	2.30	2.30	0.225	5.69		
63.00	71.00		Cum	1	8.00	1.60	1.60	1.60	0.225	2.88		
77.00	87.00		Cum	1	10.00	1.45	1.45	1.45	0.225	3.26		
93.50	103.00		Cum	1	9.50	1.80	1.80	1.80	0.225	3.85		
107.00	118.00		Cum	1	11.00	2.20	2.20	2.20	0.225	5.45		
123.00	134.00		Cum	1	11.00	2.00	2.00	2.00	0.225	4.95		
137.60	149.50		Cum	1	11.90	1.90	1.90	1.90	0.225	5.09		
151.00	163.40		Cum	1	12.40	1.60	1.60	1.60	0.225	4.46		
165.00	180.00		Cum	1	15.00	1.55	1.55	1.55	0.225	5.23		
183.00	194.30		Cum	1	11.30	1.30	1.30	1.30	0.225	3.31		
196.50	210.00		Cum	1	13.50	1.40	1.40	1.40	0.225	4.25		
212.30	225.00		Cum	1	12.70	1.25	1.25	1.25	0.225	3.57		
227.00	237.20		Cum	1	10.20	1.80	1.80	1.80	0.225	4.13		
237.20	239.00		Cum	1	1.80	2.00	2.00	2.00	0.225	0.81		
239.00	241.50		Cum	1	2.50	1.20	1.20	1.20	0.225	0.68		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Cum	1	3.20	1.10	1.10	1.10	0.225	0.79		
7.00	15.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
18.00	28.40		Cum	1	10.40	0.90	0.90	0.90	0.225	2.11		
36.00	45.00		Cum	1	9.00	0.75	0.75	0.75	0.225	1.52		
47.80	57.90		Cum	1	10.10	1.60	1.60	1.60	0.225	3.64		
63.70	72.30		Cum	1	8.60	1.20	1.20	1.20	0.225	2.32		
78.90	88.00		Cum	1	9.10	1.70	1.70	1.70	0.225	3.48		
93.60	103.70		Cum	1	10.10	1.20	1.20	1.20	0.225	2.73		
111.00	120.00		Cum	1	9.00	1.45	1.45	1.45	0.225	2.94		
127.00	135.00		Cum	1	8.00	1.65	1.65	1.65	0.225	2.97		
138.90	149.00		Cum	1	10.10	1.80	1.80	1.80	0.225	4.09		
154.70	162.60		Cum	1	7.90	1.70	1.70	1.70	0.225	3.02		
168.90	177.50		Cum	1	8.60	1.90	1.90	1.90	0.225	3.68		
180.00	184.70		Cum	1	4.70	1.60	1.60	1.60	0.225	1.69		
184.70	186.20		Cum	1	1.50	1.70	1.70	1.70	0.225	0.57		
186.20	195.00		Cum	1	8.80	1.60	1.60	1.60	0.225	3.17		
197.00	208.90		Cum	1	11.90	1.40	1.40	1.40	0.225	3.75		
213.00	223.60		Cum	1	10.60	1.25	1.25	1.25	0.225	2.98		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
227.00	237.80		Cum	1	10.80	1.30	1.30	1.30	0.225	3.16		
242.60	251.00		Cum	1	8.40	1.40	1.40	1.40	0.225	2.65		
257.00	267.60		Cum	1	10.60	1.60	1.60	1.60	0.225	3.82		
273.00	281.60		Cum	1	8.60	1.20	1.20	1.20	0.225	2.32		
286.00	293.70		Cum	1	7.70	0.90	0.90	0.90	0.225	1.56		
293.70	298.70		Cum	1	5.00	1.90	1.90	1.90	0.225	2.14		
298.70	300.00		Cum	1	1.30	0.90	0.90	0.90	0.225	0.26		
303.60	313.80		Cum	1	10.20	1.40	1.40	1.40	0.225	3.21		
317.00	328.70		Cum	1	11.70	1.30	1.30	1.30	0.225	3.42		
332.40	342.60		Cum	1	10.20	1.15	1.15	1.15	0.225	2.64		
348.90	358.00		Cum	1	9.10	1.35	1.35	1.35	0.225	2.76		
360.00	363.50		Cum	1	3.50	2.00	2.00	2.00	0.225	1.58		
363.50	372.30		Cum	1	8.80	1.70	1.70	1.70	0.225	3.37		
374.00	386.00		Cum	1	12.00	1.50	1.50	1.50	0.225	4.05		
387.30	390.00		Cum	1	2.70	2.00	2.00	2.00	0.225	1.21		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
3.00	13.40		Cum	1	10.40	1.20	1.20	1.20	0.225	2.81		
18.00	29.50		Cum	1	11.50	1.90	1.90	1.90	0.225	4.92		
29.50	47.20	No Work	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
51.00	58.70		Cum	1	7.70	1.50	1.50	1.50	0.225	2.60		
62.70	73.80		Cum	1	11.10	1.70	1.70	1.70	0.225	4.25		
77.00	88.90		Cum	1	11.90	1.90	1.90	1.90	0.225	5.09		
92.60	103.50		Cum	1	10.90	1.35	1.35	1.35	0.225	3.31		
108.90	120.00		Cum	1	11.10	1.60	1.60	1.60	0.225	4.00		
123.60	134.50		Cum	1	10.90	1.80	1.80	1.80	0.225	4.41		
137.80	148.90		Cum	1	11.10	1.55	1.55	1.55	0.225	3.87		
150.30	158.50		Cum	1	8.20	1.70	1.70	1.70	0.225	3.14		
158.50	165.30		Cum	1	6.80	2.00	2.00	2.00	0.225	3.06		
168.00	179.00		Cum	1	11.00	1.80	1.80	1.80	0.225	4.46		
180.30	189.60		Cum	1	9.30	1.90	1.90	1.90	0.225	3.98		
189.60	193.50		Cum	1	3.90	2.00	2.00	2.00	0.225	1.76		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Cum	1	4.00	2.00	2.00	2.00	0.225	1.80		
6.00	12.50		Cum	1	6.50	1.80	1.80	1.80	0.225	2.63		
15.00	22.00		Cum	1	7.00	1.90	1.90	1.90	0.225	2.99		
24.10	30.00		Cum	1	5.90	1.65	1.65	1.65	0.225	2.19		
32.40	38.10		Cum	1	5.70	1.50	1.50	1.50	0.225	1.92		
38.10	46.00		Cum	1	7.90	1.20	1.20	1.20	0.225	2.13		
48.90	58.00		Cum	1	9.10	1.30	1.30	1.30	0.225	2.66		
60.00	67.00		Cum	1	7.00	1.65	1.65	1.65	0.225	2.60		
69.00	75.00		Cum	1	6.00	1.30	1.30	1.30	0.225	1.76		
77.00	83.50		Cum	1	6.50	2.00	2.00	2.00	0.225	2.93		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
2.60	12.60		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
17.80	27.60		Cum	1	9.80	1.60	1.60	1.60	0.225	3.53		
33.70	43.50		Cum	1	9.80	1.40	1.40	1.40	0.225	3.09		
47.00	56.90		Cum	1	9.90	1.15	1.15	1.15	0.225	2.56		
62.00	74.00		Cum	1	12.00	1.85	1.85	1.85	0.225	5.00		
75.00	87.00		Cum	1	12.00	1.10	1.10	1.10	0.225	2.97		
87.00	90.00		Cum	1	3.00	2.00	2.00	2.00	0.225	1.35		
92.30	102.00		Cum	1	9.70	1.80	1.80	1.80	0.225	3.93		
107.00	118.00		Cum	1	11.00	1.35	1.35	1.35	0.225	3.34		
120.00	129.20		Cum	1	9.20	1.75	1.75	1.75	0.225	3.62		
129.20	135.00		Cum	1	5.80	2.00	2.00	2.00	0.225	2.61		
136.70	148.70		Cum	1	12.00	1.25	1.25	1.25	0.225	3.38		
152.60	163.00		Cum	1	10.40	1.15	1.15	1.15	0.225	2.69		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
om	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
107.00	179.80		Cum	1	12.80	1.05	1.05	1.05	0.225	3.02		
180.00	195.00		Cum	1	15.00	1.40	1.40	1.40	0.225	4.73		
195.00	209.00		Cum	1	14.00	1.30	1.30	1.30	0.225	4.10		
211.00	221.50		Cum	1	10.50	0.90	0.90	0.90	0.225	2.13		
		1st Cross Road										
		(From North to South)										
4.60	13.40		Cum	1	8.80	1.10	1.10	1.10	0.225	2.18		
15.00	17.10		Cum	1	2.10	1.05	1.05	1.05	0.225	0.50		
17.10	22.80		Cum	1	5.70	1.20	1.20	1.20	0.225	1.54		
22.80	30.00		Cum	1	7.20	0.90	0.90	0.90	0.225	1.46		
34.30	41.00		Cum	1	6.70	0.75	0.75	0.75	0.225	1.13		
47.60	53.20		Cum	1	5.60	0.90	0.90	0.90	0.225	1.13		
54.00	60.00		Cum	1	6.00	0.90	0.90	0.90	0.225	1.22		
63.00	71.60		Cum	1	8.60	0.75	0.75	0.75	0.225	1.45		
79.00	85.20		Cum	1	6.20	1.00	1.00	1.00	0.225	1.40		
		2nd Cross Road										
		(From North to South)										
3.00	12.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
18.90	27.60		Cum	1	8.70	1.30	1.30	1.30	0.225	2.54		
33.60	42.50		Cum	1	8.90	1.10	1.10	1.10	0.225	2.20		
48.90	56.30		Cum	1	7.40	1.40	1.40	1.40	0.225	2.33		
62.80	71.60		Cum	1	8.80	1.00	1.00	1.00	0.225	1.98		
75.00	82.10		Cum	1	7.10	0.65	0.65	0.65	0.225	1.04		
		2nd A Cross Road										
		(From South to North)										
3.80	13.40		Cum	1	9.60	1.60	1.60	1.60	0.225	3.46		
16.70	25.90		Cum	1	9.20	1.70	1.70	1.70	0.225	3.52		
37.00	44.90		Cum	1	7.90	1.10	1.10	1.10	0.225	1.96		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Cum	1	4.20	1.90	1.90	1.90	0.225	1.80		
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.225	1.98		
21.00	28.50		Cum	1	7.50	1.60	1.60	1.60	0.225	2.70		
34.50	41.00		Cum	1	6.50	1.50	1.50	1.50	0.225	2.19		
46.00	52.20		Cum	1	6.20	1.40	1.40	1.40	0.225	1.95		
53.00	60.00		Cum	1	7.00	0.65	0.65	0.65	0.225	1.02		
62.00	67.30		Cum	1	5.30	0.75	0.75	0.75	0.225	0.89		
69.00	70.60		Cum	1	1.60	0.90	0.90	0.90	0.225	0.32		
73.00	81.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
85.00	89.00		Cum	1	4.00	1.10	1.10	1.10	0.225	0.99		
90.00	92.10		Cum	1	2.10	0.90	0.90	0.90	0.225	0.43		
92.10	95.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
98.00	103.40		Cum	1	5.40	1.40	1.40	1.40	0.225	1.70		
107.80	108.90		Cum	1	1.10	1.70	1.70	1.70	0.225	0.42		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
30.00	45.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
45.00	47.80		Cum	1	2.80	1.50	1.50	1.50	0.225	0.94		
47.80	56.10		Cum	1	8.30	1.50	1.50	1.50	0.225	2.80		
56.10	63.90		Cum	1	7.80	1.50	1.50	1.50	0.225	2.63		
63.90	65.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
65.50	75.00		Cum	1	9.50	1.50	1.50	1.50	0.225	3.21		
75.00	90.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
90.00	94.50		Cum	1	4.50	1.50	1.50	1.50	0.225	1.52		
94.50	105.00		Cum	1	10.50	1.50	1.50	1.50	0.225	3.54		
105.00	120.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
120.00	122.00		Cum	1	2.00	1.50	1.50	1.50	0.225	0.68		
122.00	135.00		Cum	1	13.00	1.50	1.50	1.50	0.225	4.39		
135.00	150.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
150.00	154.00		Cum	1	4.00	1.50	1.50	1.50	0.225	1.35		
154.00	163.70		Cum	1	9.70	1.50	1.50	1.50	0.225	3.27		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
169.70	169.70		Cum	1	6.00	1.50	1.50	1.50	0.225	2.03		
169.70	171.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
171.20	180.00		Cum	1	8.80	1.50	1.50	1.50	0.225	2.97		
180.00	181.80		Cum	1	1.80	1.50	1.50	1.50	0.225	0.61		
181.80	190.00		Cum	1	8.20	1.50	1.50	1.50	0.225	2.77		
190.00	205.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
205.00	216.10		Cum	1	11.10	1.50	1.50	1.50	0.225	3.75		
216.10	231.10		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
231.10	235.00		Cum	1	3.90	1.50	1.50	1.50	0.225	1.32		
235.00	250.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
250.00	265.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
265.00	280.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
280.00	295.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
295.00	300.00		Cum	1	5.00	1.50	1.50	1.50	0.225	1.69		
300.00	315.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
315.00	330.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
330.00	345.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
345.00	360.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
360.00	369.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	8.40	6.80	7.60	0.225	25.65		
15.00	29.20		Cum	1	14.20	6.80	6.90	6.85	0.225	21.89		
29.20	30.30	Culvert	Cum	0	0.00	0.00	0.00	0.00	0.225	0.00		
30.30	45.00		Cum	1	14.70	6.85	6.70	6.78	0.225	22.41		
45.00	60.00		Cum	1	15.00	6.70	6.60	6.65	0.225	22.44		
60.00	75.00		Cum	1	15.00	6.60	6.40	6.50	0.225	21.94		
75.00	79.70		Cum	1	4.70	6.40	5.75	6.08	0.225	6.42		
79.70	90.00		Cum	1	10.30	2.50	2.50	2.50	0.225	5.79		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
105.00	108.50		Cum	1	3.50	2.50	2.50	2.50	0.225	1.97		
108.50	118.70		Cum	1	10.20	2.50	2.50	2.50	0.225	5.74		
118.70	124.80		Cum	1	6.10	2.50	2.50	2.50	0.225	3.43		
124.80	135.00		Cum	1	10.20	2.50	2.50	2.50	0.225	5.74		
135.00	150.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
150.00	165.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
195.00	210.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
210.00	225.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
240.00	255.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
255.00	270.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
270.00	285.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
285.00	291.50		Cum	1	6.50	2.50	2.50	2.50	0.225	3.66		
291.50	298.00		Cum	1	6.50	2.50	2.50	2.50	0.225	3.66		
		1st Cross Road										
		(From East to West)										
3.40	13.70		Cum	1	10.30	1.60	1.60	1.60	0.225	3.71		
15.00	17.20		Cum	1	2.20	2.00	2.00	2.00	0.225	0.99		
18.90	28.00		Cum	1	9.10	1.40	1.40	1.40	0.225	2.87		
34.60	41.00		Cum	1	6.40	1.50	1.50	1.50	0.225	2.16		
41.00	50.20		Cum	1	9.20	1.30	1.30	1.30	0.225	2.69		
		2nd Cross Road										
		(From East to West)										
3.60	12.80		Cum	1	9.20	1.30	1.30	1.30	0.225	2.69		
17.80	27.90		Cum	1	10.10	1.10	1.10	1.10	0.225	2.50		
32.00	41.20		Cum	1	9.20	1.50	1.50	1.50	0.225	3.11		
45.00	50.20		Cum	1	5.20	2.00	2.00	2.00	0.225	2.34		
50.20	52.80		Cum	1	2.60	1.00	1.00	1.00	0.225	0.58		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	15.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
15.00	30.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
30.00	45.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
45.00	60.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
60.00	63.30		Cum	1	3.30	2.50	2.50	2.50	0.225	1.86		
63.30	75.00		Cum	1	11.70	2.50	2.50	2.50	0.225	6.58		
75.00	90.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
105.00	120.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
120.00	132.90		Cum	1	12.90	2.50	2.50	2.50	0.225	7.26		
132.90	147.10		Cum	1	14.20	2.50	2.50	2.50	0.225	7.99		
147.10	160.00		Cum	1	12.90	2.50	2.50	2.50	0.225	7.26		
160.00	165.00		Cum	1	5.00	2.50	2.50	2.50	0.225	2.81		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
195.00	198.80		Cum	1	3.80	2.50	2.50	2.50	0.225	2.14		
198.80	210.00		Cum	1	11.20	2.50	2.50	2.50	0.225	6.30		
210.00	219.70		Cum	1	9.70	2.50	2.50	2.50	0.225	5.46		
219.70	222.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.225	0.00		
222.20	225.00		Cum	1	2.80	2.50	2.50	2.50	0.225	1.58		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
240.00	249.60		Cum	1	9.60	2.50	2.50	2.50	0.225	5.40		
249.60	257.30		Cum	1	7.70	2.50	2.50	2.50	0.225	4.33		
257.30	260.00		Cum	1	2.70	2.50	2.50	2.50	0.225	1.52		
260.00	275.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
275.00	292.00		Cum	1	17.00	2.50	2.50	2.50	0.225	9.56		
292.00	297.10		Cum	1	5.10	2.50	2.50	2.50	0.225	2.87		
297.10	300.00		Cum	1	2.90	2.50	2.50	2.50	0.225	1.63		
300.00	315.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
315.00	330.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
330.00	345.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
345.00	360.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
360.00	375.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
375.00	390.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
390.00	405.00		Cum	1	15.00	2.50	2.50	2.50	0.225	8.44		
405.00	414.50		Cum	1	9.50	2.50	2.50	2.50	0.225	5.34		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
30.00	45.00		Cum	1	15.00	1.65	1.65	1.65	0.225	5.57		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.225	4.73		
60.00	69.30		Cum	1	9.30	1.10	1.10	1.10	0.225	2.30		
69.30	75.00		Cum	1	5.70	2.00	2.00	2.00	0.225	2.57		
75.00	90.00		Cum	1	15.00	2.20	2.20	2.20	0.225	7.43		
90.00	105.00		Cum	1	15.00	1.60	1.60	1.60	0.225	5.40		
105.00	111.40		Cum	1	6.40	3.50	3.50	3.50	0.225	5.04		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Cum	1	4.60	4.00	4.00	4.00	0.225	4.14		
4.60	15.00		Cum	1	10.40	2.10	2.10	2.10	0.225	4.91		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
30.00	45.00		Cum	1	15.00	1.40	1.40	1.40	0.225	4.73		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
60.00	75.00		Cum	1	15.00	2.00	2.00	2.00	0.225	6.75		
75.00	90.00		Cum	1	15.00	1.40	1.40	1.40	0.225	4.73		
90.00	100.30		Cum	1	10.30	1.30	1.30	1.30	0.225	3.01		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.225	3.71		
15.00	30.00		Cum	1	15.00	1.30	1.30	1.30	0.225	4.39		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	45.00		Cum	1	15.00	1.00	1.00	1.00	0.225	3.38		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.225	4.73		
60.00	73.50		Cum	1	13.50	1.20	1.20	1.20	0.225	3.65		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Cum	1	15.00	1.30	1.30	1.30	0.225	4.39		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
30.00	45.00		Cum	1	15.00	1.35	1.35	1.35	0.225	4.56		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.225	3.71		
60.00	75.00		Cum	1	15.00	1.00	1.00	1.00	0.225	3.38		
75.00	81.00		Cum	1	6.00	1.40	1.40	1.40	0.225	1.89		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.225	3.71		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.225	6.75		
45.00	60.00		Cum	1	15.00	1.70	1.70	1.70	0.225	5.74		
60.00	75.00		Cum	1	15.00	1.90	1.90	1.90	0.225	6.41		
75.00	90.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
90.00	95.80		Cum	1	5.80	5.80	5.80	5.80	0.225	7.57		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Cum	1	15.00	2.20	2.20	2.20	0.225	7.43		
15.00	26.20		Cum	1	11.20	1.80	1.80	1.80	0.225	4.54		
		(North To South)										
0.00	15.00		Cum	1	15.00	1.70	1.70	1.70	0.225	5.74		
15.00	30.00		Cum	1	15.00	1.60	1.60	1.60	0.225	5.40		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.225	6.75		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
60.00	75.00		Cum	1	15.00	2.30	2.30	2.30	0.225	7.76		
75.00	90.00		Cum	1	15.00	1.90	1.90	1.90	0.225	6.41		
90.00	105.00		Cum	1	15.00	1.80	1.80	1.80	0.225	6.08		
105.00	120.00		Cum	1	15.00	2.20	2.20	2.20	0.225	7.43		
120.00	135.00		Cum	1	15.00	1.60	1.60	1.60	0.225	5.40		
135.00	150.00		Cum	1	15.00	2.10	2.10	2.10	0.225	7.09		
150.00	165.00		Cum	1	15.00	1.60	1.60	1.60	0.225	5.40		
165.00	169.00		Cum	1	4.00	1.90	1.90	1.90	0.225	1.71		
		Ward No 10										
		Vidyaranyapura Sub division										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
4.00	9.00		Cum	1	5.00	0.90	0.90	0.90	0.225	1.01		
20.00	28.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
35.00	42.00		Cum	1	7.00	1.20	1.20	1.20	0.225	1.89		
65.00	71.00		Cum	1	6.00	1.30	1.30	1.30	0.225	1.76		
80.00	87.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
94.00	102.00		Cum	1	8.00	0.90	0.90	0.90	0.225	1.62		
111.00	118.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
125.00	133.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
140.00	148.00		Cum	1	8.00	1.50	1.50	1.50	0.225	2.70		
155.00	162.00		Cum	1	7.00	1.20	1.20	1.20	0.225	1.89		
170.00	178.00		Cum	1	8.00	1.50	1.50	1.50	0.225	2.70		
185.00	195.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
195.00	203.10		Cum	1	8.10	1.50	1.50	1.50	0.225	2.73		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
3.10	12.00		Cum	1	8.90	1.10	1.10	1.10	0.225	2.20		
20.00	28.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
50.00	58.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
80.00	87.00		Cum	1	7.00	1.30	1.30	1.30	0.225	2.05		
96.00	100.00		Cum	1	4.00	1.45	1.45	1.45	0.225	1.31		
112.00	120.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
128.00	135.00		Cum	1	7.00	0.90	0.90	0.90	0.225	1.42		
137.00	150.00		Cum	1	13.00	0.60	0.60	0.60	0.225	1.76		
158.00	165.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
173.00	180.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
188.00	195.00		Cum	1	7.00	0.90	0.90	0.90	0.225	1.42		
200.00	210.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
217.00	225.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
232.00	240.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
248.00	255.00		Cum	1	7.00	0.90	0.90	0.90	0.225	1.42		
264.00	270.00		Cum	1	6.00	1.10	1.10	1.10	0.225	1.49		
272.00	277.40		Cum	1	5.40	1.00	1.00	1.00	0.225	1.21		
278.50	285.00		Cum	1	6.50	1.00	1.00	1.00	0.225	1.46		
290.00	300.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
3.50	12.00		Cum	1	8.50	0.60	0.60	0.60	0.225	1.15		
20.00	25.20		Cum	1	5.20	1.10	1.10	1.10	0.225	1.29		
27.00	33.90		Cum	1	6.90	0.50	0.50	0.50	0.225	0.78		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
50.00	60.00		Cum	1	10.00	0.80	0.80	0.80	0.225	1.80		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
80.00	90.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
95.00	105.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
106.00	109.10		Cum	1	3.10	1.10	1.10	1.10	0.225	0.77		
112.00	120.00		Cum	1	8.00	1.10	1.10	1.10	0.225	1.98		
125.00	135.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
138.00	142.80		Cum	1	4.80	1.10	1.10	1.10	0.225	1.19		
145.00	150.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
151.00	154.80		Cum	1	3.80	1.10	1.10	1.10	0.225	0.94		
157.00	165.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
168.00	172.80		Cum	1	4.80	1.10	1.10	1.10	0.225	1.19		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
181.00	185.00		Cum	1	4.00	1.20	1.20	1.20	0.225	1.08		
190.00	195.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
198.00	209.40		Cum	1	11.40	0.60	0.60	0.60	0.225	1.54		
215.00	221.00		Cum	1	6.00	1.10	1.10	1.10	0.225	1.49		
		Samashana Road										
		2nd main Road										
		(From East to West)										
5.00	11.80		Cum	1	6.80	0.60	0.60	0.60	0.225	0.92		
13.00	15.00		Cum	1	2.00	1.20	1.20	1.20	0.225	0.54		
20.00	30.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
66.00	75.00		Cum	1	9.00	1.10	1.10	1.10	0.225	2.23		
81.00	90.00		Cum	1	9.00	1.10	1.10	1.10	0.225	2.23		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
115.00	120.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
125.00	135.00		Cum	1	10.00	0.70	0.70	0.70	0.225	1.58		
138.00	140.50		Cum	1	2.50	0.70	0.70	0.70	0.225	0.39		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	15.50		Cum	1	9.50	1.20	1.20	1.20	0.225	2.57		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
25.00	30.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
47.00	51.00		Cum	1	4.00	1.00	1.00	1.00	0.225	0.90		
53.00	60.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
95.00	105.10		Cum	1	10.10	1.00	1.00	1.00	0.225	2.27		
110.00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
122.00	126.50		Cum	1	4.50	0.60	0.60	0.60	0.225	0.61		
130.00	135.00		Cum	1	5.00	0.60	0.60	0.60	0.225	0.68		
138.00	141.90		Cum	1	3.90	0.70	0.70	0.70	0.225	0.61		
144.00	150.00		Cum	1	6.00	0.70	0.70	0.70	0.225	0.95		
152.00	154.10		Cum	1	2.10	0.90	0.90	0.90	0.225	0.43		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Cum	1	1.60	0.60	0.60	0.60	0.225	0.22		
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.225	1.76		
34.00	45.00		Cum	1	11.00	1.00	1.00	1.00	0.225	2.48		
48.00	60.00		Cum	1	12.00	0.60	0.60	0.60	0.225	1.62		
63.00	75.00		Cum	1	12.00	0.90	0.90	0.90	0.225	2.43		
75.00	79.10		Cum	1	4.10	0.60	0.60	0.60	0.225	0.55		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
6.00	15.00		Cum	1	9.00	1.20	1.20	1.20	0.225	2.43		
17.00	23.30		Cum	1	6.30	0.70	0.70	0.70	0.225	0.99		
		From house no #15 to house no -7										
		(From North to South)										
5.00	15.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
22.00	30.00		Cum	1	8.00	1.20	1.20	1.20	0.225	2.16		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
51.00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.225	2.03		
65.00	73.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
74.00	79.00		Cum	1	5.00	1.50	1.50	1.50	0.225	1.69		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
4.00	15.00		Cum	1	11.00	1.00	1.00	1.00	0.225	2.48		
20.00	29.60		Cum	1	9.60	1.40	1.40	1.40	0.225	3.02		
32.00	38.70		Cum	1	6.70	1.00	1.00	1.00	0.225	1.51		
40.00	45.00		Cum	1	5.00	1.80	1.80	1.80	0.225	2.03		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
65.00	75.00		Cum	1	10.00	1.70	1.70	1.70	0.225	3.83		
78.00	84.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
86.00	90.00		Cum	1	4.00	2.00	2.00	2.00	0.225	1.80		
100.00	103.00		Cum	1	3.00	0.60	0.60	0.60	0.225	0.41		
106.00	115.00		Cum	1	9.00	1.00	1.00	1.00	0.225	2.03		
117.00	127.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
129.00	139.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
140.00	148.00		Cum	1	8.00	1.40	1.40	1.40	0.225	2.52		
150.00	153.30		Cum	1	3.30	1.00	1.00	1.00	0.225	0.74		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
8.00	15.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
20.00	30.00		Cum	1	10.00	1.60	1.60	1.60	0.225	3.60		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
39.00	43.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
45.00	47.30		Cum	1	2.30	1.30	1.30	1.30	0.225	0.67		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
7.00	15.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
22.00	30.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
38.00	45.00		Cum	1	7.00	1.80	1.80	1.80	0.225	2.84		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
65.00	75.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
108.00	112.00		Cum	1	4.00	0.70	0.70	0.70	0.225	0.63		
		3rd Cross Road										
		From House no: #14&15 to [illegible]										
		(From South to North)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
20.00	30.00		Cum	1	10.00	1.30	1.30	1.30	0.225	2.93		
34.00	45.00		Cum	1	11.00	1.20	1.20	1.20	0.225	2.97		
49.00	50.10		Cum	1	1.10	2.00	2.00	2.00	0.225	0.50		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
5.00	15.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.225	1.76		
35.00	45.00		Cum	1	10.00	0.80	0.80	0.80	0.225	1.80		
50.00	60.00		Cum	1	10.00	0.70	0.70	0.70	0.225	1.58		
68.00	75.10		Cum	1	7.10	1.10	1.10	1.10	0.225	1.76		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	15.00		Cum	1	11.00	1.20	1.20	1.20	0.225	2.97		
20.00	30.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
30.00	34.30		Cum	1	4.30	1.00	1.00	1.00	0.225	0.97		
36.00	45.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.225	2.93		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
82.00	90.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
125.00	135.00		Cum	1	10.00	1.25	1.25	1.25	0.225	2.81		
140.00	150.00		Cum	1	10.00	0.90	0.90	0.90	0.225	2.03		
157.00	165.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
170.00	180.00		Cum	1	10.00	0.80	0.80	0.80	0.225	1.80		
182.00	187.20		Cum	1	5.20	2.00	2.00	2.00	0.225	2.34		
190.00	195.00		Cum	1	5.00	1.00	1.00	1.00	0.225	1.13		
199.00	210.00		Cum	1	11.00	1.10	1.10	1.10	0.225	2.72		
212.00	215.10		Cum	1	3.10	1.50	1.50	1.50	0.225	1.05		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
18.00	28.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
30.00	34.00		Cum	1	4.00	0.70	0.70	0.70	0.225	0.63		
36.00	40.00		Cum	1	4.00	0.80	0.80	0.80	0.225	0.72		
42.00	44.00		Cum	1	2.00	1.10	1.10	1.10	0.225	0.50		
		1st Main Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	6.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
8.00	15.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.225	1.62		
38.00	45.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
51.00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.225	2.03		
63.00	75.00		Cum	1	12.00	0.70	0.70	0.70	0.225	1.89		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
96.00	105.00		Cum	1	9.00	1.00	1.00	1.00	0.225	2.03		
108.00	117.00		Cum	1	9.00	0.70	0.70	0.70	0.225	1.42		
119.00	120.80		Cum	1	1.80	0.70	0.70	0.70	0.225	0.28		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
4.00	13.00		Cum	1	9.00	0.80	0.80	0.80	0.225	1.62		
15.00	28.00		Cum	1	13.00	1.00	1.00	1.00	0.225	2.93		
31.00	37.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
39.00	45.00		Cum	1	6.00	0.60	0.60	0.60	0.225	0.81		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
83.00	90.00		Cum	1	7.00	0.80	0.80	0.80	0.225	1.26		
95.00	105.00		Cum	1	10.00	0.70	0.70	0.70	0.225	1.58		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
142.00	150.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
153.00	161.00		Cum	1	8.00	0.50	0.50	0.50	0.225	0.90		
165.00	172.00		Cum	1	7.00	0.70	0.70	0.70	0.225	1.10		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
183.00	190.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
195.00	200.20		Cum	1	5.20	1.60	1.60	1.60	0.225	1.87		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.50	0.50	0.50	0.225	0.79		
13.00	23.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
25.00	30.00		Cum	1	5.00	1.10	1.10	1.10	0.225	1.24		
37.00	45.00		Cum	1	8.00	0.70	0.70	0.70	0.225	1.26		
51.00	60.00		Cum	1	9.00	0.80	0.80	0.80	0.225	1.62		
61.00	65.50		Cum	1	4.50	1.40	1.40	1.40	0.225	1.42		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.00	1.00	1.00	0.225	1.13		
12.00	19.00		Cum	1	7.00	0.60	0.60	0.60	0.225	0.95		
21.00	30.00		Cum	1	9.00	1.00	1.00	1.00	0.225	2.03		
34.00	45.00		Cum	1	11.00	0.70	0.70	0.70	0.225	1.73		
50.00	60.00		Cum	1	10.00	0.50	0.50	0.50	0.225	1.13		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
95.00	105.00		Cum	1	10.00	0.80	0.80	0.80	0.225	1.80		
110.00	120.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
123.00	127.60		Cum	1	4.60	1.30	1.30	1.30	0.225	1.35		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
4.00	11.00		Cum	1	7.00	0.60	0.60	0.60	0.225	0.95		
13.00	20.00		Cum	1	7.00	1.30	1.30	1.30	0.225	2.05		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
34.00	45.00		Cum	1	11.00	0.75	0.75	0.75	0.225	1.86		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	60.00		Cum	1	9.00	0.90	0.90	0.90	0.225	1.82		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
78.00	90.00		Cum	1	12.00	0.70	0.70	0.70	0.225	1.89		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.225	1.22		
111.00	120.00		Cum	1	9.00	1.20	1.20	1.20	0.225	2.43		
123.00	128.30		Cum	1	5.30	1.00	1.00	1.00	0.225	1.19		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.60	0.60	0.60	0.225	0.95		
12.00	20.00		Cum	1	8.00	0.70	0.70	0.70	0.225	1.26		
23.00	30.00		Cum	1	7.00	0.60	0.60	0.60	0.225	0.95		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.225	2.93		
63.00	71.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
75.00	79.00		Cum	1	4.00	1.20	1.20	1.20	0.225	1.08		
81.00	83.40		Cum	1	2.40	1.60	1.60	1.60	0.225	0.86		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
5.00	13.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
15.00	20.00		Cum	1	5.00	0.80	0.80	0.80	0.225	0.90		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
50.00	60.00		Cum	1	10.00	1.40	1.40	1.40	0.225	3.15		
63.00	75.00		Cum	1	12.00	1.20	1.20	1.20	0.225	3.24		
79.00	90.00		Cum	1	11.00	1.30	1.30	1.30	0.225	3.22		
97.00	105.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
110.00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
123.00	135.00		Cum	1	12.00	1.20	1.20	1.20	0.225	3.24		
140.00	150.00		Cum	1	10.00	0.60	0.60	0.60	0.225	1.35		
155.00	165.00		Cum	1	10.00	0.80	0.80	0.80	0.225	1.80		
172.00	180.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
189.00	195.00		Cum	1	6.00	1.00	1.00	1.00	0.225	1.35		
200.00	210.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
218.00	225.00		Cum	1	7.00	0.80	0.80	0.80	0.225	1.26		
230.00	240.00		Cum	1	10.00	1.00	1.00	1.00	0.225	2.25		
250.00	255.00		Cum	1	5.00	1.40	1.40	1.40	0.225	1.58		
261.00	270.00		Cum	1	9.00	1.30	1.30	1.30	0.225	2.63		
275.00	283.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
287.00	300.40		Cum	1	13.40	1.30	1.30	1.30	0.225	3.92		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
6.00	14.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.225	1.62		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
53.00	60.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
62.00	66.00		Cum	1	4.00	1.10	1.10	1.10	0.225	0.99		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.225	2.36		
80.00	90.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
97.00	105.00		Cum	1	8.00	0.60	0.60	0.60	0.225	1.08		
111.00	120.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
129.00	135.00		Cum	1	6.00	0.90	0.90	0.90	0.225	1.22		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Cum	1	3.70	1.20	1.20	1.20	0.225	1.00		
3.70	5.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0	0.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	30.00		Cum	1	15.00	0.60	0.50	0.55	0.225	1.86		
30.00	40.80		Cum	1	10.80	0.90	0.85	0.88	0.225	2.13		
40.80	55.00		Cum	1	14.20	1.10	0.60	0.85	0.225	2.72		
		9th A Cross Road										
		(From South to North)										
3.70	15.00		Cum	1	11.30	0.50	0.65	0.58	0.225	1.46		
15.00	16.10		Cum	1	1.10	1.15	0.35	0.75	0.225	0.19		
		9th Cross Road										
		(From North to South)										
23.00	30.00		Cum	1	7.00	1.20	1.20	1.20	0.225	1.89		
45.00	52.00		Cum	1	7.00	0.95	0.65	0.80	0.225	1.26		
60.00	71.00		Cum	1	11.00	1.15	1.15	1.15	0.225	2.85		
75.00	90.10		Cum	1	15.10	1.20	1.20	1.20	0.225	4.08		
90.90	97.30		Cum	1	6.40	0.85	0.50	0.68	0.225	0.97		
		7th A Cross Road										
		(From South to North)										
9.10	15.00		Cum	1	5.90	1.50	1.50	1.50	0.225	1.99		
15.00	18.30		Cum	1	3.30	0.35	0.35	0.35	0.225	0.26		
		7th Cross Road										
		(From North to South)										
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.225	3.71		
33.00	42.00		Cum	1	9.00	1.20	1.20	1.20	0.225	2.43		
45.00	55.80		Cum	1	10.80	0.60	0.60	0.60	0.225	1.46		
60.00	75.00		Cum	1	15.00	1.50	1.50	1.50	0.225	5.06		
79.00	84.50		Cum	1	5.50	1.20	1.20	1.20	0.225	1.49		
84.50	90.00		Cum	1	5.50	0.60	0.35	0.48	0.225	0.59		
91.20	93.10		Cum	1	1.90	1.20	1.20	1.20	0.225	0.51		
		6th Cross Road										
		(From North to South)										
10.00	15.00		Cum	1	5.00	0.60	0.60	0.60	0.225	0.68		
15.00	28.00		Cum	1	13.00	0.50	0.50	0.50	0.225	1.46		
42.00	45.00		Cum	1	3.00	0.70	0.70	0.70	0.225	0.47		
52.00	60.00		Cum	1	8.00	1.10	1.10	1.10	0.225	1.98		
62.50	75.00		Cum	1	12.50	1.00	1.00	1.00	0.225	2.81		
83.00	90.00		Cum	1	7.00	1.60	1.60	1.60	0.225	2.52		
91.50	92.30		Cum	1	0.80	1.20	1.20	1.20	0.225	0.22		
		6th A Cross Road										
		(From South to North)										
5.00	9.60		Cum	1	4.60	1.20	1.20	1.20	0.225	1.24		
11.80	15.00		Cum	1	3.20	1.20	1.20	1.20	0.225	0.86		
		5th Cross Road										
		(From North to South)										
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.225	1.98		
33.00	40.70		Cum	1	7.70	1.40	1.40	1.40	0.225	2.43		
48.00	56.00		Cum	1	8.00	1.00	1.00	1.00	0.225	1.80		
65.00	70.00		Cum	1	5.00	1.30	1.30	1.30	0.225	1.46		
79.00	85.00		Cum	1	6.00	1.45	1.45	1.45	0.225	1.96		
		5th A Cross Road										
		(From South to North)										
2.00	4.00		Cum	1	2.00	0.50	0.40	0.45	0.225	0.20		
9.20	15.00		Cum	1	5.80	1.20	1.20	1.20	0.225	1.57		
17.60	19.60		Cum	1	2.00	1.30	0.60	0.95	0.225	0.43		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
16.00	28.30		Cum	1	12.30	0.90	0.80	0.85	0.225	2.35		
30.00	44.20		Cum	1	14.20	1.10	0.35	0.73	0.225	2.32		
45.00	58.00		Cum	1	13.00	1.30	0.45	0.88	0.225	2.56		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	73.00		Cum	1	13.00	0.70	0.55	0.63	0.225	1.83		
107.00	120.00		Cum	1	13.00	1.50	1.20	1.35	0.225	3.95		
124.00	134.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
135.00	149.00		Cum	1	14.00	0.60	0.60	0.60	0.225	1.89		
153.00	165.00		Cum	1	12.00	1.60	1.60	1.60	0.225	4.32		
173.00	180.00		Cum	1	7.00	0.70	0.70	0.70	0.225	1.10		
183.00	195.00		Cum	1	12.00	1.10	1.10	1.10	0.225	2.97		
201.00	225.00		Cum	1	24.00	1.00	1.00	1.00	0.225	5.40		
228.00	240.00		Cum	1	12.00	1.60	1.60	1.60	0.225	4.32		
245.00	255.00		Cum	1	10.00	1.40	0.75	1.08	0.225	2.42		
258.00	270.00		Cum	1	12.00	1.20	1.20	1.20	0.225	3.24		
274.00	285.00		Cum	1	11.00	1.00	0.70	0.85	0.225	2.10		
287.00	300.00		Cum	1	13.00	1.20	1.20	1.20	0.225	3.51		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.50	10.00		Cum	1	5.50	1.50	1.50	1.50	0.225	1.86		
15.20	24.70		Cum	1	9.50	1.15	1.15	1.15	0.225	2.46		
29.00	30.00		Cum	1	1.00	1.45	1.45	1.45	0.225	0.33		
32.00	45.00		Cum	1	13.00	1.20	1.20	1.20	0.225	3.51		
48.00	60.00		Cum	1	12.00	1.40	1.40	1.40	0.225	3.78		
80.20	90.00		Cum	1	9.80	1.80	1.80	1.80	0.225	3.97		
97.00	105.00		Cum	1	8.00	1.20	1.20	1.20	0.225	2.16		
110.00	120.00		Cum	1	10.00	1.15	1.15	1.15	0.225	2.59		
125.00	136.00		Cum	1	11.00	1.20	1.20	1.20	0.225	2.97		
145.00	150.00		Cum	1	5.00	1.70	1.70	1.70	0.225	1.91		
154.00	165.00		Cum	1	11.00	1.35	1.35	1.35	0.225	3.34		
168.00	178.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
2.50	15.00		Cum	1	12.50	1.20	0.95	1.08	0.225	3.02		
30.00	44.00		Cum	1	14.00	1.70	1.20	1.45	0.225	4.57		
45.00	55.60		Cum	1	10.60	1.20	1.15	1.18	0.225	2.80		
60.00	74.30		Cum	1	14.30	1.10	1.10	1.10	0.225	3.54		
90.00	103.00		Cum	1	13.00	1.00	1.00	1.00	0.225	2.93		
105.00	122.00		Cum	1	17.00	1.40	1.40	1.40	0.225	5.36		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.225	1.73		
150.00	162.00		Cum	1	12.00	1.20	1.15	1.18	0.225	3.17		
165.00	168.60		Cum	1	3.60	1.60	1.60	1.60	0.225	1.30		
168.60	169.50		Cum	1	0.90	1.20	1.20	1.20	0.225	0.24		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
9.30	14.50		Cum	1	5.20	1.20	1.20	1.20	0.225	1.40		
15.00	25.00		Cum	1	10.00	1.60	1.20	1.40	0.225	3.15		
30.00	44.20		Cum	1	14.20	1.20	1.20	1.20	0.225	3.83		
49.00	52.70		Cum	1	3.70	2.00	1.20	1.60	0.225	1.33		
55.00	57.60		Cum	1	2.60	1.20	1.20	1.20	0.225	0.70		
60.00	70.00		Cum	1	10.00	1.50	1.50	1.50	0.225	3.38		
71.50	85.00		Cum	1	13.50	0.50	0.50	0.50	0.225	1.52		
86.10	90.00		Cum	1	3.90	0.70	0.70	0.70	0.225	0.61		
93.50	103.00		Cum	1	9.50	1.10	1.10	1.10	0.225	2.35		
110.00	119.00		Cum	1	9.00	1.40	1.40	1.40	0.225	2.84		
120.00	132.00		Cum	1	12.00	1.60	1.60	1.60	0.225	4.32		
135.00	148.00		Cum	1	13.00	1.30	1.20	1.25	0.225	3.66		
150.00	158.00		Cum	1	8.00	1.20	1.20	1.20	0.225	2.16		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
13.00	24.00		Cum	1	11.00	1.60	1.60	1.60	0.225	3.96		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
6.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
39.00	50.00		Cum	1	11.00	2.10	2.10	2.10	0.225	5.20		
54.00	64.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
66.00	75.00		Cum	1	9.00	1.80	1.80	1.80	0.225	3.65		
82.00	90.00		Cum	1	8.00	1.80	1.80	1.80	0.225	3.24		
92.00	101.00		Cum	1	9.00	1.80	1.80	1.80	0.225	3.65		
103.00	110.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
112.00	118.00		Cum	1	6.00	1.50	1.50	1.50	0.225	2.03		
120.00	123.00		Cum	1	3.00	1.10	1.10	1.10	0.225	0.74		
		11th Cross Road										
		North to South										
2.00	11.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
13.00	20.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
23.00	33.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
35.00	45.00		Cum	1	10.00	1.20	1.20	1.20	0.225	2.70		
50.00	60.00		Cum	1	10.00	1.10	1.10	1.10	0.225	2.48		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
74.00	80.00		Cum	1	6.00	1.90	1.90	1.90	0.225	2.57		
82.00	90.00		Cum	1	8.00	2.00	2.00	2.00	0.225	3.60		
93.00	100.00		Cum	1	7.00	2.00	2.00	2.00	0.225	3.15		
102.00	111.00		Cum	1	9.00	1.80	1.80	1.80	0.225	3.65		
115.00	122.00		Cum	1	7.00	1.70	1.70	1.70	0.225	2.68		
		17th Cross Road										
		North to South										
4.00	10.00		Cum	1	6.00	1.50	1.50	1.50	0.225	2.03		
13.00	23.00		Cum	1	10.00	1.80	1.80	1.80	0.225	4.05		
25.00	36.00		Cum	1	11.00	2.00	2.00	2.00	0.225	4.95		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
49.00	59.00		Cum	1	10.00	1.80	1.80	1.80	0.225	4.05		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
75.00	84.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
86.00	98.00		Cum	1	12.00	1.80	1.80	1.80	0.225	4.86		
100.00	109.00		Cum	1	9.00	1.20	1.20	1.20	0.225	2.43		
		3rd Cross Road										
		North to South										
3.00	10.00		Cum	1	7.00	1.00	1.00	1.00	0.225	1.58		
13.00	24.00		Cum	1	11.00	2.00	2.00	2.00	0.225	4.95		
26.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
37.00	47.00		Cum	1	10.00	1.80	1.80	1.80	0.225	4.05		
50.00	59.00		Cum	1	9.00	2.00	2.00	2.00	0.225	4.05		
		2nd Cross Road										
		North To South										
4.00	13.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
15.00	26.00		Cum	1	11.00	2.00	2.00	2.00	0.225	4.95		
28.00	36.00		Cum	1	8.00	1.30	1.30	1.30	0.225	2.34		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.225	3.04		
50.00	60.00		Cum	1	10.00	1.50	1.50	1.50	0.225	3.38		
66.00	73.00		Cum	1	7.00	1.50	1.50	1.50	0.225	2.36		
									Total Executed Quantity	**3308.74**		
									Tender Quantity	**2823.93**		
									Quantity Upto 125%	**3308.74**	**2764.54**	**9147131.00**
Item no.17		**Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means.**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
3.00	8.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
10.00	15.00		Sqm	1	5.00	2.00	2.00	2.00		10.00		
19.00	30.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
35.00	45.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
50.00	60.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
68.00	75.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
81.00	90.00		Sqm	1	9.00	1.40	1.40	1.40		12.60		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	105.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
107.00	112.00		Sqm	1	5.00	2.00	2.00	2.00		10.00		
114.00	120.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
126.00	135.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
138.00	145.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
149.00	152.00		Sqm	1	3.00	2.00	2.00	2.00		6.00		
154.00	165.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
167.00	171.00		Sqm	1	4.00	1.80	1.80	1.80		7.20		
173.00	178.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
180.00	190.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
193.00	199.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
		Ravi Gowda Layout										
		(From North to South)										
2.00	6.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
8.00	15.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
20.00	30.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
35.00	45.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
49.00	60.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
68.00	75.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
80.00	90.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
99.00	105.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
110.00	117.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
119.00	126.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
129.00	135.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
137.00	141.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
143.00	150.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
155.00	165.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
172.00	180.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
183.00	191.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
193.00	197.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
199.00	212.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	1.40	1.40	1.40		7.00		
15.00	28.00		Sqm	1	13.00	1.80	1.80	1.80		23.40		
34.00	42.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
45.00	54.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
56.00	62.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
63.00	68.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
		Jai Rama Layout Main Road										
		(From East to West)										
5.00	12.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
15.00	28.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
30.00	41.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
45.00	54.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
58.00	68.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
72.00	80.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
85.00	98.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
100.00	108.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
110.00	117.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
4.00	11.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
15.00	30.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
35.00	44.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
46.00	56.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
58.00	67.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
3.00	10.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
[illegible].00	18.00		Sqm	1	6.00	1.90	1.90	1.90		11.40		
[illegible].00	30.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
62.00	75.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
95.00	105.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
110.00	120.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
125.00	135.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
139.00	150.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
153.00	165.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
169.00	180.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
182.00	195.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
197.00	206.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
210.00	215.60		Sqm	1	5.60	1.60	1.60	1.60		8.96		
		2nd B Cross Road										
		(From North to South)										
2.00	6.00		Sqm	1	4.00	1.40	1.40	1.40		5.60		
8.00	15.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
17.00	25.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
27.00	30.00		Sqm	1	3.00	1.50	1.50	1.50		4.50		
31.00	37.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
		2nd A Cross Road										
		(From North to South)										
3.00	9.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
11.00	15.00		Sqm	1	4.00	1.90	1.90	1.90		7.60		
19.00	30.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
35.00	45.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
50.00	60.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
63.00	75.00		Sqm	1	12.00	0.60	0.60	0.60		7.20		
77.00	90.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
92.00	102.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
104.00	110.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
4.00	11.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
13.00	21.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
24.00	33.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
37.00	49.00		Sqm	1	12.00	1.00	1.00	1.00		12.00		
53.00	62.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
68.00	75.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
80.00	90.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
92.00	100.00		Sqm	1	8.00	1.90	1.90	1.90		15.20		
103.00	108.00		Sqm	1	5.00	1.80	1.80	1.80		9.00		
		2nd Cross Road										
		(From South to North)										
4.00	11.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
14.00	25.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
30.00	42.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
48.00	59.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
63.00	75.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
80.00	90.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
95.00	105.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
108.00	117.00		Sqm	1	9.00	1.70	1.70	1.70		15.30		
119.00	122.00		Sqm	1	3.00	1.70	1.70	1.70		5.10		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
4.00	13.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
19.00	30.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
35.00	45.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
51.00	60.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
66.00	75.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
[illegible].00	90.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
90.00	105.00		Sqm	1	9.00	1.40	1.40	1.40		12.60		
107.00	115.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
119.00	125.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
127.00	135.00		Sqm	1	8.00	1.70	1.70	1.70		13.60		
		1st A K.V.J Road										
		(From West to East)										
3.00	12.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
15.00	23.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
25.00	30.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
31.00	34.00		Sqm	1	3.00	1.00	1.00	1.00		3.00		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
2.00	13.00		Sqm	1	11.00	1.40	1.40	1.40		15.40		
21.00	30.00		Sqm	1	9.00	1.60	1.60	1.60		14.40		
35.00	45.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
49.00	58.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
60.00	66.00		Sqm	1	6.00	0.70	0.70	0.70		4.20		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
3.00	9.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
11.00	18.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
20.00	30.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
33.00	40.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
42.00	52.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
54.00	60.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
62.00	67.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
68.00	73.00		Sqm	1	5.00	0.70	0.70	0.70		3.50		
75.00	78.00		Sqm	1	3.00	1.00	1.00	1.00		3.00		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
13.00	23.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
25.00	35.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
40.00	48.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
50.00	54.00		Sqm	1	4.00	0.60	0.60	0.60		2.40		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
4.00	11.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
12.00	22.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
24.00	30.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
48.00	57.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
59.00	65.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
68.00	80.00		Sqm	1	12.00	1.50	1.50	1.50		18.00		
83.00	94.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
96.00	106.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
120.00	129.30		Sqm	1	9.30	1.80	1.80	1.80		16.74		
133.00	137.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
4.00	13.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
15.00	25.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
28.00	38.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
40.00	52.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
54.00	63.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
65.00	75.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
77.00	87.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	5.00		Sqm	1	7.00	1.90	1.90	1.90		13.30		
		6th B Cross Road										
		(From South to North)										
4.00	.00		Sqm	1	6.00	1.80	1.80	1.80		10.80		
12.00	.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
23.00	.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
35.00	.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
48.00	.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
60.00	.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
75.00	.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
90.00	.00		Sqm	1	12.00	1.50	1.50	1.50		18.00		
		6th Cross Road										
		(From East to West)										
5.00	.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
15.00	.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
25.00	.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
40.00	.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
52.00	.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		
63.00	.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
94.00	.00		Sqm	1	7.00	0.80	0.80	0.80		5.60		
102.00	.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
3.00	.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
11.00	.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
20.00	.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
34.00	.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
45.00	.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
55.00	.00		Sqm	1	6.00	1.60	1.60	1.60		9.60		
		10th Cross Road, 13th main										
		(North To South)										
2.00	.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
12.00	.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
21.00	.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
28.00	.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
35.00	.00		Sqm	1	3.00	1.70	1.70	1.70		5.10		
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
13.00	.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
20.00	.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
33.00	.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
42.00	.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
53.00	.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
65.00	.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
81.00	.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
97.00	.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
112.00	.00		Sqm	1	8.00	0.80	0.80	0.80		6.40		
122.00	.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
133.00	.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
		9th A Cross, 13th main										
		(North To South)										
2.00	.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
14.00	.00		Sqm	1	6.00	1.60	1.60	1.60		9.60		
22.00	.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
34.00	.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
50.00	.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
67.00	.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
81.00	.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
95.00	.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
105.00	.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		For Cut Portion										
		GKVK Layout										
		Main Road										
		(From West to East)										
2.00	6.00		Sqm	1	4.00	0.60	0.60	0.60		2.40		
8.00	13.00		Sqm	1	5.00	0.75	0.75	0.75		3.75		
17.00	29.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
32.00	43.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
48.00	57.00		Sqm	1	9.00	1.60	1.60	1.60		14.40		
63.00	71.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
77.00	88.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
94.00	103.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
107.00	110.00		Sqm	1	3.00	0.60	0.60	0.60		1.80		
112.00	118.00		Sqm	1	6.00	1.70	1.70	1.70		10.20		
123.00	133.00		Sqm	1	10.00	1.70	1.70	1.70		17.00		
137.00	144.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
145.00	152.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
154.00	163.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
165.00	172.40		Sqm	1	7.40	1.60	1.60	1.60		11.84		
173.10	180.00		Sqm	1	6.90	1.50	1.50	1.50		10.35		
184.00	192.80		Sqm	1	8.80	1.90	1.90	1.90		16.72		
195.00	200.80		Sqm	1	5.80	2.00	2.00	2.00		11.60		
		Ravi Gowda Layout										
		(From North to South)										
3.50	12.00		Sqm	1	8.50	1.30	1.30	1.30		11.05		
18.00	28.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
32.80	41.00		Sqm	1	8.20	2.30	2.30	2.30		18.86		
48.00	57.00		Sqm	1	9.00	2.60	2.60	2.60		23.40		
62.40	70.00		Sqm	1	7.60	1.80	1.80	1.80		13.68		
79.00	88.30		Sqm	1	9.30	1.90	1.90	1.90		17.67		
96.00	101.20		Sqm	1	5.20	2.30	2.30	2.30		11.96		
107.60	117.00		Sqm	1	9.40	2.25	2.25	2.25		21.15		
120.00	126.00		Sqm	1	6.00	1.40	1.40	1.40		8.40		
128.00	133.00		Sqm	1	5.00	1.70	1.70	1.70		8.50		
137.00	140.00		Sqm	1	3.00	1.60	1.60	1.60		4.80		
143.00	148.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
155.00	162.60		Sqm	1	7.60	1.70	1.70	1.70		12.92		
167.90	178.20		Sqm	1	10.30	1.50	1.50	1.50		15.45		
183.00	191.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
198.00	207.00		Sqm	1	9.00	1.35	1.35	1.35		12.15		
212.00	213.50		Sqm	1	1.50	1.00	1.00	1.00		1.50		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
6.00	11.00		Sqm	1	5.00	1.40	1.40	1.40		7.00		
17.00	28.00		Sqm	1	11.00	1.60	1.60	1.60		17.60		
32.00	41.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
47.00	55.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
58.70	64.70		Sqm	1	6.00	2.00	2.00	2.00		12.00		
66.00	69.20		Sqm	1	3.20	1.30	1.30	1.30		4.16		
		Jai Rama Layout Main Road										
		(From East to West)										
4.00	11.00		Sqm	1	7.00	1.60	1.60	1.60		11.20		
17.00	27.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
33.70	41.60		Sqm	1	7.90	1.00	1.00	1.00		7.90		
45.80	57.30		Sqm	1	11.50	2.30	2.30	2.30		26.45		
63.40	73.40		Sqm	1	10.00	1.70	1.70	1.70		17.00		
80.00	88.90		Sqm	1	8.90	1.60	1.60	1.60		14.24		
94.60	103.00		Sqm	1	8.40	1.90	1.90	1.90		15.96		
108.00	111.00		Sqm	1	3.00	2.00	2.00	2.00		6.00		
114.70	118.30		Sqm	1	3.60	3.00	3.00	3.00		10.80		
		1st Cross Road (Or)										
		Five Star Security Service Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From South to North)										
3.00	10.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
18.00	27.80		Sqm	1	9.80	1.70	1.70	1.70		16.66		
33.00	41.50		Sqm	1	8.50	1.65	1.65	1.65		14.03		
48.90	57.60		Sqm	1	8.70	1.90	1.90	1.90		16.53		
61.80	67.90		Sqm	1	6.10	2.60	2.60	2.60		15.86		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Sqm	1	3.50	3.00	3.00	3.00		10.50		
6.00	13.00		Sqm	1	7.00	3.00	3.00	3.00		21.00		
18.00	28.90		Sqm	1	10.90	1.60	1.60	1.60		17.44		
32.60	42.70		Sqm	1	10.10	1.90	1.90	1.90		19.19		
44.60	57.80		Sqm	1	13.20	2.00	2.00	2.00		26.40		
63.50	74.50		Sqm	1	11.00	2.30	2.30	2.30		25.30		
79.00	88.00		Sqm	1	9.00	1.60	1.60	1.60		14.40		
94.60	103.00		Sqm	1	8.40	1.90	1.90	1.90		15.96		
108.00	118.00		Sqm	1	10.00	2.60	2.60	2.60		26.00		
122.00	133.00		Sqm	1	11.00	2.20	2.20	2.20		24.20		
137.00	147.00		Sqm	1	10.00	1.70	1.70	1.70		17.00		
152.00	164.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
167.00	178.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
182.70	192.30		Sqm	1	9.60	1.90	1.90	1.90		18.24		
197.60	208.60		Sqm	1	11.00	2.20	2.20	2.20		24.20		
211.00	215.60		Sqm	1	4.60	1.80	1.80	1.80		8.28		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	1.80	1.80	1.80		6.12		
5.00	9.40		Sqm	1	4.40	2.50	2.50	2.50		11.00		
12.00	18.50		Sqm	1	6.50	1.70	1.70	1.70		11.05		
22.00	28.00		Sqm	1	6.00	1.60	1.60	1.60		9.60		
34.00	37.80		Sqm	1	3.80	1.10	1.10	1.10		4.18		
		2nd A Cross Road										
		(From North to South)										
3.00	4.30		Sqm	1	1.30	1.60	1.60	1.60		2.08		
6.00	13.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
18.00	27.90		Sqm	1	9.90	1.45	1.45	1.45		14.36		
34.60	42.10		Sqm	1	7.50	1.75	1.75	1.75		13.13		
49.00	58.60		Sqm	1	9.60	1.60	1.60	1.60		15.36		
63.60	72.90		Sqm	1	9.30	1.45	1.45	1.45		13.49		
77.80	88.90		Sqm	1	11.10	1.35	1.35	1.35		14.99		
93.10	103.60		Sqm	1	10.50	1.20	1.20	1.20		12.60		
108.00	111.10		Sqm	1	3.10	2.80	2.80	2.80		8.68		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
3.00	11.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
18.00	27.60		Sqm	1	9.60	1.30	1.30	1.30		12.48		
34.00	42.60		Sqm	1	8.60	1.60	1.60	1.60		13.76		
47.00	59.70		Sqm	1	12.70	1.80	1.80	1.80		22.86		
62.30	74.20		Sqm	1	11.90	2.00	2.00	2.00		23.80		
77.00	87.60		Sqm	1	10.60	1.30	1.30	1.30		13.78		
92.60	94.40		Sqm	1	1.80	1.10	1.10	1.10		1.98		
97.60	101.00		Sqm	1	3.40	1.80	1.80	1.80		6.12		
105.00	109.20		Sqm	1	4.20	1.10	1.10	1.10		4.62		
		2nd Cross Road										
		(From South to North)										
4.60	13.50		Sqm	1	8.90	1.60	1.60	1.60		14.24		
17.80	27.90		Sqm	1	10.10	1.20	1.20	1.20		12.12		
34.60	44.20		Sqm	1	9.60	1.40	1.40	1.40		13.44		
47.60	58.70		Sqm	1	11.10	1.80	1.80	1.80		19.98		
64.50	72.50		Sqm	1	8.00	2.30	2.30	2.30		18.40		
77.00	88.00		Sqm	1	11.00	1.90	1.90	1.90		20.90		
93.00	101.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	117.00		Sqm	1	10.00	1.70	1.70	1.70		17.00		
120.00	122.10		Sqm	1	2.10	3.00	3.00	3.00		6.30		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
4.60	11.00		Sqm	1	6.40	1.60	1.60	1.60		10.24		
18.60	27.60		Sqm	1	9.00	1.55	1.55	1.55		13.95		
35.60	44.00		Sqm	1	8.40	1.85	1.85	1.85		15.54		
49.50	57.60		Sqm	1	8.10	2.00	2.00	2.00		16.20		
64.60	73.40		Sqm	1	8.80	1.95	1.95	1.95		17.16		
78.90	87.90		Sqm	1	9.00	2.10	2.10	2.10		18.90		
94.20	102.00		Sqm	1	7.80	1.70	1.70	1.70		13.26		
108.00	117.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
126.00	132.00		Sqm	1	6.00	1.70	1.70	1.70		10.20		
135.00	136.00		Sqm	1	1.00	2.10	2.10	2.10		2.10		
		1st A K.V.J Road										
		(From West to East)										
3.60	12.50		Sqm	1	8.90	0.90	0.90	0.90		8.01		
21.20	27.60		Sqm	1	6.40	1.80	1.80	1.80		11.52		
31.00	33.30		Sqm	1	2.30	1.60	1.60	1.60		3.68		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
3.00	11.80		Sqm	1	8.80	2.00	2.00	2.00		17.60		
17.60	27.80		Sqm	1	10.20	1.40	1.40	1.40		14.28		
32.80	41.20		Sqm	1	8.40	1.70	1.70	1.70		14.28		
48.60	57.90		Sqm	1	9.30	1.65	1.65	1.65		15.35		
61.00	67.20		Sqm	1	6.20	1.00	1.00	1.00		6.20		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
2.30	8.70		Sqm	1	6.40	1.75	1.75	1.75		11.20		
9.90	15.00		Sqm	1	5.10	2.10	2.10	2.10		10.71		
19.00	27.60		Sqm	1	8.60	1.80	1.80	1.80		15.48		
33.60	43.50		Sqm	1	9.90	1.60	1.60	1.60		15.84		
50.00	57.80		Sqm	1	7.80	1.50	1.50	1.50		11.70		
68.50	73.00		Sqm	1	4.50	1.20	1.20	1.20		5.40		
78.00	79.50		Sqm	1	1.50	1.00	1.00	1.00		1.50		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
4.60	13.20		Sqm	1	8.60	1.80	1.80	1.80		15.48		
18.50	27.40		Sqm	1	8.90	1.60	1.60	1.60		14.24		
36.00	43.60		Sqm	1	7.60	1.30	1.30	1.30		9.88		
47.00	52.30		Sqm	1	5.30	1.40	1.40	1.40		7.42		
54.00	55.00		Sqm	1	1.00	1.25	1.25	1.25		1.25		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
3.70	11.40		Sqm	1	7.70	1.80	1.80	1.80		13.86		
16.90	25.80		Sqm	1	8.90	1.60	1.60	1.60		14.24		
34.60	41.20		Sqm	1	6.60	1.40	1.40	1.40		9.24		
47.90	57.60		Sqm	1	9.70	2.00	2.00	2.00		19.40		
64.50	74.50		Sqm	1	10.00	2.60	2.60	2.60		26.00		
79.00	88.00		Sqm	1	9.00	1.70	1.70	1.70		15.30		
92.60	98.80		Sqm	1	6.20	2.40	2.40	2.40		14.88		
101.00	105.00		Sqm	1	4.00	2.20	2.20	2.20		8.80		
108.60	117.00		Sqm	1	8.40	1.90	1.90	1.90		15.96		
121.00	129.30		Sqm	1	8.30	2.10	2.10	2.10		17.43		
129.30	131.50	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
132.00	138.00		Sqm	1	6.00	1.70	1.70	1.70		10.20		
		Veerannapalya										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		6th A Cross Road										
		(From North to South)										
3.00	13.40		Sqm	1	10.40	1.40	1.40	1.40		14.56		
17.60	26.80		Sqm	1	9.20	1.70	1.70	1.70		15.64		
33.00	43.20		Sqm	1	10.20	1.60	1.60	1.60		16.32		
48.60	57.60		Sqm	1	9.00	1.85	1.85	1.85		16.65		
62.80	74.00		Sqm	1	11.20	1.90	1.90	1.90		21.28		
78.00	88.90		Sqm	1	10.90	1.10	1.10	1.10		11.99		
92.80	104.00		Sqm	1	11.20	1.85	1.85	1.85		20.72		
		6th B Cross Road										
		(From South to North)										
2.60	11.50		Sqm	1	8.90	2.10	2.10	2.10		18.69		
18.00	27.60		Sqm	1	9.60	1.90	1.90	1.90		18.24		
36.00	43.20		Sqm	1	7.20	2.30	2.30	2.30		16.56		
51.00	57.90		Sqm	1	6.90	2.00	2.00	2.00		13.80		
65.00	72.60		Sqm	1	7.60	1.85	1.85	1.85		14.06		
80.00	87.50		Sqm	1	7.50	2.10	2.10	2.10		15.75		
92.70	101.00		Sqm	1	8.30	1.95	1.95	1.95		16.19		
114.00	118.50		Sqm	1	4.50	2.00	2.00	2.00		9.00		
		6th Cross Road										
		(From East to West)										
7.00	13.00		Sqm	1	6.00	1.90	1.90	1.90		11.40		
17.00	27.60		Sqm	1	10.60	1.45	1.45	1.45		15.37		
33.00	43.10		Sqm	1	10.10	1.75	1.75	1.75		17.68		
47.60	58.00		Sqm	1	10.40	1.85	1.85	1.85		19.24		
62.00	74.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
78.00	86.90		Sqm	1	8.90	1.60	1.60	1.60		14.24		
89.10	90.30	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
94.60	103.00		Sqm	1	8.40	1.40	1.40	1.40		11.76		
108.00	117.10		Sqm	1	9.10	1.60	1.60	1.60		14.56		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
2.00	5.00		Sqm	1	3.00	0.80	0.80	0.80		2.40		
8.00	12.00		Sqm	1	4.00	1.80	1.80	1.80		7.20		
15.00	23.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
25.00	38.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
40.00	50.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
52.00	60.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
		10th Cross Road,13th main										
		(North To South)										
3.00	9.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
10.00	15.00		Sqm	1	5.00	2.00	2.00	2.00		10.00		
18.00	25.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
27.00	33.00		Sqm	1	6.00	1.80	1.80	1.80		10.80		
35.00	38.00		Sqm	1	3.00	0.90	0.90	0.90		2.70		
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	6.00		Sqm	1	4.00	2.00	2.00	2.00		8.00		
8.00	15.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
18.00	26.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
28.00	36.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
38.00	45.00		Sqm	1	7.00	1.40	1.40	1.40		9.80		
47.00	60.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
63.00	75.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
79.00	90.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
95.00	105.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
112.00	120.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		
123.00	130.00		Sqm	1	7.00	1.60	1.60	1.60		11.20		
133.00	137.00		Sqm	1	4.00	1.40	1.40	1.40		5.60		
		9th A Cross, 13th main										
		(North To South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	8.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
10.00	15.00		Sqm	1	5.00	2.00	2.00	2.00		10.00		
19.00	30.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
34.00	45.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
83.00	90.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
92.00	100.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
102.00	108.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Sqm	1	15.00	5.10	5.95	5.53		82.88		
15.00	27.10		Sqm	1	12.10	5.95	4.70	5.33		64.43		
27.10	30.00		Sqm	1	2.90	6.30	5.95	6.13		17.76		
30.00	45.00		Sqm	1	15.00	5.95	4.95	5.45		81.75		
45.00	60.00		Sqm	1	15.00	4.95	5.75	5.35		80.25		
60.00	75.00		Sqm	1	15.00	5.75	5.80	5.78		86.63		
75.00	90.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
90.00	105.00		Sqm	1	15.00	5.40	5.30	5.35		80.25		
105.00	120.00		Sqm	1	15.00	5.30	5.85	5.58		83.63		
120.00	135.00		Sqm	1	15.00	5.85	6.55	6.20		93.00		
135.00	139.20		Sqm	1	4.20	6.55	6.00	6.28		26.35		
		Shanubhoga Narayanappa										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Sqm	1	15.00	7.85	7.00	7.43		111.38		
15.00	30.00		Sqm	1	15.00	7.00	5.95	6.48		97.13		
30.00	38.40		Sqm	1	8.40	5.95	5.60	5.78		48.51		
38.40	45.00		Sqm	1	6.60	7.25	6.85	7.05		46.53		
45.00	60.00		Sqm	1	15.00	6.85	6.10	6.48		97.13		
60.00	75.00		Sqm	1	15.00	6.10	6.55	6.33		94.88		
75.00	90.00		Sqm	1	15.00	6.55	6.70	6.63		99.38		
90.00	105.00		Sqm	1	15.00	6.70	7.10	6.90		103.50		
105.00	113.00		Sqm	1	8.00	7.10	7.00	7.05		56.40		
113.00	120.00		Sqm	1	7.00	5.05	5.00	5.03		35.18		
120.00	126.20		Sqm	1	6.20	5.00	5.10	5.05		31.31		
126.20	130.50		Sqm	1	4.30	5.95	6.00	5.98		25.69		
130.50	135.00		Sqm	1	4.50	6.00	6.15	6.08		27.34		
135.00	150.00		Sqm	1	15.00	6.15	6.80	6.48		97.13		
150.00	165.00		Sqm	1	15.00	6.80	6.75	6.78		101.63		
165.00	165.40		Sqm	1	0.40	6.75	6.80	6.78		2.71		
165.40	180.00		Sqm	1	14.60	6.30	6.35	6.33		92.35		
180.00	195.00		Sqm	1	15.00	6.35	6.00	6.18		92.63		
195.00	210.00		Sqm	1	15.00	6.00	5.90	5.95		89.25		
210.00	225.00		Sqm	1	15.00	5.90	6.20	6.05		90.75		
225.00	240.00		Sqm	1	15.00	6.20	5.75	5.98		89.63		
240.00	249.30		Sqm	1	9.30	5.75	6.00	5.88		54.64		
249.30	258.30		Sqm	1	9.00	5.10	4.65	4.88		43.88		
258.30	273.30		Sqm	1	15.00	5.45	5.25	5.35		80.25		
273.30	275.00		Sqm	1	1.70	5.25	5.25	5.25		8.92		
273.30	284.00		Sqm	1	10.70	5.25	5.75	5.50		58.85		
		1st Cross Road										
		(From North To South)										
6.00	13.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
18.00	23.00		Sqm	1	5.00	1.60	1.60	1.60		8.00		
27.00	35.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
43.00	50.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
52.00	58.00		Sqm	1	6.00	1.60	1.60	1.60		9.60		
63.00	72.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
77.00	88.00		Sqm	1	11.00	1.70	1.70	1.70		18.70		
94.00	103.00		Sqm	1	9.00	1.25	1.25	1.25		11.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	116.00		Sqm	1	8.00	1.15	1.15	1.15		9.20		
124.00	131.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
138.00	147.00		Sqm	1	9.00	1.40	1.40	1.40		12.60		
		Balaji Layout										
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
2.50	10.00		Sqm	1	7.50	0.90	0.90	0.90		6.75		
18.00	27.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
34.00	41.00		Sqm	1	7.00	0.75	0.75	0.75		5.25		
48.00	52.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
54.20	55.80	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
58.00	60.00		Sqm	1	2.00	1.00	1.00	1.00		2.00		
63.00	72.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
76.00	88.00		Sqm	1	12.00	1.40	1.40	1.40		16.80		
93.00	103.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
108.00	118.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
123.00	132.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
137.00	149.00		Sqm	1	12.00	1.60	1.60	1.60		19.20		
152.00	163.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
169.00	178.00		Sqm	1	9.00	1.40	1.40	1.40		12.60		
182.00	193.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
197.00	209.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
212.00	223.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
225.00	228.20		Sqm	1	3.20	0.60	0.60	0.60		1.92		
228.20	232.00		Sqm	1	3.80	0.75	0.75	0.75		2.85		
234.00	245.20		Sqm	1	11.20	1.25	1.25	1.25		14.00		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
3.00	13.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
18.00	28.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
34.00	43.60		Sqm	1	9.60	1.70	1.70	1.70		16.32		
		(From West To East)										
0.00	3.90		Sqm	1	3.90	1.30	1.30	1.30		5.07		
3.90	11.10		Sqm	1	7.20	1.20	1.20	1.20		8.64		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
5.00	10.00		Sqm	1	5.00	0.80	0.80	0.80		4.00		
13.00	17.00		Sqm	1	4.00	0.50	0.50	0.50		2.00		
20.00	28.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
31.00	41.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
46.00	53.00		Sqm	1	7.00	0.80	0.80	0.80		5.60		
57.00	63.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
67.00	75.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
80.00	86.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
90.00	100.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
104.00	112.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
116.00	127.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
130.00	139.00		Sqm	1	9.00	0.80	0.80	0.80		7.20		
145.00	152.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
		6th A Cross Road										
		(From West to East)										
1.00	7.40		Sqm	1	6.40	1.80	1.80	1.80		11.52		
		(From South to North)										
2.00	6.00		Sqm	1	4.00	0.80	0.80	0.80		3.20		
8.00	14.00		Sqm	1	6.00	0.50	0.50	0.50		3.00		
16.00	25.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
28.00	42.00		Sqm	1	14.00	1.20	1.20	1.20		16.80		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	51.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
53.00	60.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
63.00	75.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
78.00	91.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
93.00	101.00		Sqm	1	8.00	0.90	0.90	0.90		7.20		
103.00	114.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
116.00	127.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
129.00	139.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
		Devi Nagar Main Road										
		(From West to East)										
5.00	14.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
16.00	28.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
33.00	43.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
45.00	55.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
58.00	72.00		Sqm	1	14.00	1.40	1.40	1.40		19.60		
75.00	83.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
86.00	102.00		Sqm	1	16.00	1.40	1.40	1.40		22.40		
105.00	118.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
120.00	130.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
133.00	145.00		Sqm	1	12.00	1.00	1.00	1.00		12.00		
148.00	160.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
163.00	175.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
178.00	188.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
190.00	198.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
200.00	213.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
215.00	224.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
226.00	231.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
235.00	240.00		Sqm	1	5.00	0.70	0.70	0.70		3.50		
		Muneshwara Layout										
		1st Main Road										
3.00	9.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
11.00	18.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
20.00	30.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
38.00	45.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
50.00	60.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
66.00	75.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
78.00	90.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
96.00	105.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
110.00	120.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
127.00	135.00		Sqm	1	8.00	0.80	0.80	0.80		6.40		
140.00	150.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
156.00	165.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
170.00	178.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
180.00	186.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
190.00	196.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
200.00	206.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
208.00	212.00		Sqm	1	4.00	0.70	0.70	0.70		2.80		
217.00	225.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
225.00	235.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
240.00	249.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
250.00	260.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
265.00	274.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
280.00	288.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
290.00	296.00		Sqm	1	6.00	0.70	0.70	0.70		4.20		
298.00	305.00		Sqm	1	7.00	0.80	0.80	0.80		5.60		
307.00	315.00		Sqm	1	8.00	0.90	0.90	0.90		7.20		
320.00	330.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
334.00	340.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
344.00	352.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
356.00	363.50		Sqm	1	7.50	1.10	1.10	1.10		8.25		
362.00	370.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
372.00	379.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
382.00	388.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
		Tata Nagar										
		1st Main Road										
		(From South to North)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	13.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
15.00	27.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
49.00	58.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
60.00	71.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
73.00	86.00		Sqm	1	13.00	1.20	1.30	1.25		16.25		
88.00	101.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
103.00	114.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
116.00	128.00		Sqm	1	12.00	1.20	1.30	1.25		15.00		
130.00	141.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
142.00	153.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
155.00	168.00		Sqm	1	13.00	1.20	1.30	1.25		16.25		
170.00	178.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
180.00	186.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
188.00	193.00		Sqm	1	5.00	0.90	0.90	0.90		4.50		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
3.00	9.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
11.00	18.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
20.00	26.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
28.00	35.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
37.00	43.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
45.00	54.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
56.00	64.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
66.00	72.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
74.00	78.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
79.00	83.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
5.00	13.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
15.00	25.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
28.00	36.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
38.00	49.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
53.00	62.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
65.00	75.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
78.00	87.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
90.00	101.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
104.00	113.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
117.00	126.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
128.00	137.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
140.00	150.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
154.00	162.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
164.00	176.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
178.00	187.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
189.00	200.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
205.00	210.00		Sqm	1	5.00	0.80	0.80	0.80		4.00		
		1st Cross Road										
		(From North to South)										
4.00	12.00		Sqm	1	8.00	0.50	0.50	0.50		4.00		
14.00	20.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
22.00	26.00		Sqm	1	4.00	0.70	0.70	0.70		2.80		
30.00	37.00		Sqm	1	7.00	0.70	0.70	0.70		4.90		
39.00	48.00		Sqm	1	9.00	0.50	0.50	0.50		4.50		
50.00	56.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
58.00	67.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
69.00	75.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
78.00	84.00		Sqm	1	6.00	0.50	0.50	0.50		3.00		
		2nd Cross Road										
		(From North to South)										
5.00	12.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	26.00		Sqm	1	12.00	1.00	1.00	1.00		12.00		
28.00	38.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
40.00	51.00		Sqm	1	11.00	0.80	0.80	0.80		8.80		
55.00	65.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
68.00	76.00		Sqm	1	8.00	0.50	0.50	0.50		4.00		
		2nd A Cross Road										
		(From South to North)										
4.00	14.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
16.00	25.00		Sqm	1	9.00	0.90	0.90	0.90		8.10		
28.00	40.00		Sqm	1	12.00	1.00	1.00	1.00		12.00		
		3rd Cross Road										
		(From North to South)										
2.00	6.00		Sqm	1	4.00	0.50	0.50	0.50		2.00		
8.00	14.00		Sqm	1	6.00	0.60	0.60	0.60		3.60		
17.00	28.00		Sqm	1	11.00	0.50	0.50	0.50		5.50		
30.00	38.00		Sqm	1	8.00	0.50	0.50	0.50		4.00		
43.00	51.00		Sqm	1	8.00	0.90	0.90	0.90		7.20		
53.00	61.00		Sqm	1	8.00	0.70	0.70	0.70		5.60		
63.00	68.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
70.00	76.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
78.00	83.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
85.00	91.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
97.00	104.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
106.00	108.00		Sqm	1	2.00	0.90	0.90	0.90		1.80		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
5.00	12.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
15.00	25.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
28.00	37.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
39.00	46.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
48.00	57.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
59.00	63.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
67.00	77.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
79.00	88.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
90.00	98.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
100.00	105.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
107.00	117.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
119.00	127.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
129.00	137.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
139.00	148.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
150.00	155.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
157.00	162.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
164.00	168.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
173.00	179.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
180.00	185.00		Sqm	1	5.00	0.80	0.80	0.80		4.00		
187.00	194.00		Sqm	1	7.00	0.90	0.90	0.90		6.30		
196.00	204.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
206.00	214.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
216.00	225.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
227.00	234.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
236.00	247.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
250.00	260.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
262.00	274.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
276.00	288.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
290.00	297.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
299.00	309.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
311.00	321.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
323.00	332.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
334.00	348.00		Sqm	1	14.00	1.30	1.30	1.30		18.20		
350.00	365.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	92.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
94.00	104.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
106.00	115.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
117.00	125.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
126.00	132.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
134.00	141.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
143.00	152.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
154.00	163.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
165.00	176.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
178.00	187.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
189.00	199.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
201.00	210.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
213.00	223.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
226.00	238.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
240.00	250.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
255.00	262.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
265.00	278.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
279.00	292.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
		1st Cross Road										
		(From East to West)										
4.00	10.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
12.00	18.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
20.00	30.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
32.00	39.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
41.00	50.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
		2nd Cross Road										
		(From East to West)										
3.00	9.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
12.00	23.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
25.00	34.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
36.00	44.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
46.00	51.00		Sqm	1	5.00	0.70	0.70	0.70		3.50		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
2.00	12.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
14.00	24.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
26.00	36.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
38.00	50.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
52.00	64.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
66.00	76.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
78.00	90.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
92.00	105.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
107.00	120.00		Sqm	1	13.00	1.30	1.30	1.30		16.90		
122.00	132.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
134.00	145.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
147.00	156.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
158.00	166.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
168.00	178.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
180.00	188.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
190.00	196.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
198.00	207.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
209.00	218.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
224.00	232.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
234.00	240.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
242.00	250.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
252.00	258.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
260.00	264.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
266.00	275.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
277.00	288.00		Sqm	1	11.00	1.10	1.10	1.10		12.10		
290.00	296.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
298.00	306.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
308.00	316.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
318.00	330.00		Sqm	1	12.00	1.30	1.30	1.30		15.60		
332.00	345.00		Sqm	1	13.00	1.30	1.30	1.30		16.90		
347.00	356.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
[illegible].00	367.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
369.00	380.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
382.00	395.00		Sqm	1	13.00	1.30	1.30	1.30		16.90		
397.00	410.00		Sqm	1	13.00	1.30	1.30	1.30		16.90		
		Road Cut portion										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
4.20	12.00		Sqm	1	7.80	1.20	1.20	1.20		9.36		
15.00	18.80		Sqm	1	3.80	3.80	3.80	3.80		14.44		
21.00	27.80		Sqm	1	6.80	1.00	1.00	1.00		6.80		
32.60	42.60		Sqm	1	10.00	1.25	1.25	1.25		12.50		
47.60	57.40		Sqm	1	9.80	1.10	1.10	1.10		10.78		
64.30	71.00		Sqm	1	6.70	1.60	1.60	1.60		10.72		
77.60	80.00		Sqm	1	2.40	1.35	1.35	1.35		3.24		
83.40	90.20		Sqm	1	6.80	1.00	1.00	1.00		6.80		
93.60	103.20		Sqm	1	9.60	0.90	0.90	0.90		8.64		
107.80	116.90		Sqm	1	9.10	1.40	1.40	1.40		12.74		
124.30	131.70		Sqm	1	7.40	1.25	1.25	1.25		9.25		
138.40	147.00		Sqm	1	8.60	1.35	1.35	1.35		11.61		
152.80	163.10		Sqm	1	10.30	1.10	1.10	1.10		11.33		
		6th A Cross Road										
		(From West to East)										
3.00	6.00		Sqm	1	3.00	3.00	3.00	3.00		9.00		
		(From South to North)										
2.30	6.40		Sqm	1	4.10	2.20	2.20	2.20		9.02		
9.00	13.40		Sqm	1	4.40	2.60	2.60	2.60		11.44		
17.90	27.60		Sqm	1	9.70	2.00	2.00	2.00		19.40		
36.20	44.20		Sqm	1	8.00	1.35	1.35	1.35		10.80		
45.00	50.70		Sqm	1	5.70	2.00	2.00	2.00		11.40		
50.70	60.00		Sqm	1	9.30	1.80	1.80	1.80		16.74		
62.30	71.20		Sqm	1	8.90	1.30	1.30	1.30		11.57		
77.80	88.90		Sqm	1	11.10	1.70	1.70	1.70		18.87		
93.40	103.80		Sqm	1	10.40	1.40	1.40	1.40		14.56		
107.00	119.00		Sqm	1	12.00	1.60	1.60	1.60		19.20		
121.00	133.20		Sqm	1	12.20	1.40	1.40	1.40		17.08		
137.00	141.70		Sqm	1	4.70	1.00	1.00	1.00		4.70		
		Devi Nagar Main Road										
		(From West to East)										
2.50	11.00		Sqm	1	8.50	1.70	1.70	1.70		14.45		
16.80	26.40		Sqm	1	9.60	2.00	2.00	2.00		19.20		
33.20	43.50		Sqm	1	10.30	1.90	1.90	1.90		19.57		
47.00	58.00		Sqm	1	11.00	2.30	2.30	2.30		25.30		
63.00	71.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
77.00	87.00		Sqm	1	10.00	1.45	1.45	1.45		14.50		
93.50	103.00		Sqm	1	9.50	1.80	1.80	1.80		17.10		
107.00	118.00		Sqm	1	11.00	2.20	2.20	2.20		24.20		
123.00	134.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
137.60	149.50		Sqm	1	11.90	1.90	1.90	1.90		22.61		
151.00	163.40		Sqm	1	12.40	1.60	1.60	1.60		19.84		
165.00	180.00		Sqm	1	15.00	1.55	1.55	1.55		23.25		
183.00	194.30		Sqm	1	11.30	1.30	1.30	1.30		14.69		
196.50	210.00		Sqm	1	13.50	1.40	1.40	1.40		18.90		
212.30	225.00		Sqm	1	12.70	1.25	1.25	1.25		15.88		
227.00	237.20		Sqm	1	10.20	1.80	1.80	1.80		18.36		
237.20	239.00		Sqm	1	1.80	2.00	2.00	2.00		3.60		
239.00	241.50		Sqm	1	2.50	1.20	1.20	1.20		3.00		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Sqm	1	3.20	1.10	1.10	1.10		3.52		
7.00	15.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
18.00	28.40		Sqm	1	10.40	0.90	0.90	0.90		9.36		
36.00	45.00		Sqm	1	9.00	0.75	0.75	0.75		6.75		
47.80	57.90		Sqm	1	10.10	1.60	1.60	1.60		16.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
70	72.30		Sqm	1	8.60	1.20	1.20	1.20		10.32		
78.90	88.00		Sqm	1	9.10	1.70	1.70	1.70		15.47		
93.60	103.70		Sqm	1	10.10	1.20	1.20	1.20		12.12		
111.00	120.00		Sqm	1	9.00	1.45	1.45	1.45		13.05		
127.00	135.00		Sqm	1	8.00	1.65	1.65	1.65		13.20		
138.90	149.00		Sqm	1	10.10	1.80	1.80	1.80		18.18		
154.70	162.60		Sqm	1	7.90	1.70	1.70	1.70		13.43		
168.90	177.50		Sqm	1	8.60	1.90	1.90	1.90		16.34		
180.00	184.70		Sqm	1	4.70	1.60	1.60	1.60		7.52		
184.70	186.20		Sqm	1	1.50	1.70	1.70	1.70		2.55		
186.20	195.00		Sqm	1	8.80	1.60	1.60	1.60		14.08		
197.00	208.90		Sqm	1	11.90	1.40	1.40	1.40		16.66		
213.00	223.60		Sqm	1	10.60	1.25	1.25	1.25		13.25		
227.00	237.80		Sqm	1	10.80	1.30	1.30	1.30		14.04		
242.60	251.00		Sqm	1	8.40	1.40	1.40	1.40		11.76		
257.00	267.60		Sqm	1	10.60	1.60	1.60	1.60		16.96		
273.00	281.60		Sqm	1	8.60	1.20	1.20	1.20		10.32		
286.00	293.70		Sqm	1	7.70	0.90	0.90	0.90		6.93		
293.70	298.70		Sqm	1	5.00	1.90	1.90	1.90		9.50		
298.70	300.00		Sqm	1	1.30	0.90	0.90	0.90		1.17		
303.60	313.80		Sqm	1	10.20	1.40	1.40	1.40		14.28		
317.00	328.70		Sqm	1	11.70	1.30	1.30	1.30		15.21		
332.40	342.60		Sqm	1	10.20	1.15	1.15	1.15		11.73		
348.90	358.00		Sqm	1	9.10	1.35	1.35	1.35		12.29		
360.00	363.50		Sqm	1	3.50	2.00	2.00	2.00		7.00		
363.50	372.30		Sqm	1	8.80	1.70	1.70	1.70		14.96		
374.00	386.00		Sqm	1	12.00	1.50	1.50	1.50		18.00		
387.30	390.00		Sqm	1	2.70	2.00	2.00	2.00		5.40		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
3.00	13.40		Sqm	1	10.40	1.20	1.20	1.20		12.48		
18.00	29.50		Sqm	1	11.50	1.90	1.90	1.90		21.85		
29.50	47.20	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
51.00	58.70		Sqm	1	7.70	1.50	1.50	1.50		11.55		
62.70	73.80		Sqm	1	11.10	1.70	1.70	1.70		18.87		
77.00	88.90		Sqm	1	11.90	1.90	1.90	1.90		22.61		
92.60	103.50		Sqm	1	10.90	1.35	1.35	1.35		14.72		
108.90	120.00		Sqm	1	11.10	1.60	1.60	1.60		17.76		
123.60	134.50		Sqm	1	10.90	1.80	1.80	1.80		19.62		
137.80	148.90		Sqm	1	11.10	1.55	1.55	1.55		17.21		
150.30	158.50		Sqm	1	8.20	1.70	1.70	1.70		13.94		
158.50	165.30		Sqm	1	6.80	2.00	2.00	2.00		13.60		
168.00	179.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
180.30	189.60		Sqm	1	9.30	1.90	1.90	1.90		17.67		
189.60	193.50		Sqm	1	3.90	2.00	2.00	2.00		7.80		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Sqm	1	4.00	2.00	2.00	2.00		8.00		
6.00	12.50		Sqm	1	6.50	1.80	1.80	1.80		11.70		
15.00	22.00		Sqm	1	7.00	1.90	1.90	1.90		13.30		
24.10	30.00		Sqm	1	5.90	1.65	1.65	1.65		9.74		
32.40	38.10		Sqm	1	5.70	1.50	1.50	1.50		8.55		
38.10	46.00		Sqm	1	7.90	1.20	1.20	1.20		9.48		
48.90	58.00		Sqm	1	9.10	1.30	1.30	1.30		11.83		
60.00	67.00		Sqm	1	7.00	1.65	1.65	1.65		11.55		
69.00	75.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
77.00	83.50		Sqm	1	6.50	2.00	2.00	2.00		13.00		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
60	12.60		Sqm	1	10.00	1.10	1.10	1.10		11.00		
1 /.80	27.60		Sqm	1	9.80	1.60	1.60	1.60		15.68		
33.70	43.50		Sqm	1	9.80	1.40	1.40	1.40		13.72		
47.00	56.90		Sqm	1	9.90	1.15	1.15	1.15		11.39		
62.00	74.00		Sqm	1	12.00	1.85	1.85	1.85		22.20		
75.00	87.00		Sqm	1	12.00	1.10	1.10	1.10		13.20		
87.00	90.00		Sqm	1	3.00	2.00	2.00	2.00		6.00		
92.30	102.00		Sqm	1	9.70	1.80	1.80	1.80		17.46		
107.00	118.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
120.00	129.20		Sqm	1	9.20	1.75	1.75	1.75		16.10		
129.20	135.00		Sqm	1	5.80	2.00	2.00	2.00		11.60		
136.70	148.70		Sqm	1	12.00	1.25	1.25	1.25		15.00		
152.60	163.00		Sqm	1	10.40	1.15	1.15	1.15		11.96		
167.00	179.80		Sqm	1	12.80	1.05	1.05	1.05		13.44		
180.00	195.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
195.00	209.00		Sqm	1	14.00	1.30	1.30	1.30		18.20		
211.00	221.50		Sqm	1	10.50	0.90	0.90	0.90		9.45		
		1st Cross Road										
		(From North to South)										
4.60	13.40		Sqm	1	8.80	1.10	1.10	1.10		9.68		
15.00	17.10		Sqm	1	2.10	1.05	1.05	1.05		2.21		
17.10	22.80		Sqm	1	5.70	1.20	1.20	1.20		6.84		
22.80	30.00		Sqm	1	7.20	0.90	0.90	0.90		6.48		
34.30	41.00		Sqm	1	6.70	0.75	0.75	0.75		5.03		
47.60	53.20		Sqm	1	5.60	0.90	0.90	0.90		5.04		
54.00	60.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
63.00	71.60		Sqm	1	8.60	0.75	0.75	0.75		6.45		
79.00	85.20		Sqm	1	6.20	1.00	1.00	1.00		6.20		
		2nd Cross Road										
		(From North to South)										
3.00	12.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
18.90	27.60		Sqm	1	8.70	1.30	1.30	1.30		11.31		
33.60	42.50		Sqm	1	8.90	1.10	1.10	1.10		9.79		
48.90	56.30		Sqm	1	7.40	1.40	1.40	1.40		10.36		
62.80	71.60		Sqm	1	8.80	1.00	1.00	1.00		8.80		
75.00	82.10		Sqm	1	7.10	0.65	0.65	0.65		4.62		
		2nd A Cross Road										
		(From South to North)										
3.80	13.40		Sqm	1	9.60	1.60	1.60	1.60		15.36		
16.70	25.90		Sqm	1	9.20	1.70	1.70	1.70		15.64		
37.00	44.90		Sqm	1	7.90	1.10	1.10	1.10		8.69		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Sqm	1	4.20	1.90	1.90	1.90		7.98		
7.00	15.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
21.00	28.50		Sqm	1	7.50	1.60	1.60	1.60		12.00		
34.50	41.00		Sqm	1	6.50	1.50	1.50	1.50		9.75		
46.00	52.20		Sqm	1	6.20	1.40	1.40	1.40		8.68		
53.00	60.00		Sqm	1	7.00	0.65	0.65	0.65		4.55		
62.00	67.30		Sqm	1	5.30	0.75	0.75	0.75		3.98		
69.00	70.60		Sqm	1	1.60	0.90	0.90	0.90		1.44		
73.00	81.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
85.00	89.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
90.00	92.10		Sqm	1	2.10	0.90	0.90	0.90		1.89		
92.10	95.30	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
98.00	103.40		Sqm	1	5.40	1.40	1.40	1.40		7.56		
107.80	108.90		Sqm	1	1.10	1.70	1.70	1.70		1.87		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
15.00	30.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
30.00	45.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
45.00	47.80		Sqm	1	2.80	1.50	1.50	1.50		4.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
80	56.10		Sqm	1	8.30	1.50	1.50	1.50		12.45		
56.10	63.90		Sqm	1	7.80	1.50	1.50	1.50		11.70		
63.90	65.50	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
65.50	75.00		Sqm	1	9.50	1.50	1.50	1.50		14.25		
75.00	90.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
90.00	94.50		Sqm	1	4.50	1.50	1.50	1.50		6.75		
94.50	105.00		Sqm	1	10.50	1.50	1.50	1.50		15.75		
105.00	120.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
120.00	122.00		Sqm	1	2.00	1.50	1.50	1.50		3.00		
122.00	135.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
135.00	150.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
150.00	154.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
154.00	163.70		Sqm	1	9.70	1.50	1.50	1.50		14.55		
163.70	169.70		Sqm	1	6.00	1.50	1.50	1.50		9.00		
169.70	171.20	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
171.20	180.00		Sqm	1	8.80	1.50	1.50	1.50		13.20		
180.00	181.80		Sqm	1	1.80	1.50	1.50	1.50		2.70		
181.80	190.00		Sqm	1	8.20	1.50	1.50	1.50		12.30		
190.00	205.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
205.00	216.10		Sqm	1	11.10	1.50	1.50	1.50		16.65		
216.10	231.10		Sqm	1	15.00	1.50	1.50	1.50		22.50		
231.10	235.00		Sqm	1	3.90	1.50	1.50	1.50		5.85		
235.00	250.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
250.00	265.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
265.00	280.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
280.00	295.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
295.00	300.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
300.00	315.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
315.00	330.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
330.00	345.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
345.00	360.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
360.00	369.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	8.40	6.80	7.60		114.00		
15.00	29.20		Sqm	1	14.20	6.80	6.90	6.85		97.27		
29.20	30.30	Culvert	Sqm	0	0.00	0.00	0.00	0.00		0.00		
30.30	45.00		Sqm	1	14.70	6.85	6.70	6.78		99.59		
45.00	60.00		Sqm	1	15.00	6.70	6.60	6.65		99.75		
60.00	75.00		Sqm	1	15.00	6.60	6.40	6.50		97.50		
75.00	79.70		Sqm	1	4.70	6.40	5.75	6.08		28.55		
79.70	90.00		Sqm	1	10.30	2.50	2.50	2.50		25.75		
90.00	105.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
105.00	108.50		Sqm	1	3.50	2.50	2.50	2.50		8.75		
108.50	118.70		Sqm	1	10.20	2.50	2.50	2.50		25.50		
118.70	124.80		Sqm	1	6.10	2.50	2.50	2.50		15.25		
124.80	135.00		Sqm	1	10.20	2.50	2.50	2.50		25.50		
135.00	150.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
150.00	165.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
165.00	180.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
180.00	195.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
195.00	210.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
210.00	225.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
225.00	240.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
240.00	255.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
255.00	270.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
270.00	285.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
285.00	291.50		Sqm	1	6.50	2.50	2.50	2.50		16.25		
291.50	298.00		Sqm	1	6.50	2.50	2.50	2.50		16.25		
		1st Cross Road										
		(From East to West)										
3.40	13.70		Sqm	1	10.30	1.60	1.60	1.60		16.48		
15.00	17.20		Sqm	1	2.20	2.00	2.00	2.00		4.40		
18.90	28.00		Sqm	1	9.10	1.40	1.40	1.40		12.74		
34.60	41.00		Sqm	1	6.40	1.50	1.50	1.50		9.60		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	50.20		Sqm	1	9.20	1.30	1.30	1.30		11.96		
		2nd Cross Road										
		(From East to West)										
3.60	12.80		Sqm	1	9.20	1.30	1.30	1.30		11.96		
17.80	27.90		Sqm	1	10.10	1.10	1.10	1.10		11.11		
32.00	41.20		Sqm	1	9.20	1.50	1.50	1.50		13.80		
45.00	50.20		Sqm	1	5.20	2.00	2.00	2.00		10.40		
50.20	52.80		Sqm	1	2.60	1.00	1.00	1.00		2.60		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
15.00	30.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
30.00	45.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
45.00	60.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
60.00	63.30		Sqm	1	3.30	2.50	2.50	2.50		8.25		
63.30	75.00		Sqm	1	11.70	2.50	2.50	2.50		29.25		
75.00	90.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
90.00	105.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
105.00	120.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
120.00	132.90		Sqm	1	12.90	2.50	2.50	2.50		32.25		
132.90	147.10		Sqm	1	14.20	2.50	2.50	2.50		35.50		
147.10	160.00		Sqm	1	12.90	2.50	2.50	2.50		32.25		
160.00	165.00		Sqm	1	5.00	2.50	2.50	2.50		12.50		
165.00	180.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
180.00	195.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
195.00	198.80		Sqm	1	3.80	2.50	2.50	2.50		9.50		
198.80	210.00		Sqm	1	11.20	2.50	2.50	2.50		28.00		
210.00	219.70		Sqm	1	9.70	2.50	2.50	2.50		24.25		
219.70	222.20	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
222.20	225.00		Sqm	1	2.80	2.50	2.50	2.50		7.00		
225.00	240.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
240.00	249.60		Sqm	1	9.60	2.50	2.50	2.50		24.00		
249.60	257.30		Sqm	1	7.70	2.50	2.50	2.50		19.25		
257.30	260.00		Sqm	1	2.70	2.50	2.50	2.50		6.75		
260.00	275.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
275.00	292.00		Sqm	1	17.00	2.50	2.50	2.50		42.50		
292.00	297.10		Sqm	1	5.10	2.50	2.50	2.50		12.75		
297.10	300.00		Sqm	1	2.90	2.50	2.50	2.50		7.25		
300.00	315.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
315.00	330.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
330.00	345.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
345.00	360.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
360.00	375.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
375.00	390.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
390.00	405.00		Sqm	1	15.00	2.50	2.50	2.50		37.50		
405.00	414.50		Sqm	1	9.50	2.50	2.50	2.50		23.75		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
15.00	30.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
30.00	45.00		Sqm	1	15.00	1.65	1.65	1.65		24.75		
45.00	60.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
60.00	69.30		Sqm	1	9.30	1.10	1.10	1.10		10.23		
69.30	75.00		Sqm	1	5.70	2.00	2.00	2.00		11.40		
75.00	90.00		Sqm	1	15.00	2.20	2.20	2.20		33.00		
90.00	105.00		Sqm	1	15.00	1.60	1.60	1.60		24.00		
105.00	111.40		Sqm	1	6.40	3.50	3.50	3.50		22.40		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Sqm	1	4.60	4.00	4.00	4.00		18.40		
4.60	15.00		Sqm	1	10.40	2.10	2.10	2.10		21.84		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	30.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
30.00	45.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
45.00	60.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
60.00	75.00		Sqm	1	15.00	2.00	2.00	2.00		30.00		
75.00	90.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
90.00	100.30		Sqm	1	10.30	1.30	1.30	1.30		13.39		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Sqm	1	15.00	1.10	1.10	1.10		16.50		
15.00	30.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
30.00	45.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
45.00	60.00		Sqm	1	15.00	1.40	1.40	1.40		21.00		
60.00	73.50		Sqm	1	13.50	1.20	1.20	1.20		16.20		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Sqm	1	15.00	1.30	1.30	1.30		19.50		
15.00	30.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
30.00	45.00		Sqm	1	15.00	1.35	1.35	1.35		20.25		
45.00	60.00		Sqm	1	15.00	1.10	1.10	1.10		16.50		
60.00	75.00		Sqm	1	15.00	1.00	1.00	1.00		15.00		
75.00	81.00		Sqm	1	6.00	1.40	1.40	1.40		8.40		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Sqm	1	15.00	1.10	1.10	1.10		16.50		
15.00	30.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
30.00	45.00		Sqm	1	15.00	2.00	2.00	2.00		30.00		
45.00	60.00		Sqm	1	15.00	1.70	1.70	1.70		25.50		
60.00	75.00		Sqm	1	15.00	1.90	1.90	1.90		28.50		
75.00	90.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
90.00	95.80		Sqm	1	5.80	5.80	5.80	5.80		33.64		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Sqm	1	15.00	2.20	2.20	2.20		33.00		
15.00	26.20		Sqm	1	11.20	1.80	1.80	1.80		20.16		
		(North To South)										
0.00	15.00		Sqm	1	15.00	1.70	1.70	1.70		25.50		
15.00	30.00		Sqm	1	15.00	1.60	1.60	1.60		24.00		
30.00	45.00		Sqm	1	15.00	2.00	2.00	2.00		30.00		
45.00	60.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
60.00	75.00		Sqm	1	15.00	2.30	2.30	2.30		34.50		
75.00	90.00		Sqm	1	15.00	1.90	1.90	1.90		28.50		
90.00	105.00		Sqm	1	15.00	1.80	1.80	1.80		27.00		
105.00	120.00		Sqm	1	15.00	2.20	2.20	2.20		33.00		
120.00	135.00		Sqm	1	15.00	1.60	1.60	1.60		24.00		
135.00	150.00		Sqm	1	15.00	2.10	2.10	2.10		31.50		
150.00	165.00		Sqm	1	15.00	1.60	1.60	1.60		24.00		
165.00	169.00		Sqm	1	4.00	1.90	1.90	1.90		7.60		
		Ward No 10										
		Vidyaranyapura Sub division`										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
6.00	13.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
15.00	20.80		Sqm	1	5.80	1.30	1.30	1.30		7.54		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	30.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
47.00	53.60		Sqm	1	6.60	1.00	1.00	1.00		6.60		
55.00	60.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
95.00	105.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
110.00	120.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
125.00	135.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
140.00	150.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
155.00	165.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
168.00	180.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
183.00	193.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
195.00	200.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
201.00	205.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
0.00	6.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
7.00	15.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
18.00	30.00		Sqm	1	12.00	0.60	0.60	0.60		7.20		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
68.00	75.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
80.00	90.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
95.00	105.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
110.00	120.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
126.00	135.00		Sqm	1	9.00	1.60	1.60	1.60		14.40		
138.00	150.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
157.00	165.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
165.00	180.00		Sqm	1	15.00	2.00	2.00	2.00		30.00		
187.00	195.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
200.00	210.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
215.00	225.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
228.00	238.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
240.00	246.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
249.00	255.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
265.00	270.00		Sqm	1	5.00	0.50	0.50	0.50		2.50		
272.00	277.40		Sqm	1	5.40	1.00	1.00	1.00		5.40		
279.00	285.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
290.00	296.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
298.00	302.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
6.00	13.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
15.00	23.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
25.00	34.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
36.00	45.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
95.00	102.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
103.00	109.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
112.00	120.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
122.00	135.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
137.00	141.00		Sqm	1	4.00	0.50	0.50	0.50		2.00		
143.00	148.00		Sqm	1	5.00	0.50	0.50	0.50		2.50		
150.00	159.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
160.00	166.00		Sqm	1	6.00	0.50	0.50	0.50		3.00		
167.00	171.00		Sqm	1	4.00	0.60	0.60	0.60		2.40		
172.00	180.00		Sqm	1	8.00	0.80	0.80	0.80		6.40		
180.00	186.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
188.00	195.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
198.00	208.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
210.00	220.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Samashana Road										
		2nd main Road										
		(From East to West)										
3.00	10.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
12.00	18.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
20.00	30.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
35.00	45.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
65.00	75.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
80.00	90.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
95.00	105.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
107.00	120.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
122.00	130.00		Sqm	1	8.00	0.80	0.80	0.80		6.40		
132.00	140.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	16.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
18.00	30.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
48.00	53.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
56.00	60.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
95.00	104.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
106.00	120.00		Sqm	1	14.00	2.00	2.00	2.00		28.00		
121.00	128.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
130.00	135.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
136.00	140.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
142.00	148.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
150.00	154.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
2.00	12.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
2.00	10.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
13.00	18.00		Sqm	1	5.00	2.00	2.00	2.00		10.00		
20.00	30.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
62.00	70.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
72.00	77.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
3.00	13.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
14.00	22.00		Sqm	1	8.00	1.60	1.60	1.60		12.80		
		From house no #15 to house no -7										
		(From North to South)										
3.00	14.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
18.00	30.00		Sqm	1	12.00	1.50	1.50	1.50		18.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
63.00	70.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
71.00	77.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
		2nd Cross road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		From House no: 81 to House no:65										
		(From North to South)										
3.00	13.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
15.00	20.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
26.00	38.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
40.00	49.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
51.00	60.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
77.00	84.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
86.00	90.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
94.00	103.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
105.00	110.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
113.00	120.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
125.00	135.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
137.00	144.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
146.00	151.00		Sqm	1	5.00	0.50	0.50	0.50		2.50		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
3.00	13.00		Sqm	1	10.00	0.70	0.70	0.70		7.00		
15.00	27.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
30.00	40.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
41.00	46.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
3.00	13.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
15.00	28.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
30.00	40.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
45.00	58.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
60.00	70.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
75.00	85.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
90.00	101.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
105.00	110.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
5.00	10.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
18.00	29.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
31.00	40.00		Sqm	1	9.00	0.80	0.80	0.80		7.20		
42.00	48.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
		(From East to West)										
4.00	15.00		Sqm	1	11.00	1.10	1.10	1.10		12.10		
17.00	30.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
35.00	45.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
48.00	60.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
68.00	74.00		Sqm	1	6.00	1.80	1.80	1.80		10.80		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	12.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
19.00	30.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	35.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
37.00	45.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
55.00	60.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
65.00	75.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
95.00	105.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
110.00	120.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
129.00	135.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
140.00	150.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
158.00	165.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
170.00	180.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
181.00	186.00		Sqm	1	5.00	1.80	1.80	1.80		9.00		
188.00	195.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
200.00	207.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
209.00	214.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
12.00	20.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
22.00	30.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
32.00	37.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
38.00	43.00		Sqm	1	5.00	1.80	1.80	1.80		9.00		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
2.00	10.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
12.00	18.00		Sqm	1	6.00	0.80	0.80	0.80		4.80		
20.00	30.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
65.00	77.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
79.00	90.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
92.00	100.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
103.00	110.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
104.00	113.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
3.00	8.00		Sqm	1	5.00	1.80	1.80	1.80		9.00		
10.00	16.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
18.00	30.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
35.00	45.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
50.00	60.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
66.00	75.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
80.00	90.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
96.00	105.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
110.00	120.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
126.00	135.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
138.00	150.00		Sqm	1	12.00	1.50	1.50	1.50		18.00		
153.00	160.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
162.00	166.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
169.00	176.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
180.00	191.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
193.00	199.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Sqm	1	7.00	1.60	1.60	1.60		11.20		
12.00	18.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
20.00	30.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
52.00	60.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
61.00	65.00		Sqm	1	4.00	0.80	0.80	0.80		3.20		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
12.00	16.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
18.00	30.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
34.00	45.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
65.00	75.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
83.00	90.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
96.00	105.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
107.00	115.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
117.00	125.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
6.00	15.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
18.00	25.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
27.00	35.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
37.00	48.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
50.00	60.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
65.00	75.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
83.00	90.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
94.00	105.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
107.00	116.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
118.00	127.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
12.00	17.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
20.00	30.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
33.00	45.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
48.00	57.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
60.00	68.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
70.00	77.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
79.00	82.00		Sqm	1	3.00	1.60	1.60	1.60		4.80		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
4.00	10.00		Sqm	1	6.00	1.80	1.80	1.80		10.80		
13.00	20.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
22.00	30.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
48.00	60.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
68.00	75.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
77.00	90.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
96.00	105.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
108.00	120.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
126.00	135.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
140.00	150.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
154.00	165.00		Sqm	1	11.00	1.50	1.50	1.50		16.50		
170.00	180.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
183.00	195.00		Sqm	1	12.00	1.40	1.40	1.40		16.80		
197.00	210.00		Sqm	1	13.00	1.80	1.80	1.80		23.40		
216.00	225.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
4.00	240.00		Sqm	1	6.00	2.00	2.00	2.00		12.00		
246.00	255.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
263.00	270.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
273.00	285.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
287.00	299.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
4.00	13.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
15.00	28.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
30.00	41.00		Sqm	1	11.00	1.80	1.80	1.80		19.80		
45.00	57.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
60.00	71.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
73.00	83.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
86.00	95.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
98.00	105.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
107.00	116.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
119.00	120.00		Sqm	1	1.00	1.00	1.00	1.00		1.00		
125.00	134.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
7.00	15.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
17.00	30.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
33.00	43.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
45.00	53.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
55.00	59.00		Sqm	1	4.00	1.40	1.40	1.40		5.60		
		9th A Cross Road										
		(From South to North)										
2.00	7.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
8.00	12.00		Sqm	1	4.00	1.50	1.50	1.50		6.00		
14.00	16.00		Sqm	1	2.00	1.50	1.50	1.50		3.00		
		9th Cross Road										
		(From North to South)										
2.00	10.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
13.00	24.00		Sqm	1	11.00	1.10	1.10	1.10		12.10		
30.00	38.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
43.00	52.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
60.00	73.00		Sqm	1	13.00	1.50	1.50	1.50		19.50		
76.00	88.00		Sqm	1	12.00	1.40	1.40	1.40		16.80		
90.00	96.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
		7th A Cross Road										
		(From South to North)										
2.00	6.00		Sqm	1	4.00	1.80	1.80	1.80		7.20		
8.00	11.00		Sqm	1	3.00	1.50	1.50	1.50		4.50		
13.00	15.00		Sqm	1	2.00	1.30	1.30	1.30		2.60		
16.00	18.00		Sqm	1	2.00	1.50	1.50	1.50		3.00		
		7th Cross Road										
		(From North to South)										
4.00	13.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
15.00	20.00		Sqm	1	5.00	0.80	0.80	0.80		4.00		
23.00	30.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
32.00	45.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
55.00	60.00		Sqm	1	5.00	1.20	1.20	1.20		6.00		
65.00	71.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
73.00	84.50		Sqm	1	11.50	2.00	2.00	2.00		23.00		
86.00	90.00		Sqm	1	4.00	0.80	0.80	0.80		3.20		
92.00	98.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
		6th Cross Road										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	11.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
13.00	24.00		Sqm	1	11.00	1.10	1.10	1.10		12.10		
30.00	40.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
48.00	56.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
60.00	70.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
72.00	80.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
82.00	88.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
90.00	94.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
		6th A Cross Road										
		(From South to North)										
2.00	7.00		Sqm	1	5.00	1.40	1.40	1.40		7.00		
9.00	13.00		Sqm	1	4.00	1.80	1.80	1.80		7.20		
15.00	18.00		Sqm	1	3.00	1.40	1.40	1.40		4.20		
		5th Cross Road										
		(From North to South)										
5.00	14.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
16.00	28.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
30.00	40.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
44.00	53.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
55.00	63.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
66.00	76.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
78.00	85.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
87.00	94.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
		5th A Cross Road										
		(From South to North)										
2.00	6.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
8.00	14.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
15.00	20.00		Sqm	1	5.00	1.20	1.20	1.20		6.00		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
5.00	13.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
18.00	30.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
62.00	75.00		Sqm	1	13.00	2.00	2.00	2.00		26.00		
80.00	90.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
97.00	105.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
106.00	120.00		Sqm	1	14.00	2.00	2.00	2.00		28.00		
127.00	135.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
140.00	150.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
156.00	165.00		Sqm	1	9.00	1.60	1.60	1.60		14.40		
170.00	180.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
185.00	195.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
198.00	210.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
215.00	225.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
230.00	240.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
242.00	251.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
253.00	265.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
270.00	282.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
284.00	293.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
295.00	305.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.00	9.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
11.00	23.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
25.00	35.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
37.00	45.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
53.00	60.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
66.00	75.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	90.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
95.00	105.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
110.00	120.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
127.00	135.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
143.00	150.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
155.00	163.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
165.00	173.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
176.00	180.00		Sqm	1	4.00	1.60	1.60	1.60		6.40		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
5.00	13.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		
15.00	25.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
35.00	45.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
50.00	60.00		Sqm	1	10.00	2.00	2.00	2.00		20.00		
66.00	75.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
83.00	90.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
94.00	105.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
111.00	120.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
122.00	130.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
132.00	140.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
144.00	150.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
153.00	160.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
162.00	169.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
6.00	14.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
16.00	28.00		Sqm	1	12.00	2.00	2.00	2.00		24.00		
37.00	45.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
47.00	58.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
60.00	66.00		Sqm	1	6.00	1.20	1.20	1.20		7.20		
68.00	75.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
78.00	85.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
87.00	90.00		Sqm	1	3.00	1.70	1.70	1.70		5.10		
95.00	105.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
111.00	120.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
125.00	135.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
137.00	148.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
150.00	158.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
		Vidyaranyapura Sub division										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
4.00	9.00		Sqm	1	5.00	0.90	0.90	0.90		4.50		
20.00	28.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
35.00	42.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
65.00	71.00		Sqm	1	6.00	1.30	1.30	1.30		7.80		
80.00	87.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
94.00	102.00		Sqm	1	8.00	0.90	0.90	0.90		7.20		
111.00	118.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
125.00	133.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
140.00	148.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
155.00	162.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
170.00	178.00		Sqm	1	8.00	1.50	1.50	1.50		12.00		
185.00	195.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
195.00	203.10		Sqm	1	8.10	1.50	1.50	1.50		12.15		
		2nd Main road, from Apollo pharmacy										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From West to East)										
3.10	12.00		Sqm	1	8.90	1.10	1.10	1.10		9.79		
20.00	28.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
35.00	45.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
50.00	58.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
80.00	87.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
96.00	100.00		Sqm	1	4.00	1.45	1.45	1.45		5.80		
112.00	120.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
128.00	135.00		Sqm	1	7.00	0.90	0.90	0.90		6.30		
137.00	150.00		Sqm	1	13.00	0.60	0.60	0.60		7.80		
158.00	165.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
173.00	180.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
188.00	195.00		Sqm	1	7.00	0.90	0.90	0.90		6.30		
200.00	210.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
217.00	225.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
232.00	240.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
248.00	255.00		Sqm	1	7.00	0.90	0.90	0.90		6.30		
264.00	270.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
272.00	277.40		Sqm	1	5.40	1.00	1.00	1.00		5.40		
278.50	285.00		Sqm	1	6.50	1.00	1.00	1.00		6.50		
290.00	300.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
3.50	12.00		Sqm	1	8.50	0.60	0.60	0.60		5.10		
20.00	25.20		Sqm	1	5.20	1.10	1.10	1.10		5.72		
27.00	33.90		Sqm	1	6.90	0.50	0.50	0.50		3.45		
35.00	45.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
50.00	60.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
65.00	75.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
80.00	90.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
95.00	105.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
106.00	109.10		Sqm	1	3.10	1.10	1.10	1.10		3.41		
112.00	120.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
125.00	135.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
138.00	142.80		Sqm	1	4.80	1.10	1.10	1.10		5.28		
145.00	150.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
151.00	154.80		Sqm	1	3.80	1.10	1.10	1.10		4.18		
157.00	165.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
168.00	172.80		Sqm	1	4.80	1.10	1.10	1.10		5.28		
175.00	180.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
181.00	185.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
190.00	195.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
198.00	209.40		Sqm	1	11.40	0.60	0.60	0.60		6.84		
215.00	221.00		Sqm	1	6.00	1.10	1.10	1.10		6.60		
		Samashana Road										
		2nd main Road										
		(From East to West)										
5.00	11.80		Sqm	1	6.80	0.60	0.60	0.60		4.08		
13.00	15.00		Sqm	1	2.00	1.20	1.20	1.20		2.40		
20.00	30.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
35.00	45.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
50.00	60.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
66.00	75.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
81.00	90.00		Sqm	1	9.00	1.10	1.10	1.10		9.90		
95.00	105.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
115.00	120.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
125.00	135.00		Sqm	1	10.00	0.70	0.70	0.70		7.00		
138.00	140.50		Sqm	1	2.50	0.70	0.70	0.70		1.75		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	15.50		Sqm	1	9.50	1.20	1.20	1.20		11.40		
20.00	30.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
35.00	45.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
7.00	51.00		Sqm	1	4.00	1.00	1.00	1.00		4.00		
53.00	60.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
65.00	75.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
80.00	90.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
95.00	105.10		Sqm	1	10.10	1.00	1.00	1.00		10.10		
110.00	120.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
122.00	126.50		Sqm	1	4.50	0.60	0.60	0.60		2.70		
130.00	135.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
138.00	141.90		Sqm	1	3.90	0.70	0.70	0.70		2.73		
144.00	150.00		Sqm	1	6.00	0.70	0.70	0.70		4.20		
152.00	154.10		Sqm	1	2.10	0.90	0.90	0.90		1.89		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Sqm	1	1.60	0.60	0.60	0.60		0.96		
6.00	15.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
17.00	30.00		Sqm	1	13.00	0.60	0.60	0.60		7.80		
34.00	45.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
48.00	60.00		Sqm	1	12.00	0.60	0.60	0.60		7.20		
63.00	75.00		Sqm	1	12.00	0.90	0.90	0.90		10.80		
75.00	79.10		Sqm	1	4.10	0.60	0.60	0.60		2.46		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
6.00	15.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
17.00	23.30		Sqm	1	6.30	0.70	0.70	0.70		4.41		
		From house no #15 to house no -7										
		(From North to South)										
5.00	15.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
22.00	30.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
35.00	45.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
51.00	60.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
65.00	73.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
74.00	79.00		Sqm	1	5.00	1.50	1.50	1.50		7.50		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
4.00	15.00		Sqm	1	11.00	1.00	1.00	1.00		11.00		
20.00	29.60		Sqm	1	9.60	1.40	1.40	1.40		13.44		
32.00	38.70		Sqm	1	6.70	1.00	1.00	1.00		6.70		
40.00	45.00		Sqm	1	5.00	1.80	1.80	1.80		9.00		
50.00	60.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
65.00	75.00		Sqm	1	10.00	1.70	1.70	1.70		17.00		
78.00	84.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
86.00	90.00		Sqm	1	4.00	2.00	2.00	2.00		8.00		
100.00	103.00		Sqm	1	3.00	0.60	0.60	0.60		1.80		
106.00	115.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
117.00	127.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
129.00	139.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
140.00	148.00		Sqm	1	8.00	1.40	1.40	1.40		11.20		
150.00	153.30		Sqm	1	3.30	1.00	1.00	1.00		3.30		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
8.00	15.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
20.00	30.00		Sqm	1	10.00	1.60	1.60	1.60		16.00		
35.00	43.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
45.00	47.30		Sqm	1	2.30	1.30	1.30	1.30		2.99		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
7.00	15.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
22.00	30.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
38.00	45.00		Sqm	1	7.00	1.80	1.80	1.80		12.60		
50.00	60.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
65.00	75.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
80.00	90.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
96.00	105.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
108.00	112.00		Sqm	1	4.00	0.70	0.70	0.70		2.80		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
6.00	15.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
20.00	30.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
34.00	45.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
49.00	50.10		Sqm	1	1.10	2.00	2.00	2.00		2.20		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
5.00	15.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
17.00	30.00		Sqm	1	13.00	0.60	0.60	0.60		7.80		
35.00	45.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
50.00	60.00		Sqm	1	10.00	0.70	0.70	0.70		7.00		
68.00	75.10		Sqm	1	7.10	1.10	1.10	1.10		7.81		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	15.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
20.00	30.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
30.00	34.30		Sqm	1	4.30	1.00	1.00	1.00		4.30		
36.00	45.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
50.00	60.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
65.00	75.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
82.00	90.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
95.00	105.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
114.00	120.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
125.00	135.00		Sqm	1	10.00	1.25	1.25	1.25		12.50		
140.00	150.00		Sqm	1	10.00	0.90	0.90	0.90		9.00		
157.00	165.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
170.00	180.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
182.00	187.20		Sqm	1	5.20	2.00	2.00	2.00		10.40		
190.00	195.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
199.00	210.00		Sqm	1	11.00	1.10	1.10	1.10		12.10		
212.00	215.10		Sqm	1	3.10	1.50	1.50	1.50		4.65		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
6.00	15.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
18.00	28.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
30.00	34.00		Sqm	1	4.00	0.70	0.70	0.70		2.80		
36.00	40.00		Sqm	1	4.00	0.80	0.80	0.80		3.20		
42.00	44.00		Sqm	1	2.00	1.10	1.10	1.10		2.20		
		1st Main Road										
		From ramachandrapura main road to house no #32										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From West to East)										
0.00	6.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
8.00	15.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
18.00	30.00		Sqm	1	12.00	0.60	0.60	0.60		7.20		
38.00	45.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
51.00	60.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
63.00	75.00		Sqm	1	12.00	0.70	0.70	0.70		8.40		
80.00	90.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
96.00	105.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
108.00	117.00		Sqm	1	9.00	0.70	0.70	0.70		6.30		
119.00	120.80		Sqm	1	1.80	0.70	0.70	0.70		1.26		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
4.00	13.00		Sqm	1	9.00	0.80	0.80	0.80		7.20		
15.00	28.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
31.00	37.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
39.00	45.00		Sqm	1	6.00	0.60	0.60	0.60		3.60		
50.00	60.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
65.00	75.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
83.00	90.00		Sqm	1	7.00	0.80	0.80	0.80		5.60		
95.00	105.00		Sqm	1	10.00	0.70	0.70	0.70		7.00		
114.00	120.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
128.00	135.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
142.00	150.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
153.00	161.00		Sqm	1	8.00	0.50	0.50	0.50		4.00		
165.00	172.00		Sqm	1	7.00	0.70	0.70	0.70		4.90		
175.00	180.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
183.00	190.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
195.00	200.20		Sqm	1	5.20	1.60	1.60	1.60		8.32		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Sqm	1	7.00	0.50	0.50	0.50		3.50		
13.00	23.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
25.00	30.00		Sqm	1	5.00	1.10	1.10	1.10		5.50		
37.00	45.00		Sqm	1	8.00	0.70	0.70	0.70		5.60		
51.00	60.00		Sqm	1	9.00	0.80	0.80	0.80		7.20		
61.00	65.50		Sqm	1	4.50	1.40	1.40	1.40		6.30		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Sqm	1	5.00	1.00	1.00	1.00		5.00		
12.00	19.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
21.00	30.00		Sqm	1	9.00	1.00	1.00	1.00		9.00		
34.00	45.00		Sqm	1	11.00	0.70	0.70	0.70		7.70		
50.00	60.00		Sqm	1	10.00	0.50	0.50	0.50		5.00		
65.00	75.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
80.00	90.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
95.00	105.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
110.00	120.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
123.00	127.60		Sqm	1	4.60	1.30	1.30	1.30		5.98		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
4.00	11.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
13.00	20.00		Sqm	1	7.00	1.30	1.30	1.30		9.10		
23.00	30.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
34.00	45.00		Sqm	1	11.00	0.75	0.75	0.75		8.25		
51.00	60.00		Sqm	1	9.00	0.90	0.90	0.90		8.10		
65.00	75.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
78.00	90.00		Sqm	1	12.00	0.70	0.70	0.70		8.40		
3.00	105.00		Sqm	1	9.00	0.60	0.60	0.60		5.40		
111.00	120.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
123.00	128.30		Sqm	1	5.30	1.00	1.00	1.00		5.30		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
12.00	20.00		Sqm	1	8.00	0.70	0.70	0.70		5.60		
23.00	30.00		Sqm	1	7.00	0.60	0.60	0.60		4.20		
35.00	45.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
50.00	60.00		Sqm	1	10.00	1.30	1.30	1.30		13.00		
63.00	71.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
75.00	79.00		Sqm	1	4.00	1.20	1.20	1.20		4.80		
81.00	83.40		Sqm	1	2.40	1.60	1.60	1.60		3.84		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
5.00	13.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
15.00	20.00		Sqm	1	5.00	0.80	0.80	0.80		4.00		
23.00	30.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
35.00	45.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
50.00	60.00		Sqm	1	10.00	1.40	1.40	1.40		14.00		
63.00	75.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
79.00	90.00		Sqm	1	11.00	1.30	1.30	1.30		14.30		
97.00	105.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
110.00	120.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
123.00	135.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
140.00	150.00		Sqm	1	10.00	0.60	0.60	0.60		6.00		
155.00	165.00		Sqm	1	10.00	0.80	0.80	0.80		8.00		
172.00	180.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
189.00	195.00		Sqm	1	6.00	1.00	1.00	1.00		6.00		
200.00	210.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
218.00	225.00		Sqm	1	7.00	0.80	0.80	0.80		5.60		
230.00	240.00		Sqm	1	10.00	1.00	1.00	1.00		10.00		
250.00	255.00		Sqm	1	5.00	1.40	1.40	1.40		7.00		
261.00	270.00		Sqm	1	9.00	1.30	1.30	1.30		11.70		
275.00	283.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
287.00	300.40		Sqm	1	13.40	1.30	1.30	1.30		17.42		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
6.00	14.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
18.00	30.00		Sqm	1	12.00	0.60	0.60	0.60		7.20		
35.00	45.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
53.00	60.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
62.00	66.00		Sqm	1	4.00	1.10	1.10	1.10		4.40		
68.00	75.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
80.00	90.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
97.00	105.00		Sqm	1	8.00	0.60	0.60	0.60		4.80		
111.00	120.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
129.00	135.00		Sqm	1	6.00	0.90	0.90	0.90		5.40		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Sqm	1	3.70	1.20	1.20	1.20		4.44		
3.70	5.50	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
15.00	30.00		Sqm	1	15.00	0.60	0.50	0.55		8.25		
30.00	40.80		Sqm	1	10.80	0.90	0.85	0.88		9.45		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
40.80	55.00		Sqm	1	14.20	1.10	0.60	0.85		12.07		
		9th A Cross Road										
		(From South to North)										
3.70	15.00		Sqm	1	11.30	0.50	0.65	0.58		6.50		
15.00	16.10		Sqm	1	1.10	1.15	0.35	0.75		0.83		
		9th Cross Road										
		(From North to South)										
23.00	30.00		Sqm	1	7.00	1.20	1.20	1.20		8.40		
45.00	52.00		Sqm	1	7.00	0.95	0.65	0.80		5.60		
60.00	71.00		Sqm	1	11.00	1.15	1.15	1.15		12.65		
75.00	90.10		Sqm	1	15.10	1.20	1.20	1.20		18.12		
90.90	97.30		Sqm	1	6.40	0.85	0.50	0.68		4.32		
		7th A Cross Road										
		(From South to North)										
9.10	15.00		Sqm	1	5.90	1.50	1.50	1.50		8.85		
15.00	18.30		Sqm	1	3.30	0.35	0.35	0.35		1.16		
		7th Cross Road										
		(From North to South)										
15.00	30.00		Sqm	1	15.00	1.10	1.10	1.10		16.50		
33.00	42.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
45.00	55.80		Sqm	1	10.80	0.60	0.60	0.60		6.48		
60.00	75.00		Sqm	1	15.00	1.50	1.50	1.50		22.50		
79.00	84.50		Sqm	1	5.50	1.20	1.20	1.20		6.60		
84.50	90.00		Sqm	1	5.50	0.60	0.35	0.48		2.61		
91.20	93.10		Sqm	1	1.90	1.20	1.20	1.20		2.28		
		6th Cross Road										
		(From North to South)										
10.00	15.00		Sqm	1	5.00	0.60	0.60	0.60		3.00		
15.00	28.00		Sqm	1	13.00	0.50	0.50	0.50		6.50		
42.00	45.00		Sqm	1	3.00	0.70	0.70	0.70		2.10		
52.00	60.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
62.50	75.00		Sqm	1	12.50	1.00	1.00	1.00		12.50		
83.00	90.00		Sqm	1	7.00	1.60	1.60	1.60		11.20		
91.50	92.30		Sqm	1	0.80	1.20	1.20	1.20		0.96		
		6th A Cross Road										
		(From South to North)										
5.00	9.60		Sqm	1	4.60	1.20	1.20	1.20		5.52		
11.80	15.00		Sqm	1	3.20	1.20	1.20	1.20		3.84		
		5th Cross Road										
		(From North to South)										
7.00	15.00		Sqm	1	8.00	1.10	1.10	1.10		8.80		
33.00	40.70		Sqm	1	7.70	1.40	1.40	1.40		10.78		
48.00	56.00		Sqm	1	8.00	1.00	1.00	1.00		8.00		
65.00	70.00		Sqm	1	5.00	1.30	1.30	1.30		6.50		
79.00	85.00		Sqm	1	6.00	1.45	1.45	1.45		8.70		
		5th A Cross Road										
		(From South to North)										
2.00	4.00		Sqm	1	2.00	0.50	0.40	0.45		0.90		
9.20	15.00		Sqm	1	5.80	1.20	1.20	1.20		6.96		
17.60	19.60		Sqm	1	2.00	1.30	0.60	0.95		1.90		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
16.00	28.30		Sqm	1	12.30	0.90	0.80	0.85		10.46		
30.00	44.20		Sqm	1	14.20	1.10	0.35	0.73		10.30		
45.00	58.00		Sqm	1	13.00	1.30	0.45	0.88		11.38		
60.00	73.00		Sqm	1	13.00	0.70	0.55	0.63		8.13		
107.00	120.00		Sqm	1	13.00	1.50	1.20	1.35		17.55		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
124.00	134.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
5.00	149.00		Sqm	1	14.00	0.60	0.60	0.60		8.40		
153.00	165.00		Sqm	1	12.00	1.60	1.60	1.60		19.20		
173.00	180.00		Sqm	1	7.00	0.70	0.70	0.70		4.90		
183.00	195.00		Sqm	1	12.00	1.10	1.10	1.10		13.20		
201.00	225.00		Sqm	1	24.00	1.00	1.00	1.00		24.00		
228.00	240.00		Sqm	1	12.00	1.60	1.60	1.60		19.20		
245.00	255.00		Sqm	1	10.00	1.40	0.75	1.08		10.75		
258.00	270.00		Sqm	1	12.00	1.20	1.20	1.20		14.40		
274.00	285.00		Sqm	1	11.00	1.00	0.70	0.85		9.35		
287.00	300.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.50	10.00		Sqm	1	5.50	1.50	1.50	1.50		8.25		
15.20	24.70		Sqm	1	9.50	1.15	1.15	1.15		10.93		
29.00	30.00		Sqm	1	1.00	1.45	1.45	1.45		1.45		
32.00	45.00		Sqm	1	13.00	1.20	1.20	1.20		15.60		
48.00	60.00		Sqm	1	12.00	1.40	1.40	1.40		16.80		
80.20	90.00		Sqm	1	9.80	1.80	1.80	1.80		17.64		
97.00	105.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
110.00	120.00		Sqm	1	10.00	1.15	1.15	1.15		11.50		
125.00	136.00		Sqm	1	11.00	1.20	1.20	1.20		13.20		
145.00	150.00		Sqm	1	5.00	1.70	1.70	1.70		8.50		
154.00	165.00		Sqm	1	11.00	1.35	1.35	1.35		14.85		
168.00	178.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
2.50	15.00		Sqm	1	12.50	1.20	0.95	1.08		13.44		
30.00	44.00		Sqm	1	14.00	1.70	1.20	1.45		20.30		
45.00	55.60		Sqm	1	10.60	1.20	1.15	1.18		12.46		
60.00	74.30		Sqm	1	14.30	1.10	1.10	1.10		15.73		
90.00	103.00		Sqm	1	13.00	1.00	1.00	1.00		13.00		
105.00	122.00		Sqm	1	17.00	1.40	1.40	1.40		23.80		
128.00	135.00		Sqm	1	7.00	1.10	1.10	1.10		7.70		
150.00	162.00		Sqm	1	12.00	1.20	1.15	1.18		14.10		
165.00	168.60		Sqm	1	3.60	1.60	1.60	1.60		5.76		
168.60	169.50		Sqm	1	0.90	1.20	1.20	1.20		1.08		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
9.30	14.50		Sqm	1	5.20	1.20	1.20	1.20		6.24		
15.00	25.00		Sqm	1	10.00	1.60	1.20	1.40		14.00		
30.00	44.20		Sqm	1	14.20	1.20	1.20	1.20		17.04		
49.00	52.70		Sqm	1	3.70	2.00	1.20	1.60		5.92		
55.00	57.60		Sqm	1	2.60	1.20	1.20	1.20		3.12		
60.00	70.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
71.50	85.00		Sqm	1	13.50	0.50	0.50	0.50		6.75		
86.10	90.00		Sqm	1	3.90	0.70	0.70	0.70		2.73		
93.50	103.00		Sqm	1	9.50	1.10	1.10	1.10		10.45		
110.00	119.00		Sqm	1	9.00	1.40	1.40	1.40		12.60		
120.00	132.00		Sqm	1	12.00	1.60	1.60	1.60		19.20		
135.00	148.00		Sqm	1	13.00	1.30	1.20	1.25		16.25		
150.00	158.00		Sqm	1	8.00	1.20	1.20	1.20		9.60		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
3.00	10.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
13.00	24.00		Sqm	1	11.00	1.60	1.60	1.60		17.60		
26.00	35.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
39.00	50.00		Sqm	1	11.00	2.10	2.10	2.10		23.10		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
54.00	64.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
5.00	75.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
82.00	90.00		Sqm	1	8.00	1.80	1.80	1.80		14.40		
92.00	101.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
103.00	110.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
112.00	118.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
120.00	123.00		Sqm	1	3.00	1.10	1.10	1.10		3.30		
		11th Cross Road										
		North to South										
2.00	11.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
13.00	20.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
23.00	33.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
35.00	45.00		Sqm	1	10.00	1.20	1.20	1.20		12.00		
50.00	60.00		Sqm	1	10.00	1.10	1.10	1.10		11.00		
63.00	72.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
74.00	80.00		Sqm	1	6.00	1.90	1.90	1.90		11.40		
82.00	90.00		Sqm	1	8.00	2.00	2.00	2.00		16.00		
93.00	100.00		Sqm	1	7.00	2.00	2.00	2.00		14.00		
102.00	111.00		Sqm	1	9.00	1.80	1.80	1.80		16.20		
115.00	122.00		Sqm	1	7.00	1.70	1.70	1.70		11.90		
		17th Cross Road										
		North to South										
4.00	10.00		Sqm	1	6.00	1.50	1.50	1.50		9.00		
13.00	23.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
25.00	36.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
38.00	47.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
49.00	59.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
63.00	72.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
75.00	84.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
86.00	98.00		Sqm	1	12.00	1.80	1.80	1.80		21.60		
100.00	109.00		Sqm	1	9.00	1.20	1.20	1.20		10.80		
		3rd Cross Road										
		North to South										
3.00	10.00		Sqm	1	7.00	1.00	1.00	1.00		7.00		
13.00	24.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
26.00	35.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
37.00	47.00		Sqm	1	10.00	1.80	1.80	1.80		18.00		
50.00	59.00		Sqm	1	9.00	2.00	2.00	2.00		18.00		
		2nd Cross Road										
		North To South										
4.00	13.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
15.00	26.00		Sqm	1	11.00	2.00	2.00	2.00		22.00		
28.00	36.00		Sqm	1	8.00	1.30	1.30	1.30		10.40		
38.00	47.00		Sqm	1	9.00	1.50	1.50	1.50		13.50		
50.00	60.00		Sqm	1	10.00	1.50	1.50	1.50		15.00		
66.00	73.00		Sqm	1	7.00	1.50	1.50	1.50		10.50		
									Total Executed Quantity	**24565.40**		
									Tender Quantity	**16638.88**		
									Quantity Upto 125%	**20798.60**	**48.50**	**1008733.00**
									Quantity Above 125%	**3766.80**	**48.50**	**182693.00**
Item no.18		**Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
0.00	7.10		Sqm	1	7.10	2.20	3.00	2.60		18.46		
7.10	15.00		Sqm	1	7.90	5.20	4.40	4.80		37.92		
15.00	30.00		Sqm	1	15.00	4.40	6.30	5.35		80.25		
30.00	45.00		Sqm	1	15.00	6.30	4.30	5.30		79.50		
45.00	60.00		Sqm	1	15.00	4.30	4.65	4.48		67.13		
60.00	75.00		Sqm	1	15.00	4.65	4.65	4.65		69.75		
75.00	90.00		Sqm	1	15.00	4.65	4.40	4.53		67.88		
90.00	105.00		Sqm	1	15.00	4.40	4.25	4.33		64.88		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
105.00	112.00		Sqm	1	7.00	4.25	5.30	4.78		33.43		
112.00	120.00		Sqm	1	8.00	7.50	6.50	7.00		56.00		
120.00	135.00		Sqm	1	15.00	5.40	5.40	5.40		81.00		
135.00	145.00		Sqm	1	10.00	5.40	5.60	5.50		55.00		
145.00	152.00		Sqm	1	7.00	7.20	6.60	6.90		48.30		
152.00	165.00		Sqm	1	13.00	6.60	6.30	6.45		83.85		
165.00	173.10		Sqm	1	8.10	6.30	6.00	6.15		49.82		
173.10	180.00		Sqm	1	6.90	3.60	3.50	3.55		24.50		
180.00	195.00		Sqm	1	15.00	3.50	3.75	3.63		54.38		
195.00	200.80		Sqm	1	5.80	3.75	6.30	5.03		29.15		
		Ravi Gowda Layout										
		(From North to South)										
0.00	3.50		Sqm	1	3.50	6.90	6.90	6.90		24.15		
3.50	15.00		Sqm	1	11.50	5.60	5.70	5.65		64.98		
15.00	30.00		Sqm	1	15.00	5.70	5.20	5.45		81.75		
30.00	45.00		Sqm	1	15.00	5.20	5.40	5.30		79.50		
45.00	60.00		Sqm	1	15.00	5.40	3.90	4.65		69.75		
60.00	75.00		Sqm	1	15.00	3.90	4.40	4.15		62.25		
75.00	90.00		Sqm	1	15.00	4.40	5.00	4.70		70.50		
90.00	105.00		Sqm	1	15.00	5.00	5.05	5.03		75.38		
105.00	120.00		Sqm	1	15.00	5.05	4.90	4.98		74.63		
120.00	126.00		Sqm	1	6.00	4.90	5.10	5.00		30.00		
126.00	135.00		Sqm	1	9.00	4.50	4.35	4.43		39.83		
135.00	141.30		Sqm	1	6.30	4.35	4.35	4.35		27.41		
141.30	150.00		Sqm	1	8.70	5.35	5.00	5.18		45.02		
150.00	165.00		Sqm	1	15.00	5.00	5.45	5.23		78.38		
165.00	180.00		Sqm	1	15.00	5.45	4.95	5.20		78.00		
180.00	195.00		Sqm	1	15.00	4.95	5.85	5.40		81.00		
195.00	210.00		Sqm	1	15.00	5.85	5.30	5.58		83.63		
210.00	213.50		Sqm	1	3.50	5.30	7.00	6.15		21.53		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.50	6.20	5.85		87.75		
15.00	30.00		Sqm	1	15.00	6.20	5.50	5.85		87.75		
30.00	45.00		Sqm	1	15.00	5.50	5.35	5.43		81.38		
45.00	58.70		Sqm	1	13.70	5.35	4.90	5.13		70.21		
58.70	64.70		Sqm	1	6.00	5.80	5.60	5.70		34.20		
64.70	69.20		Sqm	1	4.50	4.70	5.00	4.85		21.83		
		Jai Rama Layout Main Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.00	4.40	4.20		63.00		
15.00	30.00		Sqm	1	15.00	4.40	5.20	4.80		72.00		
30.00	45.00		Sqm	1	15.00	5.20	4.40	4.80		72.00		
45.00	60.00		Sqm	1	15.00	4.40	4.85	4.63		69.38		
60.00	75.00		Sqm	1	15.00	4.85	4.90	4.88		73.13		
75.00	90.00		Sqm	1	15.00	4.90	5.10	5.00		75.00		
90.00	105.00		Sqm	1	15.00	5.10	6.50	5.80		87.00		
105.00	114.70		Sqm	1	9.70	6.50	6.65	6.58		63.78		
114.70	118.30		Sqm	1	3.60	6.65	8.30	7.48		26.91		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	6.35	6.00	6.18		92.63		
15.00	30.00		Sqm	1	15.00	6.00	5.20	5.60		84.00		
30.00	45.00		Sqm	1	15.00	5.20	5.50	5.35		80.25		
45.00	60.00		Sqm	1	15.00	5.50	4.85	5.18		77.63		
60.00	67.90		Sqm	1	7.90	4.85	5.30	5.08		40.09		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Sqm	1	3.50	8.50	6.50	7.50		26.25		
3.50	15.00		Sqm	1	11.50	6.50	7.00	6.75		77.63		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
15.00	30.00		Sqm	1	15.00	7.00	6.65	6.83		102.38		
.00	45.00		Sqm	1	15.00	6.65	7.10	6.88		103.13		
45.00	60.00		Sqm	1	15.00	7.10	7.15	7.13		106.88		
60.00	75.00		Sqm	1	15.00	7.15	7.40	7.28		109.13		
75.00	90.00		Sqm	1	15.00	7.40	7.00	7.20		108.00		
90.00	105.00		Sqm	1	15.00	7.00	7.05	7.03		105.38		
105.00	120.00		Sqm	1	15.00	7.05	8.15	7.60		114.00		
120.00	135.00		Sqm	1	15.00	8.15	7.50	7.83		117.38		
135.00	150.00		Sqm	1	15.00	7.50	7.40	7.45		111.75		
150.00	165.00		Sqm	1	15.00	7.40	7.10	7.25		108.75		
165.00	180.00		Sqm	1	15.00	7.10	7.80	7.45		111.75		
180.00	195.00		Sqm	1	15.00	7.80	8.00	7.90		118.50		
195.00	210.00		Sqm	1	15.00	8.00	7.05	7.53		112.88		
210.00	215.60		Sqm	1	5.60	7.05	7.00	7.03		39.34		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Sqm	1	3.40	6.10	4.80	5.45		18.53		
3.40	9.40		Sqm	1	6.00	4.80	4.75	4.78		28.65		
9.40	18.50		Sqm	1	9.10	4.15	4.60	4.38		39.81		
18.50	30.00		Sqm	1	11.50	4.70	5.75	5.23		60.09		
30.00	37.80		Sqm	1	7.80	5.75	5.40	5.58		43.49		
		2nd A Cross Road										
		(From North to South)										
0.00	4.30		Sqm	1	4.30	5.80	5.00	5.40		23.22		
4.30	15.00		Sqm	1	10.70	5.00	4.65	4.83		51.63		
15.00	30.00		Sqm	1	15.00	4.65	4.50	4.58		68.63		
30.00	45.00		Sqm	1	15.00	4.50	4.20	4.35		65.25		
45.00	60.00		Sqm	1	15.00	4.20	5.00	4.60		69.00		
60.00	75.00		Sqm	1	15.00	5.00	4.90	4.95		74.25		
75.00	90.00		Sqm	1	15.00	4.90	4.30	4.60		69.00		
90.00	105.00		Sqm	1	15.00	4.30	4.80	4.55		68.25		
105.00	111.10		Sqm	1	6.10	4.80	4.75	4.78		29.13		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	5.20	5.30	5.25		78.75		
15.00	30.00		Sqm	1	15.00	5.30	4.20	4.75		71.25		
30.00	45.00		Sqm	1	15.00	4.20	5.10	4.65		69.75		
45.00	60.00		Sqm	1	15.00	5.10	5.10	5.10		76.50		
60.00	75.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
75.00	90.20		Sqm	1	15.20	5.00	4.60	4.80		72.96		
90.20	94.40		Sqm	1	4.20	6.00	6.40	6.20		26.04		
94.40	105.00		Sqm	1	10.60	5.00	4.80	4.90		51.94		
105.00	109.20		Sqm	1	4.20	4.80	4.90	4.85		20.37		
		2nd Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.70	4.60	5.15		77.25		
15.00	30.00		Sqm	1	15.00	4.60	4.90	4.75		71.25		
30.00	45.00		Sqm	1	15.00	4.90	4.70	4.80		72.00		
45.00	60.00		Sqm	1	15.00	4.70	4.80	4.75		71.25		
60.00	75.00		Sqm	1	15.00	4.80	5.70	5.25		78.75		
75.00	90.00		Sqm	1	15.00	5.70	6.00	5.85		87.75		
90.00	105.00		Sqm	1	15.00	6.00	6.80	6.40		96.00		
105.00	120.00		Sqm	1	15.00	6.80	7.15	6.98		104.63		
120.00	122.10		Sqm	1	2.10	7.15	9.30	8.23		17.27		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.10	5.00	4.55		68.25		
15.00	30.00		Sqm	1	15.00	5.00	4.25	4.63		69.38		
30.00	45.00		Sqm	1	15.00	4.25	4.00	4.13		61.88		
45.00	60.00		Sqm	1	15.00	4.00	4.30	4.15		62.25		
60.00	75.00		Sqm	1	15.00	4.30	4.55	4.43		66.38		
75.00	90.00		Sqm	1	15.00	4.55	4.45	4.50		67.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
90.00	105.00		Sqm	1	15.00	4.45	5.30	4.88		73.13		
105.00	120.00		Sqm	1	15.00	5.30	5.65	5.48		82.13		
120.00	135.00		Sqm	1	15.00	5.65	5.50	5.58		83.63		
135.00	136.00		Sqm	1	1.00	5.50	5.00	5.25		5.25		
		1st A K.V.J Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	3.90	3.65	3.78		56.63		
15.00	30.00		Sqm	1	15.00	3.65	3.00	3.33		49.88		
30.00	33.30		Sqm	1	3.30	3.00	3.40	3.20		10.56		
33.30	34.20		Sqm	1	0.90	2.90	2.50	2.70		2.43		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.45	5.05	5.25		78.75		
15.00	30.00		Sqm	1	15.00	5.05	4.70	4.88		73.13		
30.00	45.00		Sqm	1	15.00	4.70	4.95	4.83		72.38		
45.00	60.00		Sqm	1	15.00	4.95	5.35	5.15		77.25		
60.00	67.20		Sqm	1	7.20	5.35	5.40	5.38		38.70		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
0.00	9.90		Sqm	1	9.90	5.35	4.80	5.08		50.24		
9.90	15.00		Sqm	1	5.10	4.15	4.10	4.13		21.04		
15.00	30.00		Sqm	1	15.00	4.10	4.60	4.35		65.25		
30.00	45.00		Sqm	1	15.00	4.60	4.15	4.38		65.63		
45.00	60.00		Sqm	1	15.00	4.15	4.25	4.20		63.00		
60.00	63.60		Sqm	1	3.60	4.25	4.55	4.40		15.84		
63.60	66.70		Sqm	1	3.10	3.90	3.50	3.70		11.47		
66.70	75.00		Sqm	1	8.30	3.50	4.55	4.03		33.41		
75.00	79.50		Sqm	1	4.50	4.55	4.30	4.43		19.91		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.30	3.50	3.90		58.50		
15.00	30.00		Sqm	1	15.00	3.50	4.50	4.00		60.00		
30.00	45.00		Sqm	1	15.00	4.50	4.85	4.68		70.13		
45.00	52.30		Sqm	1	7.30	4.85	5.10	4.98		36.32		
52.30	55.00		Sqm	1	2.70	3.35	3.10	3.23		8.71		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	7.00	6.60	6.80		102.00		
15.00	30.00		Sqm	1	15.00	6.60	6.50	6.55		98.25		
30.00	45.00		Sqm	1	15.00	6.50	6.45	6.48		97.13		
45.00	60.00		Sqm	1	15.00	6.45	6.85	6.65		99.75		
60.00	75.00		Sqm	1	15.00	6.85	6.95	6.90		103.50		
75.00	90.00		Sqm	1	15.00	6.95	6.65	6.80		102.00		
90.00	98.80		Sqm	1	8.80	6.65	4.85	5.75		50.60		
98.80	105.00		Sqm	1	6.20	3.95	4.05	4.00		24.80		
105.00	120.00		Sqm	1	15.00	4.05	4.45	4.25		63.75		
120.00	129.30		Sqm	1	9.30	4.45	4.90	4.68		43.48		
129.30	131.50	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
131.50	138.00		Sqm	1	6.50	5.20	5.15	5.18		33.64		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.30	6.60	6.45		96.75		
15.00	30.00		Sqm	1	15.00	6.60	6.40	6.50		97.50		
30.00	45.00		Sqm	1	15.00	6.40	5.60	6.00		90.00		
45.00	60.00		Sqm	1	15.00	5.60	5.80	5.70		85.50		
60.00	75.00		Sqm	1	15.00	5.80	5.55	5.68		85.13		
75.00	90.00		Sqm	1	15.00	5.55	5.25	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.25	5.60	5.43		81.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
105.00	115.00		Sqm	1	10.00	5.60	5.35	5.48		54.75		
		6th B Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.60	5.25	4.93		73.88		
15.00	30.00		Sqm	1	15.00	5.25	4.50	4.88		73.13		
30.00	45.00		Sqm	1	15.00	4.50	4.90	4.70		70.50		
45.00	60.00		Sqm	1	15.00	4.90	4.80	4.85		72.75		
60.00	75.00		Sqm	1	15.00	4.80	4.70	4.75		71.25		
75.00	90.00		Sqm	1	15.00	4.70	4.50	4.60		69.00		
90.00	105.00		Sqm	1	15.00	4.50	4.50	4.50		67.50		
105.00	118.50		Sqm	1	13.50	4.50	4.60	4.55		61.43		
		6th Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.95	4.85	4.90		73.50		
15.00	30.00		Sqm	1	15.00	4.85	4.80	4.83		72.38		
30.00	45.00		Sqm	1	15.00	4.80	4.50	4.65		69.75		
45.00	60.00		Sqm	1	15.00	4.50	4.45	4.48		67.13		
60.00	75.00		Sqm	1	15.00	4.45	4.10	4.28		64.13		
75.00	89.10		Sqm	1	14.10	4.10	5.00	4.55		64.16		
89.10	90.30	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
90.30	105.00		Sqm	1	14.70	4.65	4.45	4.55		66.89		
105.00	117.10		Sqm	1	12.10	4.45	4.35	4.40		53.24		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
0.00	5.50		Sqm	1	5.50	8.20	5.25	6.73		36.99		
5.50	15.00		Sqm	1	9.50	5.25	4.75	5.00		47.50		
15.00	30.00		Sqm	1	15.00	4.75	4.80	4.78		71.63		
30.00	45.00		Sqm	1	15.00	4.80	4.80	4.80		72.00		
45.00	60.00		Sqm	1	15.00	4.80	5.75	5.28		79.13		
60.00	62.50		Sqm	1	2.50	5.75	5.60	5.68		14.19		
		10th Cross Road,13th main										
		(North To South)										
0.00	5.00		Sqm	1	5.00	8.15	4.65	6.40		32.00		
5.00	15.00		Sqm	1	10.00	4.65	5.05	4.85		48.50		
15.00	30.00		Sqm	1	15.00	5.05	5.00	5.03		75.38		
30.00	32.30		Sqm	1	2.30	5.00	4.00	4.50		10.35		
32.30	38.90		Sqm	1	6.60	5.00	4.75	4.88		32.18		
		9th B Cross, 13th Main Road										
		(North To South)										
0.00	4.30		Sqm	1	4.30	7.30	5.05	6.18		26.55		
4.30	15.00		Sqm	1	10.70	5.05	4.70	4.88		52.16		
15.00	30.00		Sqm	1	15.00	4.70	5.80	5.25		78.75		
30.00	30.60		Sqm	1	0.60	5.80	5.75	5.78		3.47		
30.60	45.00		Sqm	1	14.40	4.35	5.05	4.70		67.68		
45.00	60.00		Sqm	1	15.00	5.05	4.60	4.83		72.38		
60.00	75.00		Sqm	1	15.00	4.60	4.55	4.58		68.63		
75.00	90.00		Sqm	1	15.00	3.40	4.20	3.80		57.00		
90.00	105.00		Sqm	1	15.00	4.20	4.45	4.33		64.88		
105.00	120.00		Sqm	1	15.00	4.45	4.10	4.28		64.13		
120.00	135.00		Sqm	1	15.00	4.10	5.25	4.68		70.13		
135.00	138.10		Sqm	1	3.10	5.25	5.15	5.20		16.12		
		9th A Cross, 13th main										
		(North To South)										
0.00	4.00		Sqm	1	4.00	7.20	5.60	6.40		25.60		
4.00	15.00		Sqm	1	11.00	5.60	5.15	5.38		59.13		
15.00	30.00		Sqm	1	15.00	5.15	4.75	4.95		74.25		
30.00	45.00		Sqm	1	15.00	4.75	4.35	4.55		68.25		
45.00	60.00		Sqm	1	15.00	4.35	4.70	4.53		67.88		
60.00	75.00		Sqm	1	15.00	4.70	5.05	4.88		73.13		
75.00	90.00		Sqm	1	15.00	5.05	4.70	4.88		73.13		
90.00	105.00		Sqm	1	15.00	4.70	3.85	4.28		64.13		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
95.00	110.30		Sqm	1	5.30	3.85	3.80	3.83		20.27		
		Deducation For Asphalt Road										
		Manhole	Sqm	-12	0.44					-5.28		
					(3.14X0.75X0.75)/4=0.44							
			Sqm	-16	0.64					-10.24		
					(3.14X0.9X0.9)/4=0.64							
			Sqm	-9	0.79					-7.11		
					(3.14X1X1)/4=0.79							
			Sqm	-7	1.13					-7.91		
					(3.14X1.2X1.2)/4=1.13							
		Chamber										
			Sqm	-21	0.90	0.70	0.70	0.70		-13.23		
			Sqm	-3	1.00	0.60	0.60	0.60		-1.80		
		Tree Pot	Sqm	-11	0.30	0.35	0.35	0.35		-1.16		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Sqm	1	15.00	5.10	5.95	5.53		82.88		
15.00	27.10		Sqm	1	12.10	5.95	4.70	5.33		64.43		
27.10	30.00		Sqm	1	2.90	6.30	5.95	6.13		17.76		
30.00	45.00		Sqm	1	15.00	5.95	4.95	5.45		81.75		
45.00	60.00		Sqm	1	15.00	4.95	5.75	5.35		80.25		
60.00	75.00		Sqm	1	15.00	5.75	5.80	5.78		86.63		
75.00	90.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
90.00	105.00		Sqm	1	15.00	5.40	5.30	5.35		80.25		
105.00	120.00		Sqm	1	15.00	5.30	5.85	5.58		83.63		
120.00	135.00		Sqm	1	15.00	5.85	6.55	6.20		93.00		
135.00	139.20		Sqm	1	4.20	6.55	6.00	6.28		26.35		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Sqm	1	15.00	7.85	7.00	7.43		111.38		
15.00	30.00		Sqm	1	15.00	7.00	5.95	6.48		97.13		
30.00	38.40		Sqm	1	8.40	5.95	5.60	5.78		48.51		
38.40	45.00		Sqm	1	6.60	7.25	6.85	7.05		46.53		
45.00	60.00		Sqm	1	15.00	6.85	6.10	6.48		97.13		
60.00	75.00		Sqm	1	15.00	6.10	6.55	6.33		94.88		
75.00	90.00		Sqm	1	15.00	6.55	6.70	6.63		99.38		
90.00	105.00		Sqm	1	15.00	6.70	7.10	6.90		103.50		
105.00	113.00		Sqm	1	8.00	7.10	7.00	7.05		56.40		
113.00	120.00		Sqm	1	7.00	5.05	5.00	5.03		35.18		
120.00	126.20		Sqm	1	6.20	5.00	5.10	5.05		31.31		
126.20	130.50		Sqm	1	4.30	5.95	6.00	5.98		25.69		
130.50	135.00		Sqm	1	4.50	6.00	6.15	6.08		27.34		
135.00	150.00		Sqm	1	15.00	6.15	6.80	6.48		97.13		
150.00	165.00		Sqm	1	15.00	6.80	6.75	6.78		101.63		
165.00	165.40		Sqm	1	0.40	6.75	6.80	6.78		2.71		
165.40	180.00		Sqm	1	14.60	6.30	6.35	6.33		92.35		
180.00	195.00		Sqm	1	15.00	6.35	6.00	6.18		92.63		
195.00	210.00		Sqm	1	15.00	6.00	5.90	5.95		89.25		
210.00	225.00		Sqm	1	15.00	5.90	6.20	6.05		90.75		
225.00	240.00		Sqm	1	15.00	6.20	5.75	5.98		89.63		
240.00	249.30		Sqm	1	9.30	5.75	6.00	5.88		54.64		
249.30	258.30		Sqm	1	9.00	5.10	4.65	4.88		43.88		
258.30	273.30		Sqm	1	15.00	5.45	5.25	5.35		80.25		
273.30	275.00		Sqm	1	1.70	5.25	5.25	5.25		8.92		
273.30	284.00		Sqm	1	10.70	5.25	5.75	5.50		58.85		
		1st Cross Road										
		(From North To South)										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	15.00		Sqm	1	15.00	6.40	5.90	6.15		92.25		
15.00	25.90		Sqm	1	10.90	5.90	6.00	5.95		64.86		
25.90	40.00		Sqm	1	14.10	7.15	5.95	6.55		92.36		
40.00	50.00		Sqm	1	10.00	5.95	5.20	5.58		55.75		
50.00	60.00		Sqm	1	10.00	5.20	4.35	4.78		47.75		
60.00	75.00		Sqm	1	15.00	4.35	4.00	4.18		62.63		
75.00	90.00		Sqm	1	15.00	4.00	4.95	4.48		67.13		
90.00	105.00		Sqm	1	15.00	4.95	4.05	4.50		67.50		
105.00	120.00		Sqm	1	15.00	4.05	4.25	4.15		62.25		
120.00	135.00		Sqm	1	15.00	4.25	5.00	4.63		69.38		
135.00	148.80		Sqm	1	13.80	5.00	4.95	4.98		68.66		
		Balaji Layout										
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
0.00	12.80		Sqm	1	12.80	1.60	1.45	1.53		19.52		
12.80	15.00		Sqm	1	2.20	3.15	3.20	3.18		6.99		
15.00	30.00		Sqm	1	15.00	3.20	3.65	3.43		51.38		
30.00	45.00		Sqm	1	15.00	3.65	4.35	4.00		60.00		
45.00	54.20		Sqm	1	9.20	4.35	3.40	3.88		35.65		
54.20	55.80	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
55.80	60.00		Sqm	1	4.20	3.55	5.40	4.48		18.80		
60.00	75.00		Sqm	1	15.00	5.40	5.30	5.35		80.25		
75.00	89.00		Sqm	1	14.00	5.30	5.45	5.38		75.25		
89.00	90.00		Sqm	1	1.00	6.40	6.55	6.48		6.48		
90.00	105.00		Sqm	1	15.00	6.55	6.60	6.58		98.63		
105.00	120.00		Sqm	1	15.00	6.60	6.35	6.48		97.13		
120.00	135.00		Sqm	1	15.00	6.35	5.95	6.15		92.25		
135.00	150.00		Sqm	1	15.00	5.95	6.60	6.28		94.13		
150.00	165.00		Sqm	1	15.00	6.60	6.60	6.60		99.00		
165.00	180.00		Sqm	1	15.00	6.60	6.85	6.73		100.88		
180.00	195.00		Sqm	1	15.00	6.85	6.60	6.73		100.88		
195.00	210.00		Sqm	1	15.00	6.60	6.35	6.48		97.13		
210.00	225.00		Sqm	1	15.00	6.35	5.90	6.13		91.88		
225.00	228.20		Sqm	1	3.20	5.90	5.90	5.90		18.88		
228.20	232.00		Sqm	1	3.80	7.10	6.20	6.65		25.27		
232.00	245.20		Sqm	1	13.20	6.20	6.25	6.23		82.17		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
0.00	15.00		Sqm	1	15.00	6.30	5.40	5.85		87.75		
15.00	30.00		Sqm	1	15.00	5.40	4.60	5.00		75.00		
30.00	31.70		Sqm	1	1.70	4.60	4.30	4.45		7.57		
31.70	43.60		Sqm	1	11.90	5.20	4.30	4.75		56.53		
		(From West To East)										
0.00	3.90		Sqm	1	3.90	5.40	5.60	5.50		21.45		
3.90	11.10		Sqm	1	7.20	4.20	3.80	4.00		28.80		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	4.20	3.80	4.00		60.00		
15.00	18.80		Sqm	1	3.80	3.80	3.30	3.55		13.49		
18.80	30.00		Sqm	1	11.20	3.30	3.90	3.60		40.32		
30.00	45.00		Sqm	1	15.00	3.90	3.85	3.88		58.13		
45.00	60.00		Sqm	1	15.00	3.85	4.10	3.98		59.63		
60.00	75.00		Sqm	1	15.00	4.10	4.20	4.15		62.25		
75.00	83.40		Sqm	1	8.40	4.20	3.10	3.65		30.66		
83.40	91.90		Sqm	1	8.50	3.10	3.10	3.10		26.35		
91.90	105.00		Sqm	1	13.10	3.10	4.00	3.55		46.51		
105.00	120.00		Sqm	1	15.00	4.00	4.00	4.00		60.00		
120.00	135.00		Sqm	1	15.00	4.00	4.20	4.10		61.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
35.00	150.00		Sqm	1	15.00	4.20	4.10	4.15		62.25		
150.00	163.10		Sqm	1	13.10	4.10	3.60	3.85		50.44		
		6th A Cross Road										
		(From West to East)										
0.00	7.80		Sqm	1	7.80	11.20	8.60	9.90		77.22		
		(From South to North)										
0.00	7.40		Sqm	1	7.40	7.80	6.90	7.35		54.39		
7.40	15.00		Sqm	1	7.60	6.90	5.20	6.05		45.98		
15.00	30.00		Sqm	1	15.00	5.20	5.10	5.15		77.25		
30.00	45.00		Sqm	1	15.00	5.10	4.70	4.90		73.50		
45.00	50.70		Sqm	1	5.70	4.70	4.70	4.70		26.79		
50.70	60.00		Sqm	1	9.30	4.70	5.00	4.85		45.11		
60.00	75.00		Sqm	1	15.00	5.00	6.10	5.55		83.25		
75.00	90.00		Sqm	1	15.00	6.10	5.50	5.80		87.00		
90.00	105.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
105.00	120.00		Sqm	1	15.00	6.00	5.70	5.85		87.75		
120.00	135.00		Sqm	1	15.00	5.70	5.90	5.80		87.00		
135.00	141.70		Sqm	1	6.70	5.90	5.25	5.58		37.35		
		Devi Nagar Main Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.10	6.50	5.80		87.00		
15.00	30.00		Sqm	1	15.00	6.50	6.10	6.30		94.50		
30.00	45.00		Sqm	1	15.00	6.10	6.40	6.25		93.75		
45.00	60.00		Sqm	1	15.00	6.40	6.50	6.45		96.75		
60.00	75.00		Sqm	1	15.00	6.50	6.90	6.70		100.50		
75.00	90.00		Sqm	1	15.00	6.90	6.60	6.75		101.25		
90.00	105.00		Sqm	1	15.00	6.60	7.35	6.98		104.63		
105.00	120.00		Sqm	1	15.00	7.35	7.00	7.18		107.63		
120.00	135.00		Sqm	1	15.00	7.00	7.00	7.00		105.00		
135.00	150.00		Sqm	1	15.00	7.00	5.20	6.10		91.50		
150.00	165.00		Sqm	1	15.00	5.20	6.00	5.60		84.00		
165.00	180.00		Sqm	1	15.00	6.00	4.90	5.45		81.75		
180.00	195.00		Sqm	1	15.00	4.90	6.30	5.60		84.00		
195.00	210.00		Sqm	1	15.00	6.30	5.60	5.95		89.25		
210.00	225.00		Sqm	1	15.00	5.60	7.50	6.55		98.25		
225.00	237.20		Sqm	1	12.20	7.50	7.00	7.25		88.45		
237.20	239.00		Sqm	1	1.80	7.00	8.00	7.50		13.50		
239.00	241.50		Sqm	1	2.50	8.00	12.00	10.00		25.00		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Sqm	1	3.20	5.20	4.40	4.80		15.36		
3.20	15.00		Sqm	1	11.80	5.70	5.60	5.65		66.67		
15.00	30.00		Sqm	1	15.00	5.60	5.25	5.43		81.38		
30.00	45.00		Sqm	1	15.00	5.25	4.50	4.88		73.13		
45.00	60.00		Sqm	1	15.00	4.50	4.10	4.30		64.50		
60.00	75.00		Sqm	1	15.00	4.10	5.30	4.70		70.50		
75.00	90.00		Sqm	1	15.00	5.30	4.50	4.90		73.50		
90.00	105.00		Sqm	1	15.00	4.50	5.25	4.88		73.13		
105.00	120.00		Sqm	1	15.00	5.25	5.40	5.33		79.88		
120.00	135.00		Sqm	1	15.00	5.40	4.70	5.05		75.75		
135.00	150.00		Sqm	1	15.00	4.70	4.60	4.65		69.75		
150.00	165.00		Sqm	1	15.00	4.60	5.10	4.85		72.75		
165.00	180.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
180.00	184.70		Sqm	1	4.70	5.00	5.10	5.05		23.73		
184.70	186.20		Sqm	1	1.50	5.10	5.10	5.10		7.65		
186.20	195.00		Sqm	1	8.80	5.10	5.30	5.20		45.76		
195.00	210.00		Sqm	1	15.00	5.30	4.45	4.88		73.13		
210.00	225.00		Sqm	1	15.00	4.45	4.90	4.68		70.13		
225.00	240.00		Sqm	1	15.00	4.90	5.20	5.05		75.75		
240.00	255.00		Sqm	1	15.00	5.20	4.40	4.80		72.00		
255.00	270.00		Sqm	1	15.00	4.40	5.10	4.75		71.25		
270.00	285.00		Sqm	1	15.00	5.10	5.10	5.10		76.50		
285.00	293.70		Sqm	1	8.70	5.10	5.70	5.40		46.98		
293.70	298.70		Sqm	1	5.00	4.90	5.00	4.95		24.75		
298.70	300.00		Sqm	1	1.30	5.80	5.20	5.50		7.15		
300.00	315.00		Sqm	1	15.00	5.20	5.05	5.13		76.88		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
315.00	330.00		Sqm	1	15.00	5.05	4.90	4.98		74.63		
330.00	344.60		Sqm	1	14.60	4.90	3.70	4.30		62.78		
344.60	360.00		Sqm	1	15.40	5.10	4.90	5.00		77.00		
360.00	363.50		Sqm	1	3.50	4.90	4.90	4.90		17.15		
363.50	372.30		Sqm	1	8.80	4.30	4.90	4.60		40.48		
372.30	387.30		Sqm	1	15.00	3.90	4.15	4.03		60.38		
387.30	390.00		Sqm	1	2.70	4.15	5.05	4.60		12.42		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.70	5.00	5.35		80.25		
15.00	29.50		Sqm	1	14.50	5.00	5.20	5.10		73.95		
29.50	47.20	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
47.20	60.00		Sqm	1	12.80	4.90	4.95	4.93		63.04		
60.00	75.00		Sqm	1	15.00	4.95	5.80	5.38		80.63		
75.00	90.00		Sqm	1	15.00	5.80	6.20	6.00		90.00		
90.00	105.00		Sqm	1	15.00	6.20	6.60	6.40		96.00		
105.00	120.00		Sqm	1	15.00	6.60	6.80	6.70		100.50		
120.00	135.00		Sqm	1	15.00	6.80	7.50	7.15		107.25		
135.00	150.30		Sqm	1	15.30	7.50	8.60	8.05		123.17		
150.30	158.50		Sqm	1	8.20	8.60	8.60	8.60		70.52		
158.50	165.30		Sqm	1	6.80	8.60	7.30	7.95		54.06		
165.30	180.30		Sqm	1	15.00	7.30	6.80	7.05		105.75		
180.30	189.60		Sqm	1	9.30	6.80	8.10	7.45		69.28		
189.60	193.50		Sqm	1	3.90	8.10	9.60	8.85		34.52		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Sqm	1	4.00	6.30	6.25	6.28		25.10		
4.00	15.00		Sqm	1	11.00	6.25	6.60	6.43		70.68		
15.00	24.10		Sqm	1	9.10	6.60	6.40	6.50		59.15		
24.10	30.00		Sqm	1	5.90	5.50	5.10	5.30		31.27		
30.00	38.10		Sqm	1	8.10	5.10	4.50	4.80		38.88		
38.10	46.00		Sqm	1	7.90	5.20	5.80	5.50		43.45		
46.00	60.00		Sqm	1	14.00	4.70	6.50	5.60		78.40		
60.00	67.00		Sqm	1	7.00	6.50	7.70	7.10		49.70		
67.00	75.00		Sqm	1	8.00	7.70	5.90	6.80		54.40		
75.00	83.50		Sqm	1	8.50	5.90	5.70	5.80		49.30		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.60	5.50	5.55		83.25		
15.00	30.00		Sqm	1	15.00	5.50	5.90	5.70		85.50		
30.00	45.00		Sqm	1	15.00	5.90	5.90	5.90		88.50		
45.00	60.00		Sqm	1	15.00	6.60	6.55	6.58		98.63		
60.00	75.00		Sqm	1	15.00	6.55	5.60	6.08		91.13		
75.00	87.00		Sqm	1	12.00	5.60	6.10	5.85		70.20		
87.00	90.00		Sqm	1	3.00	6.10	5.80	5.95		17.85		
90.00	105.00		Sqm	1	15.00	5.80	5.90	5.85		87.75		
105.00	120.00		Sqm	1	15.00	5.90	5.20	5.55		83.25		
120.00	129.20		Sqm	1	9.20	5.20	5.70	5.45		50.14		
129.20	135.00		Sqm	1	5.80	5.70	5.70	5.70		33.06		
135.00	150.00		Sqm	1	15.00	5.70	5.70	5.70		85.50		
150.00	165.00		Sqm	1	15.00	5.70	5.50	5.60		84.00		
165.00	180.00		Sqm	1	15.00	5.50	5.20	5.35		80.25		
180.00	195.00		Sqm	1	15.00	5.20	4.00	4.60		69.00		
195.00	210.00		Sqm	1	15.00	4.00	4.15	4.08		61.13		
210.00	221.50		Sqm	1	11.50	4.15	4.50	4.33		49.74		
		1st Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.00	4.20	4.10		61.50		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
5.00	17.10		Sqm	1	2.10	4.20	4.40	4.30		9.03		
17.10	22.80		Sqm	1	5.70	3.50	3.50	3.50		19.95		
22.80	30.00		Sqm	1	7.20	2.80	2.60	2.70		19.44		
30.00	45.00		Sqm	1	15.00	2.60	2.40	2.50		37.50		
45.00	54.00		Sqm	1	9.00	2.40	2.80	2.60		23.40		
54.00	60.00		Sqm	1	6.00	2.80	2.60	2.70		16.20		
60.00	75.00		Sqm	1	15.00	2.60	3.00	2.80		42.00		
75.00	85.20		Sqm	1	10.20	3.00	3.00	3.00		30.60		
		2nd Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.10	3.40	3.75		56.25		
15.00	30.00		Sqm	1	15.00	3.40	3.90	3.65		54.75		
30.00	45.00		Sqm	1	15.00	3.90	4.00	3.95		59.25		
45.00	60.00		Sqm	1	15.00	4.00	3.30	3.65		54.75		
60.00	75.00		Sqm	1	15.00	3.30	2.50	2.90		43.50		
75.00	82.10		Sqm	1	7.10	2.50	2.60	2.55		18.11		
		2nd A Cross Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	5.20	4.50	4.85		72.75		
15.00	30.00		Sqm	1	15.00	4.50	4.65	4.58		68.63		
30.00	44.90		Sqm	1	14.90	4.65	3.30	3.98		59.23		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Sqm	1	4.20	4.20	4.20	4.20		17.64		
4.20	15.00		Sqm	1	10.80	4.20	4.30	4.25		45.90		
15.00	30.00		Sqm	1	15.00	4.30	4.10	4.20		63.00		
30.00	45.00		Sqm	1	15.00	4.10	4.15	4.13		61.88		
45.00	52.20		Sqm	1	7.20	4.15	4.20	4.18		30.06		
52.20	60.00		Sqm	1	7.80	2.60	2.35	2.48		19.31		
60.00	67.30		Sqm	1	7.30	2.50	2.50	2.50		18.25		
67.30	70.60		Sqm	1	3.30	2.50	3.30	2.90		9.57		
70.60	85.00		Sqm	1	14.40	3.60	3.45	3.53		50.76		
85.00	90.00		Sqm	1	5.00	3.45	3.50	3.48		17.38		
90.00	92.10		Sqm	1	2.10	3.50	3.40	3.45		7.24		
92.10	95.30	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
95.30	105.00		Sqm	1	9.70	4.00	4.10	4.05		39.29		
105.00	108.90		Sqm	1	3.90	4.00	4.10	4.05		15.80		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	6.15	6.15	6.15		92.25		
15.00	30.00		Sqm	1	15.00	5.40	5.50	5.45		81.75		
30.00	45.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
45.00	47.80		Sqm	1	2.80	6.00	6.10	6.05		16.94		
47.80	56.10		Sqm	1	8.30	5.30	5.00	5.15		42.75		
56.10	63.90		Sqm	1	7.80	5.85	4.90	5.38		41.93		
63.90	65.50	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
65.50	75.00		Sqm	1	9.50	5.65	5.65	5.65		53.68		
75.00	90.00		Sqm	1	15.00	5.65	4.60	5.13		76.88		
90.00	94.50		Sqm	1	4.50	4.60	6.05	5.33		23.96		
94.50	105.00		Sqm	1	10.50	6.05	6.70	6.38		66.94		
105.00	120.00		Sqm	1	15.00	6.70	6.15	6.43		96 38		
120.00	122.00		Sqm	1	2.00	6.15	5.15	5.65		11.30		
122.00	135.00		Sqm	1	13.00	5.65	5.45	5.55		72.15		
135.00	150.00		Sqm	1	15.00	5.45	4.80	5.13		76.88		
150.00	154.00		Sqm	1	4.00	4.80	6.50	5.65		22.60		
154.00	163.70		Sqm	1	9.70	6.50	6.65	6.58		63.78		
163.70	169.70		Sqm	1	6.00	8.10	6.65	7.38		44.25		
169.70	171.20	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
171.20	180.00		Sqm	1	8.80	7.30	7.35	7.33		64.46		
180.00	181.80		Sqm	1	1.80	7.35	6.70	7.03		12.65		
181.80	190.00		Sqm	1	8.20	6.70	7.15	6.93		56.78		
190.00	205.00		Sqm	1	15.00	7.15	7.50	7.33		109.88		
205.00	216.10		Sqm	1	11.10	7.50	8.50	8.00		88.80		
216.10	231.10		Sqm	1	15.00	8.50	7.15	7.83		117.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
231.10	235.00		Sqm	1	3.90	7.15	7.40	7.28		28.37		
235.00	250.00		Sqm	1	15.00	7.40	7.00	7.20		108.00		
250.00	265.00		Sqm	1	15.00	7.00	7.20	7.10		106.50		
265.00	280.00		Sqm	1	15.00	7.20	5.30	6.25		93.75		
280.00	295.00		Sqm	1	15.00	5.30	4.70	5.00		75.00		
295.00	300.00		Sqm	1	5.00	4.70	4.85	4.78		23.88		
300.00	315.00		Sqm	1	15.00	4.85	5.35	5.10		76.50		
315.00	330.00		Sqm	1	15.00	5.35	5.85	5.60		84.00		
330.00	345.00		Sqm	1	15.00	5.85	5.50	5.68		85.13		
345.00	360.00		Sqm	1	15.00	5.50	6.15	5.83		87.38		
360.00	369.00		Sqm	1	9.00	6.15	5.95	6.05		54.45		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	8.40	6.80	7.60		114.00		
15.00	29.20		Sqm	1	14.20	6.80	6.90	6.85		97.27		
29.20	30.30	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
30.30	45.00		Sqm	1	14.70	6.85	6.70	6.78		99.59		
45.00	60.00		Sqm	1	15.00	6.70	6.60	6.65		99.75		
60.00	75.00		Sqm	1	15.00	6.60	6.40	6.50		97.50		
75.00	90.00		Sqm	1	15.00	6.40	5.75	6.08		91.13		
90.00	105.00		Sqm	1	15.00	5.75	6.15	5.95		89.25		
105.00	108.50		Sqm	1	3.50	5.60	5.60	5.60		19.60		
108.50	118.70		Sqm	1	10.20	4.70	4.90	4.80		48.96		
118.70	124.80		Sqm	1	6.10	6.25	6.85	6.55		39.96		
124.80	135.00		Sqm	1	10.20	6.10	5.90	6.00		61.20		
135.00	150.00		Sqm	1	15.00	5.90	6.10	6.00		90.00		
150.00	165.00		Sqm	1	15.00	6.10	6.05	6.08		91.13		
165.00	180.00		Sqm	1	15.00	6.05	6.10	6.08		91.13		
180.00	195.00		Sqm	1	15.00	6.10	6.15	6.13		91.88		
195.00	210.00		Sqm	1	15.00	6.15	6.45	6.30		94.50		
210.00	225.00		Sqm	1	15.00	6.45	6.20	6.33		94.88		
225.00	240.00		Sqm	1	15.00	6.20	6.15	6.18		92.63		
240.00	255.00		Sqm	1	15.00	6.15	6.10	6.13		91.88		
255.00	270.00		Sqm	1	15.00	6.10	6.40	6.25		93.75		
270.00	285.00		Sqm	1	15.00	6.40	7.10	6.75		101.25		
285.00	291.50		Sqm	1	6.50	7.10	7.20	7.15		46.48		
291.50	298.00		Sqm	1	6.50	6.70	5.70	6.20		40.30		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.80	6.70	6.75		101.25		
15.00	17.20		Sqm	1	2.20	6.70	5.80	6.25		13.75		
17.20	30.00		Sqm	1	12.80	5.80	5.10	5.45		69.76		
30.00	41.00		Sqm	1	11.00	5.10	4.90	5.00		55.00		
41.00	50.20		Sqm	1	9.20	4.85	5.40	5.13		47.15		
		2nd Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.30	5.25	5.78		86.63		
15.00	30.00		Sqm	1	15.00	5.25	5.25	5.25		78.75		
30.00	45.00		Sqm	1	15.00	5.25	5.15	5.20		78.00		
45.00	50.20		Sqm	1	5.20	5.15	5.20	5.18		26.91		
50.20	52.80		Sqm	1	2.60	2.40	2.50	2.45		6.37		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	6.40	6.45	6.43		96.38		
15.00	30.00		Sqm	1	15.00	6.45	5.10	5.78		86.63		
30.00	45.00		Sqm	1	15.00	5.10	5.65	5.38		80.63		
45.00	60.00		Sqm	1	15.00	5.65	4.35	5.00		75.00		
60.00	63.30		Sqm	1	3.30	4.35	5.40	4.88		16.09		
63.30	75.00		Sqm	1	11.70	6.30	6.34	6.32		73.94		
75.00	90.00		Sqm	1	15.00	6.34	6.70	6.52		97.80		
90.00	105.00		Sqm	1	15.00	6.70	6.60	6.65		99.75		
105.00	120.00		Sqm	1	15.00	6.60	7.05	6.83		102.38		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
0.00	132.90		Sqm	1	12.90	7.05	7.00	7.03		90.62		
132.90	147.10		Sqm	1	14.20	5.80	5.95	5.88		83.42		
147.10	160.00		Sqm	1	12.90	5.30	5.20	5.25		67.73		
160.00	165.00		Sqm	1	5.00	6.55	6.00	6.28		31.38		
165.00	180.00		Sqm	1	15.00	6.00	6.80	6.40		96.00		
180.00	195.00		Sqm	1	15.00	6.80	6.10	6.45		96.75		
195.00	198.80		Sqm	1	3.80	6.10	6.10	6.10		23.18		
198.80	210.00		Sqm	1	11.20	5.50	5.50	5.50		61.60		
210.00	219.70		Sqm	1	9.70	5.50	5.90	5.70		55.29		
219.70	222.20	Culvert	Sqm	1	0.00	0.00	0.00	0.00		0.00		
222.20	225.00		Sqm	1	2.80	6.85	6.80	6.83		19.11		
225.00	240.00		Sqm	1	15.00	6.80	6.40	6.60		99.00		
240.00	249.60		Sqm	1	9.60	6.40	6.90	6.65		63.84		
249.60	257.30		Sqm	1	7.70	7.60	7.50	7.55		58.14		
257.30	260.00		Sqm	1	2.70	6.35	6.30	6.33		17.08		
260.00	275.00		Sqm	1	15.00	6.30	6.40	6.35		95.25		
275.00	292.00		Sqm	1	17.00	6.40	6.40	6.40		108.80		
292.00	297.10		Sqm	1	5.10	7.20	7.40	7.30		37.23		
297.10	300.00		Sqm	1	2.90	6.40	6.60	6.50		18.85		
300.00	315.00		Sqm	1	15.00	6.60	7.10	6.85		102.75		
315.00	330.00		Sqm	1	15.00	7.10	6.60	6.85		102.75		
330.00	345.00		Sqm	1	15.00	6.60	6.55	6.58		98.63		
345.00	360.00		Sqm	1	15.00	6.55	7.35	6.95		104.25		
360.00	375.00		Sqm	1	15.00	7.35	7.40	7.38		110.63		
375.00	390.00		Sqm	1	15.00	7.40	6.85	7.13		106.88		
390.00	405.00		Sqm	1	15.00	6.85	7.20	7.03		105.38		
405.00	414.50		Sqm	1	9.50	7.20	7.55	7.38		70.06		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Sqm	1	15.00	6.50	6.10	6.30		94.50		
15.00	30.00		Sqm	1	15.00	6.10	7.00	6.55		98.25		
30.00	45.00		Sqm	1	15.00	7.00	5.90	6.45		96.75		
45.00	60.00		Sqm	1	15.00	5.90	6.20	6.05		90.75		
60.00	69.30		Sqm	1	9.30	6.20	5.75	5.98		55.57		
69.30	75.00		Sqm	1	5.70	4.60	4.10	4.35		24.80		
75.00	90.00		Sqm	1	15.00	4.10	5.50	4.80		72.00		
90.00	105.00		Sqm	1	15.00	5.50	5.05	5.28		79.13		
105.00	111.40		Sqm	1	6.40	5.05	7.00	6.03		38.56		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Sqm	1	4.60	6.70	6.80	6.75		31.05		
4.60	15.00		Sqm	1	10.40	6.80	6.30	6.55		68.12		
15.00	30.00		Sqm	1	15.00	6.30	5.75	6.03		90.38		
30.00	45.00		Sqm	1	15.00	5.75	5.00	5.38		80.63		
45.00	60.00		Sqm	1	15.00	5.00	6.25	5.63		84.38		
60.00	75.00		Sqm	1	15.00	6.25	6.10	6.18		92.63		
75.00	90.00		Sqm	1	15.00	6.10	5.80	5.95		89.25		
90.00	100.30		Sqm	1	10.30	5.80	5.80	5.80		59.74		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Sqm	1	15.00	4.20	4.00	4.10		61.50		
15.00	30.00		Sqm	1	15.00	4.00	3.70	3.85		57.75		
30.00	45.00		Sqm	1	15.00	3.70	3.60	3.65		54.75		
45.00	60.00		Sqm	1	15.00	3.60	3.90	3.75		56.25		
60.00	73.50		Sqm	1	13.50	3.90	4.00	3.95		53.33		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Sqm	1	15.00	3.60	3.75	3.68		55.13		
15.00	30.00		Sqm	1	15.00	3.75	4.10	3.93		58.88		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	45.00		Sqm	1	15.00	4.10	3.90	4.00		60.00		
45.00	60.00		Sqm	1	15.00	3.90	4.25	4.08		61.13		
60.00	75.00		Sqm	1	15.00	4.25	4.00	4.13		61.88		
75.00	81.00		Sqm	1	6.00	4.00	4.30	4.15		24.90		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Sqm	1	15.00	5.95	5.85	5.90		88.50		
15.00	30.00		Sqm	1	15.00	5.85	5.60	5.73		85.88		
30.00	45.00		Sqm	1	15.00	5.60	5.15	5.38		80.63		
45.00	60.00		Sqm	1	15.00	5.15	5.55	5.35		80.25		
60.00	75.00		Sqm	1	15.00	5.55	5.80	5.68		85.13		
75.00	90.00		Sqm	1	15.00	5.80	5.90	5.85		87.75		
90.00	95.80		Sqm	1	5.80	5.90	5.50	5.70		33.06		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Sqm	1	15.00	5.80	4.85	5.33		79.88		
15.00	26.20		Sqm	1	11.20	4.85	3.90	4.38		49.00		
		(North To South)										
0.00	15.00		Sqm	1	15.00	5.40	5.60	5.50		82.50		
15.00	30.00		Sqm	1	15.00	5.60	5.45	5.53		82.88		
30.00	45.00		Sqm	1	15.00	5.45	5.95	5.70		85.50		
45.00	60.00		Sqm	1	15.00	5.95	5.80	5.88		88.13		
60.00	75.00		Sqm	1	15.00	5.80	6.80	6.30		94.50		
75.00	90.00		Sqm	1	15.00	6.80	6.00	6.40		96.00		
90.00	105.00		Sqm	1	15.00	6.00	7.20	6.60		99.00		
105.00	120.00		Sqm	1	15.00	7.20	5.80	6.50		97.50		
120.00	135.00		Sqm	1	15.00	5.80	7.00	6.40		96.00		
135.00	150.00		Sqm	1	15.00	7.00	5.70	6.35		95.25		
150.00	165.00		Sqm	1	15.00	5.70	7.20	6.45		96.75		
165.00	169.00		Sqm	1	4.00	7.20	6.90	7.05		28.20		
		Deducation										
		Manhole	Sqm	-16	0.44					-7.07		
					(3.14X0.75X0.75)/4=0.44							
			Sqm	-14	0.64					-8.90		
					(3.14X0.9X0.9)/4=0.64							
			Sqm	-13	0.79					-10.21		
					(3.14X1X1)/4=0.79							
			Sqm	-7	1.13					-7.91		
					(3.14X1.2X1.2)/4=1.13							
		Chamber										
			Sqm	-19	0.90	0.70	0.70	0.70		-11.97		
			Sqm	-3	1.00	0.60	0.60	0.60		-1.80		
		Tree Pot	Sqm	-12	0.30	0.35	0.35	0.35		-1.26		
		Ward No 10										
		Vidyaranyapura Sub division'										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	8.70	5.70	7.20		108.00		
15.00	20.80		Sqm	1	5.80	5.70	5.50	5.60		32.48		
20.80	30.00		Sqm	1	9.20	6.00	6.05	6.03		55.43		
30.00	45.00		Sqm	1	15.00	6.05	5.20	5.63		84.38		
45.00	53.60		Sqm	1	8.60	5.20	5.30	5.25		45.15		
53.60	60.00		Sqm	1	6.40	6.35	5.80	6.08		38.88		
60.00	75.00		Sqm	1	15.00	5.80	5.55	5.68		85.13		
75.00	90.00		Sqm	1	15.00	5.55	5.15	5.35		80.25		
90.00	105.00		Sqm	1	15.00	5.15	5.35	5.25		78.75		
105.00	120.00		Sqm	1	15.00	5.35	4.70	5.03		75.38		
120.00	135.00		Sqm	1	15.00	4.70	4.65	4.68		70.13		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
25.00	150.00		Sqm	1	15.00	4.65	4.70	4.68		70.13		
150.00	165.00		Sqm	1	15.00	4.70	5.15	4.93		73.88		
165.00	180.00		Sqm	1	15.00	5.15	6.10	5.63		84.38		
180.00	195.00		Sqm	1	15.00	6.10	6.35	6.23		93.38		
195.00	203.30		Sqm	1	8.30	6.35	7.00	6.68		55.40		
203.30	205.80		Sqm	1	2.50	7.00	7.80	7.40		18.50		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
0.00	3.10		Sqm	1	3.10	7.50	5.00	6.25		19.38		
3.10	15.00		Sqm	1	11.90	5.00	4.80	4.90		58.31		
15.00	30.00		Sqm	1	15.00	4.80	4.70	4.75		71.25		
30.00	45.00		Sqm	1	15.00	4.70	5.10	4.90		73.50		
45.00	60.00		Sqm	1	15.00	5.10	5.05	5.08		76.13		
60.00	75.00		Sqm	1	15.00	5.05	4.70	4.88		73.13		
75.00	90.00		Sqm	1	15.00	4.70	4.70	4.70		70.50		
90.00	105.00		Sqm	1	15.00	4.70	4.65	4.68		70.13		
105.00	120.00		Sqm	1	15.00	4.65	5.00	4.83		72.38		
120.00	135.00		Sqm	1	15.00	5.00	4.65	4.83		72.38		
135.00	150.00		Sqm	1	15.00	4.65	4.40	4.53		67.88		
150.00	165.00		Sqm	1	15.00	4.40	4.95	4.68		70.13		
165.00	180.00		Sqm	1	15.00	4.95	4.80	4.88		73.13		
180.00	195.00		Sqm	1	15.00	4.80	5.05	4.93		73.88		
195.00	210.00		Sqm	1	15.00	5.05	5.60	5.33		79.88		
210.00	225.00		Sqm	1	15.00	5.60	5.10	5.35		80.25		
225.00	240.00		Sqm	1	15.00	6.70	6.70	6.70		100.50		
240.00	245.30		Sqm	1	5.30	6.70	5.20	5.95		31.54		
245.30	255.00		Sqm	1	9.70	5.20	5.90	5.55		53.83		
255.00	270.00		Sqm	1	15.00	5.90	6.40	6.15		92.25		
270.00	277.40		Sqm	1	7.40	6.40	6.60	6.50		48.10		
277.40	285.00		Sqm	1	7.60	5.70	5.60	5.65		42.94		
285.00	300.00		Sqm	1	15.00	5.60	6.00	5.80		87.00		
300.00	303.00		Sqm	1	3.00	6.00	6.20	6.10		18.30		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.70	5.15	5.43		81.38		
15.00	25.20		Sqm	1	10.20	5.15	5.60	5.38		54.83		
25.20	33.90		Sqm	1	8.70	6.30	6.10	6.20		53.94		
33.90	45.00		Sqm	1	11.10	5.55	5.55	5.55		61.61		
45.00	60.00		Sqm	1	15.00	5.55	6.95	6.25		93.75		
60.00	75.00		Sqm	1	15.00	6.95	6.20	6.58		98.63		
75.00	90.00		Sqm	1	15.00	6.20	5.75	5.98		89.63		
90.00	105.00		Sqm	1	15.00	5.75	5.80	5.78		86.63		
105.00	109.10		Sqm	1	4.10	5.80	5.90	5.85		23.99		
109.10	120.00		Sqm	1	10.90	5.00	5.10	5.05		55.05		
120.00	135.00		Sqm	1	15.00	5.10	4.65	4.88		73.13		
135.00	142.80		Sqm	1	7.80	4.65	5.80	5.23		40.76		
142.80	150.00		Sqm	1	7.20	4.90	4.35	4.63		33.30		
150.00	154.80		Sqm	1	4.80	4.35	4.35	4.35		20.88		
154.80	165.00		Sqm	1	10.20	5.60	6.15	5.88		59.92		
165.00	172.80		Sqm	1	7.80	6.15	5.90	6.03		47.00		
172.80	180.00		Sqm	1	7.20	4.90	4.50	4.70		33.84		
180.00	181.40		Sqm	1	1.40	4.50	4.45	4.48		6.27		
181.40	195.00		Sqm	1	13.60	5.65	5.00	5.33		72.42		
195.00	209.40		Sqm	1	14.40	5.00	4.60	4.80		69.12		
209.40	221.00		Sqm	1	11.60	5.85	6.40	6.13		71.05		
		Samashana Road										
		2nd main Road										
		(From East to West)										
0.00	11.80		Sqm	1	11.80	4.25	3.95	4.10		48.38		
11.80	15.00		Sqm	1	3.20	4.45	5.40	4.93		15.76		
15.00	30.00		Sqm	1	15.00	5.40	5.80	5.60		84.00		
30.00	45.00		Sqm	1	15.00	5.80	5.80	5.80		87.00		
45.00	60.00		Sqm	1	15.00	5.80	5.20	5.50		82.50		
60.00	75.00		Sqm	1	15.00	5.20	5.55	5.38		80.63		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00		Sqm	1	15.00	5.55	5.05	5.30		79.50		
90.00	105.00		Sqm	1	15.00	5.05	6.10	5.58		83.63		
105.00	120.00		Sqm	1	15.00	6.10	5.60	5.85		87.75		
120.00	135.00		Sqm	1	15.00	5.60	6.35	5.98		89.63		
135.00	140.50		Sqm	1	5.50	6.35	6.80	6.58		36.16		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
0.00	15.50		Sqm	1	15.50	5.40	6.75	6.08		94.16		
15.50	30.00		Sqm	1	14.50	5.40	5.75	5.58		80.84		
30.00	45.00		Sqm	1	15.00	5.75	5.70	5.73		85.88		
45.00	46.40		Sqm	1	1.40	5.70	6.00	5.85		8.19		
46.40	60.00		Sqm	1	13.60	4.70	5.30	5.00		68.00		
60.00	75.00		Sqm	1	15.00	6.15	5.00	5.58		83.63		
75.00	90.00		Sqm	1	15.00	5.00	5.20	5.10		76.50		
90.00	105.10		Sqm	1	15.10	5.20	5.00	5.10		77.01		
105.10	120.00		Sqm	1	14.90	5.85	5.85	5.85		87.17		
120.00	126.50		Sqm	1	6.50	5.85	5.70	5.78		37.54		
126.50	135.00		Sqm	1	8.50	5.40	5.95	5.68		48.24		
135.00	141.90		Sqm	1	6.90	5.95	6.20	6.08		41.92		
141.90	150.00		Sqm	1	8.10	6.60	6.30	6.45		52.25		
150.00	154.10		Sqm	1	4.10	6.30	6.40	6.35		26.04		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
0.00	15.60		Sqm	1	15.60	5.60	5.70	5.65		88.14		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Sqm	1	1.60	3.20	5.80	4.50		7.20		
1.60	15.00		Sqm	1	13.40	5.80	5.00	5.40		72.36		
15.00	30.00		Sqm	1	15.00	5.00	5.75	5.38		80.63		
30.00	45.00		Sqm	1	15.00	5.75	6.30	6.03		90.38		
45.00	60.00		Sqm	1	15.00	6.30	5.90	6.10		91.50		
60.00	75.00		Sqm	1	15.00	5.90	6.10	6.00		90.00		
75.00	79.10		Sqm	1	4.10	6.10	5.95	6.03		24.70		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	6.40	6.60	6.50		97.50		
15.00	23.30		Sqm	1	8.30	6.60	6.70	6.65		55.20		
		From house no #15 to house no -7										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.50	6.00	5.75		86.25		
15.00	30.00		Sqm	1	15.00	6.00	6.10	6.05		90.75		
30.00	45.00		Sqm	1	15.00	6.10	5.50	5.80		87.00		
45.00	60.00		Sqm	1	15.00	5.50	6.80	6.15		92.25		
60.00	75.00		Sqm	1	15.00	6.80	5.90	6.35		95.25		
75.00	79.00		Sqm	1	4.00	5.90	5.65	5.78		23.10		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.00	5.90	5.95		89.25		
15.00	29.60		Sqm	1	14.60	5.90	4.00	4.95		72.27		
29.60	38.70		Sqm	1	9.10	5.10	4.20	4.65		42.32		
38.70	45.00		Sqm	1	6.30	5.60	5.95	5.78		36.38		
45.00	60.00		Sqm	1	15.00	5.95	5.65	5.80		87.00		
60.00	75.00		Sqm	1	15.00	5.65	5.10	5.38		80.63		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
5.00	84.00		Sqm	1	9.00	6.05	5.80	5.93		53.33		
84.00	90.00		Sqm	1	6.00	4.50	4.65	4.58		27.45		
90.00	103.00		Sqm	1	13.00	4.65	5.85	5.25		68.25		
103.00	105.00		Sqm	1	2.00	6.50	6.50	6.50		13.00		
105.00	120.00		Sqm	1	15.00	6.50	5.15	5.83		87.38		
120.00	135.00		Sqm	1	15.00	5.15	4.75	4.95		74.25		
135.00	150.00		Sqm	1	15.00	4.75	5.40	5.08		76.13		
150.00	153.30		Sqm	1	3.30	5.40	5.50	5.45		17.99		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.10	5.00	5.55		83.25		
15.00	30.00		Sqm	1	15.00	5.00	4.70	4.85		72.75		
30.00	45.00		Sqm	1	15.00	4.70	5.45	5.08		76.13		
45.00	47.30		Sqm	1	2.30	5.45	5.50	5.48		12.59		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
0.00	15.00		Sqm	1	15.00	5.45	3.50	4.48		67.13		
15.00	30.00		Sqm	1	15.00	3.50	4.95	4.23		63.38		
30.00	45.00		Sqm	1	15.00	4.95	4.95	4.95		74.25		
45.00	60.00		Sqm	1	15.00	4.95	4.40	4.68		70.13		
60.00	75.00		Sqm	1	15.00	4.40	4.70	4.55		68.25		
75.00	90.00		Sqm	1	15.00	4.70	4.90	4.80		72.00		
90.00	105.00		Sqm	1	15.00	4.90	4.80	4.85		72.75		
105.00	112.00		Sqm	1	7.00	4.80	5.10	4.95		34.65		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
0.00	15.00		Sqm	1	15.00	4.95	4.50	4.73		70.88		
15.00	30.00		Sqm	1	15.00	4.50	4.00	4.25		63.75		
30.00	45.00		Sqm	1	15.00	4.00	3.75	3.88		58.13		
45.00	50.10		Sqm	1	5.10	3.75	3.60	3.68		18.74		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.30	5.25	5.78		86.63		
15.00	30.00		Sqm	1	15.00	5.25	5.20	5.23		78.38		
30.00	45.00		Sqm	1	15.00	5.20	5.45	5.33		79.88		
45.00	60.00		Sqm	1	15.00	5.45	5.10	5.28		79.13		
60.00	75.10		Sqm	1	15.10	5.10	5.80	5.45		82.30		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
0.00	15.00		Sqm	1	15.00	6.40	6.45	6.43		96.38		
15.00	30.00		Sqm	1	15.00	6.45	6.00	6.23		93.38		
30.00	34.30		Sqm	1	4.30	6.00	6.10	6.05		26.02		
34.30	45.00		Sqm	1	10.70	5.15	5.70	5.43		58.05		
45.00	60.00		Sqm	1	15.00	5.70	5.75	5.73		85.88		
60.00	75.00		Sqm	1	15.00	5.75	5.50	5.63		84.38		
75.00	90.00		Sqm	1	15.00	5.50	5.65	5.58		83.63		
90.00	105.00		Sqm	1	15.00	5.65	5.50	5.58		83.63		
105.00	120.00		Sqm	1	15.00	5.50	5.40	5.45		81.75		
120.00	135.00		Sqm	1	15.00	5.40	5.25	5.33		79.88		
135.00	150.00		Sqm	1	15.00	5.25	5.05	5.15		77.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0.00	165.00		Sqm	1	15.00	5.05	5.10	5.08		76.13		
165.00	180.00		Sqm	1	15.00	5.10	5.10	5.10		76.50		
180.00	187.20		Sqm	1	7.20	5.10	5.10	5.10		36.72		
187.20	195.00		Sqm	1	7.80	5.45	6.10	5.78		45.05		
195.00	210.00		Sqm	1	15.00	6.10	7.20	6.65		99.75		
210.00	215.40		Sqm	1	5.40	7.20	7.25	7.23		39.02		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.65	5.90	5.78		86.63		
15.00	30.00		Sqm	1	15.00	5.90	5.85	5.88		88.13		
30.00	32.30		Sqm	1	2.30	5.85	5.25	5.55		12.77		
32.30	36.20		Sqm	1	3.90	5.75	5.75	5.75		22.43		
36.20	44.00		Sqm	1	7.80	4.85	4.60	4.73		36.86		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	1.10		Sqm	1	1.10	3.70	4.95	4.33		4.76		
1.10	15.00		Sqm	1	13.90	4.95	5.85	5.40		75.06		
15.00	30.00		Sqm	1	15.00	5.85	5.60	5.73		85.88		
30.00	45.00		Sqm	1	15.00	5.60	6.05	5.83		87.38		
45.00	60.00		Sqm	1	15.00	6.05	5.60	5.83		87.38		
60.00	75.00		Sqm	1	15.00	5.60	5.75	5.68		85.13		
75.00	90.00		Sqm	1	15.00	5.75	5.40	5.58		83.63		
90.00	105.00		Sqm	1	15.00	5.40	5.50	5.45		81.75		
105.00	119.50		Sqm	1	14.50	5.50	5.50	5.50		79.75		
119.50	120.80		Sqm	1	1.30	5.50	7.45	6.48		8.42		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
0.00	2.90		Sqm	1	2.90	6.75	5.65	6.20		17.98		
2.90	15.00		Sqm	1	12.10	5.65	5.10	5.38		65.04		
15.00	30.00		Sqm	1	15.00	5.10	4.75	4.93		73.88		
30.00	45.00		Sqm	1	15.00	4.75	5.50	5.13		76.88		
45.00	60.00		Sqm	1	15.00	5.50	5.10	5.30		79.50		
60.00	75.00		Sqm	1	15.00	5.10	5.60	5.35		80.25		
75.00	90.00		Sqm	1	15.00	5.60	5.20	5.40		81.00		
90.00	105.00		Sqm	1	15.00	5.20	5.45	5.33		79.88		
105.00	120.00		Sqm	1	15.00	5.45	5.20	5.33		79.88		
120.00	135.00		Sqm	1	15.00	5.20	5.95	5.58		83.63		
135.00	150.00		Sqm	1	15.00	5.95	5.75	5.85		87.75		
150.00	163.70		Sqm	1	13.70	5.75	5.40	5.58		76.38		
163.70	165.00		Sqm	1	1.30	4.85	5.00	4.93		6.40		
165.00	180.00		Sqm	1	15.00	5.00	5.00	5.00		75.00		
180.00	195.00		Sqm	1	15.00	5.00	5.00	5.00		75.00		
195.00	200.20		Sqm	1	5.20	5.00	5.50	5.25		27.30		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
0.00	1.80		Sqm	1	1.80	7.60	5.90	6.75		12.15		
1.80	15.00		Sqm	1	13.20	5.90	5.10	5.50		72.60		
15.00	30.00		Sqm	1	15.00	5.10	5.00	5.05		75.75		
30.00	45.00		Sqm	1	15.00	5.00	5.60	5.30		79.50		
45.00	60.00		Sqm	1	15.00	5.60	5.30	5.45		81.75		
60.00	65.50		Sqm	1	5.50	5.30	5.20	5.25		28.88		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
0.00	2.00		Sqm	1	2.00	6.80	5.60	6.20		12.40		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	15.00		Sqm	1	13.00	5.60	5.80	5.70		74.10		
15.00	30.00		Sqm	1	15.00	5.80	5.50	5.65		84.75		
30.00	45.00		Sqm	1	15.00	5.50	5.80	5.65		84.75		
45.00	60.00		Sqm	1	15.00	5.80	5.40	5.60		84.00		
60.00	75.00		Sqm	1	15.00	5.40	5.50	5.45		81.75		
75.00	90.00		Sqm	1	15.00	5.50	5.45	5.48		82.13		
90.00	105.00		Sqm	1	15.00	5.45	5.45	5.45		81.75		
105.00	120.00		Sqm	1	15.00	5.45	5.30	5.38		80.63		
120.00	127.60		Sqm	1	7.60	5.30	5.80	5.55		42.18		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
0.00	3.20		Sqm	1	3.20	6.20	5.15	5.68		18.16		
3.20	15.00		Sqm	1	11.80	5.15	6.00	5.58		65.79		
15.00	30.00		Sqm	1	15.00	6.00	5.20	5.60		84.00		
30.00	45.00		Sqm	1	15.00	5.20	5.50	5.35		80.25		
45.00	60.00		Sqm	1	15.00	5.50	5.30	5.40		81.00		
60.00	75.00		Sqm	1	15.00	5.30	5.50	5.40		81.00		
75.00	90.00		Sqm	1	15.00	5.50	5.85	5.68		85.13		
90.00	105.00		Sqm	1	15.00	5.85	4.90	5.38		80.63		
105.00	120.00		Sqm	1	15.00	4.90	5.50	5.20		78.00		
120.00	128.30		Sqm	1	8.30	5.50	5.60	5.55		46.07		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
0.00	2.60		Sqm	1	2.60	5.75	6.00	5.88		15.28		
2.60	15.00		Sqm	1	12.40	6.00	5.80	5.90		73.16		
15.00	30.00		Sqm	1	15.00	5.80	4.90	5.35		80.25		
30.00	45.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
45.00	60.00		Sqm	1	15.00	5.00	6.00	5.50		82.50		
60.00	75.00		Sqm	1	15.00	6.00	5.90	5.95		89.25		
75.00	80.80		Sqm	1	5.80	5.90	6.00	5.95		34.51		
80.80	83.40		Sqm	1	2.60	6.00	6.30	6.15		15.99		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
0.00	4.00		Sqm	1	4.00	6.35	6.30	6.33		25.30		
4.00	15.00		Sqm	1	11.00	6.30	6.65	6.48		71.23		
15.00	30.00		Sqm	1	15.00	6.65	6.40	6.53		97.88		
30.00	45.00		Sqm	1	15.00	6.40	6.65	6.53		97.88		
45.00	60.00		Sqm	1	15.00	6.65	6.70	6.68		100.13		
60.00	75.00		Sqm	1	15.00	6.70	6.70	6.70		100.50		
75.00	90.00		Sqm	1	15.00	6.70	6.20	6.45		96.75		
90.00	105.00		Sqm	1	15.00	6.20	6.75	6.48		97.13		
105.00	120.00		Sqm	1	15.00	6.75	5.80	6.28		94.13		
120.00	135.00		Sqm	1	15.00	5.80	5.15	5.48		82.13		
135.00	150.00		Sqm	1	15.00	5.15	6.40	5.78		86.63		
150.00	165.00		Sqm	1	15.00	6.40	6.40	6.40		96.00		
165.00	180.00		Sqm	1	15.00	6.40	5.80	6.10		91.50		
180.00	195.00		Sqm	1	15.00	5.80	6.30	6.05		90.75		
195.00	210.00		Sqm	1	15.00	6.30	6.75	6.53		97.88		
210.00	225.00		Sqm	1	15.00	6.75	5.80	6.28		94.13		
225.00	240.00		Sqm	1	15.00	5.80	6.45	6.13		91.88		
240.00	255.00		Sqm	1	15.00	6.45	5.90	6.18		92.63		
255.00	270.00		Sqm	1	15.00	5.90	6.00	5.95		89.25		
270.00	285.00		Sqm	1	15.00	6.00	4.80	5.40		81.00		
285.00	300.40		Sqm	1	15.40	4.80	4.45	4.63		71.22		
		S.L.V Kaveri House										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	6.35	6.30	6.33		94.88		
15.00	30.00		Sqm	1	15.00	6.30	6.10	6.20		93.00		
30.00	45.00		Sqm	1	15.00	6.10	5.85	5.98		89.63		
45.00	60.00		Sqm	1	15.00	5.85	5.50	5.68		85.13		
60.00	75.00		Sqm	1	15.00	5.50	6.60	6.05		90.75		
75.00	90.00		Sqm	1	15.00	6.60	6.30	6.45		96.75		
90.00	101.20		Sqm	1	11.20	6.30	6.65	6.48		72.52		
101.20	104.80		Sqm	1	3.60	5.95	5.95	5.95		21.42		
104.80	120.00		Sqm	1	15.20	6.60	6.50	6.55		99.56		
120.00	132.60		Sqm	1	12.60	6.50	6.80	6.65		83.79		
132.60	136.60		Sqm	1	4.00	7.85	8.20	8.03		32.10		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Sqm	1	3.70	5.45	5.50	5.48		20.26		
3.70	5.50	Culvert	Sqm	1	1.80	0.00	0.00	0.00		0.00		
5.50	15.00		Sqm	1	9.50	5.45	5.05	5.25		49.88		
15.00	30.00		Sqm	1	15.00	5.05	5.35	5.20		78.00		
30.00	40.80		Sqm	1	10.80	5.35	4.65	5.00		54.00		
40.80	45.00		Sqm	1	4.20	4.10	4.05	4.08		17.12		
45.00	60.10		Sqm	1	15.10	4.05	5.35	4.70		70.97		
		9th A Cross Road										
		(From South to North)										
0.00	3.70		Sqm	1	3.70	4.95	5.00	4.98		18.41		
3.70	15.00		Sqm	1	11.30	5.00	4.65	4.83		54.52		
15.00	17.10		Sqm	1	2.10	4.65	4.60	4.63		9.71		
		9th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	4.80	3.95	4.38		65.63		
15.00	30.00		Sqm	1	15.00	3.95	3.75	3.85		57.75		
30.00	45.00		Sqm	1	15.00	3.75	4.30	4.03		60.38		
45.00	60.00		Sqm	1	15.00	4.30	5.00	4.65		69.75		
60.00	75.00		Sqm	1	15.00	5.00	4.30	4.65		69.75		
75.00	90.90		Sqm	1	15.90	4.30	4.25	4.28		67.97		
90.90	98.80		Sqm	1	7.90	3.80	4.70	4.25		33.58		
		7th A Cross Road										
		(From South to North)										
0.00	4.20		Sqm	1	4.20	4.85	4.85	4.85		20.37		
4.20	9.10		Sqm	1	4.90	4.25	4.50	4.38		21.44		
9.10	15.00		Sqm	1	5.90	4.90	4.90	4.90		28.91		
15.00	18.30		Sqm	1	3.30	4.90	4.95	4.93		16.25		
		7th Cross Road										
		(From North to South)										
0.00	3.00		Sqm	1	3.00	6.50	4.75	5.63		16.88		
3.00	15.00		Sqm	1	12.00	4.75	4.00	4.38		52.50		
15.00	30.00		Sqm	1	15.00	4.00	4.35	4.18		62.63		
30.00	45.00		Sqm	1	15.00	4.35	4.60	4.48		67.13		
45.00	60.00		Sqm	1	15.00	4.60	4.55	4.58		68.63		
60.00	75.00		Sqm	1	15.00	4.55	4.50	4.53		67.88		
75.00	84.50		Sqm	1	9.50	4.50	4.60	4.55		43.23		
84.50	90.00		Sqm	1	5.50	4.40	4.55	4.48		24.61		
90.00	99.20		Sqm	1	9.20	4.55	4.50	4.53		41.63		
		6th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.60	4.70	5.15		77.25		
15.00	30.00		Sqm	1	15.00	4.70	4.80	4.75		71.25		
30.00	45.00		Sqm	1	15.00	4.80	4.45	4.63		69.38		
45.00	60.00		Sqm	1	15.00	4.45	4.60	4.53		67.88		
60.00	75.00		Sqm	1	15.00	4.60	5.30	4.95		74.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00		Sqm	1	15.00	5.30	5.00	5.15		77.25		
0.00	92.30		Sqm	1	2.30	5.00	5.05	5.03		11.56		
92.30	95.90		Sqm	1	3.60	3.90	3.80	3.85		13.86		
		6th A Cross Road										
		(From South to North)										
0.00	9.60		Sqm	1	9.60	5.60	5.50	5.55		53.28		
9.60	15.00		Sqm	1	5.40	4.95	4.25	4.60		24.84		
15.00	18.30		Sqm	1	3.30	4.25	4.35	4.30		14.19		
		5th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	1	15.00	5.35	4.60	4.98		74.63		
15.00	30.00		Sqm	1	15.00	4.60	4.00	4.30		64.50		
30.00	45.00		Sqm	1	15.00	4.00	3.70	3.85		57.75		
45.00	60.00		Sqm	1	15.00	3.70	3.70	3.70		55.50		
60.00	74.80		Sqm	1	14.80	3.70	4.00	3.85		56.98		
74.80	83.40		Sqm	1	8.60	4.65	5.20	4.93		42.36		
83.40	91.60		Sqm	1	8.20	4.40	4.80	4.60		37.72		
91.60	95.00		Sqm	1	3.40	4.60	4.50	4.55		15.47		
		5th A Cross Road										
		(From South to North)										
0.00	4.00		Sqm	1	4.00	5.15	4.60	4.88		19.50		
4.00	15.00		Sqm	1	11.00	4.00	4.30	4.15		45.65		
15.00	20.60		Sqm	1	5.60	4.30	4.50	4.40		24.64		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
0.00	15.00		Sqm	1	15.00	6.90	7.20	7.05		105.75		
15.00	30.00		Sqm	1	15.00	7.20	7.25	7.23		108.38		
30.00	45.00		Sqm	1	15.00	7.25	6.30	6.78		101.63		
45.00	60.00		Sqm	1	15.00	6.30	7.50	6.90		103.50		
60.00	75.00		Sqm	1	15.00	7.50	7.35	7.43		111.38		
75.00	90.00		Sqm	1	15.00	7.35	7.45	7.40		111.00		
90.00	105.00		Sqm	1	15.00	7.45	7.45	7.45		111.75		
105.00	120.00		Sqm	1	15.00	7.45	6.90	7.18		107.63		
120.00	135.00		Sqm	1	15.00	6.90	6.85	6.88		103.13		
135.00	150.00		Sqm	1	15.00	6.85	6.10	6.48		97.13		
150.00	165.00		Sqm	1	15.00	6.10	7.05	6.58		98.63		
165.00	180.00		Sqm	1	15.00	7.05	6.85	6.95		104.25		
180.00	195.00		Sqm	1	15.00	6.85	7.05	6.95		104.25		
195.00	210.00		Sqm	1	15.00	7.05	6.80	6.93		103.88		
210.00	225.00		Sqm	1	15.00	6.80	6.15	6.48		97.13		
225.00	240.00		Sqm	1	15.00	6.15	6.45	6.30		94.50		
240.00	255.00		Sqm	1	15.00	6.45	6.20	6.33		94.88		
255.00	270.00		Sqm	1	15.00	6.20	6.25	6.23		93.38		
270.00	285.00		Sqm	1	15.00	6.25	6.40	6.33		94.88		
285.00	300.00		Sqm	1	15.00	6.40	6.75	6.58		98.63		
300.00	308.90		Sqm	1	8.90	6.75	6.55	6.65		59.18		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
0.00	10.00		Sqm	1	10.00	6.15	5.85	6.00		60.00		
10.00	24.70		Sqm	1	14.70	5.05	4.50	4.78		70.19		
24.70	30.00		Sqm	1	5.30	4.50	4.40	4.45		23.59		
30.00	45.00		Sqm	1	15.00	5.15	5.40	5.28		79.13		
45.00	60.00		Sqm	1	15.00	5.40	6.05	5.73		85.88		
60.00	75.00		Sqm	1	15.00	6.05	6.10	6.08		91.13		
75.00	90.00		Sqm	1	15.00	6.10	6.05	6.08		91.13		
90.00	105.00		Sqm	1	15.00	6.05	5.75	5.90		88.50		
105.00	120.00		Sqm	1	15.00	5.75	5.30	5.53		82.88		
120.00	135.00		Sqm	1	15.00	5.30	6.00	5.65		84.75		
135.00	150.00		Sqm	1	15.00	6.00	5.50	5.75		86.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
150.00	165.00		Sqm	1	15.00	5.50	5.20	5.35		80.25		
165.00	180.00		Sqm	1	15.00	5.20	6.05	5.63		84.38		
180.00	181.20		Sqm	1	1.20	6.05	6.10	6.08		7.29		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
0.00	15.00		Sqm	1	15.00	7.10	6.65	6.88		103.13		
15.00	30.00		Sqm	1	15.00	6.65	6.25	6.45		96.75		
30.00	45.00		Sqm	1	15.00	6.25	7.10	6.68		100.13		
45.00	60.00		Sqm	1	15.00	7.10	6.40	6.75		101.25		
60.00	75.00		Sqm	1	15.00	6.40	6.05	6.23		93.38		
75.00	90.00		Sqm	1	15.00	6.05	5.60	5.83		87.38		
90.00	105.00		Sqm	1	15.00	5.60	5.60	5.60		84.00		
105.00	120.00		Sqm	1	15.00	5.60	5.40	5.50		82.50		
120.00	135.00		Sqm	1	15.00	5.40	5.50	5.45		81.75		
135.00	150.00		Sqm	1	15.00	5.50	5.45	5.48		82.13		
150.00	161.50		Sqm	1	11.50	5.45	5.45	5.45		62.68		
161.50	168.60		Sqm	1	7.10	5.45	5.50	5.48		38.87		
168.60	170.00		Sqm	1	1.40	5.50	6.85	6.18		8.65		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
0.00	15.00		Sqm	1	15.00	6.10	6.50	6.30		94.50		
15.00	30.00		Sqm	1	15.00	6.50	6.80	6.65		99.75		
30.00	45.00		Sqm	1	15.00	6.80	6.85	6.83		102.38		
45.00	52.70		Sqm	1	7.70	6.85	6.05	6.45		49.67		
52.70	57.60		Sqm	1	4.90	3.80	3.85	3.83		18.74		
57.60	70.00		Sqm	1	12.40	5.90	6.60	6.25		77.50		
70.00	85.00		Sqm	1	15.00	6.60	6.40	6.50		97.50		
85.00	90.00		Sqm	1	5.00	6.40	6.30	6.35		31.75		
90.00	105.00		Sqm	1	15.00	6.30	5.90	6.10		91.50		
105.00	120.00		Sqm	1	15.00	5.90	6.00	5.95		89.25		
120.00	135.00		Sqm	1	15.00	6.00	6.05	6.03		90.38		
135.00	150.00		Sqm	1	15.00	6.05	6.30	6.18		92.63		
150.00	159.10		Sqm	1	9.10	6.30	6.90	6.60		60.06		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
0.00	15.00		Sqm	1	15.00	5.45	5.15	5.30		79.50		
15.00	30.00		Sqm	1	15.00	5.15	4.25	4.70		70.50		
30.00	45.00		Sqm	1	15.00	4.25	4.00	4.13		61.88		
45.00	60.00		Sqm	1	15.00	4.00	4.30	4.15		62.25		
60.00	69.20		Sqm	1	9.20	4.30	4.10	4.20		38.64		
69.20	75.00		Sqm	1	5.80	3.90	3.65	3.78		21.90		
75.00	90.00		Sqm	1	15.00	3.65	4.20	3.93		58.88		
90.00	105.00		Sqm	1	15.00	4.20	4.90	4.55		68.25		
105.00	120.00		Sqm	1	15.00	4.90	5.00	4.95		74.25		
120.00	122.70		Sqm	1	2.70	5.00	5.00	5.00		13.50		
122.70	124.80		Sqm	1	2.10	5.00	5.95	5.48		11.50		
		11th Cross Road										
		North to South										
0.00	9.80		Sqm	1	9.80	5.30	4.50	4.90		48.02		
9.80	15.00		Sqm	1	5.20	3.70	3.75	3.73		19.37		
15.00	30.00		Sqm	1	15.00	3.75	4.60	4.18		62.63		
30.00	45.00		Sqm	1	15.00	4.60	5.00	4.80		72.00		
45.00	60.00		Sqm	1	15.00	5.00	5.40	5.20		78.00		
60.00	75.00		Sqm	1	15.00	3.90	4.10	4.00		60.00		
75.00	90.00		Sqm	1	15.00	4.10	4.75	4.43		66.38		
90.00	105.00		Sqm	1	15.00	4.75	3.45	4.10		61.50		
105.00	106.40		Sqm	1	1.40	3.45	3.40	3.43		4.80		
106.40	120.00		Sqm	1	13.60	3.85	4.30	4.08		55.42		
120.00	129.10		Sqm	1	9.10	4.30	4.55	4.43		40.27		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		17th Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	4.90	4.60	4.75		71.25		
15.00	30.00		Sqm	1	15.00	4.60	4.30	4.45		66.75		
30.00	45.00		Sqm	1	15.00	4.30	4.10	4.20		63.00		
45.00	60.00		Sqm	1	15.00	4.10	4.00	4.05		60.75		
60.00	75.00		Sqm	1	15.00	4.00	4.55	4.28		64.13		
75.00	90.00		Sqm	1	15.00	4.55	4.20	4.38		65.63		
90.00	105.00		Sqm	1	15.00	4.20	4.15	4.18		62.63		
105.00	120.00		Sqm	1	15.00	4.15	4.60	4.38		65.63		
120.00	131.80		Sqm	1	11.80	4.60	5.25	4.93		58.12		
		3rd Cross Road										
		North to South										
0.00	15.00		Sqm	1	15.00	3.90	4.95	4.43		66.38		
15.00	30.00		Sqm	1	15.00	4.95	4.40	4.68		70.13		
30.00	45.00		Sqm	1	15.00	4.40	4.90	4.65		69.75		
45.00	60.00		Sqm	1	15.00	4.90	4.65	4.78		71.63		
60.00	71.70		Sqm	1	11.70	4.65	4.65	4.65		54.41		
		2nd Cross Road										
		North To South										
0.00	15.00		Sqm	1	15.00	5.60	4.05	4.83		72.38		
15.00	30.00		Sqm	1	15.00	4.05	4.30	4.18		62.63		
30.00	45.00		Sqm	1	15.00	4.30	4.35	4.33		64.88		
45.00	60.00		Sqm	1	15.00	4.35	4.40	4.38		65.63		
60.00	75.00		Sqm	1	15.00	4.40	4.80	4.60		69.00		
75.00	76.10		Sqm	1	1.10	4.80	4.85	4.83		5.31		
		DEDUCTION										
		Manhole	Sqm	-12	0.44					-5.30		
							(3.14X0.75X0.75)/4=0.44					
			Sqm	-15	0.64					-9.54		
							(3.14X0.9X0.9)/4=0.64					
			Sqm	-8	0.79					-6.28		
							(3.14X1X1)/4=0.79					
			Sqm	-7	1.13					-7.91		
							(3.14X1.2X1.2)/4=1.13					
		ELETRIC POLE	Sqm	-1	2.30	1.00	1.00	1.00		-2.30		
		CHAMBER	Sqm	-34	0.90	0.60	0.60	0.60		-18.36		
			Sqm	-1	0.80	0.70	0.70	0.70		-0.56		
			Sqm	-1	1.90	1.80	1.80	1.80		-3.42		
			Sqm	-1	2.40	0.90	0.90	0.90		-2.16		
		TRANSFORMER	Sqm	-1	2.40	0.80	0.80	0.80		-1.92		
		TREE PATH	Sqm	-1	1.00	1.00	1.00	1.00		-1.00		
									Total Executed Quantity	**64570.28**	**13.86**	**894945.00**
									Tender Quantity	**77565.91**		
Item no.19		**Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
3.00	8.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.05	0.50		
19.00	30.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
35.00	45.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
50.00	60.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
81.00	90.00		Cum	1	9.00	1.40	1.40	1.40	0.05	0.63		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
107.00	112.00		Cum	1	5.00	2.00	2.00	2.00	0.05	0.50		
114.00	120.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
126.00	135.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
138.00	145.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
149.00	152.00		Cum	1	3.00	2.00	2.00	2.00	0.05	0.30		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
154.00	165.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
167.00	171.00		Cum	1	4.00	1.80	1.80	1.80	0.05	0.36		
173.00	178.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
180.00	190.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
193.00	199.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
		Ravi Gowda Layout										
		(From North to South)										
2.00	6.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
8.00	15.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
20.00	30.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
35.00	45.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
49.00	60.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
68.00	75.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
80.00	90.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
99.00	105.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
110.00	117.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
119.00	126.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
129.00	135.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
137.00	141.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
143.00	150.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
155.00	165.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
172.00	180.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
183.00	191.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
193.00	197.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
199.00	212.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.40	1.40	1.40	0.05	0.35		
15.00	28.00		Cum	1	13.00	1.80	1.80	1.80	0.05	1.17		
34.00	42.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
45.00	54.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
56.00	62.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
63.00	68.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
		Jai Rama Layout Main Road										
		(From East to West)										
5.00	12.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
15.00	28.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
30.00	41.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
45.00	54.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
58.00	68.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
72.00	80.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
85.00	98.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
100.00	108.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
110.00	117.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
4.00	11.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
15.00	30.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
35.00	44.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
46.00	56.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
58.00	67.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
12.00	18.00		Cum	1	6.00	1.90	1.90	1.90	0.05	0.57		
19.00	30.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
62.00	75.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
95.00	105.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
110.00	120.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
125.00	135.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
139.00	150.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
153.00	165.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
169.00	180.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
182.00	195.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
197.00	206.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
210.00	215.60		Cum	1	5.60	1.60	1.60	1.60	0.05	0.45		
		2nd B Cross Road										
		(From North to South)										
2.00	6.00		Cum	1	4.00	1.40	1.40	1.40	0.05	0.28		
8.00	15.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
17.00	25.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
27.00	30.00		Cum	1	3.00	1.50	1.50	1.50	0.05	0.23		
31.00	37.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
		2nd A Cross Road										
		(From North to South)										
3.00	9.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
11.00	15.00		Cum	1	4.00	1.90	1.90	1.90	0.05	0.38		
19.00	30.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
50.00	60.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
63.00	75.00		Cum	1	12.00	0.60	0.60	0.60	0.05	0.36		
77.00	90.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		
92.00	102.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
104.00	110.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
4.00	11.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
13.00	21.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
24.00	33.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
37.00	49.00		Cum	1	12.00	1.00	1.00	1.00	0.05	0.60		
53.00	62.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
80.00	90.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
92.00	100.00		Cum	1	8.00	1.90	1.90	1.90	0.05	0.76		
103.00	108.00		Cum	1	5.00	1.80	1.80	1.80	0.05	0.45		
		2nd Cross Road										
		(From South to North)										
4.00	11.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
14.00	25.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
30.00	42.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
48.00	59.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
63.00	75.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
80.00	90.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
95.00	105.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
108.00	117.00		Cum	1	9.00	1.70	1.70	1.70	0.05	0.77		
119.00	122.00		Cum	1	3.00	1.70	1.70	1.70	0.05	0.26		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
4.00	13.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
19.00	30.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
35.00	45.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
51.00	60.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
66.00	75.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
82.00	90.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
96.00	105.00		Cum	1	9.00	1.40	1.40	1.40	0.05	0.63		
107.00	115.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
119.00	125.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
127.00	135.00		Cum	1	8.00	1.70	1.70	1.70	0.05	0.68		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		1st A K.V.J Road										
		(From West to East)										
3.00	12.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
15.00	23.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
25.00	30.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
31.00	34.00		Cum	1	3.00	1.00	1.00	1.00	0.05	0.15		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
2.00	13.00		Cum	1	11.00	1.40	1.40	1.40	0.05	0.77		
21.00	30.00		Cum	1	9.00	1.60	1.60	1.60	0.05	0.72		
35.00	45.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
49.00	58.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
60.00	66.00		Cum	1	6.00	0.70	0.70	0.70	0.05	0.21		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
3.00	9.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
11.00	18.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
20.00	30.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
33.00	40.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
42.00	52.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
54.00	60.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
62.00	67.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
68.00	73.00		Cum	1	5.00	0.70	0.70	0.70	0.05	0.18		
75.00	78.00		Cum	1	3.00	1.00	1.00	1.00	0.05	0.15		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
13.00	23.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
25.00	35.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
40.00	48.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
50.00	54.00		Cum	1	4.00	0.60	0.60	0.60	0.05	0.12		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
4.00	11.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
12.00	22.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
24.00	30.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
48.00	57.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
59.00	65.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
68.00	80.00		Cum	1	12.00	1.50	1.50	1.50	0.05	0.90		
83.00	94.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
96.00	106.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
120.00	129.30		Cum	1	9.30	1.80	1.80	1.80	0.05	0.84		
133.00	137.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
4.00	13.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
15.00	25.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
28.00	38.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
40.00	52.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
54.00	63.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
65.00	75.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
77.00	87.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
98.00	105.00		Cum	1	7.00	1.90	1.90	1.90	0.05	0.67		
		6th B Cross Road										
		(From South to North)										
4.00	10.00		Cum	1	6.00	1.80	1.80	1.80	0.05	0.54		
12.00	20.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
23.00	33.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
35.00	45.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
48.00	57.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
60.00	70.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
75.00	84.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
90.00	102.00		Cum	1	12.00	1.50	1.50	1.50	0.05	0.90		
		6th Cross Road										
		(From East to West)										
5.00	12.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
15.00	23.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
25.00	35.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
40.00	50.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
52.00	60.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
63.00	73.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
94.00	101.00		Cum	1	7.00	0.80	0.80	0.80	0.05	0.28		
102.00	110.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
3.00	9.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
11.00	18.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
20.00	30.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
34.00	42.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
45.00	53.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
55.00	61.00		Cum	1	6.00	1.60	1.60	1.60	0.05	0.48		
		10th Cross Road,13th main										
		(North To South)										
2.00	10.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
12.00	19.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
21.00	26.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
28.00	33.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
35.00	38.00		Cum	1	3.00	1.70	1.70	1.70	0.05	0.26		
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	10.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
13.00	18.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
20.00	30.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
33.00	40.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
42.00	50.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
53.00	60.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
81.00	90.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
97.00	105.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
112.00	120.00		Cum	1	8.00	0.80	0.80	0.80	0.05	0.32		
122.00	131.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
133.00	137.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
		9th A Cross, 13th main										
		(North To South)										
2.00	12.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
14.00	20.00		Cum	1	6.00	1.60	1.60	1.60	0.05	0.48		
22.00	30.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
34.00	45.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
67.00	75.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
81.00	90.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
95.00	103.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
105.00	110.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
		For Cut Portion										
		GKVK Layout										
		Main Road										
		(From West to East)										
2.00	6.00		Cum	1	4.00	0.60	0.60	0.60	0.05	0.12		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
8.00	13.00		Cum	1	5.00	0.75	0.75	0.75	0.05	0.19		
17.00	29.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
32.00	43.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
48.00	57.00		Cum	1	9.00	1.60	1.60	1.60	0.05	0.72		
63.00	71.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
77.00	88.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
94.00	103.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
107.00	110.00		Cum	1	3.00	0.60	0.60	0.60	0.05	0.09		
112.00	118.00		Cum	1	6.00	1.70	1.70	1.70	0.05	0.51		
123.00	133.00		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
137.00	144.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
145.00	152.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
154.00	163.00		Cum	1	9.00	1.35	1.35	1.35	0.05	0.61		
165.00	172.40		Cum	1	7.40	1.60	1.60	1.60	0.05	0.59		
173.10	180.00		Cum	1	6.90	1.50	1.50	1.50	0.05	0.52		
184.00	192.80		Cum	1	8.80	1.90	1.90	1.90	0.05	0.84		
195.00	200.80		Cum	1	5.80	2.00	2.00	2.00	0.05	0.58		
		Ravi Gowda Layout										
		(From North to South)										
3.50	12.00		Cum	1	8.50	1.30	1.30	1.30	0.05	0.55		
18.00	28.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
32.80	41.00		Cum	1	8.20	2.30	2.30	2.30	0.05	0.94		
48.00	57.00		Cum	1	9.00	2.60	2.60	2.60	0.05	1.17		
62.40	70.00		Cum	1	7.60	1.80	1.80	1.80	0.05	0.68		
79.00	88.30		Cum	1	9.30	1.90	1.90	1.90	0.05	0.88		
96.00	101.20		Cum	1	5.20	2.30	2.30	2.30	0.05	0.60		
107.60	117.00		Cum	1	9.40	2.25	2.25	2.25	0.05	1.06		
120.00	126.00		Cum	1	6.00	1.40	1.40	1.40	0.05	0.42		
128.00	133.00		Cum	1	5.00	1.70	1.70	1.70	0.05	0.43		
137.00	140.00		Cum	1	3.00	1.60	1.60	1.60	0.05	0.24		
143.00	148.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
155.00	162.60		Cum	1	7.60	1.70	1.70	1.70	0.05	0.65		
167.90	178.20		Cum	1	10.30	1.50	1.50	1.50	0.05	0.77		
183.00	191.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
198.00	207.00		Cum	1	9.00	1.35	1.35	1.35	0.05	0.61		
212.00	213.50		Cum	1	1.50	1.00	1.00	1.00	0.05	0.08		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
6.00	11.00		Cum	1	5.00	1.40	1.40	1.40	0.05	0.35		
17.00	28.00		Cum	1	11.00	1.60	1.60	1.60	0.05	0.88		
32.00	41.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
47.00	55.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
58.70	64.70		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
66.00	69.20		Cum	1	3.20	1.30	1.30	1.30	0.05	0.21		
		Jai Rama Layout Main Road										
		(From East to West)										
4.00	11.00		Cum	1	7.00	1.60	1.60	1.60	0.05	0.56		
17.00	27.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
33.70	41.60		Cum	1	7.90	1.00	1.00	1.00	0.05	0.40		
45.80	57.30		Cum	1	11.50	2.30	2.30	2.30	0.05	1.32		
63.40	73.40		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
80.00	88.90		Cum	1	8.90	1.60	1.60	1.60	0.05	0.71		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.05	0.80		
108.00	111.00		Cum	1	3.00	2.00	2.00	2.00	0.05	0.30		
114.70	118.30		Cum	1	3.60	3.00	3.00	3.00	0.05	0.54		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
18.00	27.80		Cum	1	9.80	1.70	1.70	1.70	0.05	0.83		
33.00	41.50		Cum	1	8.50	1.65	1.65	1.65	0.05	0.70		
48.90	57.60		Cum	1	8.70	1.90	1.90	1.90	0.05	0.83		
61.80	67.90		Cum	1	6.10	2.60	2.60	2.60	0.05	0.79		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Cum	1	3.50	3.00	3.00	3.00	0.05	0.53		
6.00	13.00		Cum	1	7.00	3.00	3.00	3.00	0.05	1.05		
18.00	28.90		Cum	1	10.90	1.60	1.60	1.60	0.05	0.87		
32.60	42.70		Cum	1	10.10	1.90	1.90	1.90	0.05	0.96		
44.60	57.80		Cum	1	13.20	2.00	2.00	2.00	0.05	1.32		
63.50	74.50		Cum	1	11.00	2.30	2.30	2.30	0.05	1.27		
79.00	88.00		Cum	1	9.00	1.60	1.60	1.60	0.05	0.72		
94.60	103.00		Cum	1	8.40	1.90	1.90	1.90	0.05	0.80		
108.00	118.00		Cum	1	10.00	2.60	2.60	2.60	0.05	1.30		
122.00	133.00		Cum	1	11.00	2.20	2.20	2.20	0.05	1.21		
137.00	147.00		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
152.00	164.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
167.00	178.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
182.70	192.30		Cum	1	9.60	1.90	1.90	1.90	0.05	0.91		
197.60	208.60		Cum	1	11.00	2.20	2.20	2.20	0.05	1.21		
211.00	215.60		Cum	1	4.60	1.80	1.80	1.80	0.05	0.41		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Cum	1	3.40	1.80	1.80	1.80	0.05	0.31		
5.00	9.40		Cum	1	4.40	2.50	2.50	2.50	0.05	0.55		
12.00	18.50		Cum	1	6.50	1.70	1.70	1.70	0.05	0.55		
22.00	28.00		Cum	1	6.00	1.60	1.60	1.60	0.05	0.48		
34.00	37.80		Cum	1	3.80	1.10	1.10	1.10	0.05	0.21		
		2nd A Cross Road										
		(From North to South)										
3.00	4.30		Cum	1	1.30	1.60	1.60	1.60	0.05	0.10		
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
18.00	27.90		Cum	1	9.90	1.45	1.45	1.45	0.05	0.72		
34.60	42.10		Cum	1	7.50	1.75	1.75	1.75	0.05	0.66		
49.00	58.60		Cum	1	9.60	1.60	1.60	1.60	0.05	0.77		
63.60	72.90		Cum	1	9.30	1.45	1.45	1.45	0.05	0.67		
77.80	88.90		Cum	1	11.10	1.35	1.35	1.35	0.05	0 75		
93.10	103.60		Cum	1	10.50	1.20	1.20	1.20	0.05	0.63		
108.00	111.10		Cum	1	3.10	2.80	2.80	2.80	0.05	0.43		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
3.00	11.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
18.00	27.60		Cum	1	9.60	1.30	1.30	1.30	0.05	0.62		
34.00	42.60		Cum	1	8.60	1.60	1.60	1.60	0.05	0.69		
47.00	59.70		Cum	1	12.70	1.80	1.80	1.80	0.05	1.14		
62.30	74.20		Cum	1	11.90	2.00	2.00	2.00	0.05	1.19		
77.00	87.60		Cum	1	10.60	1.30	1.30	1.30	0.05	0.69		
92.60	94.40		Cum	1	1.80	1.10	1.10	1.10	0.05	0.10		
97.60	101.00		Cum	1	3.40	1.80	1.80	1.80	0.05	0.31		
105.00	109.20		Cum	1	4.20	1.10	1.10	1.10	0.05	0.23		
		2nd Cross Road										
		(From South to North)										
4.60	13.50		Cum	1	8.90	1.60	1.60	1.60	0.05	0.71		
17.80	27.90		Cum	1	10.10	1.20	1.20	1.20	0.05	0.61		
34.60	44.20		Cum	1	9.60	1.40	1.40	1.40	0.05	0.67		
47.60	58.70		Cum	1	11.10	1.80	1.80	1.80	0.05	1.00		
64.50	72.50		Cum	1	8.00	2.30	2.30	2.30	0.05	0.92		
77.00	88.00		Cum	1	11.00	1.90	1.90	1.90	0.05	1.05		
93.00	101.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
107.00	117.00		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
120.00	122.10		Cum	1	2.10	3.00	3.00	3.00	0.05	0.31		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
4.60	11.00		Cum	1	6.40	1.60	1.60	1.60	0.05	0.51		
18.60	27.60		Cum	1	9.00	1.55	1.55	1.55	0.05	0.70		
35.60	44.00		Cum	1	8.40	1.85	1.85	1.85	0.05	0.78		
49.50	57.60		Cum	1	8.10	2.00	2.00	2.00	0.05	0.81		
64.60	73.40		Cum	1	8.80	1.95	1.95	1.95	0.05	0.86		
78.90	87.90		Cum	1	9.00	2.10	2.10	2.10	0.05	0.95		
94.20	102.00		Cum	1	7.80	1.70	1.70	1.70	0.05	0.66		
108.00	117.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
126.00	132.00		Cum	1	6.00	1.70	1.70	1.70	0.05	0.51		
135.00	136.00		Cum	1	1.00	2.10	2.10	2.10	0.05	0.11		
		1st A K.V.J Road										
		(From West to East)										
3.60	12.50		Cum	1	8.90	0.90	0.90	0.90	0.05	0.40		
21.20	27.60		Cum	1	6.40	1.80	1.80	1.80	0.05	0.58		
31.00	33.30		Cum	1	2.30	1.60	1.60	1.60	0.05	0.18		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
3.00	11.80		Cum	1	8.80	2.00	2.00	2.00	0.05	0.88		
17.60	27.80		Cum	1	10.20	1.40	1.40	1.40	0.05	0.71		
32.80	41.20		Cum	1	8.40	1.70	1.70	1.70	0.05	0.71		
48.60	57.90		Cum	1	9.30	1.65	1.65	1.65	0.05	0.77		
61.00	67.20		Cum	1	6.20	1.00	1.00	1.00	0.05	0.31		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
2.30	8.70		Cum	1	6.40	1.75	1.75	1.75	0.05	0.56		
9.90	15.00		Cum	1	5.10	2.10	2.10	2.10	0.05	0.54		
19.00	27.60		Cum	1	8.60	1.80	1.80	1.80	0.05	0.77		
33.60	43.50		Cum	1	9.90	1.60	1.60	1.60	0.05	0.79		
50.00	57.80		Cum	1	7.80	1.50	1.50	1.50	0.05	0.59		
68.50	73.00		Cum	1	4.50	1.20	1.20	1.20	0.05	0.27		
78.00	79.50		Cum	1	1.50	1.00	1.00	1.00	0.05	0.08		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
4.60	13.20		Cum	1	8.60	1.80	1.80	1.80	0.05	0.77		
18.50	27.40		Cum	1	8.90	1.60	1.60	1.60	0.05	0.71		
36.00	43.60		Cum	1	7.60	1.30	1.30	1.30	0.05	0.49		
47.00	52.30		Cum	1	5.30	1.40	1.40	1.40	0.05	0.37		
54.00	55.00		Cum	1	1.00	1.25	1.25	1.25	0.05	0.06		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
3.70	11.40		Cum	1	7.70	1.80	1.80	1.80	0.05	0.69		
16.90	25.80		Cum	1	8.90	1.60	1.60	1.60	0.05	0.71		
34.60	41.20		Cum	1	6.60	1.40	1.40	1.40	0.05	0.46		
47.90	57.60		Cum	1	9.70	2.00	2.00	2.00	0.05	0.97		
64.50	74.50		Cum	1	10.00	2.60	2.60	2.60	0.05	1.30		
79.00	88.00		Cum	1	9.00	1.70	1.70	1.70	0.05	0.77		
92.60	98.80		Cum	1	6.20	2.40	2.40	2.40	0.05	0.74		
101.00	105.00		Cum	1	4.00	2.20	2.20	2.20	0.05	0.44		
108.60	117.00		Cum	1	8.40	1.90	1.90	1.90	0.05	0.80		
121.00	129.30		Cum	1	8.30	2.10	2.10	2.10	0.05	0.87		
129.30	131.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
132.00	138.00		Cum	1	6.00	1.70	1.70	1.70	0.05	0.51		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
3.00	13.40		Cum	1	10.40	1.40	1.40	1.40	0.05	0.73		
17.60	26.80		Cum	1	9.20	1.70	1.70	1.70	0.05	0.78		
33.00	43.20		Cum	1	10.20	1.60	1.60	1.60	0.05	0.82		
48.60	57.60		Cum	1	9.00	1.85	1.85	1.85	0.05	0.83		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
2.80	74.00		Cum	1	11.20	1.90	1.90	1.90	0.05	1.06		
78.00	88.90		Cum	1	10.90	1.10	1.10	1.10	0.05	0.60		
92.80	104.00		Cum	1	11.20	1.85	1.85	1.85	0.05	1.04		
		6th B Cross Road										
		(From South to North)										
2.60	11.50		Cum	1	8.90	2.10	2.10	2.10	0.05	0.93		
18.00	27.60		Cum	1	9.60	1.90	1.90	1.90	0.05	0.91		
36.00	43.20		Cum	1	7.20	2.30	2.30	2.30	0.05	0.83		
51.00	57.90		Cum	1	6.90	2.00	2.00	2.00	0.05	0.69		
65.00	72.60		Cum	1	7.60	1.85	1.85	1.85	0.05	0.70		
80.00	87.50		Cum	1	7.50	2.10	2.10	2.10	0.05	0.79		
92.70	101.00		Cum	1	8.30	1.95	1.95	1.95	0.05	0.81		
114.00	118.50		Cum	1	4.50	2.00	2.00	2.00	0.05	0.45		
		6th Cross Road										
		(From East to West)										
7.00	13.00		Cum	1	6.00	1.90	1.90	1.90	0.05	0.57		
17.00	27.60		Cum	1	10.60	1.45	1.45	1.45	0.05	0.77		
33.00	43.10		Cum	1	10.10	1.75	1.75	1.75	0.05	0.88		
47.60	58.00		Cum	1	10.40	1.85	1.85	1.85	0.05	0.96		
62.00	74.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
78.00	86.90		Cum	1	8.90	1.60	1.60	1.60	0.05	0.71		
89.10	90.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
94.60	103.00		Cum	1	8.40	1.40	1.40	1.40	0.05	0.59		
108.00	117.10		Cum	1	9.10	1.60	1.60	1.60	0.05	0.73		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
2.00	5.00		Cum	1	3.00	0.80	0.80	0.80	0.05	0.12		
8.00	12.00		Cum	1	4.00	1.80	1.80	1.80	0.05	0.36		
15.00	23.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
25.00	38.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
40.00	50.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
52.00	60.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
		10th Cross Road,13th main										
		(North To South)										
3.00	9.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.05	0.50		
18.00	25.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
27.00	33.00		Cum	1	6.00	1.80	1.80	1.80	0.05	0.54		
35.00	38.00		Cum	1	3.00	0.90	0.90	0.90	0.05	0.14		
		9th B Cross, 13th Main Road										
		(North To South)										
2.00	6.00		Cum	1	4.00	2.00	2.00	2.00	0.05	0.40		
8.00	15.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
18.00	26.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
28.00	36.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
38.00	45.00		Cum	1	7.00	1.40	1.40	1.40	0.05	0.49		
47.00	60.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
63.00	75.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
79.00	90.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
95.00	105.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
112.00	120.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
123.00	130.00		Cum	1	7.00	1.60	1.60	1.60	0.05	0.56		
133.00	137.00		Cum	1	4.00	1.40	1.40	1.40	0.05	0.28		
		9th A Cross, 13th main										
		(North To South)										
3.00	8.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
10.00	15.00		Cum	1	5.00	2.00	2.00	2.00	0.05	0.50		
19.00	30.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
34.00	45.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
3.00	90.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
92.00	100.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
102.00	108.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Cum	1	15.00	5.10	5.95	5.53	0.05	4.14		
15.00	27.10		Cum	1	12.10	5.95	4.70	5.33	0.05	3.22		
27.10	30.00		Cum	1	2.90	6.30	5.95	6.13	0.05	0.89		
30.00	45.00		Cum	1	15.00	5.95	4.95	5.45	0.05	4.09		
45.00	60.00		Cum	1	15.00	4.95	5.75	5.35	0.05	4.01		
60.00	75.00		Cum	1	15.00	5.75	5.80	5.78	0.05	4.33		
75.00	90.00		Cum	1	15.00	5.80	5.40	5.60	0.05	4.20		
90.00	105.00		Cum	1	15.00	5.40	5.30	5.35	0.05	4.01		
105.00	120.00		Cum	1	15.00	5.30	5.85	5.58	0.05	4.18		
120.00	135.00		Cum	1	15.00	5.85	6.55	6.20	0.05	4.65		
135.00	139.20		Cum	1	4.20	6.55	6.00	6.28	0.05	1.32		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Cum	1	15.00	7.85	7.00	7.43	0.05	5.57		
15.00	30.00		Cum	1	15.00	7.00	5.95	6.48	0.05	4.86		
30.00	38.40		Cum	1	8.40	5.95	5.60	5.78	0.05	2.43		
38.40	45.00		Cum	1	6.60	7.25	6.85	7.05	0.05	2.33		
45.00	60.00		Cum	1	15.00	6.85	6.10	6.48	0.05	4.86		
60.00	75.00		Cum	1	15.00	6.10	6.55	6.33	0.05	4.74		
75.00	90.00		Cum	1	15.00	6.55	6.70	6.63	0.05	4.97		
90.00	105.00		Cum	1	15.00	6.70	7.10	6.90	0.05	5.18		
105.00	113.00		Cum	1	8.00	7.10	7.00	7.05	0.05	2.82		
113.00	120.00		Cum	1	7.00	5.05	5.00	5.03	0.05	1.76		
120.00	126.20		Cum	1	6.20	5.00	5.10	5.05	0.05	1.57		
126.20	130.50		Cum	1	4.30	5.95	6.00	5.98	0.05	1.28		
130.50	135.00		Cum	1	4.50	6.00	6.15	6.08	0.05	1.37		
135.00	150.00		Cum	1	15.00	6.15	6.80	6.48	0.05	4.86		
150.00	165.00		Cum	1	15.00	6.80	6.75	6.78	0.05	5.08		
165.00	165.40		Cum	1	0.40	6.75	6.80	6.78	0.05	0.14		
165.40	180.00		Cum	1	14.60	6.30	6.35	6.33	0.05	4.62		
180.00	195.00		Cum	1	15.00	6.35	6.00	6.18	0.05	4.63		
195.00	210.00		Cum	1	15.00	6.00	5.90	5.95	0.05	4.46		
210.00	225.00		Cum	1	15.00	5.90	6.20	6.05	0.05	4.54		
225.00	240.00		Cum	1	15.00	6.20	5.75	5.98	0.05	4.48		
240.00	249.30		Cum	1	9.30	5.75	6.00	5.88	0.05	2.73		
249.30	258.30		Cum	1	9.00	5.10	4.65	4.88	0.05	2.19		
258.30	273.30		Cum	1	15.00	5.45	5.25	5.35	0.05	4.01		
273.30	275.00		Cum	1	1.70	5.25	5.25	5.25	0.05	0.45		
273.30	284.00		Cum	1	10.70	5.25	5.75	5.50	0.05	2.94		
		1st Cross Road										
		(From North To South)										
6.00	13.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
18.00	23.00		Cum	1	5.00	1.60	1.60	1.60	0.05	0.40		
27.00	35.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
43.00	50.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
52.00	58.00		Cum	1	6.00	1.60	1.60	1.60	0.05	0.48		
63.00	72.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
77.00	88.00		Cum	1	11.00	1.70	1.70	1.70	0.05	0.94		
94.00	103.00		Cum	1	9.00	1.25	1.25	1.25	0.05	0.56		
108.00	116.00		Cum	1	8.00	1.15	1.15	1.15	0.05	0.46		
124.00	131.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
138.00	147.00		Cum	1	9.00	1.40	1.40	1.40	0.05	0.63		
		Balaji Layout										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
2.50	10.00		Cum	1	7.50	0.90	0.90	0.90	0.05	0.34		
18.00	27.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
34.00	41.00		Cum	1	7.00	0.75	0.75	0.75	0.05	0.26		
48.00	52.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
54.20	55.80	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
58.00	60.00		Cum	1	2.00	1.00	1.00	1.00	0.05	0.10		
63.00	72.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
76.00	88.00		Cum	1	12.00	1.40	1.40	1.40	0.05	0.84		
93.00	103.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
108.00	118.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
123.00	132.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
137.00	149.00		Cum	1	12.00	1.60	1.60	1.60	0.05	0.96		
152.00	163.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
169.00	178.00		Cum	1	9.00	1.40	1.40	1.40	0.05	0.63		
182.00	193.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
197.00	209.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
212.00	223.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
225.00	228.20		Cum	1	3.20	0.60	0.60	0.60	0.05	0.10		
228.20	232.00		Cum	1	3.80	0.75	0.75	0.75	0.05	0.14		
234.00	245.20		Cum	1	11.20	1.25	1.25	1.25	0.05	0.70		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
3.00	13.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
18.00	28.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
34.00	43.60		Cum	1	9.60	1.70	1.70	1.70	0.05	0.82		
		(From West To East)										
0.00	3.90		Cum	1	3.90	1.30	1.30	1.30	0.05	0.25		
3.90	11.10		Cum	1	7.20	1.20	1.20	1.20	0.05	0.43		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
5.00	10.00		Cum	1	5.00	0.80	0.80	0.80	0.05	0.20		
13.00	17.00		Cum	1	4.00	0.50	0.50	0.50	0.05	0.10		
20.00	28.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
31.00	41.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
46.00	53.00		Cum	1	7.00	0.80	0.80	0.80	0.05	0.28		
57.00	63.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
67.00	75.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
80.00	86.00		Cum	1	6.00	0.90	0.90	0.90	0.05	0.27		
90.00	100.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
104.00	112.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
116.00	127.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
130.00	139.00		Cum	1	9.00	0.80	0.80	0.80	0.05	0.36		
145.00	152.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
		6th A Cross Road										
		(From West to East)										
1.00	7.40		Cum	1	6.40	1.80	1.80	1.80	0.05	0.58		
		(From South to North)										
2.00	6.00		Cum	1	4.00	0.80	0.80	0.80	0.05	0.16		
8.00	14.00		Cum	1	6.00	0.50	0.50	0.50	0.05	0.15		
16.00	25.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
28.00	42.00		Cum	1	14.00	1.20	1.20	1.20	0.05	0.84		
44.00	51.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
53.00	60.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
63.00	75.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
78.00	91.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
.00	101.00		Cum	1	8.00	0.90	0.90	0.90	0.05	0.36		
103.00	114.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
116.00	127.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
129.00	139.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
		Devi Nagar Main Road										
		(From West to East)										
5.00	14.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
16.00	28.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
33.00	43.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
45.00	55.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
58.00	72.00		Cum	1	14.00	1.40	1.40	1.40	0.05	0.98		
75.00	83.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
86.00	102.00		Cum	1	16.00	1.40	1.40	1.40	0.05	1.12		
105.00	118.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
120.00	130.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
133.00	145.00		Cum	1	12.00	1.00	1.00	1.00	0.05	0.60		
148.00	160.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
163.00	175.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
178.00	188.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
190.00	198.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
200.00	213.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
215.00	224.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
226.00	231.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
235.00	240.00		Cum	1	5.00	0.70	0.70	0.70	0.05	0.18		
		Muneshwara Layout										
		1st Main Road										
3.00	9.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
11.00	18.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
20.00	30.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
38.00	45.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
50.00	60.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
66.00	75.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
78.00	90.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
96.00	105.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
110.00	120.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
127.00	135.00		Cum	1	8.00	0.80	0.80	0.80	0.05	0.32		
140.00	150.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
156.00	165.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
170.00	178.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
180.00	186.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
190.00	196.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
200.00	206.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
208.00	212.00		Cum	1	4.00	0.70	0.70	0.70	0.05	0.14		
217.00	225.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
225.00	235.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
240.00	249.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
250.00	260.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
265.00	274.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
280.00	288.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
290.00	296.00		Cum	1	6.00	0.70	0.70	0.70	0.05	0.21		
298.00	305.00		Cum	1	7.00	0.80	0.80	0.80	0.05	0.28		
307.00	315.00		Cum	1	8.00	0.90	0.90	0.90	0.05	0.36		
320.00	330.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
334.00	340.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
344.00	352.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
356.00	363.50		Cum	1	7.50	1.10	1.10	1.10	0.05	0.41		
362.00	370.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
372.00	379.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
382.00	388.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
4.00	13.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
15.00	27.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
49.00	58.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
60.00	71.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	86.00		Cum	1	13.00	1.20	1.30	1.25	0.05	0.81		
88.00	101.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		
103.00	114.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
116.00	128.00		Cum	1	12.00	1.20	1.30	1.25	0.05	0.75		
130.00	141.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
142.00	153.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
155.00	168.00		Cum	1	13.00	1.20	1.30	1.25	0.05	0.81		
170.00	178.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
180.00	186.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
188.00	193.00		Cum	1	5.00	0.90	0.90	0.90	0.05	0.23		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
3.00	9.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
11.00	18.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
20.00	26.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
28.00	35.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
37.00	43.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
45.00	54.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
56.00	64.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
66.00	72.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
74.00	78.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
79.00	83.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
5.00	13.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
15.00	25.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
28.00	36.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
38.00	49.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
53.00	62.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
65.00	75.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
78.00	87.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
90.00	101.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
104.00	113.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
117.00	126.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
128.00	137.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
140.00	150.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
154.00	162.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
164.00	176.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
178.00	187.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
189.00	200.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
205.00	210.00		Cum	1	5.00	0.80	0.80	0.80	0.05	0.20		
		1st Cross Road										
		(From North to South)										
4.00	12.00		Cum	1	8.00	0.50	0.50	0.50	0.05	0.20		
14.00	20.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
22.00	26.00		Cum	1	4.00	0.70	0.70	0.70	0.05	0.14		
30.00	37.00		Cum	1	7.00	0.70	0.70	0.70	0.05	0.25		
39.00	48.00		Cum	1	9.00	0.50	0.50	0.50	0.05	0.23		
50.00	56.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
58.00	67.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
69.00	75.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
78.00	84.00		Cum	1	6.00	0.50	0.50	0.50	0.05	0.15		
		2nd Cross Road										
		(From North to South)										
5.00	12.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
14.00	26.00		Cum	1	12.00	1.00	1.00	1.00	0.05	0.60		
28.00	38.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
40.00	51.00		Cum	1	11.00	0.80	0.80	0.80	0.05	0.44		
55.00	65.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
3.00	76.00		Cum	1	8.00	0.50	0.50	0.50	0.05	0.20		
		2nd A Cross Road										
		(From South to North)										
4.00	14.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
16.00	25.00		Cum	1	9.00	0.90	0.90	0.90	0.05	0.41		
28.00	40.00		Cum	1	12.00	1.00	1.00	1.00	0.05	0.60		
		3rd Cross Road										
		(From North to South)										
2.00	6.00		Cum	1	4.00	0.50	0.50	0.50	0.05	0.10		
8.00	14.00		Cum	1	6.00	0.60	0.60	0.60	0.05	0.18		
17.00	28.00		Cum	1	11.00	0.50	0.50	0.50	0.05	0.28		
30.00	38.00		Cum	1	8.00	0.50	0.50	0.50	0.05	0.20		
43.00	51.00		Cum	1	8.00	0.90	0.90	0.90	0.05	0.36		
53.00	61.00		Cum	1	8.00	0.70	0.70	0.70	0.05	0.28		
63.00	68.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
70.00	76.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
78.00	83.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
85.00	91.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
97.00	104.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
106.00	108.00		Cum	1	2.00	0.90	0.90	0.90	0.05	0.09		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
5.00	12.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
15.00	25.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
28.00	37.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
39.00	46.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
48.00	57.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
59.00	63.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
67.00	77.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
79.00	88.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
90.00	98.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
100.00	105.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
107.00	117.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
119.00	127.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
129.00	137.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
139.00	148.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
150.00	155.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
157.00	162.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
164.00	168.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
173.00	179.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
180.00	185.00		Cum	1	5.00	0.80	0.80	0.80	0.05	0.20		
187.00	194.00		Cum	1	7.00	0.90	0.90	0.90	0.05	0.32		
196.00	204.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
206.00	214.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
216.00	225.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
227.00	234.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
236.00	247.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
250.00	260.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
262.00	274.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
276.00	288.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
290.00	297.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
299.00	309.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
311.00	321.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
323.00	332.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
334.00	348.00		Cum	1	14.00	1.30	1.30	1.30	0.05	0.91		
350.00	365.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
81.00	92.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
94.00	104.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
106.00	115.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
117.00	125.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
6.00	132.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
134.00	141.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
143.00	152.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
154.00	163.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
165.00	176.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
178.00	187.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
189.00	199.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
201.00	210.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
213.00	223.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
226.00	238.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
240.00	250.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
255.00	262.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
265.00	278.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
279.00	292.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
		1st Cross Road										
		(From East to West)										
4.00	10.00		Cum	1	6.00	0.90	0.90	0.90	0.05	0.27		
12.00	18.00		Cum	1	6.00	0.90	0.90	0.90	0.05	0.27		
20.00	30.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
32.00	39.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
41.00	50.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
		2nd Cross Road										
		(From East to West)										
3.00	9.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
12.00	23.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
25.00	34.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
36.00	44.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
46.00	51.00		Cum	1	5.00	0.70	0.70	0.70	0.05	0.18		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
2.00	12.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
14.00	24.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
26.00	36.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
38.00	50.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
52.00	64.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
66.00	76.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
78.00	90.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
92.00	105.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
107.00	120.00		Cum	1	13.00	1.30	1.30	1.30	0.05	0.85		
122.00	132.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
134.00	145.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
147.00	156.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
158.00	166.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
168.00	178.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
180.00	188.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
190.00	196.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
198.00	207.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
209.00	218.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
224.00	232.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
234.00	240.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
242.00	250.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
252.00	258.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
260.00	264.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
266.00	275.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
277.00	288.00		Cum	1	11.00	1.10	1.10	1.10	0.05	0.61		
290.00	296.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
298.00	306.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
308.00	316.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
318.00	330.00		Cum	1	12.00	1.30	1.30	1.30	0.05	0.78		
332.00	345.00		Cum	1	13.00	1.30	1.30	1.30	0.05	0.85		
347.00	356.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
358.00	367.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
369.00	380.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
382.00	395.00		Cum	1	13.00	1.30	1.30	1.30	0.05	0.85		
397.00	410.00		Cum	1	13.00	1.30	1.30	1.30	0.05	0.85		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
4.20	12.00		Cum	1	7.80	1.20	1.20	1.20	0.05	0.47		
15.00	18.80		Cum	1	3.80	3.80	3.80	3.80	0.05	0.72		
21.00	27.80		Cum	1	6.80	1.00	1.00	1.00	0.05	0.34		
32.60	42.60		Cum	1	10.00	1.25	1.25	1.25	0.05	0.63		
47.60	57.40		Cum	1	9.80	1.10	1.10	1.10	0.05	0.54		
64.30	71.00		Cum	1	6.70	1.60	1.60	1.60	0.05	0.54		
77.60	80.00		Cum	1	2.40	1.35	1.35	1.35	0.05	0.16		
83.40	90.20		Cum	1	6.80	1.00	1.00	1.00	0.05	0.34		
93.60	103.20		Cum	1	9.60	0.90	0.90	0.90	0.05	0.43		
107.80	116.90		Cum	1	9.10	1.40	1.40	1.40	0.05	0.64		
124.30	131.70		Cum	1	7.40	1.25	1.25	1.25	0.05	0.46		
138.40	147.00		Cum	1	8.60	1.35	1.35	1.35	0.05	0.58		
152.80	163.10		Cum	1	10.30	1.10	1.10	1.10	0.05	0.57		
		6th A Cross Road										
		(From West to East)										
3.00	6.00		Cum	1	3.00	3.00	3.00	3.00	0.05	0.45		
		(From South to North)										
2.30	6.40		Cum	1	4.10	2.20	2.20	2.20	0.05	0.45		
9.00	13.40		Cum	1	4.40	2.60	2.60	2.60	0.05	0.57		
17.90	27.60		Cum	1	9.70	2.00	2.00	2.00	0.05	0.97		
36.20	44.20		Cum	1	8.00	1.35	1.35	1.35	0.05	0.54		
45.00	50.70		Cum	1	5.70	2.00	2.00	2.00	0.05	0.57		
50.70	60.00		Cum	1	9.30	1.80	1.80	1.80	0.05	0.84		
62.30	71.20		Cum	1	8.90	1.30	1.30	1.30	0.05	0.58		
77.80	88.90		Cum	1	11.10	1.70	1.70	1.70	0.05	0.94		
93.40	103.80		Cum	1	10.40	1.40	1.40	1.40	0.05	0.73		
107.00	119.00		Cum	1	12.00	1.60	1.60	1.60	0.05	0.96		
121.00	133.20		Cum	1	12.20	1.40	1.40	1.40	0.05	0.85		
137.00	141.70		Cum	1	4.70	1.00	1.00	1.00	0.05	0.23		
		Devi Nagar Main Road										
		(From West to East)										
2.50	11.00		Cum	1	8.50	1.70	1.70	1.70	0.05	0.72		
16.80	26.40		Cum	1	9.60	2.00	2.00	2.00	0.05	0.96		
33.20	43.50		Cum	1	10.30	1.90	1.90	1.90	0.05	0.98		
47.00	58.00		Cum	1	11.00	2.30	2.30	2.30	0.05	1.27		
63.00	71.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
77.00	87.00		Cum	1	10.00	1.45	1.45	1.45	0.05	0.73		
93.50	103.00		Cum	1	9.50	1.80	1.80	1.80	0.05	0.86		
107.00	118.00		Cum	1	11.00	2.20	2.20	2.20	0.05	1.21		
123.00	134.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
137.60	149.50		Cum	1	11.90	1.90	1.90	1.90	0.05	1.13		
151.00	163.40		Cum	1	12.40	1.60	1.60	1.60	0.05	0.99		
165.00	180.00		Cum	1	15.00	1.55	1.55	1.55	0.05	1.16		
183.00	194.30		Cum	1	11.30	1.30	1.30	1.30	0.05	0.73		
196.50	210.00		Cum	1	13.50	1.40	1.40	1.40	0.05	0.95		
212.30	225.00		Cum	1	12.70	1.25	1.25	1.25	0.05	0.79		
227.00	237.20		Cum	1	10.20	1.80	1.80	1.80	0.05	0.92		
237.20	239.00		Cum	1	1.80	2.00	2.00	2.00	0.05	0.18		
239.00	241.50		Cum	1	2.50	1.20	1.20	1.20	0.05	0.15		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Cum	1	3.20	1.10	1.10	1.10	0.05	0.18		
7.00	15.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
18.00	28.40		Cum	1	10.40	0.90	0.90	0.90	0.05	0.47		
36.00	45.00		Cum	1	9.00	0.75	0.75	0.75	0.05	0.34		
47.80	57.90		Cum	1	10.10	1.60	1.60	1.60	0.05	0.81		
63.70	72.30		Cum	1	8.60	1.20	1.20	1.20	0.05	0.52		
78.90	88.00		Cum	1	9.10	1.70	1.70	1.70	0.05	0.77		
93.60	103.70		Cum	1	10.10	1.20	1.20	1.20	0.05	0.61		
111.00	120.00		Cum	1	9.00	1.45	1.45	1.45	0.05	0.65		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
7.00	135.00		Cum	1	8.00	1.65	1.65	1.65	0.05	0.66		
138.90	149.00		Cum	1	10.10	1.80	1.80	1.80	0.05	0.91		
154.70	162.60		Cum	1	7.90	1.70	1.70	1.70	0.05	0.67		
168.90	177.50		Cum	1	8.60	1.90	1.90	1.90	0.05	0.82		
180.00	184.70		Cum	1	4.70	1.60	1.60	1.60	0.05	0.38		
184.70	186.20		Cum	1	1.50	1.70	1.70	1.70	0.05	0.13		
186.20	195.00		Cum	1	8.80	1.60	1.60	1.60	0.05	0.70		
197.00	208.90		Cum	1	11.90	1.40	1.40	1.40	0.05	0.83		
213.00	223.60		Cum	1	10.60	1.25	1.25	1.25	0.05	0.66		
227.00	237.80		Cum	1	10.80	1.30	1.30	1.30	0.05	0.70		
242.60	251.00		Cum	1	8.40	1.40	1.40	1.40	0.05	0.59		
257.00	267.60		Cum	1	10.60	1.60	1.60	1.60	0.05	0.85		
273.00	281.60		Cum	1	8.60	1.20	1.20	1.20	0.05	0.52		
286.00	293.70		Cum	1	7.70	0.90	0.90	0.90	0.05	0.35		
293.70	298.70		Cum	1	5.00	1.90	1.90	1.90	0.05	0.48		
298.70	300.00		Cum	1	1.30	0.90	0.90	0.90	0.05	0.06		
303.60	313.80		Cum	1	10.20	1.40	1.40	1.40	0.05	0.71		
317.00	328.70		Cum	1	11.70	1.30	1.30	1.30	0.05	0.76		
332.40	342.60		Cum	1	10.20	1.15	1.15	1.15	0.05	0.59		
348.90	358.00		Cum	1	9.10	1.35	1.35	1.35	0.05	0.61		
360.00	363.50		Cum	1	3.50	2.00	2.00	2.00	0.05	0.35		
363.50	372.30		Cum	1	8.80	1.70	1.70	1.70	0.05	0.75		
374.00	386.00		Cum	1	12.00	1.50	1.50	1.50	0.05	0.90		
387.30	390.00		Cum	1	2.70	2.00	2.00	2.00	0.05	0.27		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
3.00	13.40		Cum	1	10.40	1.20	1.20	1.20	0.05	0.62		
18.00	29.50		Cum	1	11.50	1.90	1.90	1.90	0.05	1.09		
29.50	47.20	No Work	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
51.00	58.70		Cum	1	7.70	1.50	1.50	1.50	0.05	0.58		
62.70	73.80		Cum	1	11.10	1.70	1.70	1.70	0.05	0.94		
77.00	88.90		Cum	1	11.90	1.90	1.90	1.90	0.05	1.13		
92.60	103.50		Cum	1	10.90	1.35	1.35	1.35	0.05	0.74		
108.90	120.00		Cum	1	11.10	1.60	1.60	1.60	0.05	0.89		
123.60	134.50		Cum	1	10.90	1.80	1.80	1.80	0.05	0.98		
137.80	148.90		Cum	1	11.10	1.55	1.55	1.55	0.05	0.86		
150.30	158.50		Cum	1	8.20	1.70	1.70	1.70	0.05	0.70		
158.50	165.30		Cum	1	6.80	2.00	2.00	2.00	0.05	0.68		
168.00	179.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
180.30	189.60		Cum	1	9.30	1.90	1.90	1.90	0.05	0.88		
189.60	193.50		Cum	1	3.90	2.00	2.00	2.00	0.05	0.39		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Cum	1	4.00	2.00	2.00	2.00	0.05	0.40		
6.00	12.50		Cum	1	6.50	1.80	1.80	1.80	0.05	0.59		
15.00	22.00		Cum	1	7.00	1.90	1.90	1.90	0.05	0.67		
24.10	30.00		Cum	1	5.90	1.65	1.65	1.65	0.05	0.49		
32.40	38.10		Cum	1	5.70	1.50	1.50	1.50	0.05	0.43		
38.10	46.00		Cum	1	7.90	1.20	1.20	1.20	0.05	0.47		
48.90	58.00		Cum	1	9.10	1.30	1.30	1.30	0.05	0.59		
60.00	67.00		Cum	1	7.00	1.65	1.65	1.65	0.05	0.58		
69.00	75.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
77.00	83.50		Cum	1	6.50	2.00	2.00	2.00	0.05	0.65		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
2.60	12.60		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
17.80	27.60		Cum	1	9.80	1.60	1.60	1.60	0.05	0.78		
33.70	43.50		Cum	1	9.80	1.40	1.40	1.40	0.05	0.69		
47.00	56.90		Cum	1	9.90	1.15	1.15	1.15	0.05	0.57		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
72.00	74.00		Cum	1	12.00	1.85	1.85	1.85	0.05	1.11		
75.00	87.00		Cum	1	12.00	1.10	1.10	1.10	0.05	0.66		
87.00	90.00		Cum	1	3.00	2.00	2.00	2.00	0.05	0.30		
92.30	102.00		Cum	1	9.70	1.80	1.80	1.80	0.05	0.87		
107.00	118.00		Cum	1	11.00	1.35	1.35	1.35	0.05	0.74		
120.00	129.20		Cum	1	9.20	1.75	1.75	1.75	0.05	0.80		
129.20	135.00		Cum	1	5.80	2.00	2.00	2.00	0.05	0.58		
136.70	148.70		Cum	1	12.00	1.25	1.25	1.25	0.05	0.75		
152.60	163.00		Cum	1	10.40	1.15	1.15	1.15	0.05	0.60		
167.00	179.80		Cum	1	12.80	1.05	1.05	1.05	0.05	0.67		
180.00	195.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
195.00	209.00		Cum	1	14.00	1.30	1.30	1.30	0.05	0.91		
211.00	221.50		Cum	1	10.50	0.90	0.90	0.90	0.05	0.47		
		1st Cross Road										
		(From North to South)										
4.60	13.40		Cum	1	8.80	1.10	1.10	1.10	0.05	0.48		
15.00	17.10		Cum	1	2.10	1.05	1.05	1.05	0.05	0.11		
17.10	22.80		Cum	1	5.70	1.20	1.20	1.20	0.05	0.34		
22.80	30.00		Cum	1	7.20	0.90	0.90	0.90	0.05	0.32		
34.30	41.00		Cum	1	6.70	0.75	0.75	0.75	0.05	0.25		
47.60	53.20		Cum	1	5.60	0.90	0.90	0.90	0.05	0.25		
54.00	60.00		Cum	1	6.00	0.90	0.90	0.90	0.05	0.27		
63.00	71.60		Cum	1	8.60	0.75	0.75	0.75	0.05	0.32		
79.00	85.20		Cum	1	6.20	1.00	1.00	1.00	0.05	0.31		
		2nd Cross Road										
		(From North to South)										
3.00	12.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
18.90	27.60		Cum	1	8.70	1.30	1.30	1.30	0.05	0.57		
33.60	42.50		Cum	1	8.90	1.10	1.10	1.10	0.05	0.49		
48.90	56.30		Cum	1	7.40	1.40	1.40	1.40	0.05	0.52		
62.80	71.60		Cum	1	8.80	1.00	1.00	1.00	0.05	0.44		
75.00	82.10		Cum	1	7.10	0.65	0.65	0.65	0.05	0.23		
		2nd A Cross Road										
		(From South to North)										
3.80	13.40		Cum	1	9.60	1.60	1.60	1.60	0.05	0.77		
16.70	25.90		Cum	1	9.20	1.70	1.70	1.70	0.05	0.78		
37.00	44.90		Cum	1	7.90	1.10	1.10	1.10	0.05	0.43		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Cum	1	4.20	1.90	1.90	1.90	0.05	0.40		
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
21.00	28.50		Cum	1	7.50	1.60	1.60	1.60	0.05	0.60		
34.50	41.00		Cum	1	6.50	1.50	1.50	1.50	0.05	0.49		
46.00	52.20		Cum	1	6.20	1.40	1.40	1.40	0.05	0.43		
53.00	60.00		Cum	1	7.00	0.65	0.65	0.65	0.05	0.23		
62.00	67.30		Cum	1	5.30	0.75	0.75	0.75	0.05	0.20		
69.00	70.60		Cum	1	1.60	0.90	0.90	0.90	0.05	0.07		
73.00	81.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
85.00	89.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
90.00	92.10		Cum	1	2.10	0.90	0.90	0.90	0.05	0.09		
92.10	95.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
98.00	103.40		Cum	1	5.40	1.40	1.40	1.40	0.05	0.38		
107.80	108.90		Cum	1	1.10	1.70	1.70	1.70	0.05	0.09		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
30.00	45.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
45.00	47.80		Cum	1	2.80	1.50	1.50	1.50	0.05	0.21		
47.80	56.10		Cum	1	8.30	1.50	1.50	1.50	0.05	0.62		
56.10	63.90		Cum	1	7.80	1.50	1.50	1.50	0.05	0.59		
63.90	65.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
65.50	75.00		Cum	1	9.50	1.50	1.50	1.50	0.05	0.71		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
m	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
90.00	94.50		Cum	1	4.50	1.50	1.50	1.50	0.05	0.34		
94.50	105.00		Cum	1	10.50	1.50	1.50	1.50	0.05	0.79		
105.00	120.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
120.00	122.00		Cum	1	2.00	1.50	1.50	1.50	0.05	0.15		
122.00	135.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
135.00	150.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
150.00	154.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
154.00	163.70		Cum	1	9.70	1.50	1.50	1.50	0.05	0.73		
163.70	169.70		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
169.70	171.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
171.20	180.00		Cum	1	8.80	1.50	1.50	1.50	0.05	0.66		
180.00	181.80		Cum	1	1.80	1.50	1.50	1.50	0.05	0.14		
181.80	190.00		Cum	1	8.20	1.50	1.50	1.50	0.05	0.61		
190.00	205.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
205.00	216.10		Cum	1	11.10	1.50	1.50	1.50	0.05	0.83		
216.10	231.10		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
231.10	235.00		Cum	1	3.90	1.50	1.50	1.50	0.05	0.29		
235.00	250.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
250.00	265.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
265.00	280.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
280.00	295.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
295.00	300.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
300.00	315.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
315.00	330.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
330.00	345.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
345.00	360.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
360.00	369.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
0.00	0.00	(From South to North)										
0.00	15.00		Cum	1	15.00	8.40	6.80	7.60	0.05	5.70		
15.00	29.20		Cum	1	14.20	6.80	6.90	6.85	0.05	4.86		
29.20	30.30	Culvert	Cum	0	0.00	0.00	0.00	0.00	0.05	0.00		
30.30	45.00		Cum	1	14.70	6.85	6.70	6.78	0.05	4.98		
45.00	60.00		Cum	1	15.00	6.70	6.60	6.65	0.05	4.99		
60.00	75.00		Cum	1	15.00	6.60	6.40	6.50	0.05	4.88		
75.00	79.70		Cum	1	4.70	6.40	5.75	6.08	0.05	1.43		
79.70	90.00		Cum	1	10.30	2.50	2.50	2.50	0.05	1.29		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
105.00	108.50		Cum	1	3.50	2.50	2.50	2.50	0.05	0.44		
108.50	118.70		Cum	1	10.20	2.50	2.50	2.50	0.05	1.28		
118.70	124.80		Cum	1	6.10	2.50	2.50	2.50	0.05	0.76		
124.80	135.00		Cum	1	10.20	2.50	2.50	2.50	0.05	1.28		
135.00	150.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
150.00	165.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
195.00	210.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
210.00	225.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
240.00	255.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
255.00	270.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
270.00	285.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
285.00	291.50		Cum	1	6.50	2.50	2.50	2.50	0.05	0.81		
291.50	298.00		Cum	1	6.50	2.50	2.50	2.50	0.05	0.81		
		1st Cross Road										
		(From East to West)										
3.40	13.70		Cum	1	10.30	1.60	1.60	1.60	0.05	0.82		
15.00	17.20		Cum	1	2.20	2.00	2.00	2.00	0.05	0.22		
18.90	28.00		Cum	1	9.10	1.40	1.40	1.40	0.05	0.64		
34.60	41.00		Cum	1	6.40	1.50	1.50	1.50	0.05	0.48		
41.00	50.20		Cum	1	9.20	1.30	1.30	1.30	0.05	0.60		
		2nd Cross Road										
		(From East to West)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
m	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
3.60	12.80		Cum	1	9.20	1.30	1.30	1.30	0.05	0.60		
17.80	27.90		Cum	1	10.10	1.10	1.10	1.10	0.05	0.56		
32.00	41.20		Cum	1	9.20	1.50	1.50	1.50	0.05	0.69		
45.00	50.20		Cum	1	5.20	2.00	2.00	2.00	0.05	0.52		
50.20	52.80		Cum	1	2.60	1.00	1.00	1.00	0.05	0.13		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
15.00	30.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
30.00	45.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
45.00	60.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
60.00	63.30		Cum	1	3.30	2.50	2.50	2.50	0.05	0.41		
63.30	75.00		Cum	1	11.70	2.50	2.50	2.50	0.05	1.46		
75.00	90.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
90.00	105.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
105.00	120.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
120.00	132.90		Cum	1	12.90	2.50	2.50	2.50	0.05	1.61		
132.90	147.10		Cum	1	14.20	2.50	2.50	2.50	0.05	1.78		
147.10	160.00		Cum	1	12.90	2.50	2.50	2.50	0.05	1.61		
160.00	165.00		Cum	1	5.00	2.50	2.50	2.50	0.05	0.63		
165.00	180.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
180.00	195.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
195.00	198.80		Cum	1	3.80	2.50	2.50	2.50	0.05	0.48		
198.80	210.00		Cum	1	11.20	2.50	2.50	2.50	0.05	1.40		
210.00	219.70		Cum	1	9.70	2.50	2.50	2.50	0.05	1.21		
219.70	222.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
222.20	225.00		Cum	1	2.80	2.50	2.50	2.50	0.05	0.35		
225.00	240.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
240.00	249.60		Cum	1	9.60	2.50	2.50	2.50	0.05	1.20		
249.60	257.30		Cum	1	7.70	2.50	2.50	2.50	0.05	0.96		
257.30	260.00		Cum	1	2.70	2.50	2.50	2.50	0.05	0.34		
260.00	275.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
275.00	292.00		Cum	1	17.00	2.50	2.50	2.50	0.05	2.13		
292.00	297.10		Cum	1	5.10	2.50	2.50	2.50	0.05	0.64		
297.10	300.00		Cum	1	2.90	2.50	2.50	2.50	0.05	0.36		
300.00	315.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
315.00	330.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
330.00	345.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
345.00	360.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
360.00	375.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
375.00	390.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
390.00	405.00		Cum	1	15.00	2.50	2.50	2.50	0.05	1.88		
405.00	414.50		Cum	1	9.50	2.50	2.50	2.50	0.05	1.19		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
30.00	45.00		Cum	1	15.00	1.65	1.65	1.65	0.05	1.24		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
60.00	69.30		Cum	1	9.30	1.10	1.10	1.10	0.05	0.51		
69.30	75.00		Cum	1	5.70	2.00	2.00	2.00	0.05	0.57		
75.00	90.00		Cum	1	15.00	2.20	2.20	2.20	0.05	1.65		
90.00	105.00		Cum	1	15.00	1.60	1.60	1.60	0.05	1.20		
105.00	111.40		Cum	1	6.40	3.50	3.50	3.50	0.05	1.12		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Cum	1	4.60	4.00	4.00	4.00	0.05	0.92		
4.60	15.00		Cum	1	10.40	2.10	2.10	2.10	0.05	1.09		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
30.00	45.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
60.00	75.00		Cum	1	15.00	2.00	2.00	2.00	0.05	1.50		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
75.00	90.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
90.00	100.30		Cum	1	10.30	1.30	1.30	1.30	0.05	0.67		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.05	0.83		
15.00	30.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
30.00	45.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
45.00	60.00		Cum	1	15.00	1.40	1.40	1.40	0.05	1.05		
60.00	73.50		Cum	1	13.50	1.20	1.20	1.20	0.05	0.81		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Cum	1	15.00	1.30	1.30	1.30	0.05	0.98		
15.00	30.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
30.00	45.00		Cum	1	15.00	1.35	1.35	1.35	0.05	1.01		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.05	0.83		
60.00	75.00		Cum	1	15.00	1.00	1.00	1.00	0.05	0.75		
75.00	81.00		Cum	1	6.00	1.40	1.40	1.40	0.05	0.42		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.05	0.83		
15.00	30.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.05	1.50		
45.00	60.00		Cum	1	15.00	1.70	1.70	1.70	0.05	1.28		
60.00	75.00		Cum	1	15.00	1.90	1.90	1.90	0.05	1.43		
75.00	90.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
90.00	95.80		Cum	1	5.80	5.80	5.80	5.80	0.05	1.68		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Cum	1	15.00	2.20	2.20	2.20	0.05	1.65		
15.00	26.20		Cum	1	11.20	1.80	1.80	1.80	0.05	1.01		
		(North To South)										
0.00	15.00		Cum	1	15.00	1.70	1.70	1.70	0.05	1.28		
15.00	30.00		Cum	1	15.00	1.60	1.60	1.60	0.05	1.20		
30.00	45.00		Cum	1	15.00	2.00	2.00	2.00	0.05	1.50		
45.00	60.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
60.00	75.00		Cum	1	15.00	2.30	2.30	2.30	0.05	1.73		
75.00	90.00		Cum	1	15.00	1.90	1.90	1.90	0.05	1.43		
90.00	105.00		Cum	1	15.00	1.80	1.80	1.80	0.05	1.35		
105.00	120.00		Cum	1	15.00	2.20	2.20	2.20	0.05	1.65		
120.00	135.00		Cum	1	15.00	1.60	1.60	1.60	0.05	1.20		
135.00	150.00		Cum	1	15.00	2.10	2.10	2.10	0.05	1.58		
150.00	165.00		Cum	1	15.00	1.60	1.60	1.60	0.05	1.20		
165.00	169.00		Cum	1	4.00	1.90	1.90	1.90	0.05	0.38		
		Ward No 10										
		Vidyaranyapura Sub division'										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
6.00	13.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
15.00	20.80		Cum	1	5.80	1.30	1.30	1.30	0.05	0.38		
25.00	30.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
47.00	53.60		Cum	1	6.60	1.00	1.00	1.00	0.05	0.33		
55.00	60.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
95.00	105.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
110.00	120.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
125.00	135.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
140.00	150.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
155.00	165.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
168.00	180.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
183.00	193.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
195.00	200.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
201.00	205.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
0.00	6.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
7.00	15.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.05	0.36		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
68.00	75.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
80.00	90.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
95.00	105.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
110.00	120.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
126.00	135.00		Cum	1	9.00	1.60	1.60	1.60	0.05	0.72		
138.00	150.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
157.00	165.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
165.00	180.00		Cum	1	15.00	2.00	2.00	2.00	0.05	1.50		
187.00	195.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
200.00	210.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
215.00	225.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
228.00	238.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
240.00	246.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
249.00	255.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
265.00	270.00		Cum	1	5.00	0.50	0.50	0.50	0.05	0.13		
272.00	277.40		Cum	1	5.40	1.00	1.00	1.00	0.05	0.27		
279.00	285.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
290.00	296.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
298.00	302.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
6.00	13.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
15.00	23.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
25.00	34.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
36.00	45.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
95.00	102.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
103.00	109.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
112.00	120.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
122.00	135.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
137.00	141.00		Cum	1	4.00	0.50	0.50	0.50	0.05	0.10		
143.00	148.00		Cum	1	5.00	0.50	0.50	0.50	0.05	0.13		
150.00	159.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
160.00	166.00		Cum	1	6.00	0.50	0.50	0.50	0.05	0.15		
167.00	171.00		Cum	1	4.00	0.60	0.60	0.60	0.05	0.12		
172.00	180.00		Cum	1	8.00	0.80	0.80	0.80	0.05	0.32		
180.00	186.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
188.00	195.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
198.00	208.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
210.00	220.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
		Samashana Road										
		2nd main Road										
		(From East to West)										
3.00	10.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
12.00	18.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
20.00	30.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
35.00	45.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
65.00	75.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
80.00	90.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
95.00	105.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
107.00	120.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
122.00	130.00		Cum	1	8.00	0.80	0.80	0.80	0.05	0.32		
132.00	140.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	16.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
18.00	30.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
48.00	53.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
56.00	60.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
95.00	104.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
106.00	120.00		Cum	1	14.00	2.00	2.00	2.00	0.05	1.40		
121.00	128.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
130.00	135.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
136.00	140.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
142.00	148.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
150.00	154.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
2.00	12.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
2.00	10.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
13.00	18.00		Cum	1	5.00	2.00	2.00	2.00	0.05	0.50		
20.00	30.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
62.00	70.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
72.00	77.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
3.00	13.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
14.00	22.00		Cum	1	8.00	1.60	1.60	1.60	0.05	0.64		
		From house no #15 to house no -7										
		(From North to South)										
3.00	14.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
18.00	30.00		Cum	1	12.00	1.50	1.50	1.50	0.05	0.90		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
63.00	70.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
71.00	77.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
3.00	13.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
13.00	20.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
26.00	38.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
40.00	49.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
51.00	60.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
77.00	84.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
86.00	90.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
94.00	103.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
105.00	110.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
113.00	120.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
125.00	135.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
137.00	144.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
146.00	151.00		Cum	1	5.00	0.50	0.50	0.50	0.05	0.13		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
3.00	13.00		Cum	1	10.00	0.70	0.70	0.70	0.05	0.35		
15.00	27.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
30.00	40.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
41.00	46.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
3.00	13.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
15.00	28.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
30.00	40.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
45.00	58.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		
60.00	70.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
75.00	85.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
90.00	101.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
105.00	110.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
5.00	10.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
18.00	29.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
31.00	40.00		Cum	1	9.00	0.80	0.80	0.80	0.05	0.36		
42.00	48.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
		(From East to West)										
4.00	15.00		Cum	1	11.00	1.10	1.10	1.10	0.05	0.61		
17.00	30.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
35.00	45.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
48.00	60.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
68.00	74.00		Cum	1	6.00	1.80	1.80	1.80	0.05	0.54		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	12.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
19.00	30.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
30.00	35.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
37.00	45.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
55.00	60.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
65.00	75.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
95.00	105.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
110.00	120.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
129.00	135.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
140.00	150.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
158.00	165.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
170.00	180.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
181.00	186.00		Cum	1	5.00	1.80	1.80	1.80	0.05	0.45		
188.00	195.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
200.00	207.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
209.00	214.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
5.00	10.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
12.00	20.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
22.00	30.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
32.00	37.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
38.00	43.00		Cum	1	5.00	1.80	1.80	1.80	0.05	0.45		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
2.00	10.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
12.00	18.00		Cum	1	6.00	0.80	0.80	0.80	0.05	0.24		
20.00	30.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
65.00	77.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
79.00	90.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
92.00	100.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
103.00	110.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
104.00	113.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
3.00	8.00		Cum	1	5.00	1.80	1.80	1.80	0.05	0.45		
10.00	16.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
18.00	30.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
35.00	45.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
50.00	60.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
66.00	75.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
80.00	90.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
96.00	105.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
110.00	120.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
126.00	135.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
138.00	150.00		Cum	1	12.00	1.50	1.50	1.50	0.05	0.90		
153.00	160.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
162.00	166.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
169.00	176.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
180.00	191.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
193.00	199.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Cum	1	7.00	1.60	1.60	1.60	0.05	0.56		
12.00	18.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
20.00	30.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
52.00	60.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
61.00	65.00		Cum	1	4.00	0.80	0.80	0.80	0.05	0.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
12.00	16.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
18.00	30.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
34.00	45.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
65.00	75.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
83.00	90.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
96.00	105.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
107.00	115.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
117.00	125.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
6.00	15.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
18.00	25.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
27.00	35.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
37.00	48.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
50.00	60.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
65.00	75.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
83.00	90.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
94.00	105.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
107.00	116.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
118.00	127.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
12.00	17.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
20.00	30.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
33.00	45.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
48.00	57.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
60.00	68.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
70.00	77.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
79.00	82.00		Cum	1	3.00	1.60	1.60	1.60	0.05	0.24		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
4.00	10.00		Cum	1	6.00	1.80	1.80	1.80	0.05	0.54		
13.00	20.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
22.00	30.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
48.00	60.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
77.00	90.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
96.00	105.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
108.00	120.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
126.00	135.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
140.00	150.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
154.00	165.00		Cum	1	11.00	1.50	1.50	1.50	0.05	0.83		
170.00	180.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
183.00	195.00		Cum	1	12.00	1.40	1.40	1.40	0.05	0.84		
197.00	210.00		Cum	1	13.00	1.80	1.80	1.80	0.05	1.17		
216.00	225.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
234.00	240.00		Cum	1	6.00	2.00	2.00	2.00	0.05	0.60		
246.00	255.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
263.00	270.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
273.00	285.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
287.00	299.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
4.00	13.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
15.00	28.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
30.00	41.00		Cum	1	11.00	1.80	1.80	1.80	0.05	0.99		
45.00	57.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
60.00	71.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
73.00	83.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
86.00	95.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
98.00	105.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
107.00	116.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
119.00	120.00		Cum	1	1.00	1.00	1.00	1.00	0.05	0.05		
125.00	134.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
7.00	15.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
17.00	30.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
33.00	43.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
45.00	53.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
55.00	59.00		Cum	1	4.00	1.40	1.40	1.40	0.05	0.28		
		9th A Cross Road										
		(From South to North)										
2.00	7.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
8.00	12.00		Cum	1	4.00	1.50	1.50	1.50	0.05	0.30		
14.00	16.00		Cum	1	2.00	1.50	1.50	1.50	0.05	0.15		
		9th Cross Road										
		(From North to South)										
2.00	10.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
13.00	24.00		Cum	1	11.00	1.10	1.10	1.10	0.05	0.61		
30.00	38.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
43.00	52.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
60.00	73.00		Cum	1	13.00	1.50	1.50	1.50	0.05	0.98		
76.00	88.00		Cum	1	12.00	1.40	1.40	1.40	0.05	0.84		
90.00	96.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
		7th A Cross Road										
		(From South to North)										
2.00	6.00		Cum	1	4.00	1.80	1.80	1.80	0.05	0.36		
8.00	11.00		Cum	1	3.00	1.50	1.50	1.50	0.05	0.23		
13.00	15.00		Cum	1	2.00	1.30	1.30	1.30	0.05	0.13		
16.00	18.00		Cum	1	2.00	1.50	1.50	1.50	0.05	0.15		
		7th Cross Road										
		(From North to South)										
4.00	13.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
15.00	20.00		Cum	1	5.00	0.80	0.80	0.80	0.05	0.20		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0 35		
32.00	45.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
55.00	60.00		Cum	1	5.00	1.20	1.20	1.20	0.05	0.30		
65.00	71.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
73.00	84.50		Cum	1	11.50	2.00	2.00	2.00	0.05	1.15		
86.00	90.00		Cum	1	4.00	0.80	0.80	0.80	0.05	0.16		
92.00	98.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
		6th Cross Road										
		(From North to South)										
4.00	11.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
13.00	24.00		Cum	1	11.00	1.10	1.10	1.10	0.05	0.61		
30.00	40.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
48.00	56.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
69.00	70.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
79.00	80.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
82.00	88.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
90.00	94.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
		6th A Cross Road										
		(From South to North)										
2.00	7.00		Cum	1	5.00	1.40	1.40	1.40	0.05	0.35		
9.00	13.00		Cum	1	4.00	1.80	1.80	1.80	0.05	0.36		
15.00	18.00		Cum	1	3.00	1.40	1.40	1.40	0.05	0.21		
		5th Cross Road										
		(From North to South)										
5.00	14.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
16.00	28.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
30.00	40.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
44.00	53.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
55.00	63.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
66.00	76.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
78.00	85.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
87.00	94.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
		5th A Cross Road										
		(From South to North)										
2.00	6.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
8.00	14.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
15.00	20.00		Cum	1	5.00	1.20	1.20	1.20	0.05	0.30		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
5.00	13.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
18.00	30.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
62.00	75.00		Cum	1	13.00	2.00	2.00	2.00	0.05	1.30		
80.00	90.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
97.00	105.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
106.00	120.00		Cum	1	14.00	2.00	2.00	2.00	0.05	1.40		
127.00	135.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
140.00	150.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
156.00	165.00		Cum	1	9.00	1.60	1.60	1.60	0.05	0.72		
170.00	180.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
185.00	195.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
198.00	210.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
215.00	225.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
230.00	240.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
242.00	251.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
253.00	265.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
270.00	282.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
284.00	293.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
295.00	305.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.00	9.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
11.00	23.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
25.00	35.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
37.00	45.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
53.00	60.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
66.00	75.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
79.00	90.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
95.00	105.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
110.00	120.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
127.00	135.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
143.00	150.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
[illegible]00	163.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
165.00	173.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
176.00	180.00		Cum	1	4.00	1.60	1.60	1.60	0.05	0.32		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
5.00	13.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
15.00	25.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
35.00	45.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
50.00	60.00		Cum	1	10.00	2.00	2.00	2.00	0.05	1.00		
66.00	75.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
83.00	90.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
94.00	105.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
111.00	120.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
122.00	130.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
132.00	140.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
144.00	150.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
153.00	160.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
162.00	169.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
6.00	14.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
16.00	28.00		Cum	1	12.00	2.00	2.00	2.00	0.05	1.20		
37.00	45.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
47.00	58.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
60.00	66.00		Cum	1	6.00	1.20	1.20	1.20	0.05	0.36		
68.00	75.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
78.00	85.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
87.00	90.00		Cum	1	3.00	1.70	1.70	1.70	0.05	0.26		
95.00	105.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
111.00	120.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
125.00	135.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
137.00	148.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
150.00	158.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
		Vidyaranyapura Sub division`										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
4.00	9.00		Cum	1	5.00	0.90	0.90	0.90	0.05	0.23		
20.00	28.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
35.00	42.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
65.00	71.00		Cum	1	6.00	1.30	1.30	1.30	0.05	0.39		
80.00	87.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
94.00	102.00		Cum	1	8.00	0.90	0.90	0.90	0.05	0.36		
111.00	118.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
125.00	133.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
140.00	148.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
155.00	162.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
170.00	178.00		Cum	1	8.00	1.50	1.50	1.50	0.05	0.60		
185.00	195.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
195.00	203.10		Cum	1	8.10	1.50	1.50	1.50	0.05	0.61		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
3.10	12.00		Cum	1	8.90	1.10	1.10	1.10	0.05	0.49		
20.00	28.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
50.00	58.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
[illegible]00	87.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
96.00	100.00		Cum	1	4.00	1.45	1.45	1.45	0.05	0.29		
112.00	120.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
128.00	135.00		Cum	1	7.00	0.90	0.90	0.90	0.05	0.32		
137.00	150.00		Cum	1	13.00	0.60	0.60	0.60	0.05	0.39		
158.00	165.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
173.00	180.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
188.00	195.00		Cum	1	7.00	0.90	0.90	0.90	0.05	0.32		
200.00	210.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
217.00	225.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
232.00	240.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
248.00	255.00		Cum	1	7.00	0.90	0.90	0.90	0.05	0.32		
264.00	270.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
272.00	277.40		Cum	1	5.40	1.00	1.00	1.00	0.05	0.27		
278.50	285.00		Cum	1	6.50	1.00	1.00	1.00	0.05	0.33		
290.00	300.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
3.50	12.00		Cum	1	8.50	0.60	0.60	0.60	0.05	0.26		
20.00	25.20		Cum	1	5.20	1.10	1.10	1.10	0.05	0.29		
27.00	33.90		Cum	1	6.90	0.50	0.50	0.50	0.05	0.17		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
50.00	60.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
80.00	90.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
95.00	105.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
106.00	109.10		Cum	1	3.10	1.10	1.10	1.10	0.05	0.17		
112.00	120.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
125.00	135.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
138.00	142.80		Cum	1	4.80	1.10	1.10	1.10	0.05	0.26		
145.00	150.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
151.00	154.80		Cum	1	3.80	1.10	1.10	1.10	0.05	0.21		
157.00	165.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
168.00	172.80		Cum	1	4.80	1.10	1.10	1.10	0.05	0.26		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
181.00	185.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
190.00	195.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
198.00	209.40		Cum	1	11.40	0.60	0.60	0.60	0.05	0.34		
215.00	221.00		Cum	1	6.00	1.10	1.10	1.10	0.05	0.33		
		Samashana Road										
		2nd main Road										
		(From East to West)										
5.00	11.80		Cum	1	6.80	0.60	0.60	0.60	0.05	0.20		
13.00	15.00		Cum	1	2.00	1.20	1.20	1.20	0.05	0.12		
20.00	30.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
66.00	75.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
81.00	90.00		Cum	1	9.00	1.10	1.10	1.10	0.05	0.50		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
115.00	120.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
125.00	135.00		Cum	1	10.00	0.70	0.70	0.70	0.05	0.35		
138.00	140.50		Cum	1	2.50	0.70	0.70	0.70	0.05	0.09		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
6.00	15.50		Cum	1	9.50	1.20	1.20	1.20	0.05	0.57		
20.00	30.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
47.00	51.00		Cum	1	4.00	1.00	1.00	1.00	0.05	0.20		
53.00	60.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
65.00	75.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
95.00	105.10		Cum	1	10.10	1.00	1.00	1.00	0.05	0.51		
1[illegible]00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
122.00	126.50		Cum	1	4.50	0.60	0.60	0.60	0.05	0.14		
130.00	135.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
138.00	141.90		Cum	1	3.90	0.70	0.70	0.70	0.05	0.14		
144.00	150.00		Cum	1	6.00	0.70	0.70	0.70	0.05	0.21		
152.00	154.10		Cum	1	2.10	0.90	0.90	0.90	0.05	0.09		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Cum	1	1.60	0.60	0.60	0.60	0.05	0.05		
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.05	0.39		
34.00	45.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
48.00	60.00		Cum	1	12.00	0.60	0.60	0.60	0.05	0.36		
63.00	75.00		Cum	1	12.00	0.90	0.90	0.90	0.05	0.54		
75.00	79.10		Cum	1	4.10	0.60	0.60	0.60	0.05	0.12		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
6.00	15.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
17.00	23.30		Cum	1	6.30	0.70	0.70	0.70	0.05	0.22		
		From house no #15 to house no -7										
		(From North to South)										
5.00	15.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
22.00	30.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
35.00	45.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
51.00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
65.00	73.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
74.00	79.00		Cum	1	5.00	1.50	1.50	1.50	0.05	0.38		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
4.00	15.00		Cum	1	11.00	1.00	1.00	1.00	0.05	0.55		
20.00	29.60		Cum	1	9.60	1.40	1.40	1.40	0.05	0.67		
32.00	38.70		Cum	1	6.70	1.00	1.00	1.00	0.05	0.34		
40.00	45.00		Cum	1	5.00	1.80	1.80	1.80	0.05	0.45		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
65.00	75.00		Cum	1	10.00	1.70	1.70	1.70	0.05	0.85		
78.00	84.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
86.00	90.00		Cum	1	4.00	2.00	2.00	2.00	0.05	0.40		
100.00	103.00		Cum	1	3.00	0.60	0.60	0.60	0.05	0.09		
106.00	115.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
117.00	127.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
129.00	139.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
140.00	148.00		Cum	1	8.00	1.40	1.40	1.40	0.05	0.56		
150.00	153.30		Cum	1	3.30	1.00	1.00	1.00	0.05	0.17		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
8.00	15.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
20.00	30.00		Cum	1	10.00	1.60	1.60	1.60	0.05	0.80		
35.00	43.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
45.00	47.30		Cum	1	2.30	1.30	1.30	1.30	0.05	0.15		
		2nd Cross Road										
		From House no: #2 to House no:13										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From West to East)										
00	15.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
22.00	30.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
38.00	45.00		Cum	1	7.00	1.80	1.80	1.80	0.05	0.63		
50.00	60.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
65.00	75.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
108.00	112.00		Cum	1	4.00	0.70	0.70	0.70	0.05	0.14		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
20.00	30.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
34.00	45.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
49.00	50.10		Cum	1	1.10	2.00	2.00	2.00	0.05	0.11		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
5.00	15.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
17.00	30.00		Cum	1	13.00	0.60	0.60	0.60	0.05	0.39		
35.00	45.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
50.00	60.00		Cum	1	10.00	0.70	0.70	0.70	0.05	0.35		
68.00	75.10		Cum	1	7.10	1.10	1.10	1.10	0.05	0.39		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
4.00	15.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
20.00	30.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
30.00	34.30		Cum	1	4.30	1.00	1.00	1.00	0.05	0.22		
36.00	45.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
82.00	90.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
95.00	105.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
125.00	135.00		Cum	1	10.00	1.25	1.25	1.25	0.05	0.63		
140.00	150.00		Cum	1	10.00	0.90	0.90	0.90	0.05	0.45		
157.00	165.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
170.00	180.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
182.00	187.20		Cum	1	5.20	2.00	2.00	2.00	0.05	0.52		
190.00	195.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
199.00	210.00		Cum	1	11.00	1.10	1.10	1.10	0.05	0.61		
212.00	215.10		Cum	1	3.10	1.50	1.50	1.50	0.05	0.23		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
6.00	15.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
18.00	28.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
30.00	34.00		Cum	1	4.00	0.70	0.70	0.70	0.05	0.14		
36.00	40.00		Cum	1	4.00	0.80	0.80	0.80	0.05	0.16		
42.00	44.00		Cum	1	2.00	1.10	1.10	1.10	0.05	0.11		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	6.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
8.00	15.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.05	0.36		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
38.00	45.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
[illegible]00	60.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
63.00	75.00		Cum	1	12.00	0.70	0.70	0.70	0.05	0.42		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
96.00	105.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
108.00	117.00		Cum	1	9.00	0.70	0.70	0.70	0.05	0.32		
119.00	120.80		Cum	1	1.80	0.70	0.70	0.70	0.05	0.06		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
4.00	13.00		Cum	1	9.00	0.80	0.80	0.80	0.05	0.36		
15.00	28.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
31.00	37.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
39.00	45.00		Cum	1	6.00	0.60	0.60	0.60	0.05	0.18		
50.00	60.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
83.00	90.00		Cum	1	7.00	0.80	0.80	0.80	0.05	0.28		
95.00	105.00		Cum	1	10.00	0.70	0.70	0.70	0.05	0.35		
114.00	120.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
142.00	150.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
153.00	161.00		Cum	1	8.00	0.50	0.50	0.50	0.05	0.20		
165.00	172.00		Cum	1	7.00	0.70	0.70	0.70	0.05	0.25		
175.00	180.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
183.00	190.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
195.00	200.20		Cum	1	5.20	1.60	1.60	1.60	0.05	0.42		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.50	0.50	0.50	0.05	0.18		
13.00	23.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
25.00	30.00		Cum	1	5.00	1.10	1.10	1.10	0.05	0.28		
37.00	45.00		Cum	1	8.00	0.70	0.70	0.70	0.05	0.28		
51.00	60.00		Cum	1	9.00	0.80	0.80	0.80	0.05	0.36		
61.00	65.50		Cum	1	4.50	1.40	1.40	1.40	0.05	0.32		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
5.00	10.00		Cum	1	5.00	1.00	1.00	1.00	0.05	0.25		
12.00	19.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
21.00	30.00		Cum	1	9.00	1.00	1.00	1.00	0.05	0.45		
34.00	45.00		Cum	1	11.00	0.70	0.70	0.70	0.05	0.39		
50.00	60.00		Cum	1	10.00	0.50	0.50	0.50	0.05	0.25		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
80.00	90.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
95.00	105.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
110.00	120.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
123.00	127.60		Cum	1	4.60	1.30	1.30	1.30	0.05	0.30		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
4.00	11.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
13.00	20.00		Cum	1	7.00	1.30	1.30	1.30	0.05	0.46		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
34.00	45.00		Cum	1	11.00	0.75	0.75	0.75	0.05	0.41		
51.00	60.00		Cum	1	9.00	0.90	0.90	0.90	0.05	0.41		
65.00	75.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
78.00	90.00		Cum	1	12.00	0.70	0.70	0.70	0.05	0.42		
96.00	105.00		Cum	1	9.00	0.60	0.60	0.60	0.05	0.27		
111.00	120.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
123.00	128.30		Cum	1	5.30	1.00	1.00	1.00	0.05	0.27		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
3.00	10.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
12.00	20.00		Cum	1	8.00	0.70	0.70	0.70	0.05	0.28		
23.00	30.00		Cum	1	7.00	0.60	0.60	0.60	0.05	0.21		
35.00	45.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
50.00	60.00		Cum	1	10.00	1.30	1.30	1.30	0.05	0.65		
63.00	71.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
75.00	79.00		Cum	1	4.00	1.20	1.20	1.20	0.05	0.24		
81.00	83.40		Cum	1	2.40	1.60	1.60	1.60	0.05	0.19		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
5.00	13.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
15.00	20.00		Cum	1	5.00	0.80	0.80	0.80	0.05	0.20		
23.00	30.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
50.00	60.00		Cum	1	10.00	1.40	1.40	1.40	0.05	0.70		
63.00	75.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
79.00	90.00		Cum	1	11.00	1.30	1.30	1.30	0.05	0.72		
97.00	105.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
110.00	120.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
123.00	135.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
140.00	150.00		Cum	1	10.00	0.60	0.60	0.60	0.05	0.30		
155.00	165.00		Cum	1	10.00	0.80	0.80	0.80	0.05	0.40		
172.00	180.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
189.00	195.00		Cum	1	6.00	1.00	1.00	1.00	0.05	0.30		
200.00	210.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
218.00	225.00		Cum	1	7.00	0.80	0.80	0.80	0.05	0.28		
230.00	240.00		Cum	1	10.00	1.00	1.00	1.00	0.05	0.50		
250.00	255.00		Cum	1	5.00	1.40	1.40	1.40	0.05	0.35		
261.00	270.00		Cum	1	9.00	1.30	1.30	1.30	0.05	0.59		
275.00	283.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
287.00	300.40		Cum	1	13.40	1.30	1.30	1.30	0.05	0.87		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
6.00	14.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
18.00	30.00		Cum	1	12.00	0.60	0.60	0.60	0.05	0.36		
35.00	45.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
53.00	60.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
62.00	66.00		Cum	1	4.00	1.10	1.10	1.10	0.05	0.22		
68.00	75.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
80.00	90.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
97.00	105.00		Cum	1	8.00	0.60	0.60	0.60	0.05	0.24		
111.00	120.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
129.00	135.00		Cum	1	6.00	0.90	0.90	0.90	0.05	0.27		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Cum	1	3.70	1.20	1.20	1.20	0.05	0.22		
3.70	5.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
15.00	30.00		Cum	1	15.00	0.60	0.50	0.55	0.05	0.41		
30.00	40.80		Cum	1	10.80	0.90	0.85	0.88	0.05	0.47		
40.80	55.00		Cum	1	14.20	1.10	0.60	0.85	0.05	0.60		
		9th A Cross Road										
		(From South to North)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
3.70	15.00		Cum	1	11.30	0.50	0.65	0.58	0.05	0.32		
00	16.10		Cum	1	1.10	1.15	0.35	0.75	0.05	0.04		
		9th Cross Road										
		(From North to South)										
23.00	30.00		Cum	1	7.00	1.20	1.20	1.20	0.05	0.42		
45.00	52.00		Cum	1	7.00	0.95	0.65	0.80	0.05	0.28		
60.00	71.00		Cum	1	11.00	1.15	1.15	1.15	0.05	0.63		
75.00	90.10		Cum	1	15.10	1.20	1.20	1.20	0.05	0.91		
90.90	97.30		Cum	1	6.40	0.85	0.50	0.68	0.05	0.22		
		7th A Cross Road										
		(From South to North)										
9.10	15.00		Cum	1	5.90	1.50	1.50	1.50	0.05	0.44		
15.00	18.30		Cum	1	3.30	0.35	0.35	0.35	0.05	0.06		
		7th Cross Road										
		(From North to South)										
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.05	0.83		
33.00	42.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
45.00	55.80		Cum	1	10.80	0.60	0.60	0.60	0.05	0.32		
60.00	75.00		Cum	1	15.00	1.50	1.50	1.50	0.05	1.13		
79.00	84.50		Cum	1	5.50	1.20	1.20	1.20	0.05	0.33		
84.50	90.00		Cum	1	5.50	0.60	0.35	0.48	0.05	0.13		
91.20	93.10		Cum	1	1.90	1.20	1.20	1.20	0.05	0.11		
		6th Cross Road										
		(From North to South)										
10.00	15.00		Cum	1	5.00	0.60	0.60	0.60	0.05	0.15		
15.00	28.00		Cum	1	13.00	0.50	0.50	0.50	0.05	0.33		
42.00	45.00		Cum	1	3.00	0.70	0.70	0.70	0.05	0.11		
52.00	60.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
62.50	75.00		Cum	1	12.50	1.00	1.00	1.00	0.05	0.63		
83.00	90.00		Cum	1	7.00	1.60	1.60	1.60	0.05	0.56		
91.50	92.30		Cum	1	0.80	1.20	1.20	1.20	0.05	0.05		
		6th A Cross Road										
		(From South to North)										
5.00	9.60		Cum	1	4.60	1.20	1.20	1.20	0.05	0.28		
11.80	15.00		Cum	1	3.20	1.20	1.20	1.20	0.05	0.19		
		5th Cross Road										
		(From North to South)										
7.00	15.00		Cum	1	8.00	1.10	1.10	1.10	0.05	0.44		
33.00	40.70		Cum	1	7.70	1.40	1.40	1.40	0.05	0.54		
48.00	56.00		Cum	1	8.00	1.00	1.00	1.00	0.05	0.40		
65.00	70.00		Cum	1	5.00	1.30	1.30	1.30	0.05	0.33		
79.00	85.00		Cum	1	6.00	1.45	1.45	1.45	0.05	0.44		
		5th A Cross Road										
		(From South to North)										
2.00	4.00		Cum	1	2.00	0.50	0.40	0.45	0.05	0.05		
9.20	15.00		Cum	1	5.80	1.20	1.20	1.20	0.05	0.35		
17.60	19.60		Cum	1	2.00	1.30	0.60	0.95	0.05	0.10		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
16.00	28.30		Cum	1	12.30	0.90	0.80	0.85	0.05	0.52		
30.00	44.20		Cum	1	14.20	1.10	0.35	0.73	0.05	0.51		
45.00	58.00		Cum	1	13.00	1.30	0.45	0.88	0.05	0.57		
60.00	73.00		Cum	1	13.00	0.70	0.55	0.63	0.05	0.41		
107.00	120.00		Cum	1	13.00	1.50	1.20	1.35	0.05	0.88		
124.00	134.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
135.00	149.00		Cum	1	14.00	0.60	0.60	0.60	0.05	0.42		
153.00	165.00		Cum	1	12.00	1.60	1.60	1.60	0.05	0.96		
173.00	180.00		Cum	1	7.00	0.70	0.70	0.70	0.05	0.25		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
183.00	195.00		Cum	1	12.00	1.10	1.10	1.10	0.05	0.66		
[illegible]00	225.00		Cum	1	24.00	1.00	1.00	1.00	0.05	1.20		
228.00	240.00		Cum	1	12.00	1.60	1.60	1.60	0.05	0.96		
245.00	255.00		Cum	1	10.00	1.40	0.75	1.08	0.05	0.54		
258.00	270.00		Cum	1	12.00	1.20	1.20	1.20	0.05	0.72		
274.00	285.00		Cum	1	11.00	1.00	0.70	0.85	0.05	0.47		
287.00	300.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
4.50	10.00		Cum	1	5.50	1.50	1.50	1.50	0.05	0.41		
15.20	24.70		Cum	1	9.50	1.15	1.15	1.15	0.05	0.55		
29.00	30.00		Cum	1	1.00	1.45	1.45	1.45	0.05	0.07		
32.00	45.00		Cum	1	13.00	1.20	1.20	1.20	0.05	0.78		
48.00	60.00		Cum	1	12.00	1.40	1.40	1.40	0.05	0.84		
80.20	90.00		Cum	1	9.80	1.80	1.80	1.80	0.05	0.88		
97.00	105.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
110.00	120.00		Cum	1	10.00	1.15	1.15	1.15	0.05	0.58		
125.00	136.00		Cum	1	11.00	1.20	1.20	1.20	0.05	0.66		
145.00	150.00		Cum	1	5.00	1.70	1.70	1.70	0.05	0.43		
154.00	165.00		Cum	1	11.00	1.35	1.35	1.35	0.05	0.74		
168.00	178.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
2.50	15.00		Cum	1	12.50	1.20	0.95	1.08	0.05	0.67		
30.00	44.00		Cum	1	14.00	1.70	1.20	1.45	0.05	1.02		
45.00	55.60		Cum	1	10.60	1.20	1.15	1.18	0.05	0.62		
60.00	74.30		Cum	1	14.30	1.10	1.10	1.10	0.05	0.79		
90.00	103.00		Cum	1	13.00	1.00	1.00	1.00	0.05	0.65		
105.00	122.00		Cum	1	17.00	1.40	1.40	1.40	0.05	1.19		
128.00	135.00		Cum	1	7.00	1.10	1.10	1.10	0.05	0.39		
150.00	162.00		Cum	1	12.00	1.20	1.15	1.18	0.05	0.71		
165.00	168.60		Cum	1	3.60	1.60	1.60	1.60	0.05	0.29		
168.60	169.50		Cum	1	0.90	1.20	1.20	1.20	0.05	0.05		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
9.30	14.50		Cum	1	5.20	1.20	1.20	1.20	0.05	0.31		
15.00	25.00		Cum	1	10.00	1.60	1.20	1.40	0.05	0.70		
30.00	44.20		Cum	1	14.20	1.20	1.20	1.20	0.05	0.85		
49.00	52.70		Cum	1	3.70	2.00	1.20	1.60	0.05	0.30		
55.00	57.60		Cum	1	2.60	1.20	1.20	1.20	0.05	0.16		
60.00	70.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
71.50	85.00		Cum	1	13.50	0.50	0.50	0.50	0.05	0.34		
86.10	90.00		Cum	1	3.90	0.70	0.70	0.70	0.05	0.14		
93.50	103.00		Cum	1	9.50	1.10	1.10	1.10	0.05	0.52		
110.00	119.00		Cum	1	9.00	1.40	1.40	1.40	0.05	0.63		
120.00	132.00		Cum	1	12.00	1.60	1.60	1.60	0.05	0.96		
135.00	148.00		Cum	1	13.00	1.30	1.20	1.25	0.05	0.81		
150.00	158.00		Cum	1	8.00	1.20	1.20	1.20	0.05	0.48		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
3.00	10.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
13.00	24.00		Cum	1	11.00	1.60	1.60	1.60	0.05	0.88		
26.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
39.00	50.00		Cum	1	11.00	2.10	2.10	2.10	0.05	1.16		
54.00	64.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
66.00	75.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
82.00	90.00		Cum	1	8.00	1.80	1.80	1.80	0.05	0.72		
92.00	101.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
103.00	110.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
[illegible]00	118.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
120.00	123.00		Cum	1	3.00	1.10	1.10	1.10	0.05	0.17		
		11th Cross Road										
		North to South										
2.00	11.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
13.00	20.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
23.00	33.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
35.00	45.00		Cum	1	10.00	1.20	1.20	1.20	0.05	0.60		
50.00	60.00		Cum	1	10.00	1.10	1.10	1.10	0.05	0.55		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
74.00	80.00		Cum	1	6.00	1.90	1.90	1.90	0.05	0.57		
82.00	90.00		Cum	1	8.00	2.00	2.00	2.00	0.05	0.80		
93.00	100.00		Cum	1	7.00	2.00	2.00	2.00	0.05	0.70		
102.00	111.00		Cum	1	9.00	1.80	1.80	1.80	0.05	0.81		
115.00	122.00		Cum	1	7.00	1.70	1.70	1.70	0.05	0.60		
		17th Cross Road										
		North to South										
4.00	10.00		Cum	1	6.00	1.50	1.50	1.50	0.05	0.45		
13.00	23.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
25.00	36.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
49.00	59.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
63.00	72.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
75.00	84.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
86.00	98.00		Cum	1	12.00	1.80	1.80	1.80	0.05	1.08		
100.00	109.00		Cum	1	9.00	1.20	1.20	1.20	0.05	0.54		
		3rd Cross Road										
		North to South										
3.00	10.00		Cum	1	7.00	1.00	1.00	1.00	0.05	0.35		
13.00	24.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
26.00	35.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
37.00	47.00		Cum	1	10.00	1.80	1.80	1.80	0.05	0.90		
50.00	59.00		Cum	1	9.00	2.00	2.00	2.00	0.05	0.90		
		2nd Cross Road										
		North To South										
4.00	13.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
15.00	26.00		Cum	1	11.00	2.00	2.00	2.00	0.05	1.10		
28.00	36.00		Cum	1	8.00	1.30	1.30	1.30	0.05	0.52		
38.00	47.00		Cum	1	9.00	1.50	1.50	1.50	0.05	0.68		
50.00	60.00		Cum	1	10.00	1.50	1.50	1.50	0.05	0.75		
66.00	73.00		Cum	1	7.00	1.50	1.50	1.50	0.05	0.53		
										Total Executed Quantity	**1228.27**	
										Modified Schedule-B Quantity	**1000.70**	
										Quantity Upto 125%	**1228.27**	**10553.53**	**12962585.00**
Item no.20		**Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
0.00	7.10		Cum	1	7.10	2.20	3.00	2.60	0.04	0.74		
7.10	15.00		Cum	1	7.90	5.20	4.40	4.80	0.04	1.52		
15.00	30.00		Cum	1	15.00	4.40	6.30	5.35	0.04	3.21		
30.00	45.00		Cum	1	15.00	6.30	4.30	5.30	0.04	3.18		
45.00	60.00		Cum	1	15.00	4.30	4.65	4.48	0.04	2.69		
60.00	75.00		Cum	1	15.00	4.65	4.65	4.65	0.04	2.79		
75.00	90.00		Cum	1	15.00	4.65	4.40	4.53	0.04	2.72		
90.00	105.00		Cum	1	15.00	4.40	4.25	4.33	0.04	2.60		
105.00	112.00		Cum	1	7.00	4.25	5.30	4.78	0.04	1.34		
112.00	120.00		Cum	1	8.00	7.50	6.50	7.00	0.04	2.24		
120.00	135.00		Cum	1	15.00	5.40	5.40	5.40	0.04	3.24		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	145.00		Cum	1	10.00	5.40	5.60	5.50	0.04	2.20		
145.00	152.00		Cum	1	7.00	7.20	6.60	6.90	0.04	1.93		
152.00	165.00		Cum	1	13.00	6.60	6.30	6.45	0.04	3.35		
165.00	173.10		Cum	1	8.10	6.30	6.00	6.15	0.04	1.99		
173.10	180.00		Cum	1	6.90	3.60	3.50	3.55	0.04	0.98		
180.00	195.00		Cum	1	15.00	3.50	3.75	3.63	0.04	2.18		
195.00	200.80		Cum	1	5.80	3.75	6.30	5.03	0.04	1.17		
		Ravi Gowda Layout										
		(From North to South)										
0.00	3.50		Cum	1	3.50	6.90	6.90	6.90	0.04	0.97		
3.50	15.00		Cum	1	11.50	5.60	5.70	5.65	0.04	2.60		
15.00	30.00		Cum	1	15.00	5.70	5.20	5.45	0.04	3.27		
30.00	45.00		Cum	1	15.00	5.20	5.40	5.30	0.04	3.18		
45.00	60.00		Cum	1	15.00	5.40	3.90	4.65	0.04	2.79		
60.00	75.00		Cum	1	15.00	3.90	4.40	4.15	0.04	2.49		
75.00	90.00		Cum	1	15.00	4.40	5.00	4.70	0.04	2.82		
90.00	105.00		Cum	1	15.00	5.00	5.05	5.03	0.04	3.02		
105.00	120.00		Cum	1	15.00	5.05	4.90	4.98	0.04	2.99		
120.00	126.00		Cum	1	6.00	4.90	5.10	5.00	0.04	1.20		
126.00	135.00		Cum	1	9.00	4.50	4.35	4.43	0.04	1.59		
135.00	141.30		Cum	1	6.30	4.35	4.35	4.35	0.04	1.10		
141.30	150.00		Cum	1	8.70	5.35	5.00	5.18	0.04	1.80		
150.00	165.00		Cum	1	15.00	5.00	5.45	5.23	0.04	3.14		
165.00	180.00		Cum	1	15.00	5.45	4.95	5.20	0.04	3.12		
180.00	195.00		Cum	1	15.00	4.95	5.85	5.40	0.04	3.24		
195.00	210.00		Cum	1	15.00	5.85	5.30	5.58	0.04	3.35		
210.00	213.50		Cum	1	3.50	5.30	7.00	6.15	0.04	0.86		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.50	6.20	5.85	0.04	3.51		
15.00	30.00		Cum	1	15.00	6.20	5.50	5.85	0.04	3.51		
30.00	45.00		Cum	1	15.00	5.50	5.35	5.43	0.04	3.26		
45.00	58.70		Cum	1	13.70	5.35	4.90	5.13	0.04	2.81		
58.70	64.70		Cum	1	6.00	5.80	5.60	5.70	0.04	1.37		
64.70	69.20		Cum	1	4.50	4.70	5.00	4.85	0.04	0.87		
		Jai Rama Layout Main Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.00	4.40	4.20	0.04	2.52		
15.00	30.00		Cum	1	15.00	4.40	5.20	4.80	0.04	2.88		
30.00	45.00		Cum	1	15.00	5.20	4.40	4.80	0.04	2.88		
45.00	60.00		Cum	1	15.00	4.40	4.85	4.63	0.04	2.78		
60.00	75.00		Cum	1	15.00	4.85	4.90	4.88	0.04	2.93		
75.00	90.00		Cum	1	15.00	4.90	5.10	5.00	0.04	3.00		
90.00	105.00		Cum	1	15.00	5.10	6.50	5.80	0.04	3.48		
105.00	114.70		Cum	1	9.70	6.50	6.65	6.58	0.04	2.55		
114.70	118.30		Cum	1	3.60	6.65	8.30	7.48	0.04	1.08		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	6.35	6.00	6.18	0.04	3.71		
15.00	30.00		Cum	1	15.00	6.00	5.20	5.60	0.04	3.36		
30.00	45.00		Cum	1	15.00	5.20	5.50	5.35	0.04	3.21		
45.00	60.00		Cum	1	15.00	5.50	4.85	5.18	0.04	3.11		
60.00	67.90		Cum	1	7.90	4.85	5.30	5.08	0.04	1.60		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Cum	1	3.50	8.50	6.50	7.50	0.04	1.05		
3.50	15.00		Cum	1	11.50	6.50	7.00	6.75	0.04	3.11		
15.00	30.00		Cum	1	15.00	7.00	6.65	6.83	0.04	4.10		
30.00	45.00		Cum	1	15.00	6.65	7.10	6.88	0.04	4.13		
45.00	60.00		Cum	1	15.00	7.10	7.15	7.13	0.04	4.28		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	75.00		Cum	1	15.00	7.15	7.40	7.28	0.04	4.37		
75.00	90.00		Cum	1	15.00	7.40	7.00	7.20	0.04	4.32		
90.00	105.00		Cum	1	15.00	7.00	7.05	7.03	0.04	4.22		
105.00	120.00		Cum	1	15.00	7.05	8.15	7.60	0.04	4.56		
120.00	135.00		Cum	1	15.00	8.15	7.50	7.83	0.04	4.70		
135.00	150.00		Cum	1	15.00	7.50	7.40	7.45	0.04	4.47		
150.00	165.00		Cum	1	15.00	7.40	7.10	7.25	0.04	4.35		
165.00	180.00		Cum	1	15.00	7.10	7.80	7.45	0.04	4.47		
180.00	195.00		Cum	1	15.00	7.80	8.00	7.90	0.04	4.74		
195.00	210.00		Cum	1	15.00	8.00	7.05	7.53	0.04	4.52		
210.00	215.60		Cum	1	5.60	7.05	7.00	7.03	0.04	1.57		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Cum	1	3.40	6.10	4.80	5.45	0.04	0.74		
3.40	9.40		Cum	1	6.00	4.80	4.75	4.78	0.04	1.15		
9.40	18.50		Cum	1	9.10	4.15	4.60	4.38	0.04	1.59		
18.50	30.00		Cum	1	11.50	4.70	5.75	5.23	0.04	2.40		
30.00	37.80		Cum	1	7.80	5.75	5.40	5.58	0.04	1.74		
		2nd A Cross Road										
		(From North to South)										
0.00	4.30		Cum	1	4.30	5.80	5.00	5.40	0.04	0.93		
4.30	15.00		Cum	1	10.70	5.00	4.65	4.83	0.04	2.07		
15.00	30.00		Cum	1	15.00	4.65	4.50	4.58	0.04	2.75		
30.00	45.00		Cum	1	15.00	4.50	4.20	4.35	0.04	2.61		
45.00	60.00		Cum	1	15.00	4.20	5.00	4.60	0.04	2.76		
60.00	75.00		Cum	1	15.00	5.00	4.90	4.95	0.04	2.97		
75.00	90.00		Cum	1	15.00	4.90	4.30	4.60	0.04	2.76		
90.00	105.00		Cum	1	15.00	4.30	4.80	4.55	0.04	2.73		
105.00	111.10		Cum	1	6.10	4.80	4.75	4.78	0.04	1.17		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	5.20	5.30	5.25	0.04	3.15		
15.00	30.00		Cum	1	15.00	5.30	4.20	4.75	0.04	2.85		
30.00	45.00		Cum	1	15.00	4.20	5.10	4.65	0.04	2.79		
45.00	60.00		Cum	1	15.00	5.10	5.10	5.10	0.04	3.06		
60.00	75.00		Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
75.00	90.20		Cum	1	15.20	5.00	4.60	4.80	0.04	2.92		
90.20	94.40		Cum	1	4.20	6.00	6.40	6.20	0.04	1.04		
94.40	105.00		Cum	1	10.60	5.00	4.80	4.90	0.04	2.08		
105.00	109.20		Cum	1	4.20	4.80	4.90	4.85	0.04	0.81		
		2nd Cross Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	5.70	4.60	5.15	0.04	3.09		
15.00	30.00		Cum	1	15.00	4.60	4.90	4.75	0.04	2.85		
30.00	45.00		Cum	1	15.00	4.90	4.70	4.80	0.04	2.88		
45.00	60.00		Cum	1	15.00	4.70	4.80	4.75	0.04	2.85		
60.00	75.00		Cum	1	15.00	4.80	5.70	5.25	0.04	3.15		
75.00	90.00		Cum	1	15.00	5.70	6.00	5.85	0.04	3.51		
90.00	105.00		Cum	1	15.00	6.00	6.80	6.40	0.04	3.84		
105.00	120.00		Cum	1	15.00	6.80	7.15	6.98	0.04	4.19		
120.00	122.10		Cum	1	2.10	7.15	9.30	8.23	0.04	0.69		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.10	5.00	4.55	0.04	2.73		
15.00	30.00		Cum	1	15.00	5.00	4.25	4.63	0.04	2.78		
30.00	45.00		Cum	1	15.00	4.25	4.00	4.13	0.04	2.48		
45.00	60.00		Cum	1	15.00	4.00	4.30	4.15	0.04	2.49		
60.00	75.00		Cum	1	15.00	4.30	4.55	4.43	0.04	2.66		
75.00	90.00		Cum	1	15.00	4.55	4.45	4.50	0.04	2.70		
90.00	105.00		Cum	1	15.00	4.45	5.30	4.88	0.04	2.93		
105.00	120.00		Cum	1	15.00	5.30	5.65	5.48	0.04	3.29		
120.00	135.00		Cum	1	15.00	5.65	5.50	5.58	0.04	3.35		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
1.00	136.00		Cum	1	1.00	5.50	5.00	5.25	0.04	0.21		
		1st A K.V.J Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	3.90	3.65	3.78	0.04	2.27		
15.00	30.00		Cum	1	15.00	3.65	3.00	3.33	0.04	2.00		
30.00	33.30		Cum	1	3.30	3.00	3.40	3.20	0.04	0.42		
33.30	34.20		Cum	1	0.90	2.90	2.50	2.70	0.04	0.10		
		2nd Cross Road Sunshine apartment										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.45	5.05	5.25	0.04	3.15		
15.00	30.00		Cum	1	15.00	5.05	4.70	4.88	0.04	2.93		
30.00	45.00		Cum	1	15.00	4.70	4.95	4.83	0.04	2.90		
45.00	60.00		Cum	1	15.00	4.95	5.35	5.15	0.04	3.09		
60.00	67.20		Cum	1	7.20	5.35	5.40	5.38	0.04	1.55		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
0.00	9.90		Cum	1	9.90	5.35	4.80	5.08	0.04	2.01		
9.90	15.00		Cum	1	5.10	4.15	4.10	4.13	0.04	0.84		
15.00	30.00		Cum	1	15.00	4.10	4.60	4.35	0.04	2.61		
30.00	45.00		Cum	1	15.00	4.60	4.15	4.38	0.04	2.63		
45.00	60.00		Cum	1	15.00	4.15	4.25	4.20	0.04	2.52		
60.00	63.60		Cum	1	3.60	4.25	4.55	4.40	0.04	0.63		
63.60	66.70		Cum	1	3.10	3.90	3.50	3.70	0.04	0.46		
66.70	75.00		Cum	1	8.30	3.50	4.55	4.03	0.04	1.34		
75.00	79.50		Cum	1	4.50	4.55	4.30	4.43	0.04	0.80		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.30	3.50	3.90	0.04	2.34		
15.00	30.00		Cum	1	15.00	3.50	4.50	4.00	0.04	2.40		
30.00	45.00		Cum	1	15.00	4.50	4.85	4.68	0.04	2.81		
45.00	52.30		Cum	1	7.30	4.85	5.10	4.98	0.04	1.45		
52.30	55.00		Cum	1	2.70	3.35	3.10	3.23	0.04	0.35		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	7.00	6.60	6.80	0.04	4.08		
15.00	30.00		Cum	1	15.00	6.60	6.50	6.55	0.04	3.93		
30.00	45.00		Cum	1	15.00	6.50	6.45	6.48	0.04	3.89		
45.00	60.00		Cum	1	15.00	6.45	6.85	6.65	0.04	3.99		
60.00	75.00		Cum	1	15.00	6.85	6.95	6.90	0.04	4.14		
75.00	90.00		Cum	1	15.00	6.95	6.65	6.80	0.04	4.08		
90.00	98.80		Cum	1	8.80	6.65	4.85	5.75	0.04	2.02		
98.80	105.00		Cum	1	6.20	3.95	4.05	4.00	0.04	0.99		
105.00	120.00		Cum	1	15.00	4.05	4.45	4.25	0.04	2.55		
120.00	129.30		Cum	1	9.30	4.45	4.90	4.68	0.04	1.74		
129.30	131.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
131.50	138.00		Cum	1	6.50	5.20	5.15	5.18	0.04	1.35		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.30	6.60	6.45	0.04	3.87		
15.00	30.00		Cum	1	15.00	6.60	6.40	6.50	0.04	3.90		
30.00	45.00		Cum	1	15.00	6.40	5.60	6.00	0.04	3.60		
45.00	60.00		Cum	1	15.00	5.60	5.80	5.70	0.04	3.42		
60.00	75.00		Cum	1	15.00	5.80	5.55	5.68	0.04	3.41		
75.00	90.00		Cum	1	15.00	5.55	5.25	5.40	0.04	3.24		
90.00	105.00		Cum	1	15.00	5.25	5.60	5.43	0.04	3.26		
105.00	115.00		Cum	1	10.00	5.60	5.35	5.48	0.04	2.19		
		6th B Cross Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.60	5.25	4.93	0.04	2.96		
15.00	30.00		Cum	1	15.00	5.25	4.50	4.88	0.04	2.93		
30.00	45.00		Cum	1	15.00	4.50	4.90	4.70	0.04	2.82		
45.00	60.00		Cum	1	15.00	4.90	4.80	4.85	0.04	2.91		
60.00	75.00		Cum	1	15.00	4.80	4.70	4.75	0.04	2.85		
75.00	90.00		Cum	1	15.00	4.70	4.50	4.60	0.04	2.76		
90.00	105.00		Cum	1	15.00	4.50	4.50	4.50	0.04	2.70		
105.00	118.50		Cum	1	13.50	4.50	4.60	4.55	0.04	2.46		
		6th Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.95	4.85	4.90	0.04	2.94		
15.00	30.00		Cum	1	15.00	4.85	4.80	4.83	0.04	2.90		
30.00	45.00		Cum	1	15.00	4.80	4.50	4.65	0.04	2.79		
45.00	60.00		Cum	1	15.00	4.50	4.45	4.48	0.04	2.69		
60.00	75.00		Cum	1	15.00	4.45	4.10	4.28	0.04	2.57		
75.00	89.10		Cum	1	14.10	4.10	5.00	4.55	0.04	2.57		
89.10	90.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
90.30	105.00		Cum	1	14.70	4.65	4.45	4.55	0.04	2.68		
105.00	117.10		Cum	1	12.10	4.45	4.35	4.40	0.04	2.13		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
0.00	5.50		Cum	1	5.50	8.20	5.25	6.73	0.04	1.48		
5.50	15.00		Cum	1	9.50	5.25	4.75	5.00	0.04	1.90		
15.00	30.00		Cum	1	15.00	4.75	4.80	4.78	0.04	2.87		
30.00	45.00		Cum	1	15.00	4.80	4.80	4.80	0.04	2.88		
45.00	60.00		Cum	1	15.00	4.80	5.75	5.28	0.04	3.17		
60.00	62.50		Cum	1	2.50	5.75	5.60	5.68	0.04	0.57		
		10th Cross Road,13th main										
		(North To South)										
0.00	5.00		Cum	1	5.00	8.15	4.65	6.40	0.04	1.28		
5.00	15.00		Cum	1	10.00	4.65	5.05	4.85	0.04	1.94		
15.00	30.00		Cum	1	15.00	5.05	5.00	5.03	0.04	3.02		
30.00	32.30		Cum	1	2.30	5.00	4.00	4.50	0.04	0.41		
32.30	38.90		Cum	1	6.60	5.00	4.75	4.88	0.04	1.29		
		9th B Cross, 13th Main Road										
		(North To South)										
0.00	4.30		Cum	1	4.30	7.30	5.05	6.18	0.04	1.06		
4.30	15.00		Cum	1	10.70	5.05	4.70	4.88	0.04	2.09		
15.00	30.00		Cum	1	15.00	4.70	5.80	5.25	0.04	3.15		
30.00	30.60		Cum	1	0.60	5.80	5.75	5.78	0.04	0.14		
30.60	45.00		Cum	1	14.40	4.35	5.05	4.70	0.04	2.71		
45.00	60.00		Cum	1	15.00	5.05	4.60	4.83	0.04	2.90		
60.00	75.00		Cum	1	15.00	4.60	4.55	4.58	0.04	2.75		
75.00	90.00		Cum	1	15.00	3.40	4.20	3.80	0.04	2.28		
90.00	105.00		Cum	1	15.00	4.20	4.45	4.33	0.04	2.60		
105.00	120.00		Cum	1	15.00	4.45	4.10	4.28	0.04	2.57		
120.00	135.00		Cum	1	15.00	4.10	5.25	4.68	0.04	2.81		
135.00	138.10		Cum	1	3.10	5.25	5.15	5.20	0.04	0.64		
		9th A Cross, 13th main										
		(North To South)										
0.00	4.00		Cum	1	4.00	7.20	5.60	6.40	0.04	1.02		
4.00	15.00		Cum	1	11.00	5.60	5.15	5.38	0.04	2.37		
15.00	30.00		Cum	1	15.00	5.15	4.75	4.95	0.04	2.97		
30.00	45.00		Cum	1	15.00	4.75	4.35	4.55	0.04	2.73		
45.00	60.00		Cum	1	15.00	4.35	4.70	4.53	0.04	2.72		
60.00	75.00		Cum	1	15.00	4.70	5.05	4.88	0.04	2.93		
75.00	90.00		Cum	1	15.00	5.05	4.70	4.88	0.04	2.93		
90.00	105.00		Cum	1	15.00	4.70	3.85	4.28	0.04	2.57		
105.00	110.30		Cum	1	5.30	3.85	3.80	3.83	0.04	0.81		
		Deducation For Asphalt Road										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Manhole	Cum	-12	0.44				0.04	-0.21		
					(3.14X0.75X0.75)/4=0.44							
			Cum	-16	0.64				0.04	-0.41		
					(3.14X0.9X0.9)/4=0.64							
			Cum	-9	0.79				0.04	-0.28		
					(3.14X1X1)/4=0.79							
			Cum	-7	1.13				0.04	-0.32		
					(3.14X1.2X1.2)/4=1.13							
		Chamber										
			Cum	-21	0.90	0.70	0.70	0.70	0.04	-0.53		
			Cum	-3	1.00	0.60	0.60	0.60	0.04	-0.07		
		Tree Pot	Cum	-11	0.30	0.35	0.35	0.35	0.04	-0.05		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Cum	1	15.00	5.10	5.95	5.53	0.04	3.32		
15.00	27.10		Cum	1	12.10	5.95	4.70	5.33	0.04	2.58		
27.10	30.00		Cum	1	2.90	6.30	5.95	6.13	0.04	0.71		
30.00	45.00		Cum	1	15.00	5.95	4.95	5.45	0.04	3.27		
45.00	60.00		Cum	1	15.00	4.95	5.75	5.35	0.04	3.21		
60.00	75.00		Cum	1	15.00	5.75	5.80	5.78	0.04	3.47		
75.00	90.00		Cum	1	15.00	5.80	5.40	5.60	0.04	3.36		
90.00	105.00		Cum	1	15.00	5.40	5.30	5.35	0.04	3.21		
105.00	120.00		Cum	1	15.00	5.30	5.85	5.58	0.04	3.35		
120.00	135.00		Cum	1	15.00	5.85	6.55	6.20	0.04	3.72		
135.00	139.20		Cum	1	4.20	6.55	6.00	6.28	0.04	1.05		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Cum	1	15.00	7.85	7.00	7.43	0.04	4.46		
15.00	30.00		Cum	1	15.00	7.00	5.95	6.48	0.04	3.89		
30.00	38.40		Cum	1	8.40	5.95	5.60	5.78	0.04	1.94		
38.40	45.00		Cum	1	6.60	7.25	6.85	7.05	0.04	1.86		
45.00	60.00		Cum	1	15.00	6.85	6.10	6.48	0.04	3.89		
60.00	75.00		Cum	1	15.00	6.10	6.55	6.33	0.04	3.80		
75.00	90.00		Cum	1	15.00	6.55	6.70	6.63	0.04	3.98		
90.00	105.00		Cum	1	15.00	6.70	7.10	6.90	0.04	4.14		
105.00	113.00		Cum	1	8.00	7.10	7.00	7.05	0.04	2.26		
113.00	120.00		Cum	1	7.00	5.05	5.00	5.03	0.04	1.41		
120.00	126.20		Cum	1	6.20	5.00	5.10	5.05	0.04	1.25		
126.20	130.50		Cum	1	4.30	5.95	6.00	5.98	0.04	1.03		
130.50	135.00		Cum	1	4.50	6.00	6.15	6.08	0.04	1.09		
135.00	150.00		Cum	1	15.00	6.15	6.80	6.48	0.04	3.89		
150.00	165.00		Cum	1	15.00	6.80	6.75	6.78	0.04	4.07		
165.00	165.40		Cum	1	0.40	6.75	6.80	6.78	0.04	0.11		
165.40	180.00		Cum	1	14.60	6.30	6.35	6.33	0.04	3.69		
180.00	195.00		Cum	1	15.00	6.35	6.00	6.18	0.04	3.71		
195.00	210.00		Cum	1	15.00	6.00	5.90	5.95	0.04	3.57		
210.00	225.00		Cum	1	15.00	5.90	6.20	6.05	0.04	3.63		
225.00	240.00		Cum	1	15.00	6.20	5.75	5.98	0.04	3.59		
240.00	249.30		Cum	1	9.30	5.75	6.00	5.88	0.04	2.19		
249.30	258.30		Cum	1	9.00	5.10	4.65	4.88	0.04	1.76		
258.30	273.30		Cum	1	15.00	5.45	5.25	5.35	0.04	3.21		
273.30	275.00		Cum	1	1.70	5.25	5.25	5.25	0.04	0.36		
273.30	284.00		Cum	1	10.70	5.25	5.75	5.50	0.04	2.35		
		1st Cross Road										
		(From North To South)										
0.00	15.00		Cum	1	15.00	6.40	5.90	6.15	0.04	3.69		
15.00	25.90		Cum	1	10.90	5.90	6.00	5.95	0.04	2.59		
25.90	40.00		Cum	1	14.10	7.15	5.95	6.55	0.04	3.69		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	50.00		Cum	1	10.00	5.95	5.20	5.58	0.04	2.23		
50.00	60.00		Cum	1	10.00	5.20	4.35	4.78	0.04	1.91		
60.00	75.00		Cum	1	15.00	4.35	4.00	4.18	0.04	2.51		
75.00	90.00		Cum	1	15.00	4.00	4.95	4.48	0.04	2.69		
90.00	105.00		Cum	1	15.00	4.95	4.05	4.50	0.04	2.70		
105.00	120.00		Cum	1	15.00	4.05	4.25	4.15	0.04	2.49		
120.00	135.00		Cum	1	15.00	4.25	5.00	4.63	0.04	2.78		
135.00	148.80		Cum	1	13.80	5.00	4.95	4.98	0.04	2.75		
		Balaji Layout										
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
0.00	12.80		Cum	1	12.80	1.60	1.45	1.53	0.04	0.78		
12.80	15.00		Cum	1	2.20	3.15	3.20	3.18	0.04	0.28		
15.00	30.00		Cum	1	15.00	3.20	3.65	3.43	0.04	2.06		
30.00	45.00		Cum	1	15.00	3.65	4.35	4.00	0.04	2.40		
45.00	54.20		Cum	1	9.20	4.35	3.40	3.88	0.04	1.43		
54.20	55.80	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
55.80	60.00		Cum	1	4.20	3.55	5.40	4.48	0.04	0.75		
60.00	75.00		Cum	1	15.00	5.40	5.30	5.35	0.04	3.21		
75.00	89.00		Cum	1	14.00	5.30	5.45	5.38	0.04	3.01		
89.00	90.00		Cum	1	1.00	6.40	6.55	6.48	0.04	0.26		
90.00	105.00		Cum	1	15.00	6.55	6.60	6.58	0.04	3.95		
105.00	120.00		Cum	1	15.00	6.60	6.35	6.48	0.04	3.89		
120.00	135.00		Cum	1	15.00	6.35	5.95	6.15	0.04	3.69		
135.00	150.00		Cum	1	15.00	5.95	6.60	6.28	0.04	3.77		
150.00	165.00		Cum	1	15.00	6.60	6.60	6.60	0.04	3.96		
165.00	180.00		Cum	1	15.00	6.60	6.85	6.73	0.04	4.04		
180.00	195.00		Cum	1	15.00	6.85	6.60	6.73	0.04	4.04		
195.00	210.00		Cum	1	15.00	6.60	6.35	6.48	0.04	3.89		
210.00	225.00		Cum	1	15.00	6.35	5.90	6.13	0.04	3.68		
225.00	228.20		Cum	1	3.20	5.90	5.90	5.90	0.04	0.76		
228.20	232.00		Cum	1	3.80	7.10	6.20	6.65	0.04	1.01		
232.00	245.20		Cum	1	13.20	6.20	6.25	6.23	0.04	3.29		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
0.00	15.00		Cum	1	15.00	6.30	5.40	5.85	0.04	3.51		
15.00	30.00		Cum	1	15.00	5.40	4.60	5.00	0.04	3.00		
30.00	31.70		Cum	1	1.70	4.60	4.30	4.45	0.04	0.30		
31.70	43.60		Cum	1	11.90	5.20	4.30	4.75	0.04	2.26		
		(From West To East)										
0.00	3.90		Cum	1	3.90	5.40	5.60	5.50	0.04	0.86		
3.90	11.10		Cum	1	7.20	4.20	3.80	4.00	0.04	1.15		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	4.20	3.80	4.00	0.04	2.40		
15.00	18.80		Cum	1	3.80	3.80	3.30	3.55	0.04	0.54		
18.80	30.00		Cum	1	11.20	3.30	3.90	3.60	0.04	1.61		
30.00	45.00		Cum	1	15.00	3.90	3.85	3.88	0.04	2.33		
45.00	60.00		Cum	1	15.00	3.85	4.10	3.98	0.04	2.39		
60.00	75.00		Cum	1	15.00	4.10	4.20	4.15	0.04	2.49		
75.00	83.40		Cum	1	8.40	4.20	3.10	3.65	0.04	1.23		
83.40	91.90		Cum	1	8.50	3.10	3.10	3.10	0.04	1.05		
91.90	105.00		Cum	1	13.10	3.10	4.00	3.55	0.04	1.86		
105.00	120.00		Cum	1	15.00	4.00	4.00	4.00	0.04	2.40		
120.00	135.00		Cum	1	15.00	4.00	4.20	4.10	0.04	2.46		
135.00	150.00		Cum	1	15.00	4.20	4.10	4.15	0.04	2.49		
150.00	163.10		Cum	1	13.10	4.10	3.60	3.85	0.04	2.02		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		6th A Cross Road										
		(From West to East)										
0.00	7.80		Cum	1	7.80	11.20	8.60	9.90	0.04	3.09		
		(From South to North)										
0.00	7.40		Cum	1	7.40	7.80	6.90	7.35	0.04	2.18		
7.40	15.00		Cum	1	7.60	6.90	5.20	6.05	0.04	1.84		
15.00	30.00		Cum	1	15.00	5.20	5.10	5.15	0.04	3.09		
30.00	45.00		Cum	1	15.00	5.10	4.70	4.90	0.04	2.94		
45.00	50.70		Cum	1	5.70	4.70	4.70	4.70	0.04	1.07		
50.70	60.00		Cum	1	9.30	4.70	5.00	4.85	0.04	1.80		
60.00	75.00		Cum	1	15.00	5.00	6.10	5.55	0.04	3.33		
75.00	90.00		Cum	1	15.00	6.10	5.50	5.80	0.04	3.48		
90.00	105.00		Cum	1	15.00	5.50	6.00	5.75	0.04	3.45		
105.00	120.00		Cum	1	15.00	6.00	5.70	5.85	0.04	3.51		
120.00	135.00		Cum	1	15.00	5.70	5.90	5.80	0.04	3.48		
135.00	141.70		Cum	1	6.70	5.90	5.25	5.58	0.04	1.49		
		Devi Nagar Main Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	5.10	6.50	5.80	0.04	3.48		
15.00	30.00		Cum	1	15.00	6.50	6.10	6.30	0.04	3.78		
30.00	45.00		Cum	1	15.00	6.10	6.40	6.25	0.04	3.75		
45.00	60.00		Cum	1	15.00	6.40	6.50	6.45	0.04	3.87		
60.00	75.00		Cum	1	15.00	6.50	6.90	6.70	0.04	4.02		
75.00	90.00		Cum	1	15.00	6.90	6.60	6.75	0.04	4.05		
90.00	105.00		Cum	1	15.00	6.60	7.35	6.98	0.04	4.19		
105.00	120.00		Cum	1	15.00	7.35	7.00	7.18	0.04	4.31		
120.00	135.00		Cum	1	15.00	7.00	7.00	7.00	0.04	4.20		
135.00	150.00		Cum	1	15.00	7.00	5.20	6.10	0.04	3.66		
150.00	165.00		Cum	1	15.00	5.20	6.00	5.60	0.04	3.36		
165.00	180.00		Cum	1	15.00	6.00	4.90	5.45	0.04	3.27		
180.00	195.00		Cum	1	15.00	4.90	6.30	5.60	0.04	3.36		
195.00	210.00		Cum	1	15.00	6.30	5.60	5.95	0.04	3.57		
210.00	225.00		Cum	1	15.00	5.60	7.50	6.55	0.04	3.93		
225.00	237.20		Cum	1	12.20	7.50	7.00	7.25	0.04	3.54		
237.20	239.00		Cum	1	1.80	7.00	8.00	7.50	0.04	0.54		
239.00	241.50		Cum	1	2.50	8.00	12.00	10.00	0.04	1.00		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Cum	1	3.20	5.20	4.40	4.80	0.04	0.61		
3.20	15.00		Cum	1	11.80	5.70	5.60	5.65	0.04	2.67		
15.00	30.00		Cum	1	15.00	5.60	5.25	5.43	0.04	3.26		
30.00	45.00		Cum	1	15.00	5.25	4.50	4.88	0.04	2.93		
45.00	60.00		Cum	1	15.00	4.50	4.10	4.30	0.04	2.58		
60.00	75.00		Cum	1	15.00	4.10	5.30	4.70	0.04	2.82		
75.00	90.00		Cum	1	15.00	5.30	4.50	4.90	0.04	2.94		
90.00	105.00		Cum	1	15.00	4.50	5.25	4.88	0.04	2.93		
105.00	120.00		Cum	1	15.00	5.25	5.40	5.33	0.04	3.20		
120.00	135.00		Cum	1	15.00	5.40	4.70	5.05	0.04	3.03		
135.00	150.00		Cum	1	15.00	4.70	4.60	4.65	0.04	2.79		
150.00	165.00		Cum	1	15.00	4.60	5.10	4.85	0.04	2.91		
165.00	180.00		Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
180.00	184.70		Cum	1	4.70	5.00	5.10	5.05	0.04	0.95		
184.70	186.20		Cum	1	1.50	5.10	5.10	5.10	0.04	0.31		
186.20	195.00		Cum	1	8.80	5.10	5.30	5.20	0.04	1.83		
195.00	210.00		Cum	1	15.00	5.30	4.45	4.88	0.04	2.93		
210.00	225.00		Cum	1	15.00	4.45	4.90	4.68	0.04	2.81		
225.00	240.00		Cum	1	15.00	4.90	5.20	5.05	0.04	3.03		
240.00	255.00		Cum	1	15.00	5.20	4.40	4.80	0.04	2.88		
255.00	270.00		Cum	1	15.00	4.40	5.10	4.75	0.04	2.85		
270.00	285.00		Cum	1	15.00	5.10	5.10	5.10	0.04	3.06		
285.00	293.70		Cum	1	8.70	5.10	5.70	5.40	0.04	1.88		
293.70	298.70		Cum	1	5.00	4.90	5.00	4.95	0.04	0.99		
298.70	300.00		Cum	1	1.30	5.80	5.20	5.50	0.04	0.29		
300.00	315.00		Cum	1	15.00	5.20	5.05	5.13	0.04	3.08		
315.00	330.00		Cum	1	15.00	5.05	4.90	4.98	0.04	2.99		
330.00	344.60		Cum	1	14.60	4.90	3.70	4.30	0.04	2.51		
344.60	360.00		Cum	1	15.40	5.10	4.90	5.00	0.04	3.08		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
3[illegible]00	363.50		Cum	1	3.50	4.90	4.90	4.90	0.04	0.69		
363.50	372.30		Cum	1	8.80	4.30	4.90	4.60	0.04	1.62		
372.30	387.30		Cum	1	15.00	3.90	4.15	4.03	0.04	2.42		
387.30	390.00		Cum	1	2.70	4.15	5.05	4.60	0.04	0.50		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	5.70	5.00	5.35	0.04	3.21		
15.00	29.50		Cum	1	14.50	5.00	5.20	5.10	0.04	2.96		
29.50	47.20	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
47.20	60.00		Cum	1	12.80	4.90	4.95	4.93	0.04	2.52		
60.00	75.00		Cum	1	15.00	4.95	5.80	5.38	0.04	3.23		
75.00	90.00		Cum	1	15.00	5.80	6.20	6.00	0.04	3.60		
90.00	105.00		Cum	1	15.00	6.20	6.60	6.40	0.04	3.84		
105.00	120.00		Cum	1	15.00	6.60	6.80	6.70	0.04	4.02		
120.00	135.00		Cum	1	15.00	6.80	7.50	7.15	0.04	4.29		
135.00	150.30		Cum	1	15.30	7.50	8.60	8.05	0.04	4.93		
150.30	158.50		Cum	1	8.20	8.60	8.60	8.60	0.04	2.82		
158.50	165.30		Cum	1	6.80	8.60	7.30	7.95	0.04	2.16		
165.30	180.30		Cum	1	15.00	7.30	6.80	7.05	0.04	4.23		
180.30	189.60		Cum	1	9.30	6.80	8.10	7.45	0.04	2.77		
189.60	193.50		Cum	1	3.90	8.10	9.60	8.85	0.04	1.38		
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Cum	1	4.00	6.30	6.25	6.28	0.04	1.00		
4.00	15.00		Cum	1	11.00	6.25	6.60	6.43	0.04	2.83		
15.00	24.10		Cum	1	9.10	6.60	6.40	6.50	0.04	2.37		
24.10	30.00		Cum	1	5.90	5.50	5.10	5.30	0.04	1.25		
30.00	38.10		Cum	1	8.10	5.10	4.50	4.80	0.04	1.56		
38.10	46.00		Cum	1	7.90	5.20	5.80	5.50	0.04	1.74		
46.00	60.00		Cum	1	14.00	4.70	6.50	5.60	0.04	3.14		
60.00	67.00		Cum	1	7.00	6.50	7.70	7.10	0.04	1.99		
67.00	75.00		Cum	1	8.00	7.70	5.90	6.80	0.04	2.18		
75.00	83.50		Cum	1	8.50	5.90	5.70	5.80	0.04	1.97		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	5.60	5.50	5.55	0.04	3.33		
15.00	30.00		Cum	1	15.00	5.50	5.90	5.70	0.04	3.42		
30.00	45.00		Cum	1	15.00	5.90	5.90	5.90	0.04	3.54		
45.00	60.00		Cum	1	15.00	6.60	6.55	6.58	0.04	3.95		
60.00	75.00		Cum	1	15.00	6.55	5.60	6.08	0.04	3.65		
75.00	87.00		Cum	1	12.00	5.60	6.10	5.85	0.04	2.81		
87.00	90.00		Cum	1	3.00	6.10	5.80	5.95	0.04	0.71		
90.00	105.00		Cum	1	15.00	5.80	5.90	5.85	0.04	3.51		
105.00	120.00		Cum	1	15.00	5.90	5.20	5.55	0.04	3.33		
120.00	129.20		Cum	1	9.20	5.20	5.70	5.45	0.04	2.01		
129.20	135.00		Cum	1	5.80	5.70	5.70	5.70	0.04	1.32		
135.00	150.00		Cum	1	15.00	5.70	5.70	5.70	0.04	3.42		
150.00	165.00		Cum	1	15.00	5.70	5.50	5.60	0.04	3.36		
165.00	180.00		Cum	1	15.00	5.50	5.20	5.35	0.04	3.21		
180.00	195.00		Cum	1	15.00	5.20	4.00	4.60	0.04	2.76		
195.00	210.00		Cum	1	15.00	4.00	4.15	4.08	0.04	2.45		
210.00	221.50		Cum	1	11.50	4.15	4.50	4.33	0.04	1.99		
		1st Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.00	4.20	4.10	0.04	2.46		
15.00	17.10		Cum	1	2.10	4.20	4.40	4.30	0.04	0.36		
17.10	22.80		Cum	1	5.70	3.50	3.50	3.50	0.04	0.80		
22.80	30.00		Cum	1	7.20	2.80	2.60	2.70	0.04	0.78		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	45.00		Cum	1	15.00	2.60	2.40	2.50	0.04	1.50		
45.00	54.00		Cum	1	9.00	2.40	2.80	2.60	0.04	0.94		
54.00	60.00		Cum	1	6.00	2.80	2.60	2.70	0.04	0.65		
60.00	75.00		Cum	1	15.00	2.60	3.00	2.80	0.04	1.68		
75.00	85.20		Cum	1	10.20	3.00	3.00	3.00	0.04	1.22		
		2nd Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.10	3.40	3.75	0.04	2.25		
15.00	30.00		Cum	1	15.00	3.40	3.90	3.65	0.04	2.19		
30.00	45.00		Cum	1	15.00	3.90	4.00	3.95	0.04	2.37		
45.00	60.00		Cum	1	15.00	4.00	3.30	3.65	0.04	2.19		
60.00	75.00		Cum	1	15.00	3.30	2.50	2.90	0.04	1.74		
75.00	82.10		Cum	1	7.10	2.50	2.60	2.55	0.04	0.72		
		2nd A Cross Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	5.20	4.50	4.85	0.04	2.91		
15.00	30.00		Cum	1	15.00	4.50	4.65	4.58	0.04	2.75		
30.00	44.90		Cum	1	14.90	4.65	3.30	3.98	0.04	2.37		
		3rd Cross Road										
		(From North to South)										
0.00	4.20		Cum	1	4.20	4.20	4.20	4.20	0.04	0.71		
4.20	15.00		Cum	1	10.80	4.20	4.30	4.25	0.04	1.84		
15.00	30.00		Cum	1	15.00	4.30	4.10	4.20	0.04	2.52		
30.00	45.00		Cum	1	15.00	4.10	4.15	4.13	0.04	2.48		
45.00	52.20		Cum	1	7.20	4.15	4.20	4.18	0.04	1.20		
52.20	60.00		Cum	1	7.80	2.60	2.35	2.48	0.04	0.77		
60.00	67.30		Cum	1	7.30	2.50	2.50	2.50	0.04	0.73		
67.30	70.60		Cum	1	3.30	2.50	3.30	2.90	0.04	0.38		
70.60	85.00		Cum	1	14.40	3.60	3.45	3.53	0.04	2.03		
85.00	90.00		Cum	1	5.00	3.45	3.50	3.48	0.04	0.70		
90.00	92.10		Cum	1	2.10	3.50	3.40	3.45	0.04	0.29		
92.10	95.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
95.30	105.00		Cum	1	9.70	4.00	4.10	4.05	0.04	1.57		
105.00	108.90		Cum	1	3.90	4.00	4.10	4.05	0.04	0.63		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	6.15	6.15	6.15	0.04	3.69		
15.00	30.00		Cum	1	15.00	5.40	5.50	5.45	0.04	3.27		
30.00	45.00		Cum	1	15.00	5.50	6.00	5.75	0.04	3.45		
45.00	47.80		Cum	1	2.80	6.00	6.10	6.05	0.04	0.68		
47.80	56.10		Cum	1	8.30	5.30	5.00	5.15	0.04	1.71		
56.10	63.90		Cum	1	7.80	5.85	4.90	5.38	0.04	1.68		
63.90	65.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
65.50	75.00		Cum	1	9.50	5.65	5.65	5.65	0.04	2.15		
75.00	90.00		Cum	1	15.00	5.65	4.60	5.13	0.04	3.08		
90.00	94.50		Cum	1	4.50	4.60	6.05	5.33	0.04	0.96		
94.50	105.00		Cum	1	10.50	6.05	6.70	6.38	0.04	2.68		
105.00	120.00		Cum	1	15.00	6.70	6.15	6.43	0.04	3.86		
120.00	122.00		Cum	1	2.00	6.15	5.15	5.65	0.04	0.45		
122.00	135.00		Cum	1	13.00	5.65	5.45	5.55	0.04	2.89		
135.00	150.00		Cum	1	15.00	5.45	4.80	5.13	0.04	3.08		
150.00	154.00		Cum	1	4.00	4.80	6.50	5.65	0.04	0.90		
154.00	163.70		Cum	1	9.70	6.50	6.65	6.58	0.04	2.55		
163.70	169.70		Cum	1	6.00	8.10	6.65	7.38	0.04	1.77		
169.70	171.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
171.20	180.00		Cum	1	8.80	7.30	7.35	7.33	0.04	2.58		
180.00	181.80		Cum	1	1.80	7.35	6.70	7.03	0.04	0.51		
181.80	190.00		Cum	1	8.20	6.70	7.15	6.93	0.04	2.27		
190.00	205.00		Cum	1	15.00	7.15	7.50	7.33	0.04	4.40		
205.00	216.10		Cum	1	11.10	7.50	8.50	8.00	0.04	3.55		
216.10	231.10		Cum	1	15.00	8.50	7.15	7.83	0.04	4.70		
231.10	235.00		Cum	1	3.90	7.15	7.40	7.28	0.04	1.13		
235.00	250.00		Cum	1	15.00	7.40	7.00	7.20	0.04	4.32		
250.00	265.00		Cum	1	15.00	7.00	7.20	7.10	0.04	4.26		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	280.00		Cum	1	15.00	7.20	5.30	6.25	0.04	3.75		
280.00	295.00		Cum	1	15.00	5.30	4.70	5.00	0.04	3.00		
295.00	300.00		Cum	1	5.00	4.70	4.85	4.78	0.04	0.96		
300.00	315.00		Cum	1	15.00	4.85	5.35	5.10	0.04	3.06		
315.00	330.00		Cum	1	15.00	5.35	5.85	5.60	0.04	3.36		
330.00	345.00		Cum	1	15.00	5.85	5.50	5.68	0.04	3.41		
345.00	360.00		Cum	1	15.00	5.50	6.15	5.83	0.04	3.50		
360.00	369.00		Cum	1	9.00	6.15	5.95	6.05	0.04	2.18		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Cum	1	15.00	8.40	6.80	7.60	0.04	4.56		
15.00	29.20		Cum	1	14.20	6.80	6.90	6.85	0.04	3.89		
29.20	30.30	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
30.30	45.00		Cum	1	14.70	6.85	6.70	6.78	0.04	3.98		
45.00	60.00		Cum	1	15.00	6.70	6.60	6.65	0.04	3.99		
60.00	75.00		Cum	1	15.00	6.60	6.40	6.50	0.04	3.90		
75.00	90.00		Cum	1	15.00	6.40	5.75	6.08	0.04	3.65		
90.00	105.00		Cum	1	15.00	5.75	6.15	5.95	0.04	3.57		
105.00	108.50		Cum	1	3.50	5.60	5.60	5.60	0.04	0.78		
108.50	118.70		Cum	1	10.20	4.70	4.90	4.80	0.04	1.96		
118.70	124.80		Cum	1	6.10	6.25	6.85	6.55	0.04	1.60		
124.80	135.00		Cum	1	10.20	6.10	5.90	6.00	0.04	2.45		
135.00	150.00		Cum	1	15.00	5.90	6.10	6.00	0.04	3.60		
150.00	165.00		Cum	1	15.00	6.10	6.05	6.08	0.04	3.65		
165.00	180.00		Cum	1	15.00	6.05	6.10	6.08	0.04	3.65		
180.00	195.00		Cum	1	15.00	6.10	6.15	6.13	0.04	3.68		
195.00	210.00		Cum	1	15.00	6.15	6.45	6.30	0.04	3.78		
210.00	225.00		Cum	1	15.00	6.45	6.20	6.33	0.04	3.80		
225.00	240.00		Cum	1	15.00	6.20	6.15	6.18	0.04	3.71		
240.00	255.00		Cum	1	15.00	6.15	6.10	6.13	0.04	3.68		
255.00	270.00		Cum	1	15.00	6.10	6.40	6.25	0.04	3.75		
270.00	285.00		Cum	1	15.00	6.40	7.10	6.75	0.04	4.05		
285.00	291.50		Cum	1	6.50	7.10	7.20	7.15	0.04	1.86		
291.50	298.00		Cum	1	6.50	6.70	5.70	6.20	0.04	1.61		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	6.80	6.70	6.75	0.04	4.05		
15.00	17.20		Cum	1	2.20	6.70	5.80	6.25	0.04	0.55		
17.20	30.00		Cum	1	12.80	5.80	5.10	5.45	0.04	2.79		
30.00	41.00		Cum	1	11.00	5.10	4.90	5.00	0.04	2.20		
41.00	50.20		Cum	1	9.20	4.85	5.40	5.13	0.04	1.89		
		2nd Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	6.30	5.25	5.78	0.04	3.47		
15.00	30.00		Cum	1	15.00	5.25	5.25	5.25	0.04	3.15		
30.00	45.00		Cum	1	15.00	5.25	5.15	5.20	0.04	3.12		
45.00	50.20		Cum	1	5.20	5.15	5.20	5.18	0.04	1.08		
50.20	52.80		Cum	1	2.60	2.40	2.50	2.45	0.04	0.25		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	6.40	6.45	6.43	0.04	3.86		
15.00	30.00		Cum	1	15.00	6.45	5.10	5.78	0.04	3.47		
30.00	45.00		Cum	1	15.00	5.10	5.65	5.38	0.04	3.23		
45.00	60.00		Cum	1	15.00	5.65	4.35	5.00	0.04	3.00		
60.00	63.30		Cum	1	3.30	4.35	5.40	4.88	0.04	0.64		
63.30	75.00		Cum	1	11.70	6.30	6.34	6.32	0.04	2.96		
75.00	90.00		Cum	1	15.00	6.34	6.70	6.52	0.04	3.91		
90.00	105.00		Cum	1	15.00	6.70	6.60	6.65	0.04	3.99		
105.00	120.00		Cum	1	15.00	6.60	7.05	6.83	0.04	4.10		
120.00	132.90		Cum	1	12.90	7.05	7.00	7.03	0.04	3.62		
132.90	147.10		Cum	1	14.20	5.80	5.95	5.88	0.04	3.34		
147.10	160.00		Cum	1	12.90	5.30	5.20	5.25	0.04	2.71		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	165.00		Cum	1	5.00	6.55	6.00	6.28	0.04	1.26		
165.00	180.00		Cum	1	15.00	6.00	6.80	6.40	0.04	3.84		
180.00	195.00		Cum	1	15.00	6.80	6.10	6.45	0.04	3.87		
195.00	198.80		Cum	1	3.80	6.10	6.10	6.10	0.04	0.93		
198.80	210.00		Cum	1	11.20	5.50	5.50	5.50	0.04	2.46		
210.00	219.70		Cum	1	9.70	5.50	5.90	5.70	0.04	2.21		
219.70	222.20	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
222.20	225.00		Cum	1	2.80	6.85	6.80	6.83	0.04	0.76		
225.00	240.00		Cum	1	15.00	6.80	6.40	6.60	0.04	3.96		
240.00	249.60		Cum	1	9.60	6.40	6.90	6.65	0.04	2.55		
249.60	257.30		Cum	1	7.70	7.60	7.50	7.55	0.04	2.33		
257.30	260.00		Cum	1	2.70	6.35	6.30	6.33	0.04	0.68		
260.00	275.00		Cum	1	15.00	6.30	6.40	6.35	0.04	3.81		
275.00	292.00		Cum	1	17.00	6.40	6.40	6.40	0.04	4.35		
292.00	297.10		Cum	1	5.10	7.20	7.40	7.30	0.04	1.49		
297.10	300.00		Cum	1	2.90	6.40	6.60	6.50	0.04	0.75		
300.00	315.00		Cum	1	15.00	6.60	7.10	6.85	0.04	4.11		
315.00	330.00		Cum	1	15.00	7.10	6.60	6.85	0.04	4.11		
330.00	345.00		Cum	1	15.00	6.60	6.55	6.58	0.04	3.95		
345.00	360.00		Cum	1	15.00	6.55	7.35	6.95	0.04	4.17		
360.00	375.00		Cum	1	15.00	7.35	7.40	7.38	0.04	4.43		
375.00	390.00		Cum	1	15.00	7.40	6.85	7.13	0.04	4.28		
390.00	405.00		Cum	1	15.00	6.85	7.20	7.03	0.04	4.22		
405.00	414.50		Cum	1	9.50	7.20	7.55	7.38	0.04	2.80		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Cum	1	15.00	6.50	6.10	6.30	0.04	3.78		
15.00	30.00		Cum	1	15.00	6.10	7.00	6.55	0.04	3.93		
30.00	45.00		Cum	1	15.00	7.00	5.90	6.45	0.04	3.87		
45.00	60.00		Cum	1	15.00	5.90	6.20	6.05	0.04	3.63		
60.00	69.30		Cum	1	9.30	6.20	5.75	5.98	0.04	2.22		
69.30	75.00		Cum	1	5.70	4.60	4.10	4.35	0.04	0.99		
75.00	90.00		Cum	1	15.00	4.10	5.50	4.80	0.04	2.88		
90.00	105.00		Cum	1	15.00	5.50	5.05	5.28	0.04	3.17		
105.00	111.40		Cum	1	6.40	5.05	7.00	6.03	0.04	1.54		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Cum	1	4.60	6.70	6.80	6.75	0.04	1.24		
4.60	15.00		Cum	1	10.40	6.80	6.30	6.55	0.04	2.72		
15.00	30.00		Cum	1	15.00	6.30	5.75	6.03	0.04	3.62		
30.00	45.00		Cum	1	15.00	5.75	5.00	5.38	0.04	3.23		
45.00	60.00		Cum	1	15.00	5.00	6.25	5.63	0.04	3.38		
60.00	75.00		Cum	1	15.00	6.25	6.10	6.18	0.04	3.71		
75.00	90.00		Cum	1	15.00	6.10	5.80	5.95	0.04	3.57		
90.00	100.30		Cum	1	10.30	5.80	5.80	5.80	0.04	2.39		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Cum	1	15.00	4.20	4.00	4.10	0.04	2.46		
15.00	30.00		Cum	1	15.00	4.00	3.70	3.85	0.04	2.31		
30.00	45.00		Cum	1	15.00	3.70	3.60	3.65	0.04	2.19		
45.00	60.00		Cum	1	15.00	3.60	3.90	3.75	0.04	2.25		
60.00	73.50		Cum	1	13.50	3.90	4.00	3.95	0.04	2.13		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Cum	1	15.00	3.60	3.75	3.68	0.04	2.21		
15.00	30.00		Cum	1	15.00	3.75	4.10	3.93	0.04	2.36		
30.00	45.00		Cum	1	15.00	4.10	3.90	4.00	0.04	2.40		
45.00	60.00		Cum	1	15.00	3.90	4.25	4.08	0.04	2.45		
60.00	75.00		Cum	1	15.00	4.25	4.00	4.13	0.04	2.48		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	81.00		Cum	1	6.00	4.00	4.30	4.15	0.04	1.00		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Cum	1	15.00	5.95	5.85	5.90	0.04	3.54		
15.00	30.00		Cum	1	15.00	5.85	5.60	5.73	0.04	3.44		
30.00	45.00		Cum	1	15.00	5.60	5.15	5.38	0.04	3.23		
45.00	60.00		Cum	1	15.00	5.15	5.55	5.35	0.04	3.21		
60.00	75.00		Cum	1	15.00	5.55	5.80	5.68	0.04	3.41		
75.00	90.00		Cum	1	15.00	5.80	5.90	5.85	0.04	3.51		
90.00	95.80		Cum	1	5.80	5.90	5.50	5.70	0.04	1.32		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Cum	1	15.00	5.80	4.85	5.33	0.04	3.20		
15.00	26.20		Cum	1	11.20	4.85	3.90	4.38	0.04	1.96		
		(North To South)										
0.00	15.00		Cum	1	15.00	5.40	5.60	5.50	0.04	3.30		
15.00	30.00		Cum	1	15.00	5.60	5.45	5.53	0.04	3.32		
30.00	45.00		Cum	1	15.00	5.45	5.95	5.70	0.04	3.42		
45.00	60.00		Cum	1	15.00	5.95	5.80	5.88	0.04	3.53		
60.00	75.00		Cum	1	15.00	5.80	6.80	6.30	0.04	3.78		
75.00	90.00		Cum	1	15.00	6.80	6.00	6.40	0.04	3.84		
90.00	105.00		Cum	1	15.00	6.00	7.20	6.60	0.04	3.96		
105.00	120.00		Cum	1	15.00	7.20	5.80	6.50	0.04	3.90		
120.00	135.00		Cum	1	15.00	5.80	7.00	6.40	0.04	3.84		
135.00	150.00		Cum	1	15.00	7.00	5.70	6.35	0.04	3.81		
150.00	165.00		Cum	1	15.00	5.70	7.20	6.45	0.04	3.87		
165.00	169.00		Cum	1	4.00	7.20	6.90	7.05	0.04	1.13		
		Deducation										
		Manhole	Cum	-16	0.44				0.04	-0.28		
						(3.14X0.75X0.75)/4=0.44						
			Cum	-14	0.64				0.04	-0.36		
						(3.14X0.9X0.9)/4=0.64						
			Cum	-13	0.79				0.04	-0.41		
						(3.14X1X1)/4=0.79						
			Cum	-7	1.13				0.04	-0.32		
						(3.14X1.2X1.2)/4=1.13						
		Chamber										
			Cum	-19	0.90	0.70	0.70	0.70	0.04	-0.48		
			Cum	-3	1.00	0.60	0.60	0.60	0.04	-0.07		
		Tree Pot	Cum	-12	0.30	0.35	0.35	0.35	0.04	-0.05		
		Ward No 10										
		Vidyaranyapura Sub division										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
0.00	15.00		Cum	1	15.00	8.70	5.70	7.20	0.04	4.32		
15.00	20.80		Cum	1	5.80	5.70	5.50	5.60	0.04	1.30		
20.80	30.00		Cum	1	9.20	6.00	6.05	6.03	0.04	2.22		
30.00	45.00		Cum	1	15.00	6.05	5.20	5.63	0.04	3.38		
45.00	53.60		Cum	1	8.60	5.20	5.30	5.25	0.04	1.81		
53.60	60.00		Cum	1	6.40	6.35	5.80	6.08	0.04	1.56		
60.00	75.00		Cum	1	15.00	5.80	5.55	5.68	0.04	3.41		
75.00	90.00		Cum	1	15.00	5.55	5.15	5.35	0.04	3.21		
90.00	105.00		Cum	1	15.00	5.15	5.35	5.25	0.04	3.15		
105.00	120.00		Cum	1	15.00	5.35	4.70	5.03	0.04	3.02		
120.00	135.00		Cum	1	15.00	4.70	4.65	4.68	0.04	2.81		
135.00	150.00		Cum	1	15.00	4.65	4.70	4.68	0.04	2.81		
150.00	165.00		Cum	1	15.00	4.70	5.15	4.93	0.04	2.96		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	180.00		Cum	1	15.00	5.15	6.10	5.63	0.04	3.38		
180.00	195.00		Cum	1	15.00	6.10	6.35	6.23	0.04	3.74		
195.00	203.30		Cum	1	8.30	6.35	7.00	6.68	0.04	2.22		
203.30	205.80		Cum	1	2.50	7.00	7.80	7.40	0.04	0.74		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
0.00	3.10		Cum	1	3.10	7.50	5.00	6.25	0.04	0.78		
3.10	15.00		Cum	1	11.90	5.00	4.80	4.90	0.04	2.33		
15.00	30.00		Cum	1	15.00	4.80	4.70	4.75	0.04	2.85		
30.00	45.00		Cum	1	15.00	4.70	5.10	4.90	0.04	2.94		
45.00	60.00		Cum	1	15.00	5.10	5.05	5.08	0.04	3.05		
60.00	75.00		Cum	1	15.00	5.05	4.70	4.88	0.04	2.93		
75.00	90.00		Cum	1	15.00	4.70	4.70	4.70	0.04	2.82		
90.00	105.00		Cum	1	15.00	4.70	4.65	4.68	0.04	2.81		
105.00	120.00		Cum	1	15.00	4.65	5.00	4.83	0.04	2.90		
120.00	135.00		Cum	1	15.00	5.00	4.65	4.83	0.04	2.90		
135.00	150.00		Cum	1	15.00	4.65	4.40	4.53	0.04	2.72		
150.00	165.00		Cum	1	15.00	4.40	4.95	4.68	0.04	2.81		
165.00	180.00		Cum	1	15.00	4.95	4.80	4.88	0.04	2.93		
180.00	195.00		Cum	1	15.00	4.80	5.05	4.93	0.04	2.96		
195.00	210.00		Cum	1	15.00	5.05	5.60	5.33	0.04	3.20		
210.00	225.00		Cum	1	15.00	5.60	5.10	5.35	0.04	3.21		
225.00	240.00		Cum	1	15.00	6.70	6.70	6.70	0.04	4.02		
240.00	245.30		Cum	1	5.30	6.70	5.20	5.95	0.04	1.26		
245.30	255.00		Cum	1	9.70	5.20	5.90	5.55	0.04	2.15		
255.00	270.00		Cum	1	15.00	5.90	6.40	6.15	0.04	3.69		
270.00	277.40		Cum	1	7.40	6.40	6.60	6.50	0.04	1.92		
277.40	285.00		Cum	1	7.60	5.70	5.60	5.65	0.04	1.72		
285.00	300.00		Cum	1	15.00	5.60	6.00	5.80	0.04	3.48		
300.00	303.00		Cum	1	3.00	6.00	6.20	6.10	0.04	0.73		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.70	5.15	5.43	0.04	3.26		
15.00	25.20		Cum	1	10.20	5.15	5.60	5.38	0.04	2.19		
25.20	33.90		Cum	1	8.70	6.30	6.10	6.20	0.04	2.16		
33.90	45.00		Cum	1	11.10	5.55	5.55	5.55	0.04	2.46		
45.00	60.00		Cum	1	15.00	5.55	6.95	6.25	0.04	3.75		
60.00	75.00		Cum	1	15.00	6.95	6.20	6.58	0.04	3.95		
75.00	90.00		Cum	1	15.00	6.20	5.75	5.98	0.04	3.59		
90.00	105.00		Cum	1	15.00	5.75	5.80	5.78	0.04	3.47		
105.00	109.10		Cum	1	4.10	5.80	5.90	5.85	0.04	0.96		
109.10	120.00		Cum	1	10.90	5.00	5.10	5.05	0.04	2.20		
120.00	135.00		Cum	1	15.00	5.10	4.65	4.88	0.04	2.93		
135.00	142.80		Cum	1	7.80	4.65	5.80	5.23	0.04	1.63		
142.80	150.00		Cum	1	7.20	4.90	4.35	4.63	0.04	1.33		
150.00	154.80		Cum	1	4.80	4.35	4.35	4.35	0.04	0.84		
154.80	165.00		Cum	1	10.20	5.60	6.15	5.88	0.04	2.40		
165.00	172.80		Cum	1	7.80	6.15	5.90	6.03	0.04	1.88		
172.80	180.00		Cum	1	7.20	4.90	4.50	4.70	0.04	1.35		
180.00	181.40		Cum	1	1.40	4.50	4.45	4.48	0.04	0.25		
181.40	195.00		Cum	1	13.60	5.65	5.00	5.33	0.04	2.90		
195.00	209.40		Cum	1	14.40	5.00	4.60	4.80	0.04	2.76		
209.40	221.00		Cum	1	11.60	5.85	6.40	6.13	0.04	2.84		
		Samashana Road										
		2nd main Road										
		(From East to West)										
0.00	11.80		Cum	1	11.80	4.25	3.95	4.10	0.04	1.94		
11.80	15.00		Cum	1	3.20	4.45	5.40	4.93	0.04	0.63		
15.00	30.00		Cum	1	15.00	5.40	5.80	5.60	0.04	3.36		
30.00	45.00		Cum	1	15.00	5.80	5.80	5.80	0.04	3.48		
45.00	60.00		Cum	1	15.00	5.80	5.20	5.50	0.04	3.30		
60.00	75.00		Cum	1	15.00	5.20	5.55	5.38	0.04	3.23		
75.00	90.00		Cum	1	15.00	5.55	5.05	5.30	0.04	3.18		
90.00	105.00		Cum	1	15.00	5.05	6.10	5.58	0.04	3.35		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	120.00		Cum	1	15.00	6.10	5.60	5.85	0.04	3.51		
120.00	135.00		Cum	1	15.00	5.60	6.35	5.98	0.04	3.59		
135.00	140.50		Cum	1	5.50	6.35	6.80	6.58	0.04	1.45		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
0.00	15.50		Cum	1	15.50	5.40	6.75	6.08	0.04	3.77		
15.50	30.00		Cum	1	14.50	5.40	5.75	5.58	0.04	3.23		
30.00	45.00		Cum	1	15.00	5.75	5.70	5.73	0.04	3.44		
45.00	46.40		Cum	1	1.40	5.70	6.00	5.85	0.04	0.33		
46.40	60.00		Cum	1	13.60	4.70	5.30	5.00	0.04	2.72		
60.00	75.00		Cum	1	15.00	6.15	5.00	5.58	0.04	3.35		
75.00	90.00		Cum	1	15.00	5.00	5.20	5.10	0.04	3.06		
90.00	105.10		Cum	1	15.10	5.20	5.00	5.10	0.04	3.08		
105.10	120.00		Cum	1	14.90	5.85	5.85	5.85	0.04	3.49		
120.00	126.50		Cum	1	6.50	5.85	5.70	5.78	0.04	1.50		
126.50	135.00		Cum	1	8.50	5.40	5.95	5.68	0.04	1.93		
135.00	141.90		Cum	1	6.90	5.95	6.20	6.08	0.04	1.68		
141.90	150.00		Cum	1	8.10	6.60	6.30	6.45	0.04	2.09		
150.00	154.10		Cum	1	4.10	6.30	6.40	6.35	0.04	1.04		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
0.00	15.60		Cum	1	15.60	5.60	5.70	5.65	0.04	3.53		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Cum	1	1.60	3.20	5.80	4.50	0.04	0.29		
1.60	15.00		Cum	1	13.40	5.80	5.00	5.40	0.04	2.89		
15.00	30.00		Cum	1	15.00	5.00	5.75	5.38	0.04	3.23		
30.00	45.00		Cum	1	15.00	5.75	6.30	6.03	0.04	3.62		
45.00	60.00		Cum	1	15.00	6.30	5.90	6.10	0.04	3.66		
60.00	75.00		Cum	1	15.00	5.90	6.10	6.00	0.04	3.60		
75.00	79.10		Cum	1	4.10	6.10	5.95	6.03	0.04	0.99		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
0.00	15.00		Cum	1	15.00	6.40	6.60	6.50	0.04	3.90		
15.00	23.30		Cum	1	8.30	6.60	6.70	6.65	0.04	2.21		
		From house no #15 to house no -7										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.50	6.00	5.75	0.04	3.45		
15.00	30.00		Cum	1	15.00	6.00	6.10	6.05	0.04	3.63		
30.00	45.00		Cum	1	15.00	6.10	5.50	5.80	0.04	3.48		
45.00	60.00		Cum	1	15.00	5.50	6.80	6.15	0.04	3.69		
60.00	75.00		Cum	1	15.00	6.80	5.90	6.35	0.04	3.81		
75.00	79.00		Cum	1	4.00	5.90	5.65	5.78	0.04	0.92		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.00	5.90	5.95	0.04	3.57		
15.00	29.60		Cum	1	14.60	5.90	4.00	4.95	0.04	2.89		
29.60	38.70		Cum	1	9.10	5.10	4.20	4.65	0.04	1.69		
38.70	45.00		Cum	1	6.30	5.60	5.95	5.78	0.04	1.46		
45.00	60.00		Cum	1	15.00	5.95	5.65	5.80	0.04	3.48		
60.00	75.00		Cum	1	15.00	5.65	5.10	5.38	0.04	3.23		
75.00	84.00		Cum	1	9.00	6.05	5.80	5.93	0.04	2.13		
84.00	90.00		Cum	1	6.00	4.50	4.65	4.58	0.04	1.10		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	103.00		Cum	1	13.00	4.65	5.85	5.25	0.04	2.73		
103.00	105.00		Cum	1	2.00	6.50	6.50	6.50	0.04	0.52		
105.00	120.00		Cum	1	15.00	6.50	5.15	5.83	0.04	3.50		
120.00	135.00		Cum	1	15.00	5.15	4.75	4.95	0.04	2.97		
135.00	150.00		Cum	1	15.00	4.75	5.40	5.08	0.04	3.05		
150.00	153.30		Cum	1	3.30	5.40	5.50	5.45	0.04	0.72		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
0.00	15.00		Cum	1	15.00	6.10	5.00	5.55	0.04	3.33		
15.00	30.00		Cum	1	15.00	5.00	4.70	4.85	0.04	2.91		
30.00	45.00		Cum	1	15.00	4.70	5.45	5.08	0.04	3.05		
45.00	47.30		Cum	1	2.30	5.45	5.50	5.48	0.04	0.50		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
0.00	15.00		Cum	1	15.00	5.45	3.50	4.48	0.04	2.69		
15.00	30.00		Cum	1	15.00	3.50	4.95	4.23	0.04	2.54		
30.00	45.00		Cum	1	15.00	4.95	4.95	4.95	0.04	2.97		
45.00	60.00		Cum	1	15.00	4.95	4.40	4.68	0.04	2.81		
60.00	75.00		Cum	1	15.00	4.40	4.70	4.55	0.04	2.73		
75.00	90.00		Cum	1	15.00	4.70	4.90	4.80	0.04	2.88		
90.00	105.00		Cum	1	15.00	4.90	4.80	4.85	0.04	2.91		
105.00	112.00		Cum	1	7.00	4.80	5.10	4.95	0.04	1.39		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
0.00	15.00		Cum	1	15.00	4.95	4.50	4.73	0.04	2.84		
15.00	30.00		Cum	1	15.00	4.50	4.00	4.25	0.04	2.55		
30.00	45.00		Cum	1	15.00	4.00	3.75	3.88	0.04	2.33		
45.00	50.10		Cum	1	5.10	3.75	3.60	3.68	0.04	0.75		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	6.30	5.25	5.78	0.04	3.47		
15.00	30.00		Cum	1	15.00	5.25	5.20	5.23	0.04	3.14		
30.00	45.00		Cum	1	15.00	5.20	5.45	5.33	0.04	3.20		
45.00	60.00		Cum	1	15.00	5.45	5.10	5.28	0.04	3.17		
60.00	75.10		Cum	1	15.10	5.10	5.80	5.45	0.04	3.29		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	6.40	6.45	6.43	0.04	3.86		
15.00	30.00		Cum	1	15.00	6.45	6.00	6.23	0.04	3.74		
30.00	34.30		Cum	1	4.30	6.00	6.10	6.05	0.04	1.04		
34.30	45.00		Cum	1	10.70	5.15	5.70	5.43	0.04	2.32		
45.00	60.00		Cum	1	15.00	5.70	5.75	5.73	0.04	3.44		
60.00	75.00		Cum	1	15.00	5.75	5.50	5.63	0.04	3.38		
75.00	90.00		Cum	1	15.00	5.50	5.65	5.58	0.04	3.35		
90.00	105.00		Cum	1	15.00	5.65	5.50	5.58	0.04	3.35		
105.00	120.00		Cum	1	15.00	5.50	5.40	5.45	0.04	3.27		
120.00	135.00		Cum	1	15.00	5.40	5.25	5.33	0.04	3.20		
135.00	150.00		Cum	1	15.00	5.25	5.05	5.15	0.04	3.09		
150.00	165.00		Cum	1	15.00	5.05	5.10	5.08	0.04	3.05		
165.00	180.00		Cum	1	15.00	5.10	5.10	5.10	0.04	3.06		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	187.20		Cum	1	7.20	5.10	5.10	5.10	0.04	1.47		
187.20	195.00		Cum	1	7.80	5.45	6.10	5.78	0.04	1.80		
195.00	210.00		Cum	1	15.00	6.10	7.20	6.65	0.04	3.99		
210.00	215.40		Cum	1	5.40	7.20	7.25	7.23	0.04	1.56		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.65	5.90	5.78	0.04	3.47		
15.00	30.00		Cum	1	15.00	5.90	5.85	5.88	0.04	3.53		
30.00	32.30		Cum	1	2.30	5.85	5.25	5.55	0.04	0.51		
32.30	36.20		Cum	1	3.90	5.75	5.75	5.75	0.04	0.90		
36.20	44.00		Cum	1	7.80	4.85	4.60	4.73	0.04	1.47		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	1.10		Cum	1	1.10	3.70	4.95	4.33	0.04	0.19		
1.10	15.00		Cum	1	13.90	4.95	5.85	5.40	0.04	3.00		
15.00	30.00		Cum	1	15.00	5.85	5.60	5.73	0.04	3.44		
30.00	45.00		Cum	1	15.00	5.60	6.05	5.83	0.04	3.50		
45.00	60.00		Cum	1	15.00	6.05	5.60	5.83	0.04	3.50		
60.00	75.00		Cum	1	15.00	5.60	5.75	5.68	0.04	3.41		
75.00	90.00		Cum	1	15.00	5.75	5.40	5.58	0.04	3.35		
90.00	105.00		Cum	1	15.00	5.40	5.50	5.45	0.04	3.27		
105.00	119.50		Cum	1	14.50	5.50	5.50	5.50	0.04	3.19		
119.50	120.80		Cum	1	1.30	5.50	7.45	6.48	0.04	0.34		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
0.00	2.90		Cum	1	2.90	6.75	5.65	6.20	0.04	0.72		
2.90	15.00		Cum	1	12.10	5.65	5.10	5.38	0.04	2.60		
15.00	30.00		Cum	1	15.00	5.10	4.75	4.93	0.04	2.96		
30.00	45.00		Cum	1	15.00	4.75	5.50	5.13	0.04	3.08		
45.00	60.00		Cum	1	15.00	5.50	5.10	5.30	0.04	3.18		
60.00	75.00		Cum	1	15.00	5.10	5.60	5.35	0.04	3.21		
75.00	90.00		Cum	1	15.00	5.60	5.20	5.40	0.04	3.24		
90.00	105.00		Cum	1	15.00	5.20	5.45	5.33	0.04	3.20		
105.00	120.00		Cum	1	15.00	5.45	5.20	5.33	0.04	3.20		
120.00	135.00		Cum	1	15.00	5.20	5.95	5.58	0.04	3.35		
135.00	150.00		Cum	1	15.00	5.95	5.75	5.85	0.04	3.51		
150.00	163.70		Cum	1	13.70	5.75	5.40	5.58	0.04	3.06		
163.70	165.00		Cum	1	1.30	4.85	5.00	4.93	0.04	0.26		
165.00	180.00		Cum	1	15.00	5.00	5.00	5.00	0.04	3.00		
180.00	195.00		Cum	1	15.00	5.00	5.00	5.00	0.04	3.00		
195.00	200.20		Cum	1	5.20	5.00	5.50	5.25	0.04	1.09		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
0.00	1.80		Cum	1	1.80	7.60	5.90	6.75	0.04	0.49		
1.80	15.00		Cum	1	13.20	5.90	5.10	5.50	0.04	2.90		
15.00	30.00		Cum	1	15.00	5.10	5.00	5.05	0.04	3.03		
30.00	45.00		Cum	1	15.00	5.00	5.60	5.30	0.04	3.18		
45.00	60.00		Cum	1	15.00	5.60	5.30	5.45	0.04	3.27		
60.00	65.50		Cum	1	5.50	5.30	5.20	5.25	0.04	1.16		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
0.00	2.00		Cum	1	2.00	6.80	5.60	6.20	0.04	0.50		
2.00	15.00		Cum	1	13.00	5.60	5.80	5.70	0.04	2.96		
15.00	30.00		Cum	1	15.00	5.80	5.50	5.65	0.04	3.39		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	45.00		Cum	1	15.00	5.50	5.80	5.65	0.04	3.39		
45.00	60.00		Cum	1	15.00	5.80	5.40	5.60	0.04	3.36		
60.00	75.00		Cum	1	15.00	5.40	5.50	5.45	0.04	3.27		
75.00	90.00		Cum	1	15.00	5.50	5.45	5.48	0.04	3.29		
90.00	105.00		Cum	1	15.00	5.45	5.45	5.45	0.04	3.27		
105.00	120.00		Cum	1	15.00	5.45	5.30	5.38	0.04	3.23		
120.00	127.60		Cum	1	7.60	5.30	5.80	5.55	0.04	1.69		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
0.00	3.20		Cum	1	3.20	6.20	5.15	5.68	0.04	0.73		
3.20	15.00		Cum	1	11.80	5.15	6.00	5.58	0.04	2.63		
15.00	30.00		Cum	1	15.00	6.00	5.20	5.60	0.04	3.36		
30.00	45.00		Cum	1	15.00	5.20	5.50	5.35	0.04	3.21		
45.00	60.00		Cum	1	15.00	5.50	5.30	5.40	0.04	3.24		
60.00	75.00		Cum	1	15.00	5.30	5.50	5.40	0.04	3.24		
75.00	90.00		Cum	1	15.00	5.50	5.85	5.68	0.04	3.41		
90.00	105.00		Cum	1	15.00	5.85	4.90	5.38	0.04	3.23		
105.00	120.00		Cum	1	15.00	4.90	5.50	5.20	0.04	3.12		
120.00	128.30		Cum	1	8.30	5.50	5.60	5.55	0.04	1.84		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
0.00	2.60		Cum	1	2.60	5.75	6.00	5.88	0.04	0.61		
2.60	15.00		Cum	1	12.40	6.00	5.80	5.90	0.04	2.93		
15.00	30.00		Cum	1	15.00	5.80	4.90	5.35	0.04	3.21		
30.00	45.00		Cum	1	15.00	4.90	5.00	4.95	0.04	2.97		
45.00	60.00		Cum	1	15.00	5.00	6.00	5.50	0.04	3.30		
60.00	75.00		Cum	1	15.00	6.00	5.90	5.95	0.04	3.57		
75.00	80.80		Cum	1	5.80	5.90	6.00	5.95	0.04	1.38		
80.80	83.40		Cum	1	2.60	6.00	6.30	6.15	0.04	0.64		
		BEL LAYOUT										
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
0.00	4.00		Cum	1	4.00	6.35	6.30	6.33	0.04	1.01		
4.00	15.00		Cum	1	11.00	6.30	6.65	6.48	0.04	2.85		
15.00	30.00		Cum	1	15.00	6.65	6.40	6.53	0.04	3.92		
30.00	45.00		Cum	1	15.00	6.40	6.65	6.53	0.04	3.92		
45.00	60.00		Cum	1	15.00	6.65	6.70	6.68	0.04	4.01		
60.00	75.00		Cum	1	15.00	6.70	6.70	6.70	0.04	4.02		
75.00	90.00		Cum	1	15.00	6.70	6.20	6.45	0.04	3.87		
90.00	105.00		Cum	1	15.00	6.20	6.75	6.48	0.04	3.89		
105.00	120.00		Cum	1	15.00	6.75	5.80	6.28	0.04	3.77		
120.00	135.00		Cum	1	15.00	5.80	5.15	5.48	0.04	3.29		
135.00	150.00		Cum	1	15.00	5.15	6.40	5.78	0.04	3.47		
150.00	165.00		Cum	1	15.00	6.40	6.40	6.40	0.04	3.84		
165.00	180.00		Cum	1	15.00	6.40	5.80	6.10	0.04	3.66		
180.00	195.00		Cum	1	15.00	5.80	6.30	6.05	0.04	3.63		
195.00	210.00		Cum	1	15.00	6.30	6.75	6.53	0.04	3.92		
210.00	225.00		Cum	1	15.00	6.75	5.80	6.28	0.04	3.77		
225.00	240.00		Cum	1	15.00	5.80	6.45	6.13	0.04	3.68		
240.00	255.00		Cum	1	15.00	6.45	5.90	6.18	0.04	3.71		
255.00	270.00		Cum	1	15.00	5.90	6.00	5.95	0.04	3.57		
270.00	285.00		Cum	1	15.00	6.00	4.80	5.40	0.04	3.24		
285.00	300.40		Cum	1	15.40	4.80	4.45	4.63	0.04	2.85		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	15.00		Cum	1	15.00	6.35	6.30	6.33	0.04	3.80		
15.00	30.00		Cum	1	15.00	6.30	6.10	6.20	0.04	3.72		
30.00	45.00		Cum	1	15.00	6.10	5.85	5.98	0.04	3.59		
45.00	60.00		Cum	1	15.00	5.85	5.50	5.68	0.04	3.41		
60.00	75.00		Cum	1	15.00	5.50	6.60	6.05	0.04	3.63		
75.00	90.00		Cum	1	15.00	6.60	6.30	6.45	0.04	3.87		
90.00	101.20		Cum	1	11.20	6.30	6.65	6.48	0.04	2.90		
101.20	104.80		Cum	1	3.60	5.95	5.95	5.95	0.04	0.86		
104.80	120.00		Cum	1	15.20	6.60	6.50	6.55	0.04	3.98		
120.00	132.60		Cum	1	12.60	6.50	6.80	6.65	0.04	3.35		
132.60	136.60		Cum	1	4.00	7.85	8.20	8.03	0.04	1.28		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Cum	1	3.70	5.45	5.50	5.48	0.04	0.81		
3.70	5.50	Culvert	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
5.50	15.00		Cum	1	9.50	5.45	5.05	5.25	0.04	2.00		
15.00	30.00		Cum	1	15.00	5.05	5.35	5.20	0.04	3.12		
30.00	40.80		Cum	1	10.80	5.35	4.65	5.00	0.04	2.16		
40.80	45.00		Cum	1	4.20	4.10	4.05	4.08	0.04	0.68		
45.00	60.10		Cum	1	15.10	4.05	5.35	4.70	0.04	2.84		
		9th A Cross Road										
		(From South to North)										
0.00	3.70		Cum	1	3.70	4.95	5.00	4.98	0.04	0.74		
3.70	15.00		Cum	1	11.30	5.00	4.65	4.83	0.04	2.18		
15.00	17.10		Cum	1	2.10	4.65	4.60	4.63	0.04	0.39		
		9th Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	4.80	3.95	4.38	0.04	2.63		
15.00	30.00		Cum	1	15.00	3.95	3.75	3.85	0.04	2.31		
30.00	45.00		Cum	1	15.00	3.75	4.30	4.03	0.04	2.42		
45.00	60.00		Cum	1	15.00	4.30	5.00	4.65	0.04	2.79		
60.00	75.00		Cum	1	15.00	5.00	4.30	4.65	0.04	2.79		
75.00	90.90		Cum	1	15.90	4.30	4.25	4.28	0.04	2.72		
90.90	98.80		Cum	1	7.90	3.80	4.70	4.25	0.04	1.34		
		7th A Cross Road										
		(From South to North)										
0.00	4.20		Cum	1	4.20	4.85	4.85	4.85	0.04	0.81		
4.20	9.10		Cum	1	4.90	4.25	4.50	4.38	0.04	0.86		
9.10	15.00		Cum	1	5.90	4.90	4.90	4.90	0.04	1.16		
15.00	18.30		Cum	1	3.30	4.90	4.95	4.93	0.04	0.65		
		7th Cross Road										
		(From North to South)										
0.00	3.00		Cum	1	3.00	6.50	4.75	5.63	0.04	0.68		
3.00	15.00		Cum	1	12.00	4.75	4.00	4.38	0.04	2.10		
15.00	30.00		Cum	1	15.00	4.00	4.35	4.18	0.04	2.51		
30.00	45.00		Cum	1	15.00	4.35	4.60	4.48	0.04	2.69		
45.00	60.00		Cum	1	15.00	4.60	4.55	4.58	0.04	2.75		
60.00	75.00		Cum	1	15.00	4.55	4.50	4.53	0.04	2.72		
75.00	84.50		Cum	1	9.50	4.50	4.60	4.55	0.04	1.73		
84.50	90.00		Cum	1	5.50	4.40	4.55	4.48	0.04	0.98		
90.00	99.20		Cum	1	9.20	4.55	4.50	4.53	0.04	1.67		
		6th Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.60	4.70	5.15	0.04	3.09		
15.00	30.00		Cum	1	15.00	4.70	4.80	4.75	0.04	2.85		
30.00	45.00		Cum	1	15.00	4.80	4.45	4.63	0.04	2.78		
45.00	60.00		Cum	1	15.00	4.45	4.60	4.53	0.04	2.72		
60.00	75.00		Cum	1	15.00	4.60	5.30	4.95	0.04	2.97		
75.00	90.00		Cum	1	15.00	5.30	5.00	5.15	0.04	3.09		
90.00	92.30		Cum	1	2.30	5.00	5.05	5.03	0.04	0.46		
92.30	95.90		Cum	1	3.60	3.90	3.80	3.85	0.04	0.55		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		6th A Cross Road										
		(From South to North)										
0.00	9.60		Cum	1	9.60	5.60	5.50	5.55	0.04	2.13		
9.60	15.00		Cum	1	5.40	4.95	4.25	4.60	0.04	0.99		
15.00	18.30		Cum	1	3.30	4.25	4.35	4.30	0.04	0.57		
		5th Cross Road										
		(From North to South)										
0.00	15.00		Cum	1	15.00	5.35	4.60	4.98	0.04	2.99		
15.00	30.00		Cum	1	15.00	4.60	4.00	4.30	0.04	2.58		
30.00	45.00		Cum	1	15.00	4.00	3.70	3.85	0.04	2.31		
45.00	60.00		Cum	1	15.00	3.70	3.70	3.70	0.04	2.22		
60.00	74.80		Cum	1	14.80	3.70	4.00	3.85	0.04	2.28		
74.80	83.40		Cum	1	8.60	4.65	5.20	4.93	0.04	1.69		
83.40	91.60		Cum	1	8.20	4.40	4.80	4.60	0.04	1.51		
91.60	95.00		Cum	1	3.40	4.60	4.50	4.55	0.04	0.62		
		5th A Cross Road										
		(From South to North)										
0.00	4.00		Cum	1	4.00	5.15	4.60	4.88	0.04	0.78		
4.00	15.00		Cum	1	11.00	4.00	4.30	4.15	0.04	1.83		
15.00	20.60		Cum	1	5.60	4.30	4.50	4.40	0.04	0.99		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
0.00	15.00		Cum	1	15.00	6.90	7.20	7.05	0.04	4.23		
15.00	30.00		Cum	1	15.00	7.20	7.25	7.23	0.04	4.34		
30.00	45.00		Cum	1	15.00	7.25	6.30	6.78	0.04	4.07		
45.00	60.00		Cum	1	15.00	6.30	7.50	6.90	0.04	4.14		
60.00	75.00		Cum	1	15.00	7.50	7.35	7.43	0.04	4.46		
75.00	90.00		Cum	1	15.00	7.35	7.45	7.40	0.04	4.44		
90.00	105.00		Cum	1	15.00	7.45	7.45	7.45	0.04	4.47		
105.00	120.00		Cum	1	15.00	7.45	6.90	7.18	0.04	4.31		
120.00	135.00		Cum	1	15.00	6.90	6.85	6.88	0.04	4.13		
135.00	150.00		Cum	1	15.00	6.85	6.10	6.48	0.04	3.89		
150.00	165.00		Cum	1	15.00	6.10	7.05	6.58	0.04	3.95		
165.00	180.00		Cum	1	15.00	7.05	6.85	6.95	0.04	4.17		
180.00	195.00		Cum	1	15.00	6.85	7.05	6.95	0.04	4.17		
195.00	210.00		Cum	1	15.00	7.05	6.80	6.93	0.04	4.16		
210.00	225.00		Cum	1	15.00	6.80	6.15	6.48	0.04	3.89		
225.00	240.00		Cum	1	15.00	6.15	6.45	6.30	0.04	3.78		
240.00	255.00		Cum	1	15.00	6.45	6.20	6.33	0.04	3.80		
255.00	270.00		Cum	1	15.00	6.20	6.25	6.23	0.04	3.74		
270.00	285.00		Cum	1	15.00	6.25	6.40	6.33	0.04	3.80		
285.00	300.00		Cum	1	15.00	6.40	6.75	6.58	0.04	3.95		
300.00	308.90		Cum	1	8.90	6.75	6.55	6.65	0.04	2.37		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
0.00	10.00		Cum	1	10.00	6.15	5.85	6.00	0.04	2.40		
10.00	24.70		Cum	1	14.70	5.05	4.50	4.78	0.04	2.81		
24.70	30.00		Cum	1	5.30	4.50	4.40	4.45	0.04	0.94		
30.00	45.00		Cum	1	15.00	5.15	5.40	5.28	0.04	3.17		
45.00	60.00		Cum	1	15.00	5.40	6.05	5.73	0.04	3.44		
60.00	75.00		Cum	1	15.00	6.05	6.10	6.08	0.04	3.65		
75.00	90.00		Cum	1	15.00	6.10	6.05	6.08	0.04	3.65		
90.00	105.00		Cum	1	15.00	6.05	5.75	5.90	0.04	3.54		
105.00	120.00		Cum	1	15.00	5.75	5.30	5.53	0.04	3.32		
120.00	135.00		Cum	1	15.00	5.30	6.00	5.65	0.04	3.39		
135.00	150.00		Cum	1	15.00	6.00	5.50	5.75	0.04	3.45		
150.00	165.00		Cum	1	15.00	5.50	5.20	5.35	0.04	3.21		
165.00	180.00		Cum	1	15.00	5.20	6.05	5.63	0.04	3.38		
180.00	181.20		Cum	1	1.20	6.05	6.10	6.08	0.04	0.29		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
0.00	15.00		Cum	1	15.00	7.10	6.65	6.88	0.04	4.13		
15.00	30.00		Cum	1	15.00	6.65	6.25	6.45	0.04	3.87		
30.00	45.00		Cum	1	15.00	6.25	7.10	6.68	0.04	4.01		
45.00	60.00		Cum	1	15.00	7.10	6.40	6.75	0.04	4.05		
60.00	75.00		Cum	1	15.00	6.40	6.05	6.23	0.04	3.74		
75.00	90.00		Cum	1	15.00	6.05	5.60	5.83	0.04	3.50		
90.00	105.00		Cum	1	15.00	5.60	5.60	5.60	0.04	3.36		
105.00	120.00		Cum	1	15.00	5.60	5.40	5.50	0.04	3.30		
120.00	135.00		Cum	1	15.00	5.40	5.50	5.45	0.04	3.27		
135.00	150.00		Cum	1	15.00	5.50	5.45	5.48	0.04	3.29		
150.00	161.50		Cum	1	11.50	5.45	5.45	5.45	0.04	2.51		
161.50	168.60		Cum	1	7.10	5.45	5.50	5.48	0.04	1.55		
168.60	170.00		Cum	1	1.40	5.50	6.85	6.18	0.04	0.35		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
0.00	15.00		Cum	1	15.00	6.10	6.50	6.30	0.04	3.78		
15.00	30.00		Cum	1	15.00	6.50	6.80	6.65	0.04	3.99		
30.00	45.00		Cum	1	15.00	6.80	6.85	6.83	0.04	4.10		
45.00	52.70		Cum	1	7.70	6.85	6.05	6.45	0.04	1.99		
52.70	57.60		Cum	1	4.90	3.80	3.85	3.83	0.04	0.75		
57.60	70.00		Cum	1	12.40	5.90	6.60	6.25	0.04	3.10		
70.00	85.00		Cum	1	15.00	6.60	6.40	6.50	0.04	3.90		
85.00	90.00		Cum	1	5.00	6.40	6.30	6.35	0.04	1.27		
90.00	105.00		Cum	1	15.00	6.30	5.90	6.10	0.04	3.66		
105.00	120.00		Cum	1	15.00	5.90	6.00	5.95	0.04	3.57		
120.00	135.00		Cum	1	15.00	6.00	6.05	6.03	0.04	3.62		
135.00	150.00		Cum	1	15.00	6.05	6.30	6.18	0.04	3.71		
150.00	159.10		Cum	1	9.10	6.30	6.90	6.60	0.04	2.40		
		Nanjappa Layout										
		12th Cross Road										
		North To South										
0.00	15.00		Cum	1	15.00	5.45	5.15	5.30	0.04	3.18		
15.00	30.00		Cum	1	15.00	5.15	4.25	4.70	0.04	2.82		
30.00	45.00		Cum	1	15.00	4.25	4.00	4.13	0.04	2.48		
45.00	60.00		Cum	1	15.00	4.00	4.30	4.15	0.04	2.49		
60.00	69.20		Cum	1	9.20	4.30	4.10	4.20	0.04	1.55		
69.20	75.00		Cum	1	5.80	3.90	3.65	3.78	0.04	0.88		
75.00	90.00		Cum	1	15.00	3.65	4.20	3.93	0.04	2.36		
90.00	105.00		Cum	1	15.00	4.20	4.90	4.55	0.04	2.73		
105.00	120.00		Cum	1	15.00	4.90	5.00	4.95	0.04	2.97		
120.00	122.70		Cum	1	2.70	5.00	5.00	5.00	0.04	0.54		
122.70	124.80		Cum	1	2.10	5.00	5.95	5.48	0.04	0.46		
		11th Cross Road										
		North to South										
0.00	9.80		Cum	1	9.80	5.30	4.50	4.90	0.04	1.92		
9.80	15.00		Cum	1	5.20	3.70	3.75	3.73	0.04	0.77		
15.00	30.00		Cum	1	15.00	3.75	4.60	4.18	0.04	2.51		
30.00	45.00		Cum	1	15.00	4.60	5.00	4.80	0.04	2.88		
45.00	60.00		Cum	1	15.00	5.00	5.40	5.20	0.04	3.12		
60.00	75.00		Cum	1	15.00	3.90	4.10	4.00	0.04	2.40		
75.00	90.00		Cum	1	15.00	4.10	4.75	4.43	0.04	2.66		
90.00	105.00		Cum	1	15.00	4.75	3.45	4.10	0.04	2.46		
105.00	106.40		Cum	1	1.40	3.45	3.40	3.43	0.04	0.19		
106.40	120.00		Cum	1	13.60	3.85	4.30	4.08	0.04	2.22		
120.00	129.10		Cum	1	9.10	4.30	4.55	4.43	0.04	1.61		
		17th Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	4.90	4.60	4.75	0.04	2.85		
15.00	30.00		Cum	1	15.00	4.60	4.30	4.45	0.04	2.67		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	45.00		Cum	1	15.00	4.30	4.10	4.20	0.04	2.52		
45.00	60.00		Cum	1	15.00	4.10	4.00	4.05	0.04	2.43		
60.00	75.00		Cum	1	15.00	4.00	4.55	4.28	0.04	2.57		
75.00	90.00		Cum	1	15.00	4.55	4.20	4.38	0.04	2.63		
90.00	105.00		Cum	1	15.00	4.20	4.15	4.18	0.04	2.51		
105.00	120.00		Cum	1	15.00	4.15	4.60	4.38	0.04	2.63		
120.00	131.80		Cum	1	11.80	4.60	5.25	4.93	0.04	2.32		
		3rd Cross Road										
		North to South										
0.00	15.00		Cum	1	15.00	3.90	4.95	4.43	0.04	2.66		
15.00	30.00		Cum	1	15.00	4.95	4.40	4.68	0.04	2.81		
30.00	45.00		Cum	1	15.00	4.40	4.90	4.65	0.04	2.79		
45.00	60.00		Cum	1	15.00	4.90	4.65	4.78	0.04	2.87		
60.00	71.70		Cum	1	11.70	4.65	4.65	4.65	0.04	2.18		
		2nd Cross Road										
		North To South										
0.00	15.00		Cum	1	15.00	5.60	4.05	4.83	0.04	2.90		
15.00	30.00		Cum	1	15.00	4.05	4.30	4.18	0.04	2.51		
30.00	45.00		Cum	1	15.00	4.30	4.35	4.33	0.04	2.60		
45.00	60.00		Cum	1	15.00	4.35	4.40	4.38	0.04	2.63		
60.00	75.00		Cum	1	15.00	4.40	4.80	4.60	0.04	2.76		
75.00	76.10		Cum	1	1.10	4.80	4.85	4.83	0.04	0.21		
		DEDUCTION										
		Manhole	Cum	-12	0.44				0.04	-0.21		
					(3.14X0.75X0.75)/4=0.44							
			Cum	-15	0.64				0.04	-0.38		
					(3.14X0.9X0.9)/4=0.64							
			Cum	-8	0.79				0.04	-0.25		
					(3.14X1X1)/4=0.79							
			Cum	-7	1.13				0.04	-0.32		
					(3.14X1.2X1.2)/4=1.13							
		ELETRIC POLE	Cum	-1	2.30	1.00	1.00	1.00	0.04	-0.09		
		CHAMBER	Cum	-34	0.90	0.60	0.60	0.60	0.04	-0.73		
			Cum	-1	0.80	0.70	0.70	0.70	0.04	-0.02		
			Cum	-1	1.90	1.80	1.80	1.80	0.04	-0.14		
			Cum	-1	2.40	0.90	0.90	0.90	0.04	-0.09		
		TRANSFORMER	Cum	-1	2.40	0.80	0.80	0.80	0.04	-0.08		
		TREE PATH	Cum	-1	1.00	1.00	1.00	1.00	0.04	-0.04		
										Total Executed Quantity	**2582.81**	**12253.37**	**31648142.00**
										Tender Quantity	**2721.26**		
Item no.21		**Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes**										
		Ward No 07										
		GKVK Layout										
		Main Road										
		(From West to East)										
0.00	7.10		Sqm	2	7.10	0.10	0.10	0.10		1.42		
7.10	15.00		Sqm	2	7.90	0.10	0.10	0.10		1.58		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	112.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
112.00	120.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	145.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
145.00	152.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
152.00	165.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
165.00	173.10		Sqm	2	8.10	0.10	0.10	0.10		1.62		
173.10	180.00		Sqm	2	6.90	0.10	0.10	0.10		1.38		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	200.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		Ravi Gowda Layout										
		(From North to South)										
0.00	3.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
3.50	15.00		Sqm	2	11.50	0.10	0.10	0.10		2.30		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	126.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
126.00	135.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
135.00	141.30		Sqm	2	6.30	0.10	0.10	0.10		1.26		
141.30	150.00		Sqm	2	8.70	0.10	0.10	0.10		1.74		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	213.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
		Jai Ram Layout										
		Anagha Dental Care Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	58.70		Sqm	2	13.70	0.10	0.10	0.10		2.74		
58.70	64.70		Sqm	2	6.00	0.10	0.10	0.10		1.20		
64.70	69.20		Sqm	2	4.50	0.10	0.10	0.10		0.90		
		Jai Rama Layout Main Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	114.70		Sqm	2	9.70	0.10	0.10	0.10		1.94		
114.70	118.30		Sqm	2	3.60	0.10	0.10	0.10		0.72		
		1st Cross Road (Or)										
		Five Star Security Service Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	67.90		Sqm	2	7.90	0.10	0.10	0.10		1.58		
		Talacauvery Layout										
		1st Main Road										
		(From West to East)										
0.00	3.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
3.50	15.00		Sqm	2	11.50	0.10	0.10	0.10		2.30		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
195.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	215.60		Sqm	2	5.60	0.10	0.10	0.10		1.12		
		2nd B Cross Road										
		(From North to South)										
0.00	3.40		Sqm	2	3.40	0.10	0.10	0.10		0.68		
3.40	9.40		Sqm	2	6.00	0.10	0.10	0.10		1.20		
9.40	18.50		Sqm	2	9.10	0.10	0.10	0.10		1.82		
18.50	30.00		Sqm	2	11.50	0.10	0.10	0.10		2.30		
30.00	37.80		Sqm	2	7.80	0.10	0.10	0.10		1.56		
		2nd A Cross Road										
		(From North to South)										
0.00	4.30		Sqm	2	4.30	0.10	0.10	0.10		0.86		
4.30	15.00		Sqm	2	10.70	0.10	0.10	0.10		2.14		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	111.10		Sqm	2	6.10	0.10	0.10	0.10		1.22		
		Dr. Rajkumar Road (or)1st A Main Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.20		Sqm	2	15.20	0.10	0.10	0.10		3.04		
90.20	94.40		Sqm	2	4.20	0.10	0.10	0.10		0.84		
94.40	105.00		Sqm	2	10.60	0.10	0.10	0.10		2.12		
105.00	109.20		Sqm	2	4.20	0.10	0.10	0.10		0.84		
		2nd Cross Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	122.10		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		Muniswamy Gowda Layout										
		1st Main Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	136.00		Sqm	2	1.00	0.10	0.10	0.10		0.20		
		1st A K.V.J Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	33.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
33.30	34.20		Sqm	2	0.90	0.10	0.10	0.10		0.18		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		2nd Cross Road Sunshine apartment										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	67.20		Sqm	2	7.20	0.10	0.10	0.10		1.44		
		G.Ramaiah Layout										
		1st Cross Road										
		(From North to South)										
0.00	9.90		Sqm	2	9.90	0.10	0.10	0.10		1.98		
9.90	15.00		Sqm	2	5.10	0.10	0.10	0.10		1.02		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	63.60		Sqm	2	3.60	0.10	0.10	0.10		0.72		
63.60	66.70		Sqm	2	3.10	0.10	0.10	0.10		0.62		
66.70	75.00		Sqm	2	8.30	0.10	0.10	0.10		1.66		
75.00	79.50		Sqm	2	4.50	0.10	0.10	0.10		0.90		
		Chiranjeevi Layout										
		3rd Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	52.30		Sqm	2	7.30	0.10	0.10	0.10		1.46		
52.30	55.00		Sqm	2	2.70	0.10	0.10	0.10		0.54		
		3rd Cross Near Vidya Niketan School Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	98.80		Sqm	2	8.80	0.10	0.10	0.10		1.76		
98.80	105.00		Sqm	2	6.20	0.10	0.10	0.10		1.24		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	129.30		Sqm	2	9.30	0.10	0.10	0.10		1.86		
129.30	131.50	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
131.50	138.00		Sqm	2	6.50	0.10	0.10	0.10		1.30		
		Veerannapalya										
		6th A Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	115.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
		6th B Cross Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
[illegible]00	118.50		Sqm	2	13.50	0.10	0.10	0.10		2.70		
		6th Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	89.10		Sqm	2	14.10	0.10	0.10	0.10		2.82		
89.10	90.30	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
90.30	105.00		Sqm	2	14.70	0.10	0.10	0.10		2.94		
105.00	117.10		Sqm	2	12.10	0.10	0.10	0.10		2.42		
		MCECHS Layout										
		11th Cross 13th Main Road										
		(North To South)										
0.00	5.50		Sqm	2	5.50	0.10	0.10	0.10		1.10		
5.50	15.00		Sqm	2	9.50	0.10	0.10	0.10		1.90		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	62.50		Sqm	2	2.50	0.10	0.10	0.10		0.50		
		10th Cross Road,13th main										
		(North To South)										
0.00	5.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
5.00	15.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	32.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
32.30	38.90		Sqm	2	6.60	0.10	0.10	0.10		1.32		
		9th B Cross, 13th Main Road										
		(North To South)										
0.00	4.30		Sqm	2	4.30	0.10	0.10	0.10		0.86		
4.30	15.00		Sqm	2	10.70	0.10	0.10	0.10		2.14		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	30.60		Sqm	2	0.60	0.10	0.10	0.10		0.12		
30.60	45.00		Sqm	2	14.40	0.10	0.10	0.10		2.88		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	138.10		Sqm	2	3.10	0.10	0.10	0.10		0.62		
		9th A Cross, 13th main										
		(North To South)										
0.00	4.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
4.00	15.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	110.30		Sqm	2	5.30	0.10	0.10	0.10		1.06		
		Ward No 08										
		Shanubhoga Narayanappa Layout										
		1st D Cross Road										
		(From East To West)										
		(From H.No #532 To Empty Site)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	27.10		Sqm	2	12.10	0.10	0.10	0.10		2.42		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
10	30.00		Sqm	2	2.90	0.10	0.10	0.10		0.58		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	139.20		Sqm	2	4.20	0.10	0.10	0.10		0.84		
		Shanubhoga Narayanappa Layout										
		2nd Main Road										
		(From West To East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	38.40		Sqm	2	8.40	0.10	0.10	0.10		1.68		
38.40	45.00		Sqm	2	6.60	0.10	0.10	0.10		1.32		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	113.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
113.00	120.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
120.00	126.20		Sqm	2	6.20	0.10	0.10	0.10		1.24		
126.20	130.50		Sqm	2	4.30	0.10	0.10	0.10		0.86		
130.50	135.00		Sqm	2	4.50	0.10	0.10	0.10		0.90		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	165.40		Sqm	2	0.40	0.10	0.10	0.10		0.08		
165.40	180.00		Sqm	2	14.60	0.10	0.10	0.10		2.92		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	249.30		Sqm	2	9.30	0.10	0.10	0.10		1.86		
249.30	258.30		Sqm	2	9.00	0.10	0.10	0.10		1.80		
258.30	273.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
273.30	275.00		Sqm	2	1.70	0.10	0.10	0.10		0.34		
273.30	284.00		Sqm	2	10.70	0.10	0.10	0.10		2.14		
		1st Cross Road										
		(From North To South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	25.90		Sqm	2	10.90	0.10	0.10	0.10		2.18		
25.90	40.00		Sqm	2	14.10	0.10	0.10	0.10		2.82		
40.00	50.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
50.00	60.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	148.80		Sqm	2	13.80	0.10	0.10	0.10		2.76		
		Balaji Layout										
		KBR Infratech Road										
		(From East To West)										
		(From Dead End To Kodigehalli Main Road)										
0.00	12.80		Sqm	2	12.80	0.10	0.10	0.10		2.56		
12.80	15.00		Sqm	2	2.20	0.10	0.10	0.10		0.44		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	54.20		Sqm	2	9.20	0.10	0.10	0.10		1.84		
54.20	55.80	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
55.80	60.00		Sqm	2	4.20	0.10	0.10	0.10		0.84		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	89.00		Sqm	2	14.00	0.10	0.10	0.10		2.80		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	90.00		Sqm	2	1.00	0.10	0.10	0.10		0.20		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	228.20		Sqm	2	3.20	0.10	0.10	0.10		0.64		
228.20	232.00		Sqm	2	3.80	0.10	0.10	0.10		0.76		
232.00	245.20		Sqm	2	13.20	0.10	0.10	0.10		2.64		
		1st Main 1st Cross Road										
		(From West To East)										
		(From Kodigehalli Main Road To Dead End)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	31.70		Sqm	2	1.70	0.10	0.10	0.10		0.34		
31.70	43.60		Sqm	2	11.90	0.10	0.10	0.10		2.38		
		(From West To East)										
0.00	3.90		Sqm	2	3.90	0.10	0.10	0.10		0.78		
3.90	11.10		Sqm	2	7.20	0.10	0.10	0.10		1.44		
		Ward No 08										
		Devi Nagar(Lottegollahalli Layout)										
		6th Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	18.80		Sqm	2	3.80	0.10	0.10	0.10		0.76		
18.80	30.00		Sqm	2	11.20	0.10	0.10	0.10		2.24		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	83.40		Sqm	2	8.40	0.10	0.10	0.10		1.68		
83.40	91.90		Sqm	2	8.50	0.10	0.10	0.10		1.70		
91.90	105.00		Sqm	2	13.10	0.10	0.10	0.10		2.62		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	163.10		Sqm	2	13.10	0.10	0.10	0.10		2.62		
		6th A Cross Road										
		(From West to East)										
0.00	7.80		Sqm	2	7.80	0.10	0.10	0.10		1.56		
		(From South to North)										
0.00	7.40		Sqm	2	7.40	0.10	0.10	0.10		1.48		
7.40	15.00		Sqm	2	7.60	0.10	0.10	0.10		1.52		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	50.70		Sqm	2	5.70	0.10	0.10	0.10		1.14		
50.70	60.00		Sqm	2	9.30	0.10	0.10	0.10		1.86		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	141.70		Sqm	2	6.70	0.10	0.10	0.10		1.34		
		Devi Nagar Main Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	237.20		Sqm	2	12.20	0.10	0.10	0.10		2.44		
237.20	239.00		Sqm	2	1.80	0.10	0.10	0.10		0.36		
239.00	241.50		Sqm	2	2.50	0.10	0.10	0.10		0.50		
		Muneshwara Layout										
		1st Main Road										
0.00	3.20		Sqm	2	3.20	0.10	0.10	0.10		0.64		
3.20	15.00		Sqm	2	11.80	0.10	0.10	0.10		2.36		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	184.70		Sqm	2	4.70	0.10	0.10	0.10		0.94		
184.70	186.20		Sqm	2	1.50	0.10	0.10	0.10		0.30		
186.20	195.00		Sqm	2	8.80	0.10	0.10	0.10		1.76		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	293.70		Sqm	2	8.70	0.10	0.10	0.10		1.74		
293.70	298.70		Sqm	2	5.00	0.10	0.10	0.10		1.00		
298.70	300.00		Sqm	2	1.30	0.10	0.10	0.10		0.26		
300.00	315.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
315.00	330.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
330.00	344.60		Sqm	2	14.60	0.10	0.10	0.10		2.92		
344.60	360.00		Sqm	2	15.40	0.10	0.10	0.10		3.08		
360.00	363.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
363.50	372.30		Sqm	2	8.80	0.10	0.10	0.10		1.76		
372.30	387.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
387.30	390.00		Sqm	2	2.70	0.10	0.10	0.10		0.54		
		Tata Nagar										
		1st Main Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	29.50		Sqm	2	14.50	0.10	0.10	0.10		2.90		
29.50	47.20	No Work	Sqm	2	0.00	0.10	0.10	0.10		0.00		
47.20	60.00		Sqm	2	12.80	0.10	0.10	0.10		2.56		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.30		Sqm	2	15.30	0.10	0.10	0.10		3.06		
150.30	158.50		Sqm	2	8.20	0.10	0.10	0.10		1.64		
158.50	165.30		Sqm	2	6.80	0.10	0.10	0.10		1.36		
165.30	180.30		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.30	189.60		Sqm	2	9.30	0.10	0.10	0.10		1.86		
189.60	193.50		Sqm	2	3.90	0.10	0.10	0.10		0.78		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		1st Cross Road										
		(West to East)										
		(From 5th Main to Rohitha Garden Apartment)										
0.00	4.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
4.00	15.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
15.00	24.10		Sqm	2	9.10	0.10	0.10	0.10		1.82		
24.10	30.00		Sqm	2	5.90	0.10	0.10	0.10		1.18		
30.00	38.10		Sqm	2	8.10	0.10	0.10	0.10		1.62		
38.10	46.00		Sqm	2	7.90	0.10	0.10	0.10		1.58		
46.00	60.00		Sqm	2	14.00	0.10	0.10	0.10		2.80		
60.00	67.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
67.00	75.00		Sqm	2	8.00	0.10	0.10	0.10		1.60		
75.00	83.50		Sqm	2	8.50	0.10	0.10	0.10		1.70		
		Kote Layout(Sapthagiri Hall)										
		Opposite Rohitha Gardens Appartment										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	87.00		Sqm	2	12.00	0.10	0.10	0.10		2.40		
87.00	90.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	129.20		Sqm	2	9.20	0.10	0.10	0.10		1.84		
129.20	135.00		Sqm	2	5.80	0.10	0.10	0.10		1.16		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	221.50		Sqm	2	11.50	0.10	0.10	0.10		2.30		
		1st Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	17.10		Sqm	2	2.10	0.10	0.10	0.10		0.42		
17.10	22.80		Sqm	2	5.70	0.10	0.10	0.10		1.14		
22.80	30.00		Sqm	2	7.20	0.10	0.10	0.10		1.44		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	54.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
54.00	60.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	85.20		Sqm	2	10.20	0.10	0.10	0.10		2.04		
		2nd Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	82.10		Sqm	2	7.10	0.10	0.10	0.10		1.42		
		2nd A Cross Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	44.90		Sqm	2	14.90	0.10	0.10	0.10		2.98		
		3rd Cross Road										
		(From North to South)										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
0	4.20		Sqm	2	4.20	0.10	0.10	0.10		0.84		
4.20	15.00		Sqm	2	10.80	0.10	0.10	0.10		2.16		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	52.20		Sqm	2	7.20	0.10	0.10	0.10		1.44		
52.20	60.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
60.00	67.30		Sqm	2	7.30	0.10	0.10	0.10		1.46		
67.30	70.60		Sqm	2	3.30	0.10	0.10	0.10		0.66		
70.60	85.00		Sqm	2	14.40	0.10	0.10	0.10		2.88		
85.00	90.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
90.00	92.10		Sqm	2	2.10	0.10	0.10	0.10		0.42		
92.10	95.30	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
95.30	105.00		Sqm	2	9.70	0.10	0.10	0.10		1.94		
105.00	108.90		Sqm	2	3.90	0.10	0.10	0.10		0.78		
		Balaji Layout										
		6th Cross Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	47.80		Sqm	2	2.80	0.10	0.10	0.10		0.56		
47.80	56.10		Sqm	2	8.30	0.10	0.10	0.10		1.66		
56.10	63.90		Sqm	2	7.80	0.10	0.10	0.10		1.56		
63.90	65.50	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
65.50	75.00		Sqm	2	9.50	0.10	0.10	0.10		1.90		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	94.50		Sqm	2	4.50	0.10	0.10	0.10		0.90		
94.50	105.00		Sqm	2	10.50	0.10	0.10	0.10		2.10		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	122.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
122.00	135.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	154.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
154.00	163.70		Sqm	2	9.70	0.10	0.10	0.10		1.94		
163.70	169.70		Sqm	2	6.00	0.10	0.10	0.10		1.20		
169.70	171.20	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
171.20	180.00		Sqm	2	8.80	0.10	0.10	0.10		1.76		
180.00	181.80		Sqm	2	1.80	0.10	0.10	0.10		0.36		
181.80	190.00		Sqm	2	8.20	0.10	0.10	0.10		1.64		
190.00	205.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
205.00	216.10		Sqm	2	11.10	0.10	0.10	0.10		2.22		
216.10	231.10		Sqm	2	15.00	0.10	0.10	0.10		3.00		
231.10	235.00		Sqm	2	3.90	0.10	0.10	0.10		0.78		
235.00	250.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
250.00	265.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
265.00	280.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
280.00	295.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
295.00	300.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
300.00	315.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
315.00	330.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
330.00	345.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
345.00	360.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
360.00	369.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
		Sarovara Layout										
		AMCO Layout 'A Block										
		1st Main Road										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	29.20		Sqm	2	14.20	0.10	0.10	0.10		2.84		
29.20	30.30	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
30.30	45.00		Sqm	2	14.70	0.10	0.10	0.10		2.94		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	108.50		Sqm	2	3.50	0.10	0.10	0.10		0.70		
108.50	118.70		Sqm	2	10.20	0.10	0.10	0.10		2.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
70	124.80		Sqm	2	6.10	0.10	0.10	0.10		1.22		
124.80	135.00		Sqm	2	10.20	0.10	0.10	0.10		2.04		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	291.50		Sqm	2	6.50	0.10	0.10	0.10		1.30		
291.50	298.00		Sqm	2	6.50	0.10	0.10	0.10		1.30		
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	17.20		Sqm	2	2.20	0.10	0.10	0.10		0.44		
17.20	30.00		Sqm	2	12.80	0.10	0.10	0.10		2.56		
30.00	41.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
41.00	50.20		Sqm	2	9.20	0.10	0.10	0.10		1.84		
		2nd Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	50.20		Sqm	2	5.20	0.10	0.10	0.10		1.04		
50.20	52.80		Sqm	2	2.60	0.10	0.10	0.10		0.52		
		Shanthivana Layout										
		1st Cross Road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	63.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
63.30	75.00		Sqm	2	11.70	0.10	0.10	0.10		2.34		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	132.90		Sqm	2	12.90	0.10	0.10	0.10		2.58		
132.90	147.10		Sqm	2	14.20	0.10	0.10	0.10		2.84		
147.10	160.00		Sqm	2	12.90	0.10	0.10	0.10		2.58		
160.00	165.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	198.80		Sqm	2	3.80	0.10	0.10	0.10		0.76		
198.80	210.00		Sqm	2	11.20	0.10	0.10	0.10		2.24		
210.00	219.70		Sqm	2	9.70	0.10	0.10	0.10		1.94		
219.70	222.20	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
222.20	225.00		Sqm	2	2.80	0.10	0.10	0.10		0.56		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	249.60		Sqm	2	9.60	0.10	0.10	0.10		1.92		
249.60	257.30		Sqm	2	7.70	0.10	0.10	0.10		1.54		
257.30	260.00		Sqm	2	2.70	0.10	0.10	0.10		0.54		
260.00	275.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
275.00	292.00		Sqm	2	17.00	0.10	0.10	0.10		3.40		
292.00	297.10		Sqm	2	5.10	0.10	0.10	0.10		1.02		
297.10	300.00		Sqm	2	2.90	0.10	0.10	0.10		0.58		
300.00	315.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
315.00	330.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
330.00	345.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
345.00	360.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
360.00	375.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
375.00	390.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
390.00	405.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	414.50		Sqm	2	9.50	0.10	0.10	0.10		1.90		
		AMCO Layout										
		1st Cross , Ganesh Temple Road										
		(South To North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	69.30		Sqm	2	9.30	0.10	0.10	0.10		1.86		
69.30	75.00		Sqm	2	5.70	0.10	0.10	0.10		1.14		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	111.40		Sqm	2	6.40	0.10	0.10	0.10		1.28		
		2nd Cross, Ganesh Temple Road										
		(North To South)										
0.00	4.60		Sqm	2	4.60	0.10	0.10	0.10		0.92		
4.60	15.00		Sqm	2	10.40	0.10	0.10	0.10		2.08		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	100.30		Sqm	2	10.30	0.10	0.10	0.10		2.06		
		Thindlu										
		Sri Laxmi Digital Shop Beside Road										
		(North To South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	73.50		Sqm	2	13.50	0.10	0.10	0.10		2.70		
		Anganawadi School Opp Road										
		(South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	81.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
		3rd Cross Road,Impact Collage										
		(South To North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	95.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		
		Balaji Layout										
		5th Main 5th Cross										
		(West To East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	26.20		Sqm	2	11.20	0.10	0.10	0.10		2.24		
		(North To South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	169.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
		Ward No 10										
		Vidyaranyapura Sub division'										
		RAMANNA GARDEN										
		1st Main road C Ramya layout										
		Ramachandra pura main road to house no.41A										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	20.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		
20.80	30.00		Sqm	2	9.20	0.10	0.10	0.10		1.84		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	53.60		Sqm	2	8.60	0.10	0.10	0.10		1.72		
53.60	60.00		Sqm	2	6.40	0.10	0.10	0.10		1.28		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	203.30		Sqm	2	8.30	0.10	0.10	0.10		1.66		
203.30	205.80		Sqm	2	2.50	0.10	0.10	0.10		0.50		
		2nd Main road, from Apollo pharmacy										
		(From West to East)										
0.00	3.10		Sqm	2	3.10	0.10	0.10	0.10		0.62		
3.10	15.00		Sqm	2	11.90	0.10	0.10	0.10		2.38		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	245.30		Sqm	2	5.30	0.10	0.10	0.10		1.06		
245.30	255.00		Sqm	2	9.70	0.10	0.10	0.10		1.94		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	277.40		Sqm	2	7.40	0.10	0.10	0.10		1.48		
277.40	285.00		Sqm	2	7.60	0.10	0.10	0.10		1.52		
285.00	300.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
300.00	303.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
		1st Cross Road										
		From house no :36 to 97										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	25.20		Sqm	2	10.20	0.10	0.10	0.10		2.04		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
20	33.90		Sqm	2	8.70	0.10	0.10	0.10		1.74		
33.90	45.00		Sqm	2	11.10	0.10	0.10	0.10		2.22		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	109.10		Sqm	2	4.10	0.10	0.10	0.10		0.82		
109.10	120.00		Sqm	2	10.90	0.10	0.10	0.10		2.18		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	142.80		Sqm	2	7.80	0.10	0.10	0.10		1.56		
142.80	150.00		Sqm	2	7.20	0.10	0.10	0.10		1.44		
150.00	154.80		Sqm	2	4.80	0.10	0.10	0.10		0.96		
154.80	165.00		Sqm	2	10.20	0.10	0.10	0.10		2.04		
165.00	172.80		Sqm	2	7.80	0.10	0.10	0.10		1.56		
172.80	180.00		Sqm	2	7.20	0.10	0.10	0.10		1.44		
180.00	181.40		Sqm	2	1.40	0.10	0.10	0.10		0.28		
181.40	195.00		Sqm	2	13.60	0.10	0.10	0.10		2.72		
195.00	209.40		Sqm	2	14.40	0.10	0.10	0.10		2.88		
209.40	221.00		Sqm	2	11.60	0.10	0.10	0.10		2.32		
		Samashana Road										
		2nd main Road										
		(From East to West)										
0.00	11.80		Sqm	2	11.80	0.10	0.10	0.10		2.36		
11.80	15.00		Sqm	2	3.20	0.10	0.10	0.10		0.64		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	140.50		Sqm	2	5.50	0.10	0.10	0.10		1.10		
		3rd Cross Road										
		from house no: 21 to site no:10										
		(From East to West)										
0.00	15.50		Sqm	2	15.50	0.10	0.10	0.10		3.10		
15.50	30.00		Sqm	2	14.50	0.10	0.10	0.10		2.90		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	46.40		Sqm	2	1.40	0.10	0.10	0.10		0.28		
46.40	60.00		Sqm	2	13.60	0.10	0.10	0.10		2.72		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.10		Sqm	2	15.10	0.10	0.10	0.10		3.02		
105.10	120.00		Sqm	2	14.90	0.10	0.10	0.10		2.98		
120.00	126.50		Sqm	2	6.50	0.10	0.10	0.10		1.30		
126.50	135.00		Sqm	2	8.50	0.10	0.10	0.10		1.70		
135.00	141.90		Sqm	2	6.90	0.10	0.10	0.10		1.38		
141.90	150.00		Sqm	2	8.10	0.10	0.10	0.10		1.62		
150.00	154.10		Sqm	2	4.10	0.10	0.10	0.10		0.82		
		#41 Sumka house opp road										
		To house no: 123										
		(From East to West)										
0.00	15.60		Sqm	2	15.60	0.10	0.10	0.10		3.12		
		1st A Main Road										
		From house no :8 to house no :83										
		(From West to East)										
0.00	1.60		Sqm	2	1.60	0.10	0.10	0.10		0.32		
1.60	15.00		Sqm	2	13.40	0.10	0.10	0.10		2.68		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	79.10		Sqm	2	4.10	0.10	0.10	0.10		0.82		
		5th A Cross Road,										
		Nithra apartment beside road										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	23.30		Sqm	2	8.30	0.10	0.10	0.10		1.66		
		From house no #15 to house no -7										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	79.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
		2nd Cross road										
		From House no: 81 to House no:65										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	29.60		Sqm	2	14.60	0.10	0.10	0.10		2.92		
29.60	38.70		Sqm	2	9.10	0.10	0.10	0.10		1.82		
38.70	45.00		Sqm	2	6.30	0.10	0.10	0.10		1.26		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	84.00		Sqm	2	9.00	0.10	0.10	0.10		1.80		
84.00	90.00		Sqm	2	6.00	0.10	0.10	0.10		1.20		
90.00	103.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
103.00	105.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	153.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
		BLOOM MOON GARDEN										
		1st Main Road										
		From House no: 47 to House no:43										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	47.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
		2nd Cross Road										
		From House no: #2 to House no:13										
		(From West to East)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	112.00		Sqm	2	7.00	0.10	0.10	0.10		1.40		
		3rd Cross Road										
		From House no: #14&15 to House no:19										
		(From South to North)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	50.10		Sqm	2	5.10	0.10	0.10	0.10		1.02		
		1st Cross Road										
		From House no: 33 to Empty site										
		1st Cross Road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.10		Sqm	2	15.10	0.10	0.10	0.10		3.02		
		BLOOM FIELD GARDEN										
		House no: #47 to Ramchandrapura main road										
		(From East to West)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	34.30		Sqm	2	4.30	0.10	0.10	0.10		0.86		
34.30	45.00		Sqm	2	10.70	0.10	0.10	0.10		2.14		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	187.20		Sqm	2	7.20	0.10	0.10	0.10		1.44		
187.20	195.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	215.40		Sqm	2	5.40	0.10	0.10	0.10		1.08		
		4th Cross Road										
		From House no: 113 to house no: 117										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	32.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
32.30	36.20		Sqm	2	3.90	0.10	0.10	0.10		0.78		
36.20	44.00		Sqm	2	7.80	0.10	0.10	0.10		1.56		
		1st Main Road										
		From ramachandrapura main road to house no #32										
		(From West to East)										
0.00	1.10		Sqm	2	1.10	0.10	0.10	0.10		0.22		
1.10	15.00		Sqm	2	13.90	0.10	0.10	0.10		2.78		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	119.50		Sqm	2	14.50	0.10	0.10	0.10		2.90		
119.50	120.80		Sqm	2	1.30	0.10	0.10	0.10		0.26		
		3rd Cross Road										
		House no: #22 to House no:38&39										
		(From South to North)										
0.00	2.90		Sqm	2	2.90	0.10	0.10	0.10		0.58		
2.90	15.00		Sqm	2	12.10	0.10	0.10	0.10		2.42		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	163.70		Sqm	2	13.70	0.10	0.10	0.10		2.74		
163.70	165.00		Sqm	2	1.30	0.10	0.10	0.10		0.26		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	200.20		Sqm	2	5.20	0.10	0.10	0.10		1.04		
		2nd Cross Road										
		House no: #48 to House no:#42										
		(From South to North)										
0.00	1.80		Sqm	2	1.80	0.10	0.10	0.10		0.36		
1.80	15.00		Sqm	2	13.20	0.10	0.10	0.10		2.64		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	65.50		Sqm	2	5.50	0.10	0.10	0.10		1.10		
		2nd Cross Road										
		House no: #68 to House no:#59										
		(From North to South)										
0.00	2.00		Sqm	2	2.00	0.10	0.10	0.10		0.40		
2.00	15.00		Sqm	2	13.00	0.10	0.10	0.10		2.60		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	127.60		Sqm	2	7.60	0.10	0.10	0.10		1.52		
		1st Cross Road,										
		House no: #127 to House no:#95										
		(From South to North)										
0.00	3.20		Sqm	2	3.20	0.10	0.10	0.10		0.64		
3.20	15.00		Sqm	2	11.80	0.10	0.10	0.10		2.36		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	128.30		Sqm	2	8.30	0.10	0.10	0.10		1.66		
		1st Cross Road										
		House no:83&84 to Ramchandrapura main road To house no: 77										
		(From South to North)										
0.00	2.60		Sqm	2	2.60	0.10	0.10	0.10		0.52		
2.60	15.00		Sqm	2	12.40	0.10	0.10	0.10		2.48		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	80.80		Sqm	2	5.80	0.10	0.10	0.10		1.16		
80.80	83.40		Sqm	2	2.60	0.10	0.10	0.10		0.52		
		BEL LAYOUT										

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		4th Main Road, BEL Layout 2nd Block From ICICI Bank to Deadend										
		(From West to East)										
0.00	4.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
4.00	15.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	300.40		Sqm	2	15.40	0.10	0.10	0.10		3.08		
		S.L.V Kaveri House										
		From house #1064 to nanjappa, vidyaranya pura Main road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	101.20		Sqm	2	11.20	0.10	0.10	0.10		2.24		
101.20	104.80		Sqm	2	3.60	0.10	0.10	0.10		0.72		
104.80	120.00		Sqm	2	15.20	0.10	0.10	0.10		3.04		
120.00	132.60		Sqm	2	12.60	0.10	0.10	0.10		2.52		
132.60	136.60		Sqm	2	4.00	0.10	0.10	0.10		0.80		
		Nanjappa Layout										
		8th A Cross Road										
		(From North to South)										
0.00	3.70		Sqm	2	3.70	0.10	0.10	0.10		0.74		
3.70	5.50	Culvert	Sqm	2	0.00	0.10	0.10	0.10		0.00		
5.50	15.00		Sqm	2	9.50	0.10	0.10	0.10		1.90		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	40.80		Sqm	2	10.80	0.10	0.10	0.10		2.16		
40.80	45.00		Sqm	2	4.20	0.10	0.10	0.10		0.84		
45.00	60.10		Sqm	2	15.10	0.10	0.10	0.10		3.02		
		9th A Cross Road										
		(From South to North)										
0.00	3.70		Sqm	2	3.70	0.10	0.10	0.10		0.74		
3.70	15.00		Sqm	2	11.30	0.10	0.10	0.10		2.26		
15.00	17.10		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		9th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.90		Sqm	2	15.90	0.10	0.10	0.10		3.18		
90.90	98.80		Sqm	2	7.90	0.10	0.10	0.10		1.58		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
		7th A Cross Road										
		(From South to North)										
0.00	4.20		Sqm	2	4.20	0.10	0.10	0.10		0.84		
4.20	9.10		Sqm	2	4.90	0.10	0.10	0.10		0.98		
9.10	15.00		Sqm	2	5.90	0.10	0.10	0.10		1.18		
15.00	18.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
		7th Cross Road										
		(From North to South)										
0.00	3.00		Sqm	2	3.00	0.10	0.10	0.10		0.60		
3.00	15.00		Sqm	2	12.00	0.10	0.10	0.10		2.40		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	84.50		Sqm	2	9.50	0.10	0.10	0.10		1.90		
84.50	90.00		Sqm	2	5.50	0.10	0.10	0.10		1.10		
90.00	99.20		Sqm	2	9.20	0.10	0.10	0.10		1.84		
		6th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	92.30		Sqm	2	2.30	0.10	0.10	0.10		0.46		
92.30	95.90		Sqm	2	3.60	0.10	0.10	0.10		0.72		
		6th A Cross Road										
		(From South to North)										
0.00	9.60		Sqm	2	9.60	0.10	0.10	0.10		1.92		
9.60	15.00		Sqm	2	5.40	0.10	0.10	0.10		1.08		
15.00	18.30		Sqm	2	3.30	0.10	0.10	0.10		0.66		
		5th Cross Road										
		(From North to South)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	74.80		Sqm	2	14.80	0.10	0.10	0.10		2.96		
74.80	83.40		Sqm	2	8.60	0.10	0.10	0.10		1.72		
83.40	91.60		Sqm	2	8.20	0.10	0.10	0.10		1.64		
91.60	95.00		Sqm	2	3.40	0.10	0.10	0.10		0.68		
		5th A Cross Road										
		(From South to North)										
0.00	4.00		Sqm	2	4.00	0.10	0.10	0.10		0.80		
4.00	15.00		Sqm	2	11.00	0.10	0.10	0.10		2.20		
15.00	20.60		Sqm	2	5.60	0.10	0.10	0.10		1.12		
		BEL Layout 2nd Block										
		2nd Cross Road										
		(From West to East)										
		(From Vidyaranyapura Main Road to 4th Main Road)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	195.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
195.00	210.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
210.00	225.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
225.00	240.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
240.00	255.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
255.00	270.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
270.00	285.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
285.00	300.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
300.00	308.90		Sqm	2	8.90	0.10	0.10	0.10		1.78		
		3rd Cross Road										
		(From South to North)										
		(From 4th Main Road to 5th Cross Road)										
0.00	10.00		Sqm	2	10.00	0.10	0.10	0.10		2.00		
10.00	24.70		Sqm	2	14.70	0.10	0.10	0.10		2.94		
24.70	30.00		Sqm	2	5.30	0.10	0.10	0.10		1.06		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	165.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
165.00	180.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
180.00	181.20		Sqm	2	1.20	0.10	0.10	0.10		0.24		
		5th Cross Road										
		(From North to South)										
		(From 2nd Cross Road to 4th Main Road)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	161.50		Sqm	2	11.50	0.10	0.10	0.10		2.30		
161.50	168.60		Sqm	2	7.10	0.10	0.10	0.10		1.42		
168.60	170.00		Sqm	2	1.40	0.10	0.10	0.10		0.28		
		5th Cross Road										
		(From North to South)										
		(From 4th Main Road to Vidyaranyapura Main Road)										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	52.70		Sqm	2	7.70	0.10	0.10	0.10		1.54		
52.70	57.60		Sqm	2	4.90	0.10	0.10	0.10		0.98		
57.60	70.00		Sqm	2	12.40	0.10	0.10	0.10		2.48		
70.00	85.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
85.00	90.00		Sqm	2	5.00	0.10	0.10	0.10		1.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	135.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
135.00	150.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
150.00	159.10		Sqm	2	9.10	0.10	0.10	0.10		1.82		
		Nanjappa Layout										
		12th Cross Road										

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		North To South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	69.20		Sqm	2	9.20	0.10	0.10	0.10		1.84		
69.20	75.00		Sqm	2	5.80	0.10	0.10	0.10		1.16		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	122.70		Sqm	2	2.70	0.10	0.10	0.10		0.54		
122.70	124.80		Sqm	2	2.10	0.10	0.10	0.10		0.42		
		11th Cross Road										
		North to South										
0.00	9.80		Sqm	2	9.80	0.10	0.10	0.10		1.96		
9.80	15.00		Sqm	2	5.20	0.10	0.10	0.10		1.04		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	106.40		Sqm	2	1.40	0.10	0.10	0.10		0.28		
106.40	120.00		Sqm	2	13.60	0.10	0.10	0.10		2.72		
120.00	129.10		Sqm	2	9.10	0.10	0.10	0.10		1.82		
		17th Cross Road										
		North to South										
0.00	15.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
15.00	30.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
30.00	45.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
45.00	60.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
60.00	75.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
75.00	90.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
90.00	105.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
105.00	120.00		Sqm	2	15.00	0.10	0.10	0.10		3.00		
120.00	131.80		Sqm	2	11.80	0.10	0.10	0.10		2.36		
										Total Executed Quantity	**2346.00**	
										Tender Quantity	**2239.40**	
										Quantity Upto 125%	**2346.00**	**551.98**	**1294946.00**
Item no.22		**Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatel**										
		Ward No 10										
		Vidyaranyapura Sub division										
		Munikalappa Layout(Doddabommasandra)										
		RC Pura Road(K.K Compound)										
		(From East to West)										
0.00	0.50		Cum	1	0.50	4.20	5.40	4.80	0.25	0.60		
0.50	9.30		Cum	1	8.80	5.40	5.50	5.45	0.25	11.99		
9.30	14.00		Cum	1	4.70	6.50	6.15	6.33	0.25	7.43		
14.00	29.00		Cum	1	15.00	5.00	4.90	4.95	0.25	18.56		
29.00	30.00		Cum	1	1.00	4.90	4.90	4.90	0.25	1.23		
30.00	45.00		Cum	1	15.00	4.90	4.65	4.78	0.25	17.91		
45.00	49.90		Cum	1	4.90	4.65	4.50	4.58	0.25	5.60		
49.90	63.70		Cum	1	13.80	5.55	5.10	5.33	0.25	18.37		
63.70	75.00		Cum	1	11.30	5.10	4.30	4.70	0.25	13.28		
75.00	77.80		Cum	1	2.80	4.30	4.35	4.33	0.25	3.03		
		Patil Gopalappa Layout										
		7th Cross Road										
		(South To North)										
0.00	2.50		Cum	1	2.50	4.25	4.25	4.25	0.25	2.66		
2.50	15.00		Cum	1	12.50	3.50	3.30	3.40	0.25	10.63		
15.00	30.00		Cum	1	15.00	3.30	3.45	3.38	0.25	12.66		

Chainage		Description of Item	Unit	No	Length	Breadth			Depth	Quantity	Rate in	Amount in
From	To				(m)	B1	B2	Avg B	(m)		RS.	RS.
00	45.00		Cum	1	15.00	3.45	3.05	3.25	0.25	12.19		
45.00	60.00		Cum	1	15.00	3.05	3.65	3.35	0.25	12.56		
60.00	75.00		Cum	1	15.00	3.65	3.40	3.53	0.25	13.22		
75.00	90.00		Cum	1	15.00	3.40	3.50	3.45	0.25	12.94		
90.00	105.00		Cum	1	15.00	3.50	4.30	3.90	0.25	14.63		
105.00	120.00		Cum	1	15.00	4.30	4.65	4.48	0.25	16.78		
120.00	129.80		Cum	1	9.80	4.65	3.25	3.95	0.25	9.68		
129.80	135.00		Cum	1	5.20	4.20	4.30	4.25	0.25	5.52		
135.00	150.00		Cum	1	15.00	4.30	4.60	4.45	0.25	16.69		
150.00	151.60		Cum	1	1.60	4.60	4.60	4.60	0.25	1.84		
151.60	156.50		Cum	1	4.90	3.65	3.50	3.58	0.25	4.38		
		Cross Road										
		East To West										
0.00	15.00		Cum	1	15.00	1.70	1.95	1.83	0.25	6.84		
		Yalagamma Layout										
		6th C Cross										
		(East To West)										
0.00	3.00	No Work	Cum	1	0.00	0.00	0.00	0.00	0.25	0.00		
3.00	15.00		Cum	1	12.00	3.90	4.10	4.00	0.25	12.00		
15.00	30.00		Cum	1	15.00	4.10	4.10	4.10	0.25	15.38		
30.00	45.00		Cum	1	15.00	4.10	4.05	4.08	0.25	15.28		
45.00	60.00		Cum	1	15.00	4.05	4.20	4.13	0.25	15.47		
60.00	75.00		Cum	1	15.00	4.20	4.10	4.15	0.25	15.56		
75.00	90.00		Cum	1	15.00	4.10	4.45	4.28	0.25	16.03		
90.00	95.10		Cum	1	5.10	4.45	4.95	4.70	0.25	5.99		
		Patil Gopalappa Layout										
		4th Block 8th Cross Road										
		South to North										
0.00	15.00		Cum	1	15.00	4.00	3.00	3.50	0.25	13.13		
15.00	30.00		Cum	1	15.00	3.00	3.35	3.18	0.25	11.91		
30.00	45.00		Cum	1	15.00	3.35	3.80	3.58	0.25	13.41		
45.00	60.00		Cum	1	15.00	3.80	4.20	4.00	0.25	15.00		
60.00	75.00		Cum	1	15.00	4.20	4.25	4.23	0.25	15.84		
75.00	90.00		Cum	1	15.00	4.25	3.90	4.08	0.25	15.28		
90.00	105.00		Cum	1	15.00	3.90	4.65	4.28	0.25	16.03		
105.00	120.00		Cum	1	15.00	4.65	5.00	4.83	0.25	18.09		
120.00	135.00		Cum	1	15.00	5.00	4.10	4.55	0.25	17.06		
135.00	150.00		Cum	1	15.00	4.10	4.65	4.38	0.25	16.41		
150.00	153.40		Cum	1	3.40	4.65	3.90	4.28	0.25	3.63		
		Chamundeswari Layout										
		Nagamma Temple Road										
		From 3rd main Road to 3rd Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	3.60	4.20	3.90	0.25	14.63		
15.00	30.00		Cum	1	15.00	4.20	4.15	4.18	0.25	15.66		
30.00	45.00		Cum	1	15.00	4.15	4.30	4.23	0.25	15.84		
45.00	60.00		Cum	1	15.00	4.30	4.10	4.20	0.25	15.75		
60.00	75.00		Cum	1	15.00	4.10	4.15	4.13	0.25	15.47		
75.00	90.00		Cum	1	15.00	4.15	4.10	4.13	0.25	15.47		
90.00	105.00		Cum	1	15.00	4.10	4.00	4.05	0.25	15.19		
105.00	120.00		Cum	1	15.00	4.00	3.50	3.75	0.25	14.06		
120.00	135.00		Cum	1	15.00	3.50	3.10	3.30	0.25	12.38		
135.00	138.20		Cum	1	3.20	3.10	3.00	3.05	0.25	2.44		
		Deduction										
		Manhole	Cum	-11	0.44				0.25	-1.21		
					(3.14X0.75X0.75)/4=0.44							
		Manhole	Cum	-8	0.64				0.25	-1.27		
					(3.14X0.9X0.9)/4=0.64							
		Chamber	Cum	-1	0.90	0.60	0.60	0.60	0.25	-0.14		
		Steps	Cum	-1	1.00	0.55	0.55	0.55	0.25	-0.14		
		Chamber										
			Cum	-2	1.00	0.70	0.70	0.70	0.25	-0.35		
			Cum	-1	1.80	1.80	1.80	1.80	0.25	-0.81		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
			Cum	-1	1.50	1.50	1.50	1.50	0.25	-0.56		
									Total Executed Quantity	**635.10**		
									Tender Quantity	**204.46**		
									Quantity Upto 125%	**255.58**	**487.32**	**124547.00**
									Quantity Above 125%	**379.52**	**487.32**	**184948.00**
Item no.23		Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates										
		Ward No 10										
		Vidyaranyapura Sub division`										
		Munikalappa Layout(Doddabommasandra)										
		RC Pura Road(K.K Compound)										
		(From East to West)										
0.00	0.50		Cum	1	0.50	4.20	5.40	4.80	0.15	0.36		
0.50	9.30		Cum	1	8.80	5.40	5.50	5.45	0.15	7.19		
9.30	14.00		Cum	1	4.70	6.50	6.15	6.33	0.15	4.46		
14.00	29.00		Cum	1	15.00	5.00	4.90	4.95	0.15	11.14		
29.00	30.00		Cum	1	1.00	4.90	4.90	4.90	0.15	0.74		
30.00	45.00		Cum	1	15.00	4.90	4.65	4.78	0.15	10.74		
45.00	49.90		Cum	1	4.90	4.65	4.50	4.58	0.15	3.36		
49.90	63.70		Cum	1	13.80	5.55	5.10	5.33	0.15	11.02		
63.70	75.00		Cum	1	11.30	5.10	4.30	4.70	0.15	7.97		
75.00	77.80		Cum	1	2.80	4.30	4.35	4.33	0.15	1.82		
		Patil Gopalappa Layout										
		7th Cross Road										
		(South To North)										
0.00	2.50		Cum	1	2.50	4.25	4.25	4.25	0.15	1.59		
2.50	15.00		Cum	1	12.50	3.50	3.30	3.40	0.15	6.38		
15.00	30.00		Cum	1	15.00	3.30	3.45	3.38	0.15	7.59		
30.00	45.00		Cum	1	15.00	3.45	3.05	3.25	0.15	7.31		
45.00	60.00		Cum	1	15.00	3.05	3.65	3.35	0.15	7.54		
60.00	75.00		Cum	1	15.00	3.65	3.40	3.53	0.15	7.93		
75.00	90.00		Cum	1	15.00	3.40	3.50	3.45	0.15	7.76		
90.00	105.00		Cum	1	15.00	3.50	4.30	3.90	0.15	8.78		
105.00	120.00		Cum	1	15.00	4.30	4.65	4.48	0.15	10.07		
120.00	129.80		Cum	1	9.80	4.65	3.25	3.95	0.15	5.81		
129.80	135.00		Cum	1	5.20	4.20	4.30	4.25	0.15	3.31		
135.00	150.00		Cum	1	15.00	4.30	4.60	4.45	0.15	10.01		
150.00	151.60		Cum	1	1.60	4.60	4.60	4.60	0.15	1.10		
151.60	156.50		Cum	1	4.90	3.65	3.50	3.58	0.15	2.63		
		Cross Road										
		East To West										
0.00	15.00		Cum	1	15.00	1.70	1.95	1.83	0.15	4.11		
		Yalagamma Layout										
		6th C Cross										
		(East To West)										
0.00	3.00	No Work	Cum	1	0.00	0.00	0.00	0.00	0.15	0.00		
3.00	15.00		Cum	1	12.00	3.90	4.10	4.00	0.15	7.20		
15.00	30.00		Cum	1	15.00	4.10	4.10	4.10	0.15	9.23		
30.00	45.00		Cum	1	15.00	4.10	4.05	4.08	0.15	9.17		
45.00	60.00		Cum	1	15.00	4.05	4.20	4.13	0.15	9.28		
60.00	75.00		Cum	1	15.00	4.20	4.10	4.15	0.15	9.34		
75.00	90.00		Cum	1	15.00	4.10	4.45	4.28	0.15	9.62		
90.00	95.10		Cum	1	5.10	4.45	4.95	4.70	0.15	3.60		
		Patil Gopalappa Layout										
		4th Block 8th Cross Road										
		South to North										
0.00	15.00		Cum	1	15.00	4.00	3.00	3.50	0.15	7.88		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
00	30.00		Cum	1	15.00	3.00	3.35	3.18	0.15	7.14		
30.00	45.00		Cum	1	15.00	3.35	3.80	3.58	0.15	8.04		
45.00	60.00		Cum	1	15.00	3.80	4.20	4.00	0.15	9.00		
60.00	75.00		Cum	1	15.00	4.20	4.25	4.23	0.15	9.51		
75.00	90.00		Cum	1	15.00	4.25	3.90	4.08	0.15	9.17		
90.00	105.00		Cum	1	15.00	3.90	4.65	4.28	0.15	9.62		
105.00	120.00		Cum	1	15.00	4.65	5.00	4.83	0.15	10.86		
120.00	135.00		Cum	1	15.00	5.00	4.10	4.55	0.15	10.24		
135.00	150.00		Cum	1	15.00	4.10	4.65	4.38	0.15	9.84		
150.00	153.40		Cum	1	3.40	4.65	3.90	4.28	0.15	2.18		
		Chamundeswari Layout										
		Nagamma Temple Road										
		From 3rd main Road to 3rd Cross Road										
		(From East to West)										
0.00	15.00		Cum	1	15.00	3.60	4.20	3.90	0.15	8.78		
15.00	30.00		Cum	1	15.00	4.20	4.15	4.18	0.15	9.39		
30.00	45.00		Cum	1	15.00	4.15	4.30	4.23	0.15	9.51		
45.00	60.00		Cum	1	15.00	4.30	4.10	4.20	0.15	9.45		
60.00	75.00		Cum	1	15.00	4.10	4.15	4.13	0.15	9.28		
75.00	90.00		Cum	1	15.00	4.15	4.10	4.13	0.15	9.28		
90.00	105.00		Cum	1	15.00	4.10	4.00	4.05	0.15	9.11		
105.00	120.00		Cum	1	15.00	4.00	3.50	3.75	0.15	8.44		
120.00	135.00		Cum	1	15.00	3.50	3.10	3.30	0.15	7.43		
135.00	138.20		Cum	1	3.20	3.10	3.00	3.05	0.15	1.46		
		Deduction										
		Manhole	Cum	-11	0.44				0.15	-0.73		
					(3.14X0.75X0.75)/4=0.44							
		Manhole	Cum	-8	0.64				0.15	-0.76		
					(3.14X0.9X0.9)/4=0.64							
		Chamber	Cum	-1	0.90	0.60	0.60	0.60	0.15	-0.08		
		Steps	Cum	-1	1.00	0.55	0.55	0.55	0.15	-0.08		
		Chamber										
			Cum	-2	1.00	0.70	0.70	0.70	0.15	-0.21		
			Cum	-1	1.80	1.80	1.80	1.80	0.15	-0.49		
			Cum	-1	1.50	1.50	1.50	1.50	0.15	-0.34		
									Total Executed Quantity	**381.06**		
									Tender Quantity	**175.25**		
									Quantity Upto 125%	**219.06**	**5611.08**	**1229178.00**
									Quantity Above 125%	**162.00**	**5611.08**	**908968.00**
Item no.24		Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work											
		Ward No 10										
		Vidyaranyapura Sub division`										
		Munikalappa Layout(Doddabommasandra)										
		RC Pura Road(K.K										
		(From East to West)										
0.00	0.50		Cum	1	0.50	4.20	5.40	4.80	0.15	0.36		
0.50	9.30		Cum	1	8.80	5.40	5.50	5.45	0.15	7.19		
9.30	14.00		Cum	1	4.70	6.50	6.15	6.33	0.15	4.46		
14.00	29.00		Cum	1	15.00	5.00	4.90	4.95	0.15	11.14		
29.00	30.00		Cum	1	1.00	4.90	4.90	4.90	0.15	0.74		
30.00	45.00		Cum	1	15.00	4.90	4.65	4.78	0.15	10.74		
45.00	49.90		Cum	1	4.90	4.65	4.50	4.58	0.15	3.36		
49.90	63.70		Cum	1	13.80	5.55	5.10	5.33	0.15	11.02		
63.70	75.00		Cum	1	11.30	5.10	4.30	4.70	0.15	7.97		
75.00	77.80		Cum	1	2.80	4.30	4.35	4.33	0.15	1.82		

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
		Patil Gopalappa Layout										
		7th Cross Road										
		(South To North)										
0	2.5		Cum	1	2.50	4.25	4.25	4.25	0.15	1.59		
2.5	15		Cum	1	12.50	3.50	3.30	3.40	0.15	6.38		
15	30		Cum	1	15.00	3.30	3.45	3.38	0.15	7.59		
30	45		Cum	1	15.00	3.45	3.05	3.25	0.15	7.31		
45	60		Cum	1	15.00	3.05	3.65	3.35	0.15	7.54		
60	75		Cum	1	15.00	3.65	3.40	3.53	0.15	7.93		
75	90		Cum	1	15.00	3.40	3.50	3.45	0.15	7.76		
90	105		Cum	1	15.00	3.50	4.30	3.90	0.15	8.78		
105	120		Cum	1	15.00	4.30	4.65	4.48	0.15	10.07		
120	129.8		Cum	1	9.80	4.65	3.25	3.95	0.15	5.81		
129.8	135		Cum	1	5.20	4.20	4.30	4.25	0.15	3.31		
135	150		Cum	1	15.00	4.30	4.60	4.45	0.15	10.01		
150	151.6		Cum	1	1.60	4.60	4.60	4.60	0.15	1.10		
151.6	156.5		Cum	1	4.90	3.65	3.50	3.58	0.15	2.63		
		Cross Road										
		East To West										
0	15		Cum	1	15.00	1.70	1.95	1.83	0.15	4.11		
		Yalagamma Layout										
		6th C Cross										
		(East To West)										
0	3	No Work	Cum	1	0.00	0.00	0.00	0.00	0.15	0.00		
3	15		Cum	1	12.00	3.90	4.10	4.00	0.15	7.20		
15	30		Cum	1	15.00	4.10	4.10	4.10	0.15	9.23		
30	45		Cum	1	15.00	4.10	4.05	4.08	0.15	9.17		
45	60		Cum	1	15.00	4.05	4.20	4.13	0.15	9.28		
60	75		Cum	1	15.00	4.20	4.10	4.15	0.15	9.34		
75	90		Cum	1	15.00	4.10	4.45	4.28	0.15	9.62		
90	95.1		Cum	1	5.10	4.45	4.95	4.70	0.15	3.60		
		Patil Gopalappa Layout										
		4th Block 8th Cross Road										
		South to North										
0	15		Cum	1	15.00	4.00	3.00	3.50	0.15	7.88		
15	30		Cum	1	15.00	3.00	3.35	3.18	0.15	7.14		
30	45		Cum	1	15.00	3.35	3.80	3.58	0.15	8.04		
45	60		Cum	1	15.00	3.80	4.20	4.00	0.15	9.00		
60	75		Cum	1	15.00	4.20	4.25	4.23	0.15	9.51		
75	90		Cum	1	15.00	4.25	3.90	4.08	0.15	9.17		
90	105		Cum	1	15.00	3.90	4.65	4.28	0.15	9.62		
105	120		Cum	1	15.00	4.65	5.00	4.83	0.15	10.86		
120	135		Cum	1	15.00	5.00	4.10	4.55	0.15	10.24		
135	150		Cum	1	15.00	4.10	4.65	4.38	0.15	9.84		
150	153.4		Cum	1	3.40	4.65	3.90	4.28	0.15	2.18		
		Chamundeswari Layout										
		Nagamma Temple Road										
		From 3rd main Road to 3rd Cross Road										
		(From East to West)										
0	15		Cum	1	15.00	3.60	4.20	3.90	0.15	8.78		
15	30		Cum	1	15.00	4.20	4.15	4.18	0.15	9.39		
30	45		Cum	1	15.00	4.15	4.30	4.23	0.15	9.51		
45	60		Cum	1	15.00	4.30	4.10	4.20	0.15	9.45		
60	75		Cum	1	15.00	4.10	4.15	4.13	0.15	9.28		
75	90		Cum	1	15.00	4.15	4.10	4.13	0.15	9.28		
90	105		Cum	1	15.00	4.10	4.00	4.05	0.15	9.11		
105	120		Cum	1	15.00	4.00	3.50	3.75	0.15	8.44		
120	135		Cum	1	15.00	3.50	3.10	3.30	0.15	7.43		
135	138.2		Cum	1	3.20	3.10	3.00	3.05	0.15	1.46		
		Deduction										
		Manhole	Cum	-11	0.44				0.15	-0.73		
					(3.14X0.75X0.75)/4=0.44							

No	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
	Manhole	Cum	-8	0.64				0.15	-0.76		
				(3.14X0.9X0.9)/4=0.64							
	Chamber	Cum	-1	0.90	0.60	0.60	0.60	0.15	-0.08		
	Steps	Cum	-1	1.00	0.55	0.55	0.55	0.15	-0.08		
	Chamber										
		Cum	-2	1.00	0.70	0.70	0.70	0.15	-0.21		
		Cum	-1	1.80	1.80	1.80	1.80	0.15	-0.49		
		Cum	-1	1.50	1.50	1.50	1.50	0.15	-0.34		
									Total Executed Quantity	**381.06**	
									Tender Quantity	**175.25**	
									Quantity Upto 125%	**219.06**	**7519.93**	**1647335.00**
									Quantity Above 125%	**162.00**	**7519.93**	**1218193.00**
Item no	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 250 t.km										
	Qty vide from 03+16+22	t.km		9828.62			1.28		12580.64		
									Total Executed Quantity	**12580.64**		
									Tender Quantity	**11120.25**		
									Quantity Upto 125%	**12580.64**	**110.86**	**1394690.00**
											Sub Total	**90878391.00**
											For 18% Applicable GST	**16358111.00**
											Total Amount	**107236502.00**

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Executive Engineer
Vijayanapura Division
Bangalore-92

Technical Sanction
Accorded For Rs.10,72,36,502/-
Head of A/C..1.3877
CER NO :..26..... Dt:21.09.2023

TA